
THILAWA SPECIAL ECONOMIC ZONE DEVELOPMENT PROJECT (ZONE B)

ENVIRONMENTAL IMPACT ASSESSMENT FOR INDUSTRIAL AREA OF ZONE B

May 2016

MYANMAR JAPAN THILAWA DEVELOPMENT LTD.



Location Map of Thilawa Special Economic Zone (SEZ) and Zone B Area



MYANMAR JAPAN THILAWA DEVELOPMENT LIMITED

Date: 27 May 2016

Ref. MJTD/O/16-05-317

Thilawa Special Economic Zone (SEZ) Management Committee No. 1234, Thanlyin Township, Yangon, The Republic of the Union of Myanmar

Attention:

Dear Excellency Mr. Set Aung

Chairman of the Thilawa SEZ Management Committee

Subject:

Environmental Impact Assessment (EIA) Report in respect of the "Thilawa Special Economic Zone Development Project (Industrial Area of Zone B)" (the EIA report including Environmental Management

Plan (EMP))

Dear Sir,

We refer to the captioned EIA report, which has been prepared and finalized by Nippon Koei Co., Ltd. in compliance with EIA Procedure (December 2015) and other relevant laws/rules and formally submitted to the Thilawa SEZ Management Committee.

We believe, to the best of our knowledge at the time of writing, that;

- a. the EIA Report is accurate and complete, and;
- b. the EIA Report has been prepared in strict compliance with all applicable laws, rules, regulations and procedures in force.

We hereby undertake that;

Myanmar Japan Thilawa Development Limited in respect of the "Industrial Area Development Project In Thilawa SEZ" will at all times comply fully with: (i) any and all commitments and obligations as set forth in the EIA Report which has been reviewed by Thilawa SEZ Management Committee, and (ii) any and all plans and the various components thereof, including without limitation, impact avoidance, mitigation, and remediation measures, and with respect to both (i) and (ii), including but not limited to such commitments, obligations, plans and measures related to the development, construction, commissioning, operation and maintenance of the project, and any circumstance in which work done or to be done, or services performed or to be performed, in connection with the project's development,



MYANMAR JAPAN THILAWA DEVELOPMENT LIMITED

construction, commissioning, operation and maintenance is carried out or intended or required to be carried out by any contractor, subcontractor or other party.

We acknowledge and understand that;

all the investors shall prepare and submit Environmental Conservation Prevention Plan (ECPP) to Thilawa SEZ Management Committee and implement it in conformity with applicable laws, rules, regulations and procedures in Myanmar including EIA Procedure under each investor's own responsibility.

Sign:

Name: Takashi YANAI

Title: President and CEO, Myanmar Japan Thilawa Development Limited

TABLE OF CONTENTS

EXECUTIVE SUMMARY

CHAPTI	ER 1: INTRODUCTION	. 1-1
1.1	Project Proponent	. 1-1
1.2	Purpose of the Study	. 1-1
1.3	Implementation Organization for Environmental Impact Assessment	. 1-1
1.4	Overall Schedule of Environmental Impact Assessment	
CHAPTI	ER 2: POLICY OF ENVIRONMENTAL AND SOCIAL CONSIDERATIONS	. 2-1
2.1	Corporate Environmental and Social Policies	. 2-1
2.2	Myanmar Regulatory Framework	. 2-1
2.2.1 2.2.2	Institutional Setting of the National Level Fundamental Laws and Regulations Related to Environmental and Social Considerations	. 2-1
2.3	Contractual and Other Commitments	
		2-1
2.4	Tentative Environmental Target Values for Consideration of Surrounding	
2.4.1	Environment	
2.4.1 2.4.2	Air Quality	
2.4.2	Water Quality	
2.4.4	Vibration	
2.5	Social and Health Standards for the Project	
2.6	Institutional Arrangement	
2.6.1	Thilawa SEZ Management Committee	
2.6.2	Project Proponent	
2.6.3	Institution Structure for Involuntary Resettlement in Thilawa SEZ	
2.7	Environmental Management in the Thliawa SEZ	. 2-20
2.7.1	Environmental Management Framework of Thilawa SEZ	. 2-20
2.7.2	Social Consideration Framework of Thilawa SEZ	
2.7.3	Environmental Management by the Project Proponent	
2.8	JICA Guidelines for Environmental and Social Considerations	2-28
CHAPTI	ER 3: PROJECT DESCRIPTION	. 3-1
3.1	Project Outline	. 3-1
3.1.1	Background	
3.1.2	Location of Thilawa SEZ	
3.2	Land Use Plan of Zone B	. 3-2
3.3	Selection of Alternative	. 3-4
3.3.1	Policy of Alternative Study	
3.3.2	Zero Option	
3.4	Land Reclamation Plan	. 3-6

3.5	Road System	3-7
3.5.1	Road Plan	3-7
3.5.2	Road Section	3-7
3.6	Drainage Plan	3-9
3.7	Water Supply System	3-11
3.7.1	Water Sources	3-11
3.7.2	Water Supply Distribution System	3-13
3.8	Sewage System	3-15
3.8.1	Sewage System	3-15
3.8.2	Wastewater Treatment Plant	
3.9	Power Supply Plan	3-17
3.9.1	Power Demand in Zone B	3-17
3.9.2	Power Supply Distribution System	
3.9.3	33 kV Distribution Plan	
3.10	Solid Waste Management	3-19
3.11	Greening Plan	
3.12	Tentative Implementation Schedule	
3.12	Tentative implementation Schedule	3-22
CHAPTE	R 4: CURRENT ENVIRONMENTAL AND SOCIAL CONDITION	<i>1</i> _1
4.1	Living Environment	
4.1.1	Air Quality	
4.1.1	Water Quality	
4.1.2	Soil Quality	
4.1.4	Noise Level	
4.2	Natural Environment	
4.2.1 4.2.2	Meteorology	
4.2.2	Hydrological Situations	
4.2.3	Geographical Features	
4.2.5	Soil Erosion	
4.2.6	Flora, Fauna, and Biodiversity	
4.2.7	Protected/Reserved Area	
4.3	Social Environment	
4.3.1	Population	
4.3.2	Ethnicity	
4.3.3	Religion	
4.3.4	Land Use	
4.3.5	Water Usage	
4.3.6	Local Economy and Livelihood	
4.3.7	Social Infrastructure and Service	
4.3.8	Public Health	
4.3.9	Cultural Heritage/Asset	
4.3.10	Landscape	
4.3.11	Emergency Risk	
4.4	Results of Survey for Framework of Resettlement Works for the 2,000 ha	4-32

4.5	Envi	ronmental Management Program in Thilawa SEZ ZoneA	4-34
CHAPT	ER 5:	SCOPING AND TERMS OF REFERENCE FOR ENVIRONMENTAL IMPACT ASSESSMENT	5 _1
5.1	Proce	edure of Scoping for Environmental and Social Impact Assessment	
5.2		lts of Scoping for Environmental and Social Impact Assessment	
5.3		as of Reference for Environmental Impact Assessment	
5.3.1		d Survey Methodology	
5.3.2		hodology of Forecast and Evaluation	
CHAPT	ER 6:	FIELD SURVEY	6-1
6.1	Air Ç	Quality	6-1
6.2	Wate	r Quality	6-6
6.3	Noise	e and Vibration Level	6-15
6.4	Traff	ic Volume	6-20
6.5	Soil	Quality	6-22
6.6	Flora	and Fauna	6-27
6.7	Cultu	ıral Assets	6-36
6.8	Hydr	ology	6-41
CHAPT	ER 7:	ENVIRONMENTAL AND SOCIAL IMPACT ASSESSMENT	7-1
7.1		mary of the Environmental and Social Impact Assessment	
7.2		Quality	
7.3		r Quality	
7.4	Wast	e	7-29
7.5	Soil (Contamination	7-36
7.6	Noise	e and Vibration	7-38
7.7	Offer	nsive Odor	7-49
7.8	Botto	om Sediment	7-50
7.9	Flora	/ Fauna and Biodiversity	7-52
7.10	Hydr	ology	7-55
7.11	Soil l	Erosion	7-58
7.12	Fram	ework of Resettlement Works for The 2000ha Development Area of	
	Thil	awa SEZ	7-60
7.13	Invol	untary Resettlement	7-63
7.14	Livin	g and Livelihood	7-65
7.15	Vuln	erable People	7-67
7.16	Loca	l Conflict of Interest	7-69
7.17	Misd	istribution of Benefit and Damage	7-71
7.18	Child	lren's Rights	7-73

7.19	Existing Social Infrastructure and Service	7-75
7.20	Water Usage	7-77
7.21	Cultural Heritage/ Asset	7-80
7.22	Landscape	7-82
7.23	Risks for Infectious Disease such as AIDS/HIV	7-84
7.24	Occupational Health and Safety	7-86
7.25	Community Health and Safety	7-91
7.26	Usage of Chemicals	7-93
7.27	Flood Risk	7-94
7.28	Risk of Fire	7-95
7.29	Earthquake	7-97
7.30	Global Warming	7-99
СНАРТЕ	ER 8: CUMULATIVE IMPACT ASSESSMENT	8-1
СНАРТЕ	ER 9: ENVIRONMENTAL AND SOCIAL CONSIDERATIONS IN	
	TERMINATION AND AFTER TERMINATION	9-1
СНАРТЬ	ER 10: ENVIRONMENTAL MITIGATION, MANAGEMENT AND	
CHAITI	MONITORING PLAN	10-1
10.1	Environmental Mitigation and Management Plan	
10.2	Environmental Monitoring Plan	
10.3	Budget for the Environmental Management and Monitoring	
10.3.1		
10.3.2	Budget Plan for Environmental Monitoring	10-15
10.4	Implementation Schedule	10-16
10.5	Institutional Arrangement	10-16
CIIA DEI	ED 11. DUDI IC CONCILITATION AND DUDI IC DISCUOSUDE	11 1
11.1	ER 11: PUBLIC CONSULTATION AND PUBLIC DISCLOSURE	
11.1	Approach and Objectives of PCM and PD for EIA	
11.1.2	11	
11.1.3	· ·	
11.2	Scoping Stage	
11.2.1	Public Consultation Meeting at the Scoping Stage	
11.2.2		
11.2.3	Conclusion for the EIA at the Scoping Stage	11-12
11.3	Draft EIA Stage	11-12
11.3.1	Public Consultation Meeting at the Draft EIA Stage	
11.3.2	\mathcal{E}	
11.3.3	i &	
11.3.4	č	
11.4	Public Consultation Meeting and Public Disclosue for the RWP	
11.4.1	Public Consultation Meeting for the RWP	11-21

11.4.2 Pub	olic Disclosure of draft RWP
CHAPTER 12	: COMMENTS FROM TSMC12-1
12.1 Commen	tts on the Scoping Report
12.2 Commen	its on the Draft EIA Report
CHAPTER 13	: CONCLUSIONS13-1
ANNEX	
Annex 1-1:	Curriculum Vitae of the Key Experts of the EIA Study Team
Annex 2-1:	Comparison between the JICA Guidelines and the relevant regulations in Myanmar
Annex 6-1:	Laboratory Analysis Record
Annex 6-2:	Flora and Fauna List of Thilawa SEZ Zone B Area
Annex 6-3:	Vulnerable and Near Threatened Species Recorded during the Survey of the Project
Annex 10-1:	List of Commitment
Annex 10-2:	Environmental Monitoring Plan
Annex 11-1:	Invitation Letter, Notice and List of Invitees for Public Consultation Meeting for EIA at Scoping Stage
Annex 11-2:	Presentation Materials, Handout and Sample of the Feedback Form in Myanmar Language for Public Consultation Meeting for EIA at Scoping Stage
Annex 11-3:	List of Attendee at Public Consultation Meeting for EIA at Scoping Stage
Annex 11-4:	Meeting Records of Public Consultation Meeting for EIA at Scoping Stage
Annex 11-5:	Announcement Letter for Public Disclosure of Scoping Report
Annex 11-6:	Invitation Letter, Notice and List of Invitees for Public Consultation Meeting for EIA at Draft EIA Stage
Annex 11-7:	Presentation Materials, Handout and Sample of the Feedback Form in Myanmar Language for Public Consultation Meeting for EIA at Draft EIA Stage
Annex 11-8:	List of Attendee at Public Consultation Meeting for EIA at Draft EIA Stage
Annex 11-9:	Meeting Records of Public Consultation Meeting for EIA at Draft EIA Stage
Annex 11-10:	Announcement Letter for Public Disclosure of the Draft EIA Report
Annex 12-1:	"Approval of Scoping Report (TSEZ-EIA-003)" issued by TSMC on February 26th, 2016
Annex 12-2:	"Notification of the Comments on Draft EIA Report (TSEZ-EIA-005)" issued by TSMC on May 17th, 2016

LIST OF TABLES

Table 1.3-1	Implementation Organization of EIA	. 1-1
Table 1.3- 2	Members of the EIA Study Team	
Table 1.4-1	EIA Schedule of the Project (as of May 2016)	1-3
Table 2.1-1	Ten Principles of UN Global Compact	.2-1
Table 2.2-1	Fundamental Laws and Regulations Related to Environmental and Social	
	Considerations and Health in Myanmar	.2-1
Table 2.2-2	Major International Agreements and Treaties that the Myanmar Government has	
	Ratified Related to Environmental and Social Considerations	.2-3
Table 2.4-1	Ambient Air Quality Standards of Myanmar, Other Countries and WHO	.2-8
Table 2.4-2	Tentative Target Value of Ambient Air Quality in the Project	.2-9
Table 2.4-3	Air Emission Level set in NEQG	2-10
Table 2.4-4	Target Value of Ambient Water Quality	2-11
Table 2.4-5	Target Value of Effluent Water Quality after Wastewater Pre-treatment by Tenant	2-12
Table 2.4-6	Tentative Target Value of Effluent Water Quality after Wastewater treatment at	
	Centralized Treatment Plant by Project Proponent (MJTD)	2-13
Table 2.4-7	Target Noise Level Set in NEQG	2-15
Table 2.4-8	Tentative Target Noise Level during the Construction Phase and Closing Phase	2-15
Table 2.4-9	Tentative Target Noise Level during the Operation Phase	
Table 2.4-10	Tentative Target Noise Level from Traffic	
Table 2.4-11	Tentative Target Vibration Level during the Construction/Closing Phase	
Table 2.4-12	Tentative Target Vibration Level during the Operation Phase	
Table 2.4-13	Tentative Target Vibration Level from Traffic	
Table 2.5-1	Community Health and Safety in IFC EHS Guidelines	
Table 2.6-1	Main Tasks for Environmental and Social Consideration in MJTD	
Table 2.7-1	Criteria for Necessity of IEE/EIA	
Table 2.7-2	List of Approved ECPP, EIA, and IEE in Thilawa SEZ (As of the end of April	
	2016)	.2-23
Table 2.7-3	Eight Responsible Investment in Thilawa SEZ stipulated in TSEZMC Notice	
	No.4/2015	.2-25
Table 2.7-4	Current Corporate Social Responsibility Activities by MJTD	
Table 3.2-1	Land Use Plan of Zone B	
Table 3.3-1	Result of Alternative Study	
Table 3.3-2	Study of Zero Option	
Table 3.4-1	Concept of Land Reclamation in the Industrial Area	
Table 3.5-1	Description of Road	
Table 3.6-1	^	3-10
Table 3.6-2	Design Criteria for Retention Ponds	
Table 3.7-1	Summary of Design Concept	
Table 3.7-2	Water Supply Plan in the Industrial Area	
Table 3.8-1		
Table 3.8-2		
	Design Criteria of Sewage System	
Table 3.9-1	Design Criteria of Sewage System	3-16
	Design Criteria of Sewage System	.3-16 .3-18
Table 3.12-1	Design Criteria of Sewage System Summary of Design Wastewater Quality Condition of Power Demand Forecast Implementation Schedule for First Phase	.3-16 .3-18
Table 3.12-1	Design Criteria of Sewage System	.3-16 .3-18 .3-22
Table 3.12-1 Table 4.1-1	Design Criteria of Sewage System Summary of Design Wastewater Quality Condition of Power Demand Forecast Implementation Schedule for First Phase Summary of Environmental Survey for Overall Conditions under the EIA Study of Class A	.3-16 .3-18 .3-22
Table 3.12-1 Table 4.1-1 Table 4.1-2	Design Criteria of Sewage System Summary of Design Wastewater Quality Condition of Power Demand Forecast Implementation Schedule for First Phase Summary of Environmental Survey for Overall Conditions under the EIA Study of Class A Results of Air Quality Survey in 2013 (TAN01)	.3-16 .3-18 .3-22 .4-1 .4-2
Table 3.12-1 Table 4.1-1 Table 4.1-2 Table 4.1-3	Design Criteria of Sewage System Summary of Design Wastewater Quality Condition of Power Demand Forecast Implementation Schedule for First Phase Summary of Environmental Survey for Overall Conditions under the EIA Study of Class A Results of Air Quality Survey in 2013 (TAN01) Results of Air Quality Survey in 2013 (TAN02)	.3-16 .3-18 .3-22 .4-1 .4-2 .4-2
Table 3.12-1 Table 4.1-1 Table 4.1-2 Table 4.1-3 Table 4.1-4	Design Criteria of Sewage System Summary of Design Wastewater Quality Condition of Power Demand Forecast Implementation Schedule for First Phase Summary of Environmental Survey for Overall Conditions under the EIA Study of Class A Results of Air Quality Survey in 2013 (TAN01) Results of Air Quality Survey in 2013 (TAN02) Results of Water Quality Survey at TW1 (April-August, 2013)	.3-16 .3-18 .3-22 .4-1 .4-2 .4-2
Table 3.12-1 Table 4.1-1 Table 4.1-2 Table 4.1-3 Table 4.1-4 Table 4.1-5	Design Criteria of Sewage System Summary of Design Wastewater Quality Condition of Power Demand Forecast Implementation Schedule for First Phase Summary of Environmental Survey for Overall Conditions under the EIA Study of Class A Results of Air Quality Survey in 2013 (TAN01) Results of Air Quality Survey in 2013 (TAN02) Results of Water Quality Survey at TW1 (April-August, 2013) Results of Water Quality Survey at TW2 (April-August, 2013)	.3-16 .3-18 .3-22 .4-1 .4-2 .4-2 .4-3
Table 3.9-1 Table 3.12-1 Table 4.1-1 Table 4.1-2 Table 4.1-3 Table 4.1-4 Table 4.1-5 Table 4.1-6 Table 4.1-7	Design Criteria of Sewage System Summary of Design Wastewater Quality Condition of Power Demand Forecast Implementation Schedule for First Phase Summary of Environmental Survey for Overall Conditions under the EIA Study of Class A Results of Air Quality Survey in 2013 (TAN01) Results of Air Quality Survey in 2013 (TAN02) Results of Water Quality Survey at TW1 (April-August, 2013)	.3-16 .3-18 .3-22 .4-1 .4-2 .4-2 .4-3 .4-3

Table 4.1-8 Table 4.2-1	Results of Noise Levels in April, 2013 (Dry Season)	4-6
1able 4.2-1		17
Table 4.2-2	Station in Yangon City (1981-2010)	
Table 4.2-2	Hydrological Data on the Yangon River	
Table 4.2-3	Geological Survey of the Region Located in and around the Yangon Area	
Table 4.3-1	Population of Thanlyin and Kyauktan Townships	
Table 4.3-2	Races in Thanlyin and Kyauktan Townships (2014)	
Table 4.3-3	Religion in Thanlyin and Kyauktan Townships (2014)	
Table 4.3-4	Land Use of Thanlyin and Kyauktan Townships (2012/2013)	
Table 4.3-5	Source of Drinking Water in Thanlyin and Kyauktan Townships	
Table 4.3-6	Source of Non-Drinking Water in Thanlyin and Kyauktan Townships	
Table 4.3-7	Existing Status of Local Livelihoods in Thanlyin and Kyauktan Townships (2014).	
Table 4.3-8	Existing Three Reservoirs in and around Thilawa SEZ	
Table 4.3-9	Utilization of Three Reservoirs in and around Thilawa SEZ (2003-2011)	
Table 4.3-10	Specification of Lagunbyin Reservoir.	
Table 4.3-11	Existing Final Disposal Site in Yangon City	
Table 4.3-12	Solid Waste Management in Thanlyin and Kyauktan Townships	
Table 4.3-13	Waste Management Facility in Zone A of Thilawa SEZ	
Table 4.3-14	Grid Substation near Thilawa Grid Substation	
Table 4.3-15	Conventional Households by Main Source of Lighting	
Table 4.3-16	List of Major Schools near Thilawa SEZ in Thanlyin Township	
Table 4.3-17	List of Major Schools near Thilawa SEZ in Kyauktan Township	.4-2/
Table 4.3-18	List of Major Medical Services near Thilawa SEZ in Thanlyin and Kyauktan	4.20
T 11 42 10	Townships	
Table 4.3-19	Morbidity and Mortality of Diseases and Accidents (2015)	
Table 4.3-20	Expanded Programme on Immunization (2015)	
Table 4.3-21	Health Impact Indicator	
Table 4.3-22	Other Parameters related to Public Health (2015)	
Table 4.3-23	Past Major Floods in Yangon Region (1997-2007)	
Table 4.3-24	Flood Experience of Residents.	
Table 4.3-25	Inundation Duration Report of Residents Who Experienced Flooding Only Once	
Table 4.4-1	Outline of PAHs/PAPs	
Table 4.4-2	Ethnicity and Religion of PAHs	
Table 4.4-3	Literacy of People	
Table 4.4-4	Major Income Source of Household Head	
Table 4.4-5	Vulnerable Households	.4-34
Table 4.5-1	Results of Monitoring of Thilawa SEZ Development Project (Zone A) during	1 2 1
T-1-1- 5 2 1	Construction	.4-34
Table 5.2-1	Results of Scoping for Environmental and Social Impact Assessment	
	(Pre-Construction/Construction Phase (PC/CO), Operation Phase (OP) and	<i>5</i> 1
Table 5 2 1	Closing Phase (CLP))	
Table 5.3-1	Field Survey Methodology	
Table 5.3-2	Basic Concept of Forecast and Evaluation Methodology	
Table 6.1-1	Location of Air Quality Survey Station	
Table 6.1-2	Sampling Duration for Air Quality Survey	
Table 6.1-3	Sampling and Analysis Method for Air Quality	
Table 6.1-4	Ambient Air Quality (Daily Average) at AQ-1	
Table 6.1-5	Ambient Air Quality (Daily Average) at AQ-2	
Table 6.1-6	Ambient Air Quality (Daily Average) at AQ-3	
Table 6.2-1	Parameters for Water Quality Survey	
Table 6.2-2	Sampling Points for Water Quality Survey	
Table 6.2-3	Survey Time for Water Quality	
Table 6.2-4	Field Equipment for Water Quality Survey.	
Table 6.2-5	Container and Preservation Method of Water Samples	0-13

Table 6.2-6	Survey Results of Surface Water Quality	6-13
Table 6.2-7	Survey Results of Groundwater Quality	
Table 6.3-1	Survey Parameters for Noise and Vibration Level	
Table 6.3-2	Location of Noise and Vibration Survey Point	
Table 6.3-3	Survey Period for Traffic Noise and Vibration Survey	
Table 6.3-4	Survey Period for Environmental Noise Survey	
Table 6.3-5	Methods for Noise and Vibration Measurement	
Table 6.3-6	Instrument for Measurement of Noise and Vibration Level	
Table 6.3-7	Equivalent Noise Levels (LAeq) Monitored along the Road	
Table 6.3-8	Equivalent Noise Levels (LAeq) in the Surrounding Environment	
Table 6.3-9	Vibration Levels (LV10) Monitored along the Road	
Table 6.4-1	Location of Traffic Volume Survey Points	
Table 6.4-2	Survey Period for Traffic Noise and Vibration Survey	
Table 6.4-3	Classification of Vehicles Types	
Table 6.4-4	Vehicle Traffic Volume Recorded at T-1 and T-2	
Table 6.5-1	Parameters for Soil Quality Survey	
Table 6.5-2	Sampling Points for Soil Quality Survey	
Table 6.5-3	Soil Quality Survey Results	
Table 6.6-1	Field Survey Periods for Flora and Fauna Survey	
Table 6.6-2	Instruments, Tools, and Materials Used for Fauna Survey	
Table 6.6-3	Identified Species of Flora and Fauna during the Survey Period	
Table 6.6-4	Threatened and Near Threatened Species Recorded during the Survey Period	
Table 6.7-1	Survey Items for Cultural Survey	
Table 6.7-2	List of Cultural Structures and Assets Within or Around Thilawa SEZ	
Table 7.1-1	Summary of the Environmental and Social Impacts of the Project (Industrial Area	
	of Zone B)	7-1
Table 7.2-1	Estimation of Commuters Using Vehicles from Thilawa SEZ	7-14
Table 7.2-2	Traffic Volume of Commuting and Returning to/from SEZ	7-14
Table 7.2-3	Estimation of Trip Generation from Commercial Area	7-15
Table 7.2-4	Traffic Volume of Commercial Area	7-15
Table 7.2-5	Amount of Freight Transportation from Thilawa SEZ Area	7-16
Table 7.2-6	Distribution Rate of Each Access Road to Thilawa SEZ	7-16
Table 7.2-7	Estimated Traffic Volume of Each Access Route	
Table 7.2-8	Traffic Volume at Forecast Point during Operation Phase	7-17
Table 7.2-9	Coefficient of Discharge for NOx	7-17
Table 7.2-10	Coefficient of Discharge for PM ₁₀	7-18
Table 7.2-11	NO ₂ Discharge Amount in Route 2 during Operation phase	7-19
Table 7.2-12	NO ₂ Discharge Amount in Route 3 during Operation phase	7-19
Table 7.2-13	Forecasted Results of NO ₂ Concentration	7-20
Table 7.2-14	PM ₁₀ Discharge Amount in Route 2 during Operation phase	7-21
Table 7.2-15	PM ₁₀ Discharge Amount in Route 3 during Operation phase	7-21
Table 7.2-16	Forecasted Results of PM ₁₀ Concentration	7-22
Table 7.3-1	Assumed Conditions of Shwe Pyauk Creek	7-27
Table 7.3-2	Results of Water Quality Forecast	
Table 7.4-1	Types of Business Not Allowed to locate in Thilawa SEZ	7-31
Table 7.4-2	Estimation of Maximum Generated Amount of Industrial Waste and Business	
	Related Waste	7-33
Table 7.4-3	Estimation of Yearly and Cumulative Generated Amount of Industrial Waste and	
	Business Related Waste in Zone A and Zone B in Thilawa SEZ	7-34
Table 7.6-1	Condition for Construction Noise Forecast	7-41
Table 7.6-2	Condition for Construction Vibration Forecast	
Table 7.6-3	Condition for Noise Forecast from Tenant Industry during Operation Phase	7-42
Table 7.6-4	Condition for Noise Forecast from Tenant Industry during Operation Phase	
Table 7.6-5	Traffic Volumes at Forecast Points during Operation Phase	
Table 7.6-6	Road Conditions at Forecast Points	7-43

Table 7.6-7	Forecast Results of Construction Noise	
Table 7.6-8	Forecast Results of Construction Vibration.	
Table 7.6-9	Forecast Results of Noise from Tenant Industry during Operation Phase	
Table 7.6-10	Forecast Results of Vibration from Tenant Industrial during Operation Phase	
Table 7.6-11	Traffic Sound Level (Leq) for With and Without Project Case along the Road	
Table 7.6-12	Traffic Vibration Level (L10) for With and Without Project Case along the Road	
Table 7.9-1	Change of Land Use Before/After Development of Zone B	
Table 7.12-1	Summary of Contents of Assistance by Myanmar Government	
Table 7.12-2	Summary of Assistance for Vulnerable Households by TSMC	
Table 7.12-3	Summary of IRP Components by TSMC	
Table 7.13-1	Number of Affected Households	
Table 7.15-1	Number of Vulnerable Households to be Affected by the Project	
Table 7.18-1	Current Activities of Students Support Program by the Project Proponent	
Table 7.20-1	Water Supply Plan in the Project Area	
Table 7.21-1	Common Assets Located in the Surrounding Area of the Industrial Area	
Table 7.23-1	Expected Mitigation Measures for Communicable and Vector-Borne Disease	7-85
Table 7.24-1	Expected Mitigation Measures for Occupational Health and Safety (During Construction/ Closing Phase)	7-87
Table 7.24-2	Expected Mitigation Measures for Occupational Health and Safety (Operation	/-0/
1401C 7.24-2	Phase)	7-88
Table 7.25-1	Expected Mitigation Measures for Public Safety and Security	
Table 7.27-1	Expected Contents for Emergency Preparedness and Response Plan	
Table 8.1-1	Brief Description of the Projects that should be assessed the cumulative impacts	
Table 8.1-2	Environmental Items of Cumulative Impact Assessment	
Table 9.1-1	Mitigation and Consideration Measures in the Termination Phase	
Table 9.1-2	Mitigation and Consideration Measures after the Termination Phase	
Table 10.1-1	Environmental Mitigation and Management Plan (Pre-construction Phase)	
Table 10.1-2	Environmental Mitigation and Management Plan (Construction/Closing Phase)	
Table 10.1-3	Environmental Mitigation and Management Plan (Operation Phase)	
Table 10.2-1	Monitoring Plan (Pre-construction Phase)	
Table 10.2-2	Monitoring Plan (Construction Phase)	
Table 10.2-3	Monitoring Plan (Operation Phase)	
Table 10.3-1	Cost for Main Mitigation Measures (as of May 2016)	
Table 10.3-2	Estimated Annual Costs for Monitoring in the Construction and Operation Phases .	
Table 10.5-1	Main Tasks for Environmental and Social Consideration in MJTD	
Table 11.1-1	Stakeholder Engagement Plan	
Table 11.2-1	Summary of Public Consultation Meeting for EIA at the Scoping Stage	
Table 11.2-2	Main Questions and Responses at the First Session of PCM at the Scoping Stage	
Table 11.2-3	Main Questions and Responses at the Second Session of PCM at the Scoping	
	Stage	11-6
Table 11.2-4	Major Comments from Feedback Forms and Responses	
Table 11.2-5	Summary of Public Disclosure for EIA at the Scoping Stage	
Table 11.2-6	Brief Summary of Public Comments and Responses	
Table 11.3-1	Summary of Public Consultation Meeting for EIA at the Draft EIA Stage	
Table 11.3-2	Main Questions and Responses at the First Session of PCM at the Draft EIA	
	Stage	11-14
Table 11.3-3	Main Questions and Responses at the Second Session of PCM at the Draft EIA	
	Stage	
Table 11.3-4	Major Comments from Feedback Forms and Responses	
Table 11.3-5	Summary of Public Disclosure for Draft EIA Stage	
Table 11.3-6	Brief Summary of Public Comments and Responses	
Table 11.3-7	Summary of Follow-up Meetings	
Table 11.3-8	Summary of Comment and Correspondence in Follow-up Meeting	
Table 11.4-1	Provisional Commencing Time of Resettlement Works for the Industrial Area	
Table 11.4-2	Summary of 1st Consultation Meeting for Area 2-1	11-22

Table 11.4-3	Summary of 2nd Consultation Meeting for Area 2-1	11-23
Table 11.4-4	Public Consultation Meetings for the RWP (Planned)	11-24
Table 11.4-5	Draft RWP Disclosure Places	11-25
Table 11.4-6	Public Disclosure for the RWP (Planned)	11-25
Table 12.1-1	Correspondence to the Terms and Conditions from TSMC (Scoping Report)	12-1
Table 12.2-1	Correspondence to the Comments from TSMC (OSSC) (Draft EIA Report)	12-2

LIST OF FIGURES

Figure 2.6-1	Organizational Structure of MJTD	2-19
Figure 2.6-2	Implementation Structure of Resettlement Works in Thilawa SEZ	2-20
Figure 2.7-1	Procedure for EIA Appraisal for Zone Development	2-21
Figure 2.7-2	Overall Procedures for Environmental Management in Thilawa SEZ	
Figure 2.7-3	Proposed Organizational Structure for Environmental Management of the Project	
	during the Pre-construction and Construction Phases	2-26
Figure 2.7-4	Proposed Organizational Structure for Environmental Management of the Project	
	during the Operation Phase	2-27
Figure 3.1-1	Location of Thilawa SEZ	
Figure 3.2-1	Land Use Plan of Zone B	3-3
Figure 3.5-1	Road Plan in the Industrial Area (Zone B)	3-7
Figure 3.5-2	Typical Section of Main Road	3-8
Figure 3.5-3	Typical Section of Sub-road	3-9
Figure 3.6-1	Drainage Plan in the Industrial Area (Zone B)	3-10
Figure 3.7-1	Location of Water Source for Thilawa SEZ	3-12
Figure 3.7-2	Location of Water Source for Thilawa SEZ	3-13
Figure 3.7-3	Water Supply Plan in the Industrial Area (Zone B)	3-14
Figure 3.8-1	General Plan of Sewage System in the Industrial Area (Zone B)	
Figure 3.8-2	Wastewater Treatment Process in Zone B Industrial Area	
Figure 3.8-3	Diagram of Conventional Activated Sludge Process	3-17
Figure 3.9-1	Power Supply System in Thilawa SEZ	3-18
Figure 3.9-2	General Plan of 33 kV Distribution System in the Industrial Area (Zone B)	3-19
Figure 3.10-1	Expected Process of Solid Waste Management in Zone B Industrial Area	3-20
Figure 3.11-1	Greening Plan in the Industrial Area (Zone B)	3-21
Figure 3.11-2	State of Green Space of Zone A Industrial Area	3-21
	Location of Environmental Survey for Overall Conditions under the EIA Study of	
	Class A	4-2
Figure 4.1-2	Location of Yangon River Water Sampling	
Figure 4.2-1	Climograph of Kaba-aye Station in Yangon City (1981-2010)	4-7
Figure 4.2-2	Location of Rivers and Elephant Point	4-8
Figure 4.2-3	Surface Water in and around Thilawa SEZ	
Figure 4.2-4	Physiographic Features in the Yangon Area	4-10
Figure 4.2-5	Geological Map in and around the Yangon Area	
Figure 4.2-6	Soil Map of Yangon Area	4-12
Figure 4.2-7	Location of Ban Bwe Gon Dam (Reserved Forest)	4-13
Figure 4.2-8	Photo of Ban Bwe Gon Dam (Reserved Forest)	4-14
Figure 4.3-1	Distribution of Tube and Dug Wells in Thanlyin and Kyauktan Townships	4-16
•	Present Conditions of the Main Roads to Thilawa SEZ	4-18
Figure 4.3-3	Location of Lagunbyin Reservoir	
Figure 4.3-4	Flow of Solid Waste Management in Yangon City	
Figure 4.3-5	Location of the Existing Disposal Sites in Yangon City	4-22
Figure 4.3-6	Location of the Existing Disposal Sites in Thanlyin and Kyauktan Townships	4-23
Figure 4.3-7	West Dumping Condition in Thanlyin and Kyauktan Townships	4-23
Figure 4.3-8	Perspective Image (Upper: Starting Operation, Lower: Completion of Operation)	
Figure 4.3-9	Location of Major Schools near Thilawa SEZ in Thanlyin Township	4-26
	Location of Major Schools near Thilawa SEZ in Kyauktan Township	
Figure 4.3-11	Location of Major Medical Services near Thilawa SEZ in Thanlyin and Kyauktan	
	Townships	4-28
Figure 4.3-12	Major National Program for Prevention of Infectious Disease	
Figure 4.5-1		
Figure 5 3-1	Field Survey Spots for Air, Water, Soil, Noise/Vibration, and Traffic Volume	5-6

0	Field Survey Area (Flora and Fauna)	
Figure 6.1-1	Location of Air Quality Survey Station	6-1
Figure 6.1-2	Air Quality Survey at AQ-1	6-2
Figure 6.1-3	Air Quality Survey at AQ-2	6-3
Figure 6.1-4	Air Quality Survey at AQ-3	6-3
Figure 6.2-1	Location of Water Quality Sampling Points	6-8
Figure 6.2-2	Surface Water Sampling at SW-1	6-9
Figure 6.2-3	Surface Water Sampling at SW-2	6-9
Figure 6.2-4	Surface Water Sampling at SW-3	6-10
Figure 6.2-5	Surface Water Sampling at SW-4	6-10
Figure 6.2-6	Surface Water Sampling at SW-5	6-11
Figure 6.2-7	Groundwater Sampling at GW-1	6-11
Figure 6.2-8	Groundwater Sampling at GW-2	6-12
Figure 6.3-1	Location of Environmental Noise Survey Points	
Figure 6.3-2	Location of Noise and Vibration Survey Point at NV-1	
Figure 6.3-3	Location of Noise and Vibration Survey Point at NV-2	
Figure 6.3-4	Environmental Noise Survey at N-3	6-17
Figure 6.3-5	Environmental Noise Survey at N-4	6-18
Figure 6.3-6	Environmental Noise Survey at N-5	6-18
Figure 6.4-1	Transportation Network and Traffic Volume Survey Points	
Figure 6.5-1	Location of Soil Quality Survey Points	
Figure 6.5-2	Soil Quality Survey at SO-1	
Figure 6.5-3	Soil Quality Survey at SO-2	
Figure 6.5-4	Soil Quality Survey at SO-3	
Figure 6.5-5	Soil Quality Survey at SO-4	
Figure 6.6-1	Survey Area for Flora and Fauna	
Figure 6.6-2	Layout Design of the Belt Transect	
Figure 6.6-3	Instruments and Tools Used for Fauna Survey	
Figure 6.6-4	Interview Survey with Local People	
Figure 6.6-5	Vegetation Map of Thilawa SEZ Zone B Area	
Figure 6.6-6	Scenery of the Survey Area	
Figure 6.6-7	Butterfly Species Recorded in Thilawa SEZ Zone B	
Figure 6.6 8	Some Bird Species Found in the Survey Area	6-35
Figure 6.7-1	Location of Cultural Structures/Assets In/Around Thilawa SEZ Area	6-38
Figure 6.8-1	Field Survey Area for Hydrology	
Figure 6.8-2	1-m Interval Contour Map with Water Flow Direction	6-43
Figure 7.2-1	Forecast Points for Air Pollution along the Road	
Figure 7.2-2	Transport Route from/to Thilawa SEZ and Forecast Points	
Figure 7.2-3	Steps of NO ₂ Concentration Calculation	
Figure 7.2-4	Steps of PM ₁₀ Concentration Calculation	
Figure 7.3-1	Location of Project Area and Creek	
Figure 7.3-2	Forecast Inflow Model into Shwe Pyauk Creek	
Figure 7.4-1	Process Flow of Solid Waste Management	
Figure 7.4-2	Cross Section of Landfill and Structure of Final Cover	
Figure 7.4-3	Examples of Eco-friendly Facilities after Completion of Closure of Landfill	
Figure 7.4-4	Yearly Cumulative Amount of Industrial Waste and Business Related Waste in	
C	Zone A and Zone B in Thilawa SEZ	7-35
Figure 7.11-1	Plan of Flood Spillway from Retention Pond	
-	Overall Framework of Assistance Package	
	Existing Community Road near the Project Area	
-	Situation of water Usage in and around the Project Area	
-	Location of the Projects that should be assessed Cumulative Impacts	
	Proposed Organizational Structure for Environmental Management of the Project	
<u> </u>	during the Operation Phase	
Figure 11.2-1	Pictures of Notice Displayed (PCM at the Scoping Stage)	

Figure 11.2-2	Pictures of PCM at Scoping Stage (First Session)	.11-6
	Pictures of PCM at the Scoping Stage (Second Session)	
Figure 11.2-4	Pictures of PCM at the Scoping Stage (Third Session)	. 11-7
Figure 11.2-5	Pictures of the Announcement Letter and the Draft Scoping Report Distributed at	
-	the Village Tract Office	.11-10
Figure 11.3-1	Pictures of Notice Displayed (PCM at the Draft EIA Stage)	.11-13
Figure 11.3-2	Pictures of PCM at Draft EIA Stage (First Session)	.11-15
Figure 11.3-3	Pictures of PCM at Draft EIA Stage (Second Session)	.11-16
Figure 11.3-4	Pictures of PCM at Draft EIA Stage (Third Session)	.11-16
Figure 11.3-5	Pictures of 2nd Follow-up Meeting	.11-20
Figure 11.4-1	Provisionally Divided Area for Resettlement Works of the 2,000 ha Development	
-	Area	.11-21
Figure 11.4-2	PCM on 14 February 2016	.11-23
Figure 11.4-3	PCM on 27 March 2016	.11-24

LIST OF ABBREVIATIONS

ADB Asian Development Bank

AIDS Acquired Immune Deficiency Syndrome

CLP Closing Phase
CO Construction Phase

CSR Corporate Social Responsibility
DMS Detailed Measurement Survey

ECD Environmental Conservation Department, MOECAF

ECL Environmental Conservation Law
ECRs Environmental Conservation Rules
EHS Environmental Health, and Safety
EIA Environmental Impact Assessment
EMP Environmental Management Plan

F/S Feasibility Study FDS Final Disposal Site GHG Greenhouse Gas

HIV Human Immunodeficiency Virus
IEE Initial Environmental Examination
IFC International Finance Corporation
IR-A Internal Regulations of Zone A
IRP Income Restoration Program

IRPISC Income Restoration Program Implementation Sub-Committee

JCM Joint Crediting Mechanism

IUCN International Union for Conservation of Nature and Natural Resource

JICA Japan International Cooperation Agency
MITT Myanmar International Terminals Thilawa
MJTD Myanmar Japan Thilawa Development Ltd.

MOECAF Ministry of Environmental Conservation and Forestry

MOI Ministry of Industry

MOC Memorandum of the Cooperation

MONREC Ministry of Natural Resources and Environmental Conservation

MMST MMS Thilawa Development Company

MTSH Myanmar Thilawa SEZ Holdings Public Limited
NEQG National Environmental Quality (Emission) Guidelines

NGO Non-Governmental Organization ODA Official Development Assistance

OP Operation Phase

OSSC One Stop Service Center

PAH Project-Affected Household

PAP Project-Affected People

PC Pre-Construction Phase

PCCD Pollution Control and Cleansing Department

PTS Pre-Treatment System

RIC Relocation Implementation Committee
RISC Relocation Implementation Sub-Committee

RWP Resettlement Work Plan
SEZ Special Economic Zone
STP Sewage Treatment Plant
TOR Terms of Reference

TPD Thilawa Property Development Ltd.

TSMC Thilawa Special Economic Zone Management Committee

U.S. Environmental Protection Agency

WB World Bank

WHO World Health Organization
WPP Water Purification Plant

YCDC Yangon City Development Committee

YRG Yangon Regional Government

EXECUTIVE SUMMARY

1. Project Proponent

- 1) Project Proponent: Myanmar Japan Thilawa Development Limited (MJTD)
- 2) Address: Corner of Thilawa Development Road and Dagon-Thilawa Road, Thilawa Special Economic Zone (SEZ), Thanlyin Township, Myanmar

2. Purpose of the Study

This Study is to assess the environmental and social impacts caused by the industrial area development project in Thilawa SEZ (approximately 262 ha) (hereinafter referred to as "the Project") operated by MJTD and consider the Environmental Management Plan (EMP) including mitigation measures to reduce and minimize the negative impacts caused by the Project.

3. Type of Project and Initial Environmental Examiniation/ Environmental Impact Assessment (IEE/EIA) Requirement

- 1) Type of Project: Construction and Development of Industrial Zone
- 2) IEE/EIA Requirement: EIA is required in accordance with the Environmental Impact Assessment Procedure (No.616/2015).

4. Implementation Organizations for EIA Study

The organizations in-charge of the implementation of EIA study are presented in Table 1.

Table 1: Organizations In-charge of EIA Study

	Organization	Responsibility
International	Nippon Koei Co., Ltd., Tokyo, Japan (NK)	Overall management and
Lead Consultant		technical aspect of EIA
Local Consultant	Myanmar Koei International Co., Ltd.	Field survey
	(MKI)	
	Resource and Environment Myanmar Ltd.	Field survey and
	(REM)	public consultation meeting

Source: EIA Study Team

5. Implementation Schedule of EIA Study

The Environmental Impact Assessment Procedure (No.616/2015) (hereinafter referred to as "EIA Procedure"), which was issued by the Ministry of Environmental Conservation and Forestry (MOECAF) (predecessor of Ministry of Natural Resources and Environmental Conservation (MONREC)) on 29 December 2015 defines the detailed legal process regarding EIA procedures including preparation of EIA/IEE report, environmental management plan (EMP), public involvement, approval of EIA/IEE report by MOECAF, and monitoring process in accordance with the EIA report. In this EIA Procedure, "Industrial Zone Construction and Development (all sizes)" projects are requested to conduct full EIA study. Therefore, the project proponent has conducted EIA based on the EIA Procedure.

On the other hand, Presidential Decree No.49/2015 was enacted and this defines the transfer of power related to administrative procedures in SEZ. According to Thilawa SEZ Management Committee (TSMC), TSMC started to develop a procedure related to environmental management for investors as well as zone development in Thilawa SEZ based on the Decree from October 2015. In February 2016, TSMC finalized a procedure of appraisal of EIA for zone development and issued the approval letters of the scoping reports submitted by the project proponent to it on 26th February 2016.

For the appraisal of the EIA study for Zone B development, a mobile review team, which is composed of staff from Environmental Conservation Department (ECD) of Ministry of Natural Resources and Environmental Conservation, Ministry of Industry, Ministry of Health, and Ministry of Labor, Immigration and Population, was established in January 2016 to review the draft EIA report. To review the draft EIA report submitted by the project proponent on 22 March 2016, EIA Review Committee was held on 5 and 6 May 2016 and TSMC released comments on the draft EIA Report on 17 May 2016. The project proponent has revised and finalized the EIA Report by reflecting the comments and is going to submit it to TSMC for approval.

EIA schedule of the Project is shown in Table 2.

Table 2: EIA Schedule of the Project (as of May 2016)

		2015				2016		
Item	September /October	November	December	January	February	March	April	May
1. Examination of the Project Plan								
2. Scoping								
Preparation of the Draft Scoping Report								
Public Consultation Meeting (PCM)			A					
Public Disclosure (PD)								
Submission of the Final Scoping Report					A			
Approval of Final Scoping Report by TSMC					A			
3. Field Survey								
Field Survey during the Rainy Season								
Field Survey during the Dry Season								
4. EIA								
Preparation of the Draft EIA Report								
Submission of the Draft EIA						A		
Public Consultation Meeting (PCM)							A	
Public Disclosure (PD)								
EIA Review Committee								A
Comments Letter of Draft EIA Report								A
Submission of the Final EIA Report								A

Source: EIA Study Team

6. Background of the Project

The Myanmar government has placed high priority on foreign direct investment as a key factor for the development of the nation. In particular, the government expects the Thilawa Special Economic Zone (SEZ), located in the outskirts of Yangon, to play an important role in economic development. Under this circumstance, the Myanmar government and the Japanese government signed a Memorandum of the Cooperation (MOC) for the development of Thilawa SEZ in December 2012.

In January 2014, the Myanmar Japan Thilawa Development Limited (MJTD) was established as a joint venture among MMS Thilawa Development Company (MMST), Thilawa SEZ Management Committee (TSMC), and Myanmar Thilawa SEZ Holdings Public Limited (MTSH) to do business as operator and developer of the Thilawa SEZ Zone A, which is an early development area that covers 396 ha of the Thilawa SEZ¹.

The construction of Zone A started in January 2014 after the completion of the feasibility study (F/S) and approval of the environmental impact assessment (EIA) report by TSMC. Its operation started in August 2015. In addition, MJTD has started to plan the development of another 700 ha in Thilawa SEZ together with MTSH as "Zone B", which includes about 262 ha of industrial area, 267 ha of logistic area, and 169 ha of residence and commercial areas.

In response to this, the EIA study has started in parallel to evaluate the environmental and social impacts caused by the development of Zone B, and consider the mitigation measures and environmental management plan. Since these three areas have different project proponents, the EIA process is going to be done separately by each project proponent. This scoping report is targeted for the industrial area development project (approximately 262 ha) whose project proponent is MJTD².

7. **Project Descrition**

7.1 Location

The Thilawa SEZ is located in Southern District, Yangon Region and about 23 km southeast of Yangon City as shown in Figure 1.

Japan International Cooperation Agency (JICA) participated in this joint venture later.

² Other development areas of Zone B, namely, the logistic area and residence and commercial areas, will be developed, operated, and managed by the Thilawa Property Development Ltd. (TPD) that was established jointly by MTSH and TSMC.




Figure 1: Location of Thilawa SEZ (Zone A and Zone B)

7.2 Land Use Plan of Zone B


Land use plan of Zone B is shown in Figure 2. Zone B will be developed by dividing the three areas, namely, industrial area, logistic dependent industrial area, and residence and commercial areas. The project proponent of each area is shown in Table 3.

Table 3: Land Use Plan of Zone B

Land Use	Area (ha)	Project Proponent
Industrial Area	Approx. 262	MJTD
Logistic Area	Approx.267	TPD
Residence and Commercial Area	Approx.169	TPD
Total	Approx.700	

Note: Above figures may be changed in the later stage.

Source: EIA Study Team prepared on the basis of the information from the Project Proponent



Source: EIA Study Team prepared on the basis of the information from the project proponent

Figure 2: Land Use Plan of Zone B

7.3 Alternative Study

In order to consider the project area and the shape of the industrial area of Zone B, two alternatives were compared comprehensively from the viewpoint of technical aspect, economical aspect, safety, and social and environmental consideration. As a result of the alternative study shown in Table 4,

Alternative A was selected as the priority option because it has advantages from the viewpoint of technical aspect, economical aspect, safety, and environmental/social consideration as follows:

- Technical aspect: higher ground elevation
- Economic aspect: less construction cost
- Safety: less traffic volume during construction
- Environment/social consideration: less scale disruption of nature and less number of project-affected households (PAHs)

Table 4: Result of Alternative Study

476 (1	Table 4. Result of Afterna	
Alternative	Alternative A	Alternative B
	Project site is adjacent to the SEZ outer road in the	Project site is adjacent to the SEZ outer road in the
General	east.	north and west, and links to the Zone A area.
	Development area is about 270 ha.	Development area is abWout 200 ha.
	There is no creek in the Alternative A area.	Existing creek is located in the Alternative B area.
Project Plan	Thanly in Journship Tangly in Journship Thanly in	Tanlyin Jownship The second s
	Since ground elevation is higher than in	Ground elevation is not high on average in this
	Alternative B on the average, land reclamation	area and earth filling work is necessary to satisfy
	work is simpler than in Alternative B.	the elevation level of +5.0 m.
Technical		The area includes a small creek running into the
Aspect		Yangon River. Therefore, it is needed to adjust
		the creek and install a drainage system in order
		to run the water from the development area into
		the creek.
	Since earthwork volume is smaller than in	Since earthwork volume is larger than in
	Alternative B, construction cost is estimated to	Alternative A, construction cost is estimated to
	be less and construction period is estimated to be	be higher and construction period is estimated to
Economic	shorter than in Alternative B.	be longer than in Alternative A.
Aspect	• Since the number of PAHs will be less than in	Since the number of PAHs will be more than in
	Alternative B as stated in the	Alternative A as stated in the environment/social
	environmental/social consideration below, the	consideration below, the compensation for
	compensation for resettlement will be reduced.	resettlement will be increased.

Alternative	Alternative A	Alternative B	
Safety	 As transportation of soil for land reclamation is basically done inside the project site, the risk of traffic accident occurring outside of the project site is not increased. 	 Since it is necessary to transport the soil for land reclamation from outside of the project site, the risk of traffic accident is increased. Possibility of flood risk might be increased in the upper course of the creek due to heavy rain and/or inappropriate maintenance of drainage system. 	
Environment /Social Consideration	 Since the traffic volumes resulting from the earthwork transportation during the construction phase are estimated to be smaller than in Alternative B, exhaust gas from the vehicular traffic will be less than in Alternative B. According to the project description, the modification in the creek is not expected. Therefore, the negative impact on natural environment is forecasted as less than Alternative B. Around 100- 150 households might be resettled in the Alternative A area, which is about 150-200 less than in Alternative B. Therefore, the social impact will be lesser than that of Alternative B. 	 Since the traffic volumes resulting from the earthwork transportation during the construction phase are estimated to be larger than in Alternative A, exhaust gas from the vehicle traffic will be more than in Alternative A. According to the project description, the modification in the creek is expected. Therefore, the negative impact on natural environment, Flora/Fauna and Ecosystem is expected. Around 300 households might be resettled in Alternative B area, which is about 150-200 more than in Alternative A. Therefore, the social impact will be greater than that of Alternative A. 	
Evaluation	• Compared with Alternative B, Alternative A has advantages from the viewpoint of technical aspect, economical aspect, safety aspect, and environmental/social consideration. Therefore, Alternative A is chosen as the preferred option.		

Source: EIA Study Team prepared on the basis of the information from the project proponent

7.4 Infrastructure Development Plan

Table 5 shows the infrastructure development plan of the industrial area.


Table 5: Infrastructure Development Plan of the Industrial Area

	Plan/ Contents
Land Reclamation	Elevation level: +5.5-7.0 m
Plan	To set the design elevation of land, the following three simulation results/conditions were taken
	into consideration for prevention of flood.
	Case 1) Storm surge simulation in Yangon River (In the case of a simulation result of assumed strongest cyclone in the future taking into consideration of climate change): E.L: 5.2 m,
	Case 2) Flood analysis (100 years return rainfall): E.L: 4.9 m, and
	Case 3) The highest water level at Myanmar International Thilawa Terminal (MITT) in the past: E.I.: 4.24 m.
	On the bases of the above information, the Project proponent sets E.L 5.5m as the target
	elevation of land of Industrial Area by adding to 0.3 m as allowance height for safety from the
	Case 1.
Road System	Main road 1 is planned in order to connect the main gate to the main points in the industrial area;
•	Main roads have retention canal in the center in order to control rain water and buffer zone at
	both sides. Sub-road is planned as access road for small-scale plots and mid-scale plots from the
	main road. (See Figures 3 and 4)
Drainage System	Drainage water will run through the drainage ditch and retention pond and will be discharged to
	Shwe Pyauk Creek that connects to the Yangon River. Discharged water volume outside of the
	industrial area is controlled at the retention pond. (See Figure 5)
Water Supply	Water demand is forecasted at 20,960m ³ /day in the project area.
System	[Before around 2019 ¹] Distribute water to each tenant from water purification plant (WPP) in
	Zone A by pumping from Zamami Reservoir
	[After around 2019] In addition, Connect to the public water supply pipe from Lagunbyin
	Reservoir and distribute water to each tenant
Sewage System	In the initial stage of the industrial area development, wastewater which was estimated to be few
	will be transferred to the sewage treatment plant (STP) in Zone A and will then be treated. In the
	Stage-2, STP in Zone A area will be extended the capacity. In the final stage, waste water
	generated in the industrial area will be treated in the central STP which will be newly established

	Plan/ Contents
	in Zone B. All of the industrial and domestic wastewater will be treated at the central STP. Before the central STP, each tenant shall install its own pre-treatment system (PTS) if the wastewater quality does not meet the influent wastewater quality.
Power Supply Plan	Necessary capacity of the facility (transformer) for Zone B is estimated at 105 MVA (262 ha x 0.8 (ratio of plot) x 0.5 MVA/ha). Power will be supplied from Thanlyin Substation to Thilawa Substation by a 230 kV transmission line. At the Thilawa Substation, power voltage is transformed from 230 kV to 33 k, and 33 kV will be distributed to Zone B.
Solid Waste Management	Industrial waste generated from the industrial area will be re-used or recycled as much as possible by collecting the waste separately. The waste which cannot be re-used or recycled may be managed by the waste treatment firm in Zone A or through public service such as by the Pollution Control and Cleansing Department of the Yangon City Development Committee (YCDC).
Greening Plan	Different kinds of trees will be located on the sidewalk and retention canal along the main road. Bushes will be located on the sidewalk along the sub-road. Surface of the sidewalk sodding along the main road and sub-road will be covered by 8 m of sodding. In addition, sodding will be spread on the surface of slopes along the project boundary fence.


Note 1: It depends on when the installation work of public water supply pipe is completed.


Source: EIA Study Team prepared on the basis of the information from the project proponent



 $Source: EIA\ Study\ Team\ prepared\ on\ the\ basis\ of\ the\ information\ from\ the\ project\ proponent$

Figure 3: Road Plan in the Industrial Area (Zone B)









Figure 4: Typical Road Section of Main Road



Source: EIA Study Team prepared on the basis of the information from the project proponent

Figure 5: Drainage Plan in the Industrial Area

8. Baseline Study

The current environmental and social conditions in and around the project area are shown in Table 6. Field survey of air quality, water quality, soil quality, noise and vibration, traffic volume, flora and fauna, cultural assets, and hydrology (topography) were conducted in and around the Project site. The other information on natural and social environment was collected through the literature survey and/or reconnaissance survey.

Table 6: Current Environmental and Social Conditions in/around the Project Area

	Item	Description			
I. I	I. Living Environment (Pollution Status)				
1)	Air Quality	The monitoring survey of CO, NO ₂ , NO, SO ₂ , PM _{2.5} , and PM ₁₀ for the ambient air quality was conducted in the Project site for continuous seven days in each of the rainy and dry seasons. Along the road, SO ₂ measured for seven days during the rainy season and SO ₂ , PM _{2.5} and PM ₁₀ measured for seven days during the dry season at one survey point exceeded the applied target value. At the other survey point, SO ₂ measured for one day during the rainy season and two days during the dry season, NO ₂ for one day during the rainy season, and PM ₁₀ for three days during the dry season exceeded the applied target value. On the other hand, SO ₂ measured for two days, NO ₂ for six days, PM _{2.5} and PM ₁₀ for one week exceeded the applied target area at one survey point in the paddy field.			
2)	Water Quality	The surface water sample and the groundwater sample were collected at five survey points of the creeks and at two survey points of the tube well, respectively, in Thilawa SEZ during both the rainy and the dry seasons. Most of the measured parameters of surface water complied with the applied target value in both the			

Item	Description									
	rainy and dry seasons at all water sampling sites, except for SS, COD, CN and oil and grease. On the other hand, most of the measured parameters of groundwater complied with the standards in both the rainy and dry seasons at all water sampling sites, except for COD, ammonium, nitrate, nitrate nitrogen, hardness, and manganese.									
3) Soil Quality	The surface soil survey in Zone B confirmed that the Project site was not originally contaminated by heavy metals as compared with the environmental standards in Vietnam and Thailand.									
4) Noise and Vibration Level	According to the results of the traffic noise and vibration survey conducted at two points along the road around Thilawa SEZ in the dry season, all measured noise level and vibration level were lower than the request limit in Japan. As for the environmental noise survey conducted at three points in and around Thilawa SEZ in the dry season, all of the noise levels except for one case were lower than the target level. Noise level recorded on Friday evening at one survey point was slightly higher than the target level.									
II. Natural Environment										
1) Flora, Fauna,	According to the field survey result, there are 158 flora species, 71 kinds of butterfly, 4 kinds of									
and Biodiversity	dragonfly, 67 kinds of bird, 7 kinds of mammals, 13 kinds of reptilian and amphibian species, and 22 kinds of fish in and around the Thilawa SEZ Zone B area. Among them, one vulnerable species (reptiles) and 5 Near Threaten Species (2 birds and 3 fishes) classified in accordance with the IUCN Red List of Threatened Species (2015-4 version 3.1) were found.									
2) Meteorology/ Temperature and Rainfall	Greater Yangon has a tropical monsoon climate characterized by altering rainy season (from May to October) and dry season (from November to April). According to the data observed in the Kaba-aye Meteorological Station from 1981 to 2010, the mean monthly temperature is highest in April at 30.7 °C and lowest in January at 25.0 °C. Except in December and January, the monthly temperatures are above 25.0 °C. The southwest monsoon wind is the main source of rain, and the Yangon area receives rain during the period from May to October. The average annual amount of rainfall is 2,787 mm. Rainfall sharply decreases from November and continues to be less than 10 mm from December to February.									
3) Hydrology/ Topography	The topography of Thilawa SEZ area is generally characterized as flat terrain with somewhat changes in elevation of the area from 3 m to 21 m. Higher areas in Thilawa SEZ is found in the middle and the east while low-elevation land is located in the west and south. Surface water flow in the main area of Thilawa SEZ mostly runs from east to west and the surface water									
	flow in the southern part of the SEZ runs from north to south. There are four creeks, running from east to west and discharging into the Yangon River, including Ah Lun Soke, Shwe Pyauk, and Bay Bauk (Pa Lan) creeks, and another creek. There are two creeks, flowing from north to south and discharging into Hmaw Wunn Chaung, including Gway and Kayat creeks. Surface water runoff in the adjacent areas of a creek flows in different directions such as east-west, north-south, and south-north, but directs to the creek. The watershed area of each creek has a span of less than 2 km, implying 1 km of length in each side from the creek.									
4) Geographical Features	Regional geomorphic features of the entire area includes ridges and deltaic lands lying in the south of the Pegu Yoma between the Sittaung River in the east and the Irrawaddy River in the west. This area is in a north-south trending sedimentary basin containing thick sedimentary deposits from the Tertiary to Quaternary periods.									
5) Soil Erosion	The main types of soil are Ferrosols, Gleysols, Solovechaks, and Arenesols. Ferrosols (plinthic) or lateritic soils are found on low hills along Thanlyin-Kyauktan. About 90% of these soils are composed of silt and clay, but humus content varies from place to place. These soils are favorable for paddy cultivation. The main problem, however, is poor drainage and water logged conditions. In the rainy season, they are covered with flood water. Because of the high content of clay, these soils become very dry and crack in the dry season. Solonchaks (gleyic) or saline swampy gluey soils are found along the coastal area. These soils develop from sediments transported and deposited on the estuaries of the Yangon River.									
III. Social Enviro										
1) Population	In 2015, there are about 268,000 in Thanlyin Township and 133,000 in Kyauktan Township. The percentage of urban population is about 32% in both townships.									
2) Ethnicity	Most of the people who live in Thanlyin and Kyauktan townships are Bamar, followed by Kayin, Rakhine, and Indian people. A small number of Pakistani and Bangladeshi live in Thanlyin Township.									
3) Religion	More than 90% of the people living in Thanlyin and Kyauktan townships are Buddhists. There are more Hindus and Muslims living in Kyauktan Township than in Thanlyin Township.									
4) Land Use	Thanlyin and Kyauktan townships mainly use its land as agricultural land followed by water area. In Thanlyin Township, settlement land covers 10.6% (3,936 ha), which is comparatively large. It is considered that Thanlyin Township is a kind of bed-town for laborers who go to Yangon to work.									
5) Water Source/ Usage	More than 60% of households in Thanlyin Township are using water for drinking and non-drinking purpose; for wells most of which are located outside of Thilawa SEZ followed by pool/pond/lake. On the other hand, about 70% of households are using water from pool/pond/lake in Kyauktan Township. There are three major water reservoirs in and around SEZ: Zarmani Reservoir, Bant Bwaykone Reservoir, and Thilawa Reservoir. Zarmani Reservoir and Bant Bwaykone Reservoir managed by the Ministry of Agriculture and Irrigation									

Item	Description
	(MOAI) mainly provide water to the agricultural field. On the other hand, Thilawa Reservoir belongs to the Ministry of Industry (MOI) and Ministry of Construction (MOC) and its water is supplied to nearby factories, irrigation, and port.
6) Local Economy and Livelihood	The main sources of livelihood in the two townships are agriculture, fishing, and official employment in the government. In Thanlyin Township, other sources of earning are livestock breeding, fish farming, casual labor, and betel leaf and coconut plantations as well as small-to-medium-size businesses. In Kyauktan Township, other livelihood activities include livestock breeding, fish farming, and betel leaf and coconut plantations. Most of the casual laborers are employed in the agricultural sector.
7) Access Road	Main access roads connected between Yangon City and Thilawa SEZ are as follows: the road that passes through Thanlyin Bridge and the other road that passes through Dagon Bridge. The peripheral road of Thilawa SEZ is paved with concrete while the road between Thanlyin Bridge and Thilawa SEZ is paved with asphalt. On the other hand, most of the roads connected into villages are still unpaved. Currently, the road expansion of connection road from Thanlyin Bridge to Thilawa SEZ has been planned supported by JICA (Infrastructure Development Project in Thilawa Area Phase 2 (Yen Credit)).
8) Waste Management	Solid wastes generated in wards of townships are collected by each township development groups. In Thanlyin Township, the Sanitary Department is in-charge of waste management and collects waste from all wards. On the other hand, the Sanitary Section of Administration Department is in charge of waste management in Kyauktan Township. Each of two townships has operated its own final disposal site as open dumping. In Zone A of Thilawa SEZ, a solid waste management company entered and has started its operation of management of industrial and business waste. The expected volume of waste is approximately 22,700 t/year, which is about 60% hazardous waste and 40% non-hazardous waste. In terms of waste weight for each treatment process, approximately, 6,100 t/year for sorting, 6,600 t/year for incineration, 4,100 t/year for fuel conversion, 2,700 t/year for landfilling, 2,600 t/year for stabilization, and tens of t/year for wastewater treatment are planned at this stage.
9) Electricity	Three substations, namely: Thanlyin Substation, Thaketa Substation, and Kamarnat Substation are located in the surrounding area of Thilawa SEZ. Among them, the Thanlyin Substation is the closest one from Thilawa SEZ, about 10 km to the north. Main source of lighting in Thanlyin and Kyauktan townships comes from electricity (47.7% and 33.1% of households) followed by battery (26.0% and 24.9%) in 2014.
10) Public Health	According to the Township Health Profile 2016 of Thanlyin and Kyauyktan townships, most immunization rates for the major diseases cover more than 90% and some exceeds 100% in both townships in 2015. Infant mortality rate/1,000 live birth is 7 and 5 in Thanlyin and Kyauyktan townships respectively in 2015.
11) Cultural Heritage/ Assets	There is no cultural heritage site designated by the United Nations Educational, Scientific and Cultural Organization (UNESCO) or the Myanmar government in Thilawa SEZ. There are two cemeteries, one is found in the industrial area of Zone B in Kyauktan Township and the other one is found in the logistic area of Zone B in Thanlyin Township. There is also a small Hindu temple found in the residence and commercial areas of Zone B in Thanlyin Township.
12) Landscape	No specific landscape located in the project was identified during the field visit in the region. The project site and its surrounding area is composed of flat plains and typical rural landscapes of urban neighborhood.
13) Emergency Risk Source: FIA Study	Flood, cyclone, and earthquake are identified as notable natural hazards around the project area.

Source: EIA Study Team

9. Summary of the Environmental and Social Impacts Assessments

Environmental and social impacts on Thilawa SEZ (Industrial Area of Zone B) Development Project are predicted and evaluated based on project description, results of baseline survey, and set target level. Table 7 shows the summary of assessments on the Project during pre-construction phase (PC), construction phase (CO), operation phase (OP), and closing phase (CLP). The impacts of pollution, natural environment and social environment, health and safety, emergency risk and others were classified as A to D in accordance with the following criteria, assuming no specific measures toward the impacts are taken:

A-: Significant negative impact

B-: Some negative impact

B+: Some positive impact

C: Impacts are not clear, need more investigation

D: No Impacts or impacts are negligible, no further study required

Table 7: Results of the Environmental and Social Impacts Assessments

~ .	Scoping Result Assessment Result		Result					
Category	Scoping Item	PC/ CO	OP	CLP	PC/ CO	OP	CLP	Reason for Assessment
Pollution	Air Quality	B-	B-	B-	B-	B-	B-	CO/CLP: Impact on air quality is expected to be limited because dust and emission gases from construction works will be within narrow area near the construction site. In addition, emission gas effect from construction vehicles travelling around the area will be little, comparatively limited vehicles are operating. OP: Impact on air quality is expected to be little, because roadside air quality is mitigated by commuter bus for workers. The tenants which may cause adverse impact to air condition by installing of combustion facilities be required to submit an EIA or IEE report with EMP including mitigation measures on air pollution to TSMC/OSSC. The proposed mitigation measures, such as energy use efficiency, process modification, selection of fuels or other materials, the processing of which may result in less polluting emission, application of emission control techniques, in necessary, in the EIA or IEE report shall be conducted by each tenant. Therefore, it is expected that the air pollution caused by the Thilawa SEZ Zone B operation would not cause any significant environmental impact
	Water Quality	В-	B-	В-	B-	B-	B-	on the surrounding area. CO/CLP: Impact on wastewater quality caused by construction/demolition work is expected to be limited because discharging muddy water from bare land of construction site will be temporary and wastewater from a construction camp will be treated by the septic tanks. OP: Impact on water quality is expected to be limited because water discharge from tenants will be treated at a treatment plant to comply with the industrial wastewater effluent guideline values stipulated by MOI and MOECAF and the proposed internal regulation. Basically, it is expected that concentration of wastewater is diluted by mixing with stormwater through the retention pond and creek flow. In case that large amount discharge which includes heavy metals and toxic substance is expected and especially low flow season, the project proponent would review the internal target value and set strict standard for pre-treatment, if necessary. Therefore, the impacts from wastewater to the surrounding environment would be less.
	Waste	B-	B-	B-	B-	B-	B-	CO/CLP: The impact of the construction waste is expected to be limited because construction waste will be utilized to embankment work and scrap material by removal of structure will also be utilized as recyclable materials as much as possible. The rest of the waste will be treated by outsourcing to the private waste treatment firm in Thilawa SEZ which has functions of recycling, intermediate treatment, and the controlled landfill site or other proper waste treatment facilities outside of Thilawa SEZ. OP: Impact of industrial and business-related waste generated from the Project in addition to logistic and commercial areas of Zone B and Zone A is expected to be limited because a solid waste management facilities in Zone A which has functions of recycling, intermediate treatment, and the controlled landfill site and enough capacity of receiving waste from all of the industrial waste and business-related waste in Zone A and Zone B.
Pollution	Soil Contamination	B-	В-	В-	D	В-	D	CO: In the construction phase, all excavated soil would be backfilled into the Thilawa SEZ Zone B area as embankment soil. Excavated soil would not cause any soil contamination inside the industrial area and the surrounding area because soil quality of the industrial area as well as the entire area of Thilawa Zone B was observed complying with the relevant environmental standards.

			ping Re	sult	Assessment Result		esult	
Category	Scoping Item	PC/ CO	OP	CLP	PC/ CO	OP	CLP	Reason for Assessment
	Noise and Vibration	В-	B-	B-	B-	B-	B-	OP: Industrial wastewater discharged by the tenants would be collected and treated properly in the central wastewater treatment plant. Domestic wastewater would be treated by septic tanks at each tenant, while the pollution from stormwater runoff would be controlled and minimized as much as possible. With reference to the process of usage, producing, storing, disposing and handling of oil, chemical, dangerous or hazardous materials in the project area, the tenants must strictly comply with applicable laws, regulations at its sole responsibility and expense. The tenants shall treat the materials safety on the covered area to prevent infiltration of the materials to ground, and eliminate or dispose of all dangerous or hazardous materials and waste including, but not limited to, industrial waste to prevent from distributing to the soil environment. Hazardous waste (if any), industrial waste, and domestic waste would be well controlled and managed by each tenant. Solid waste receptacles or trash containers must be large enough to facilitate storage and collection and be installed within the land of tenant. Therefore, soil contamination caused by the tenants is estimated to be limited. CLP: Demolition work in the Project site and domestic activities during the period would not be expected to cause any pollution to the soil environment. CO/CLP: Impacts of noise and vibration from construction machineries are expected to be limited because noise and vibration from construction vehicles is expected to be limited because the construction work are site specific and temporary events. Impact of noise and vibration from construction vehicles is expected to be limited because mitigation measures such as, sound—absorbing materials, installing the facility in the house, having the enough buffer zone for noise and installing vibration control devices for equipment, design of the structure to disconnect between the sources and ground for vibration, will be installed as necessary. In addition, the arrangement of the land alloca
	Ground Subsidence	D	D	D	D	D	D	CO: Groundwater will be used during the construction phase; however, no impact is expected because there is no change in ground elevation as monitored by Zone A Project and the same kind of construction work will be conducted in the industrial area of Zone B. OP/CLP: No activities are planned that will cause ground subsidence.
	Offensive Odor	D	B-	D	D	B-	D	CO/CLP: There is no factor to cause offensive odor OP: With reference to usage, producing of disposing and handling of dangerous or hazardous materials in the project area, the tenants must, at its sole responsibility and expense, shall treat safety manage, eliminate or dispose of all dangerous or hazardous materials and waste to prevent from distributing to the offensive odor. Stack emissions of odor generally can be controlled using waste reduction, waste minimization and cleaner production principles or conventional emission control equipment. Therefore, odor caused by tenants is estimated to be limited.
	Bottom Sediment	D	В-	D	D	В-	D	CO/CLP: No construction works are planned that will cause impact on bottom sediment. OP: Impact on bottom sediment is expected to be limited

			ping Re	sult		sment R	esult	
Category	Scoping Item	PC/ CO	OP	CLP	PC/ CO	OP	CLP	Reason for Assessment
								because water discharge from the tenants will be treated at the treatment plant to comply with the industrial wastewater effluent guideline value stipulated by MOI and MOECAF and the proposed internal regulation. Basically, it is expected that concentration of wastewater is diluted by mixing with stormwater through the retention pond and creek flow. In case that large amount discharge which includes heavy metals and toxic substance is expected and especially low flow season, the project proponent would review the internal target value and set strict standard for pre-treatment, if necessary.
Natural Environment	Protected Areas	D	D	D	D	D	D	Since no natural preservation area and national parks exist in and around Zone B, impact on the protected areas is not expected.
	Flora/Fauna and Ecosystem	C	C	C	B-	B-	B-	Based on the field survey, it was observed that biodiversity in the project area is not rich because of the fact that the area has been inhabited and cultivated by local people for a long time. In addition, the area, located near Yangon City, has been recently urbanized and strongly industrialized with the presence of industrial areas and deep terminals. The project area is not a special area in terms of biodiversity and ecosystem. Similar ecosystem and equivalent level of biodiversity would be found in nearby areas. There were 1 threatened species (1 reptile) and 5 near threatened species (2 birds and 3 fishes) recorded in the area. However, threatened species was interview information around 2008 and no information in recent years and this field survey. As for 2 birds, near threatened bird species are relatively common and observed in a wide area in Myanmar, though classified as NT by IUCN list. These bird species can easily move to other places, because they can find similar habitats such as near water, grassland, marshes, etc. in nearby areas. Clear marking of boundary of the project site to prevent the contractor from clearing the vegetation outside of the project site. Considering near threatened fish species, their habitats would remain unchanged as they can keep living in the existing creeks and lakes. Though clearing the vegetation due to the implementation of the project, greening of the public space along the main road, sub road and retention pond in the project area of Zone A and Zone B will help to mitigate the change of biodiversity and ecosystem. Therefore, the development of the project would not cause any significant impact on biodiversity and ecosystem of the region
	Hydrology Topography and	B-	B-	B-	B-	B-	B-	PC/CO: Impact on hydrology is expected to be limited because the excavation and embankment work would be designed to minimize the excavation volume and embankment volume as much as possible, so that the water flow would not change significantly. OP: Impact on hydrology is limited because stormwater flow to the river will be equalized through retention ponds and minimized making changes to the water current and riverbed. CO/CLP: Since there are no unique topography and
	Geology							geology in this area, no impact from construction is expected. OP: No activities are planned that will cause impact on topography and geology.
	Soil Erosion	B-	В-	В-	В-	В-	B-	CO/CLP: Soil erosion in the bare area/bank would occur as a result of rainwater. OP: Impact of erosion on the creek is limited because the storm water and wastewater from the project site will be controlled by the designed retention pond and retention canals.
Social Environment	Involuntary Resettlement	A-	A-	D	A-	A-	D	PC: Impact of Land Acquisition and Involuntary Resettlement Involuntary resettlement of 161 households is expected because the land acquisition of uncompensated land will be required partially for the implementation of the Project. However, the impact will be minimized by providing assistance for the loss of assets/income source and

G t	G . T		ping Re	sult		sment R	esult	D 6 A
Category	Scoping Item	PC/ CO	OP	CLP	PC/ CO	OP	CLP	Reason for Assessment
								livelihood/relocation in kind or with cash based on Resettlement Framework for 2,000 ha prepared by TSMC. In addition, the relocation of the households currently living in the proposed relocation site is anticipated because of the development of the relocation site. However, TSMC will organize an adequate consultation with the households in a timely manner and provide compensation/ assistance as necessary. OP: Impact on Livelihood of Relocated Households Among the 161 households to be affected by the Project, 141 households are required to relocate from their current living place to other place. Therefore, it is expected the impact on the livelihood of relocated household is expected due to the changes more or less in their situation. However, the impact will be mitigated due to the implementation of an Income Restoration Program (IRP) based on the Framework for 2,000 ha by TSMC.
	Living and Livelihood	A-/ B+	A-/ B+	C	A-/B-/ B+	A-/B- /B+	B-/B+	PC/ CO/ OP: Impact to PAHs by Land Reclamation (A-) Among the project affected households (PAHs), approx. 40% would lose their land-based income source and approx. 60% would lose their non land-based income source due to the resettlement through the land reclamation. However, the impact on PAHs will be minimized by providing assistance package based on the Resettlement Framework for 2,000 ha under the responsibility of TSMC. In addition, TSMC will provide IRP activities such as job matching and facilitation of job opportunity for some PAHs who would spend some time to restore their living after their resettlement. Furthermore, the project proponent will provide job opportunity and community support program as necessary together with TSMC in order to improve the situation on the living and livelihood in the community. CO/ OP/ CLP: Impact to Surrounding Community (B-) In construction and operation phase, unexpected impact on living and livelihood of the surrounding community would be arisen due to the construction work and the operation. In order to improve the situation on the living and livelihood, the project proponent will provide job opportunity and community support program targeting the surrounding community based on the request from the community. In closing phase, it is expected that some people who would lose their income source belonging to the Project due to the termination on the operation of tenants. Employment contract between tenants and workers is prepared under the supervision of OSSC labor section in order to secure the worker's labor right by confirming termination service. In case the termination service will be not preceded fairly, workers are able to request authorized labors officers of OSSC to settle and resolve the situation. In addition, the employment service will be provided with the cooperation and facilitation of Dept. of Labor for terminated worker's alternative livelihood. CO/ OP/ CLP: Impact on Improvement of Local Economy (B+) There will be the improvement of local econom
	Vulnerable Group	A-/ B+	A-/ B+	D	A-/B-/ B+	A-/B- /B+	D	the Project. PC/ CO/ OP: Impact to Vulnerable PAHs by Land Reclamation (A-) Among the PAHs, 36 households are defined as vulnerable people in the Project. In order to mitigate the impact, special attention will be given to them by providing additional assistance based on the Resettlement Framework for 2,000

			ping Re	sult	Asses	sment R	esult	
Category	Scoping Item	PC/ CO	OP	CLP	PC/ CO	OP	CLP	Reason for Assessment
								ha under the responsibility of TSMC since they are more easily affected by the Project than non-vulnerable people. In addition, TSMC will provide IRP activities such as job matching and facilitation of job opportunity for some PAHs who would spend some time to restore their living after their resettlement. Furthermore, the project proponent will provide special support targeting vulnerable people based on their request as necessary in order to mitigate the impact on their living and livelihood. CO/ OP: Impact to Surrounding community (B-) Unexpected impact on vulnerable group of the surrounding community would be arisen due to the construction work and the operation. In order to improve the situation on their living and livelihood, the project proponent will provide job opportunity and community support program based on the request from the community. CO/ OP: Impact on Improvement of Local Economy (B+) There will be the improvement of local economy due to the increase of job opportunity with the start of the construction/ demolished work and the operation by the Project
	Local Conflict of Interests	A-	A-	D	B-	B-	D	the Project. PC/CO/OP: Relocated PAHs and the host community in the relocation site In the proposed relocation site, sudden increase of the population is expected during the short period due to the relocation of PAHs. The host community will face more or less changes and inconvenience in various aspects of their life. Also, there would raise negative feeling to PAPs among host community. In response to the situation above, TSMC will consider planning the arrangement of necessary public facilities, and also will support to establishment the harmonization with host communities based on Resettlement Framework for 2000 ha to avoid the serious conflict. PAHs of Zone A and PAHs of the Project There is a possibility to occur complains regarding difference in compensation between PAHs of Zone A and the Project (Zone B). In this case, TSMC will provide enough explanation of the fairness in compensation in order to avoid serious conflict. Construction workers and local people It is expected to raise complain from local people against migrated construction workers because of worker's behavior such as disposing garbage and bad driving manner in community without any consideration etc. In this case, the construction contractor should provide necessary education and instruction to worker in order to avoid the conflict.
	Misdistribution of Benefit and Damage	В-	В-	D	В-	В-	D	PC/CO/OP: Impact of the assistance to be provided by TSMC Under the Project, the assistance for PAHs is basically designed to restore their livelihood to at least the pre-displacement level by mitigating the negative impact of the involuntary resettlement due to the change caused by the Project. Therefore, there is no misdistribution of benefit between PAHs and non-PAHs by the Project as a result of the assistance to be provided by TSMC. Impact on the living environment in the local community The living environment of local people would be directly or indirectly affected by the construction work or the operation of each tenant. In case of the problem, local people can communicate with the community relation department of the project proponent to solve the raised issues. In addition, the project proponent will implement community support

			ping Re	sult				
Category	Scoping Item	PC/ CO	OP	CLP	PC/ CO	OP	CLP	Reason for Assessment
								programs as the one of CSR activities in order to help establishing harmonization with local communities and to balance the impacts of the Project. As a result, misdistribution of benefit and damage would be minimized by the effort of the project proponent.
	Children's Right	B-	B-/ B+	D	В-	B-/ B+	В-	Impact on Educational Opportunity of School Children in Relocated PAHs PC/CO: Since there are a total of 118 school children among the relocated PAHs, children's education would be temporarily disrupted due to relocation. In this case, TSMC will provide cash assistance for commuting to school and will consider measure as part of the IRP activities to minimize the impact based on the dialogue with PAHs. On the other hand, it is expected the educational opportunity will be provided more with the community support programs by the project proponent and also children would be indirectly influenced by the improvement of social infrastructure in the region as a result of the Project. Impact on Educational Opportunity of School Children of local community OP: So far, the project proponent has implemented "Thilawa SEZ neighboring students Support Program" and, around 1,000 students were benefited from this program. In addition, the project proponent will implement the educational programs continuously based on needs and requests from the community in the future. Therefore, it is expected that the educational opportunity will be improved by the effort of the project proponent by the Project. Impact on Increase of Child Labor CO/OP/CLP: Basically, children below 13 years old are not prohibited to work in any shop, commercial establishment or factory according to the labor law in Myanmar. As long as the Project and tenants keep laws in Myanmar, illegal child labor will be prevented in employment of labors. In addition, the labor section of OSSC will supervise tenants not to employ children as labors illegally at the time of each worker's registration for Thilawa SEZ. Therefore, child labor would be controlled well to prevent employing.
	Existing Social Infrastructures and Services	B-/ B+	B-/ B+	D	B-/ B+	B-/ B+	D	Impact to Relocated PAHs of the Project PC/CO: Accessibility of PAHs to social infrastructure/service would be affected more or less due to the relocation. On the other hand, the proposed relocation site will be arranged with basic social infrastructures as a part of the assistance by TSMC. Impact to Local People in the local Community of the project area CO: Accessibility of social infrastructure/ service will be affected due to the increase of construction vehicles. The traffic volume should be controlled by construction contractor to avoid serious traffic congestion. OP: Accessibility to social infrastructure would be limited by the existence of the tenants. On the other hands, it is planned to construct community road which has alternative function in order to keep the accessibility of the existing road for the local community. In addition, basic infrastructures such as the existing road and power supply will be improved due to the ongoing infrastructure development projects around Thilawa SEZ.
	Water Usage	С	С	D	В-	В-	D	CO: One pond and one water pump will not be able to use continuously due to the development. Basically it should be appropriately compensated under the compensation policy of YRG and TSMC. Moreover, the project proponent will arrange alternative pond near the pond for the community considering the situation as necessary. In addition, the deterioration of the local water resource such as adjacent wells and lake is expected due to the discharging water from construction site. However, it will be controlled well by installing

			ping Re	sult		sment R	esult	
Category	Scoping Item	PC/ CO	OP	CLP	PC/ CO	OP	CLP	Reason for Assessment
								settling ponds or simple turbid water treatment and septic tank. OP: The impact on the local water reservoir is not expected since the amount of water consumption for the Project will be managed and additional water supply source is planned to utilize. For the water quality in creek near the project area, it will be controlled well by managing drainage ditch and retention ponds. Basically, it is expected that concentration of wastewater is diluted by mixing with stormwater through the retention pond and creek flow. In case that large amount discharge which includes heavy metals and toxic substance is expected and especially low flow season, the project proponent would review the internal target value and set strict standard for pre-treatment, if necessary.
	Cultural Heritage/Asset	В-	D	D	В-	D	D	CO: One cemetery will be directly affected by the Project and some adjacent monasteries and Hindu temples will be indirectly affected due to the construction work. Therefore, it will be considered the several measure to keep this utility for the community under the understanding of local people by the adequate dialogue with them.
	Landscape	D	B-/ B+	D	D	B-/ B+	D	Impact of alteration of landscape resources (B-) OP: Since the late of 2013, the landscape has been already changed time by time since the construction work of Zone A. Moreover, 266ha of agricultural land will be cleared and altered to industrial area as the part of Zone B development. Therefore, the existing landscape is in the process of semi-urbanization due to Zone A development and it will push the semi-urbanization more and more due to the Project. Impact of Landscape design within the SEZ (B+) PP: Although semi-urbanization of landscape in and around Thilawa SEZ is inevitable, the development will be implemented under the project proponent internal regulation which rules to secure the environmental friendliness for users and residents, and harmonization with the surrounding area. In addition, greening area will be established in each plot and public space. Therefore, as long as the tenants follows the internal regulation and the project proponent will make effort to maintain the public area, the landscape of the project area is expected to be well-maintained semi-urbanized area
Health and Safety	Risks for Infectious Diseases such as AIDS/HIV	В-	В-	В-	В-	В-	B-	CO/OP/CLP: Risks for communicable and vector-borne disease are expected among workers and the surrounding local community due to the influx of labors from outside. In order to minimize the impact, preventive measures against such diseases, which is stipulated in the Environment, Health, and Safety (EHS) Guidelines of the International Finance Corporation (IFC), should be considered and implemented by construction contractor and each tenant in respective stage. In addition, existing public health care program will be utilized in cooperation with local government, and the project proponent will plan CSR activities regarding health care.
	Occupational Health and Safety	В-	В-	В-	В-	В-	В-	Impact on occupational health and safety CO/OP/CLP: Impacts on occupational health and safety (OHS) are inevitable due to the construction/demolished work, operation of tenants. In order to minimize the impacts, construction contractor/each tenant/ the project proponent shall take mitigation measures stipulated in EHS Guidelines of IFC Since the type of business is different in each tenant, the mitigation measure should be prepared considering the respective occupational risk under the respective impact assessment. Impact on labor right CO/OP/CLP: It is expected that labor rights for workers of the Project would be secured by construction constructor and each tenant with the related labor laws

			ping Re	sult		sment R	esult	
Category	Scoping Item	PC/ CO	OP	CLP	PC/ CO	OP	CLP	Reason for Assessment
								under the supervision of TSMC. In case of any disputes or conflicts between employee and employer, authorized labors officers of TSMC provide the coordination with employee to resolve the situation.
	Community Health and Safety	В-	B-	B-	B-	B-	B-	CO/CLP/OP: It is expected the impact on public safety due to the vehicle traffic, which is cumulatively increased by the surrounding development project, and the operation of heavy machineries. It is also expected the impact on public security due to the influx of labors and people for the implementation of the Project. To minimize impacts, the mitigation measures stipulated in the EHS Guidelines of the IFC should be taken by construction contractor/the project proponent. In addition, the project proponent will consider community health program as a part of CSR activities based on the request from the community regarding public safety and security.
Emergency Risk	Usage of Chemicals	D	B-	D	D	В-	D	OP: During the operation phase, some tenants would use chemical materials to be managed under specific condition. In addition, Material Safety Data Sheet (MSDS) will be utilized in order to let workers know about requirements and standards of the chemicals. Risk of chemical material is expected to be limited because the tenants will be required to prepare proper chemical substances management plan and to comply with applicable regulations/laws with reference to usage, producing, storing, disposing and handling of dangerous and hazardous materials as stipulated in the proposed internal regulation
	Flood Risk	В-	В-	В-	В-	В-	В-	CO/OP/CLP: Flood risks such as heavy rain, cyclone, and high tide are expected to be limited because land reclamation plan is prepared considering EL+5.5-7.0 m, which is higher than EL +4.24 m, 100 years return rainfall flood analysis of EL +4.9 m, storm surge simulation in Yangon River of E.L. +5.5.
Emergency Risk	Risk of Fire	В-	В-	B-	В-	В-	B-	CO/CLP: Risk of fire is expected to be limited because the fire safety plan and equipment will be prepared by the project proponent to comply with the Building Construction and Fire Safety Rule regulated by TSMC. OP: Risk of fire is expected to be limited because the tenants shall install and maintain an effective fire alarm system and firefighting system for each building in the plot with reference to the TSMC rules and the proposed internal regulation.
	Earthquake	В-	B-	В-	B-	В-	B-	CO/CLP: There is a possibility for an earthquake to occur. However, the contractor for construction and demolition work will prepare disaster prevention activities to minimize the damage. Therefore, the negative impact of the earthquake would be limited. OP: There is a possibility for an earthquake to occur. However, each tenant would design and construct properly to meet the required standard such as quake-resistance standard. Therefore, the negative impact of anon earthquake would be limited.
Other	Global Warming	В-	В-	B-/ B+	В-	B-	В-	CO: Emission of greenhouse gases (GHGs) would be generated from construction machineries and vehicular traffic caused by the Project. OP: Emissions of GHGs would be generated from vehicular traffic in the Project and operation of the tenants. CLP: Emission of GHGs would be generated from construction machineries and vehicular traffic caused by the Project. On the other hand, emissions of GHGs from operation activities would be reduced.

Note: PC: Pre-construction Phase, CO: Construction Phase, OP: Operation Phase, CLP: Closing Phase

Evaluation: A-: Significant Negative Impact
B-: Some Negative Impact A+: Significant Positive Impact

B+: Some Positive Impact


C: Impacts are not clear, need more investigation

D: No Impacts or impacts are negligible, no further study required Source: EIA Study Team

10. Cumulative Impact Assessment

Thilawa SEZ has been developed by each zone starting from Zone A since 2014. So far, there are three projects that have been operated/planned in the Thilawa SEZ, i.e. [Project 1] the development project of Zone A, [Project 2] the development project of the industrial area of Zone B (the Project) and [Project 3] the development project of the logistic, residence and commercial areas of Zone B. When assessing the impacts of the Project, it is necessary to consider the cumulative impacts that might occur from the combined effect over a given resource of several projects that will be operated physically close to the Project in future. Figure 6 shows the location of two surrounding projects and the Project.

In the assessment of the Project, air quality, water quality, waste, noise and vibration, flora and fauna, biodiversity and community health and safety were identified that should be considered the cumulative impacts of the two projects in Thilawa SEZ as mentioned above. Table 8 summarizes the basic concept of cumulative impact assessment of each item.



Source: EIA Study Team prepared on the basis of the information from the project proponent

Figure 6: Location of the Projects that should be assessed Cumulative Impacts

Table 8: Environmental Items of Cumulative Impact Assessment

	Environmental Item	Basic Concept of Cumulative Impact Assessment
(3)	Waste	When all three projects start their operation and the number of tenants that start its operation is going to increase, amount of industrial and business related waste generated from the three projects will proportionately be increased. Therefore it is needed to evaluate impact of generated industrial and business related waste in terms of receiving capacity of the final disposal site located in Zone A.
(4)	Noise and Vibration	When all three projects start their operation and all the tenants in the industrial, logistic and commercial areas of three projects start their operation, traffic volume will be increased cumulatively in and around the Thilawa SEZ. Therefore, impact of noise and vibration increased by vehicle traffic generated from operation of all three projects should be estimated.
(5)	Flora/Fauna and Ecosystem	Change of land use and reduction of the habitat of species in the Thilawa SEZ will impact on ecosystem. Since land reclamation of Zone A had already conducted when this assessment started, cumulative impacts on ecosystem will be assessed by considering the change of each land area including grass land, shrub, and reservoirs caused by the development of whole Zone B.
(6)	Community Health and Safety	Community safety might be influenced by the increase of traffic volume in and around the Thilawa SEZ caused by the operation of all three projects.

11. Environmental Mitigation/Management and Monitoring Plan

(1) Environmental Mitigation and Management Plan

The categories evaluated as A⁻ or B⁻ in accordance with the results of the impact assessment, mitigation of its measures for each of the three phases separately pre-construction phase, construction/closing phase, and operation phase are shown in Tables 9 to 11.

The implementing resettlement works including income restoration program activities, of the Thilawa SEZ will be conducted by TSMC supported by the two committees, namely: Relocation Implementation Committee (RIC) and Income Restoration Program Implementation Committee (IRPIC). These organizations will be in-charge of the actual relocation and resettlement works in Thilawa SEZ.

Table 9: Environmental Mitigation and Management Plan (Pre-construction Phase)

Category	Item	Expected Environmental and Social Impacts	Proposed Environmental Mitigation Measures and Environmental Management	Implementing Organization	Responsible Organization	Item of Expenditure
Pollution	Noise and Vibration	- Noise and vibration from tenants	 Arrangement of the land allocation for each tenant and the installation of buffer zone with less noise and vibration impacts to the surrounding sensitive receivers (monastery, residence etc.), as possible. 	Project Proponent	Project Proponent	-Layout planning cost
Social Environment	Involuntary Resettlement	 Loss or change of livelihood of relocated PAHs Social impact to households that currently occupying the proposed relocation site 	 Provision of land compensation (if applicable) Provision of assistance package based on Resettlement Framework for 2000 ha Preliminary discussion and provision of compensation and assistance for the households in the proposed relocation site as necessary 	TSMC	TSMC	Cost for land compensation, Cost for assistance package determined by Resettlement Framework for 2000 ha
	Living and Livelihood	 Impact of loss of livelihood opportunity, especially land-based livelihood such as paddy field and/or vegetable field 	- Provision of assistance on loss of income source and full implementation of IRP based on Resettlement Framework for 2000ha	TSMC	TSMC	Cost for assistance package
	Vulnerable Group	- Loss or change of livelihood	Provision of special assistance in addition to the assistance on loss of assets and income source based on Resettlement Framework for 2000 ha	TSMC	TSMC	
	Local Conflict of Interests	 Shortage of capacity on the existing infrastructure and service around the proposed relocation site 	- Arrangement of adequate infrastructure and service based on the actual demand	TSMC	TSMC	Installation cost
	Children's right	- Impact on expenditure and time for commuting	Commuting assistance for school for children of relocated PAHs	TSMC	TSMC	Cost for assistance package
	Existing Infrastructures and Services	- Suspension of existing road due to the construction work	- Construction of alternative community road	Project Proponent	Project Proponent	Cost for constructing road
		- Impact on accessibility of existing infrastructure and service to relocated PAHs	- Arrangement of alternative option for infrastructure and service after relocation	TSMC	TSMC	Installation cost
	Water Usage	- Suspension of using pond located inside the project area	- Arrangement of alternative pond near the project area	Project Proponent	Project Proponent	Cost for constructing pond
	Cultural Heritage/ Asset	Possibility on the relocation of cemetery Indirect impact on other common asset	Adequate dialogue with local community in order to discuss necessity of relocation and the detail process for cemetary	TSMC	TSMC	Cost for the relocation of cemetary (if required to relocate) or cost for securing the space for the affected common asset

Table 10: Environmental Mitigation and Management Plan (Construction/Closing Phase)

Category	Item	Expected Environmental and Social Impacts	Proposed Environmental Mitigation Measures and Environmental Management	Implementing Organization	Responsible Organization	Item of expenditure
Pollution	Air Quality	- Impact of air pollution, dust/emission gases by construction work	 Sprinkle water around the project site and roads. Avoidance of intensive operation of construction machineries 	Contractor	Project Proponent	- Water and car running cost for sprinkling water
	Water Quality	Discharging muddy water from bare land Wastewater from construction camps	 Installation of settling ponds or simple turbid water treatment Installation of septic tank Preparation of the discharge water treatment plan 	Contractor	Project Proponent	- Equipment Installation Cost
	Waste	- Construction waste by cut earthwork	Reuse the residual soil generated in cutting work for filling work in the site Preparation and implementation of the waste management program	Contractor	Project Proponent	-Included in construction cost
	Noise and Vibration	Impacts of noise and vibration by construction machineries and vehicles	 Installation of sound-proofing sheet, Avoidance of construction at nighttime, Advanced notice for construction work time near the monastery and residential area Avoidance of intensive operation of construction machineries Speed limit for drivers 	Contractor	Project Proponent	- Facility installation cost - Education cost -Miscellaneous expenses
Natural Environment	Flora, Fauna, and Biodiversity	- Clearance of existing vegetation	- Clear marking of boundary of the project site to prevent the contractor from clearing the vegetation outside of the project site	Contractor	Project Proponent	-Miscellaneous expenses
	Hydrology	Impact on hydrology due to water consumption used in the construction work	Limited and short term usage of groundwater Preparation of tentative retention pond	Contractor	Project Proponent	- Construction cost for tentative retention pond
	Soil Erosion	- Soil erosion of the bank	- Provision of temporary drainage and/or sandbag to minimize soil erosion due to rainy water	Contractor	Project Proponent	-Miscellaneous expenses
Social Environment	Living and livelihood/	Impact on the living and livelihood by construction	- Implementation of IRP for PAHs based on Resettlement Framework for 2000ha	TSMC	TSMC	-Assistance Package
	Vulnerable Group	works	 Advanced notice for construction work time Avoidance of intensive operation of construction vehicle 	Contractor	Project Proponent	-Miscellaneous expenses
	Local Conflict of Interests	- Conflict between construction workers and local people	- Education and training to give instruction to workers to avoid the conflict with local people	Contractor	Project Proponent	- Education cost
	Misdistribution of Benefit and Damage	- Impact on living environment in local community	- Communication with local community though community relation department	Project Proponent	Project Proponent	-Operation cost
	Children's right	- Impact on illegal child labor	- Compliance with the relevant regulations	Contractor	Project Proponent	-Miscellaneous expenses
	Existing Infrastructures and Services	Accessibility to social infrastructure for local community	- Control of traffic volume	Contractor	Project Proponent	-Miscellaneous expenses

Category	Item	Expected Environmental and Social Impacts	Proposed Environmental Mitigation Measures and Environmental Management	Implementing Organization	Responsible Organization	Item of expenditure
	Water Usage	Impact on the daily water use of local people by well or pond near project site	 Installation of settling ponds or simple turbid water treatment Installation of septic tank Preparation of the discharge water treatment plan 	Contractor	Project Proponent	-Assistance Package
	Cultural Heritage/ Asset	- Impact of dust, noise and vibration, traffic caused by construction work	- Securing adequate space for the assets to keep enough distance from construction site	Contractor	Project Proponent	-Miscellaneous expenses
Health and Safety	Risks for infectious diseases such as AIDS/HIV	- Increasing risks for infectious diseases due to the influx of workers	Conducting OHS training stipulated in the international guidelines such as EHS Guidelines of IFC such as; - To provide surveillance for worker's health - Prevention of illness among workers by undertaking health awareness and education initiatives and by conducting immunization programs for workers - To provide treatment through standard case management in on-site and community health care facilities as necessary - Educating project personnel and area residents on risks, prevention, and available treatment - Promoting collaboration with local authorities to enhance access of worker's families and the community to public health services and promote immunization as necessary - Promoting use of repellents, clothing, netting, and other barriers to prevent insect bites - Prevention of larval and adult propagation through sanitary improvements and elimination of breeding habitats close to human settlements - Elimination of unusable impounded water	Contractor	Project Proponent	- Education cost
Health and Safety	Occupational Health and Safety	- Accidents during construction work/closing work	Conducting OHS training stipulated in the international guidelines such as EHS Guidelines of IFC such as; [Common] - To provide adequate health care facilities and first aid within construction sites - To provide OHS training program and information of basic site rules of work, basic hazard awareness, site specific hazards, safe work practices, and emergency procedure [Occupational Health] - To provide adequate lavatory facilities for the number of people expected to work in the facility - To provide adequate supplies and easy access of drinking water with a sanitary means - To provide temporary shelters to protect against heat stroke	Contractor	Project Proponent	- Education cost - Water and car running cost for sprinkling water

Item	Expected Environmental and Social Impacts	Proposed Environmental Mitigation Measures and Environmental Management	Implementing Organization	Responsible Organization	Item of expenditure
Community Health and Safety	- Third party accidents with residents near the construction site - Accidents with local people by the traffic of construction vehicles - Disputes among local people and migrated workers	during working activities or for use as rest areas as needed To promote the use of repellents, clothing, netting, and other barriers to prevent insect bites and snake bite [Occupation Safety] Adequate preventive measures from negative factors such as over-exertion, slips and falls, work in heights, struck by objects, moving machinery, dust, confined spaces and excavations, and other site hazards To train and license industrial vehicle operators in the safe operation of specialized vehicles To establish driving and traffic rules To identify and provide appropriate PPE that offers adequate protection to the worker, co-workers, and occasional visitors Proper maintenance of PPE and the instruction of proper use Conducting OHS training stipulated in the international guidelines such as EHS Guidelines of IFC such as; [Common & Other] Establish the plan of site safety and security measures to communities and its implementation Education and instruction to the project personnel and construction workers on risks, prevention, and available treatment Dispute settlement among stakeholders in case incidences occur Arrangement of worker's accommodation as necessary Securing the existing water source [General Site Hazard] Restricting access to the site with a focus on high risk structures or areas depending on site-specific situations including fencing, signage, and communication of risks to the local community Removing hazardous conditions on construction sites such as covering openings to small confined spaces, ensuring means of escape for larger openings such as trenches or excavations, or locked storage of hazardous materials [Traffic Safety] Emphasizing safety aspects among drivers			- Education cost - Water and car running cost for sprinkling water
	Community Health and	Community Health and Safety - Third party accidents with residents near the construction site - Accidents with local people by the traffic of construction vehicles - Disputes among local people	Impacts during working activities or for use as rest areas as needed To promote the use of repellents, clothing, netting, and other barriers to prevent insect bites and snake bite [Ioccupation Safety]	during working activities or for use as rest areas as needed - To promote the use of repellents, clothing, netting, and other barriers to prevent insect bites and snake bite Coccupation Safety - Adequate preventive measures from negative factors such as over-exertion, slips and falls, work in heights, struck by objects, moving machinery, dust, confined spaces and excavations, and other site hazards - To train and license industrial vehicle operators in the safe operation of specialized vehicles - To identify and provide appropriate PPE that offers adequate protection to the worker, co-workers, and occasional visitors - Proper maintenance of PPE and the instruction of proper use Conducting OHS training stipulated in the international guidelines such as EHS Guidelines of IFC such as: Common & Other - Establish the plan of site safety and security measures to communities and its implementation - Education and instruction to the project personnel and construction workers on risks, prevention, and available treatment - Dispute settlement among stakeholders in case incidences occur - Arrangement of worker's accommodation as necessary - Securing the existing water source (General Site Hazard) - Restricting access to the site with a focus on high risk structures or areas depending on site-specific situations including fencing, signage, and communication of risks to the local community - Removing hazardous conditions on construction sites such as covering openings to small confined spaces, ensuring means of escape for larger openings such as trenches or excavations, or locked storage of hazardous materials (Traffic Safety)	Management Management Management Organization Organization

Category	Item	Expected Environmental and Social Impacts	Proposed Environmental Mitigation Measures and Environmental Management	Implementing Organization	Responsible Organization	Item of expenditure
			- Avoiding dangerous routes and times of day to reduce the risk of accidents			
Emergency	Flood Risk	- Increase of the impact of flood in and around the projects site	- Preparation of the disaster prevention equipment and management manual	Contractor	Project Proponent	- Education cost - Equipment purchase cost
	Risk of Fire	- Impact on the community around the project site by increasing of risk of fire	- Compliance with the TSMC's regulation for building construction and fire safety	Contractor	Project Proponent	- Education cost - Equipment purchase cost
	Earthquake	Increasing of the damage of the earthquake in and around the projects site	- Preparation of the disaster prevention equipment and management manual	Contractor	Project Proponent	-Education cost -Equipment purchase cost
Others	Global Warming	- Emission of greenhouse gases (GHGs) construction machineries and vehicles	- Control of GHGs emission in the construction work	Contractor	Project Proponent	-Miscellaneous expenses

Table 11: Environmental Mitigation and Management Plan (Operation Phase)

Category	Item	Expected Environmental and Social Impacts	Proposed Environmental Mitigation Measures and Environmental Management	Implementing Organization	Responsible Organization	Item of expenditure
Pollution	Air Quality	- Impact of air pollution caused by the tenants	Provision of commuter busSpeed limit for drivers in the project area	Project Proponent	Tenants including Project Proponent	- Bus Operation cost
			 Preparation of feasible mitigation measures, such as, energy use efficiency, process modification, selection of fuels or other materials, the processing of which may result in less polluting emission, application of emission control techniques, if necessary 	Tenants	Tenants	- Installation cost
	Water Quality	- Effluent water from tenants and offices	- Operation and maintenance of pre-wastewater treatment	Tenants	Tenants	Installation costO&M cost
			 Operation and maintenance of centralized wastewater treatment system In case that large amount discharge which includes heavy metals and toxic substance is expected and especially low flow season, the project proponent would review the internal target value and set strict standard for pre-treatment, if necessary. 	Project Proponent	Project Proponent	 Installation cost of water treatment system O&M cost
	Waste	 Impact of waste generated from factories and offices. 	- Management of non-hazardous waste from tenants and utility area of themselves	Tenants	Tenants	- Disposal cost
			- Management of hazardous waste by tenants	Tenants	Tenants	Treatment costDisposal cost
	Soil Contamination	- Soil contamination is caused by the tenants and offices	 With reference to usage, the process of usage, producing, storing, disposing and handling of oil, chemical, dangerous or hazardous materials in the project area, the tenants shall treat the materials safety on the covered area to prevent infiltration of the materials to ground or dispose of all dangerous or hazardous materials and waste Solid waste receptacles or trash containers which must be large enough to facilitate storage and collection and which must be installed within the land of tenant. 	Tenants	Tenants	- Treatment cost
	Noise and Vibration	- Noise and vibration from tenants	 Preparation of the sound barrier, sound–absorbing materials, installing the facility in the house, having the enough buffer zone as necessary Installing vibration control devices for equipment, design of the structure to disconnect between the sources and ground as necessary 	Tenants	Tenants	-Installation cost
	Offensive Odor	- Odor caused by the tenants.	 With reference to usage, producing of disposing and handling of dangerous or hazardous materials in the project area, the tenants must, at its sole responsibility and expense, shall treat 	Tenants	Tenants	- Treatment cost

Category	Item	Expected Environmental and Social Impacts	Proposed Environmental Mitigation Measures and Environmental Management	Implementing Organization	Responsible Organization	Item of expenditure
			safety manage, eliminate or dispose of all dangerous or hazardous materials and waste - Waste reduction, waste minimization and cleaner production principles or conventional emission control equipment, as necessary			
	Bottom Sediment	Impact on bottom sediment by discharge water	 Operation and maintenance of the centralized wastewater treatment system In case that large amount discharge which includes heavy metals and toxic substance is expected and especially low flow season, the project proponent would review the internal target value and set strict standard for pre-treatment, if necessary. 	Project Proponent	Project Proponent	- Installation cost - O&M cost
Natural Environment	Flora, Fauna, and Biodiversity	- Impact of changing the vegetation	 Planting trees, vegetation, sodding of public spaces such as road, retention ponds, and other open space of each tenant 	Tenants and Project Proponent	Tenants and Project Proponent	Installation costMaintenance cost
	Hydrological	- Impact on hydrology due to the change in land use.	- Management of retention ponds	Project Proponent	Project Proponent	Installation costO&M cost
			 Install of additional earth drain line around the boundary of the project area if a flood were to occur. 	Project Proponent	Project Proponent	Installation costO&M cost
	Soil Erosion	 Impact on existing canal by discharge water 	- Management of retention pond	Project Proponent	Project Proponent	Installation costO&M cost
Social Environment	Living and Livelihood/ Vulnerable Group	- Impact on the living and livelihood for PAHs	- Implementation of IRP for PAHs based on Resettlement Framework for 2000ha	TSMC	TSMC	-Assistance Package
	Misdistribution of Benefit and Damage	Impact on living environment in local community	Communication with local community though community relation department	Project Proponent	Project Proponent	-Operation cost
	Children's right	- Impact on illegal child labor	- Compliance with the relevant regulations	Tenants and Project Proponent	Tenants and Project Proponent	-Miscellaneous expenses
	Water Usage	- Impact on the daily water use of local people by well of lake near project site	 Management of drainage ditch and retention ponds inside of the Zone B industrial area In case that large amount discharge which includes heavy metals and toxic substance is expected and especially low flow season, the project proponent would review the internal target value and set strict standard for pre-treatment, if necessary. 	Project Proponent	Project Proponent	- Installation cost - O&M cost
	Cultural Heritage/ Asset	- Impact of dust, noise and vibration, traffic caused by	- Securing adequate space for the assets to keep enough distance from construction site	Project Proponent	Proponent	-Miscellaneous expenses
	Landscape	- Alternation of the landscape	 Following the rule of landscape in accordance with proposed industrial internal regulation 	Tenants including Project Proponent	Tenants including Project Proponent	- Design and construction cost

Category	Item	Expected Environmental and Social Impacts	Proposed Environmental Mitigation Measures and Environmental Management	Implementing Organization	Responsible Organization	Item of expenditure
Health and Safety	Risks for Infectious Diseases such as AIDS/HIV	- Increasing risks for infectious diseases due to the influx of workers	Conducting OHS training stipulated in the international guidelines such as EHS Guidelines of IFC such as; - To provide surveillance for worker's health - Prevention of illness among workers by undertaking health awareness and education initiatives and by conducting immunization programs for workers - To provide treatment through standard case management in on-site and community health care facilities as necessary - Educating project personnel and area residents on risks, prevention, and available treatment - Promoting collaboration with local authorities to enhance access of worker's families and the community to public health services and promote immunization as necessary - Promoting use of repellents, clothing, netting, and other barriers to prevent insect bites - Prevention of larval and adult propagation through sanitary improvements and elimination of breeding habitats close to human settlements - Elimination of unusable impounded water	Tenants including Project Proponent	Tenants including Project Proponent	-Education cost
	Occupational Health and Safety	- Accidents and incidents during the operation of each tenant	Conducting OHS training stipulated in the international guidelines such as EHS Guidelines of IFC such as; [Common] - To provide adequate health care facilities and first aid within construction sites - To provide OHS training program and information of basic site rules of work, basic hazard awareness, site specific hazards, safe work practices, and emergency procedure [Occupational Health] - To provide adequate lavatory facilities for the number of people expected to work in the facility - To provide adequate supplies and easy access of drinking water with a sanitary means - To provide temporary shelters to protect against heat stroke during working activities or for use as rest areas as needed - To arrange for provision of clean eating areas where workers are not exposed to the hazardous or noxious substances where there is potential for exposure to substances poisonous by ingestion of food as necessary - To promote the use of repellents, clothing, netting, and other	Tenants	Tenants	- Education cost - Cost for installation of safety facilities

Item	Expected Environmental and Social Impacts	Proposed Environmental Mitigation Measures and Environmental Management	Implementing Organization	Responsible Organization	Item of expenditure
Community Health and Safety	- Third party accidents with residents near the construction site - Accidents with local people by the traffic of construction vehicles - Disputes among local people and migrated workers	guidelines such as EHS Guidelines of IFC such as; [Common] - Establish the plan of site safety and security measures to communities and its implementation - Education and instruction to the project personnel and construction workers on risks, prevention, and available treatment [General Site Hazard] - Restricting access to the site with a focus on high risk structures or areas depending on site-specific situations including fencing, signage, and communication of risks to the local community - Removing hazardous conditions on construction sites such as covering openings to small confined spaces, ensuring means of escape for larger openings such as trenches or excavations, or locked storage of hazardous materials [Traffic Safety] - Emphasizing safety aspects among drivers - Improving driving skills and requiring licensing of drivers - Adopting limits for trip duration and arranging driver rosters to avoid overtiredness	Tenants	Tenants	- Education cost - Cost for installation of safety facilities
	Community Health and	Community Health and Safety - Third party accidents with residents near the construction site - Accidents with local people by the traffic of construction vehicles - Disputes among local people	Impacts Barriers to prevent insect bites and snake bite	Impacts	Adequate preventive measures from negative factors such as fire precautions, lighting, safe access, work environment temperature, area signage, labeling of equipment, communicate Hazard codes, electrical - To establish rights-of-way, site speed limits, vehicle inspection requirements, operating rules and procedures, and control of traffic patterns or direction - To identify and provide appropriate PPE that offers adequate protection to the worker, co-workers, and occasional visitors - Proper maintenance of PPE and the instruction of proper use Community Health and Safety - Accidents with local people by the traffic of construction vehicles - Disputes among local people and migrated workers - Establish the plan of site safety and security measures to communities and its implementation ecommunities and its implementation of construction workers on risks, prevention, and available treatment (General Site Hazard) - Restricting access to the site with a focus on high risk structures or areas depending on site-specific situations including fencing, signage, and communication of risks to the local community - Removing hazardous conditions on construction sites such as covering openings to small confined spaces, ensuring means of escape for larger openings such as trenches or excavations, or locked storage of hazardous materials [Traffic Safety] - Emphasizing safety aspects among drivers - Improving driving skills and requiring licensing of drivers - Adopting limits for trip duration and arranging driver rosters to avoid overtiredness

Category	Item	Expected Environmental and Social Impacts	Proposed Environmental Mitigation Measures and Environmental Management	Implementing Organization	Responsible Organization	Item of expenditure
			- Arrangement of worker's accommodation as necessary			
Emergency	Usage of Chemical	- Risk of chemical material	 Formulation of chemical management plan as necessary Training of safety usage and preparation of the emergency response plans Implementation of the proper storage and record of usage. Applying for the acquisition of the license with management plan in accordance with the relevant law, and compliance with the law. Provision of protective equipment and clothes to workers as necessary. 	Tenants	Tenants	-Education cost - Equipment purchase cost
	Flood Risk	Increasing of the impact of flood in and around the projects site	Preparation of the disaster prevention equipment and management manual	Tenants including Project Proponent	Tenants including Project Proponent	-Education cost - Equipment purchase cost
	Risk of Fire	- Impact on the community around the project site by increasing of risk of fire	 Installation of the fire hydrants along the road Implementation of emergency drill 	Tenants including Project Proponent	Tenants including Project Proponent	-Education cost - Equipment purchase cost
	Earthquake	Increasing of the damage of the earthquake in and around the projects site	 Compliance with the TSMC's Standard Operational Procedure for (SOP) for building construction Preparation of the disaster prevention plan such as emergency contact list 	Tenants including Project Proponent	Tenants including Project Proponent	-Education cost - Equipment purchase cost
Others	Global Warming	- Impact in the increase of GHGs by vehicle traffic operation of tenants in the operation phase.	- Control of GHGs emission by energy use efficiency, process modification, selection of fuels or other materials, the processing of which may result in less emission, application of emission control techniques, if possible - Provision of commuter bus	Tenants	Tenants	- Installation cost - O&M cost - Bus operation cost

(2) Environmental Monitoring Plan

Environmental monitoring plan including monitoring items, location, frequency and responsible organization at the pre-construction phase, construction phase, and operation phase are shown in Table 12 to Table 14. Responsible organizations shall review the monitoring plan in accordance with the progress of the Project and status of the situation before monitoring, if necessary, and are in charge of monitoring and preparation of its results. The project proponent will submit the monitoring report at the pre-construction phase, construction phase and operation phase to TSMC.

Table 12: Environmental Monitoring Plan (Pre-construction Phase)

Category	Item	Location	Frequency	Responsible Organizations
Common	 Checking and revising the Environmental Mitigation (as shown in Table 9,10 and11)and Management Plan by reviewing the final detailed design of the Project Checking the Environmental Monitoring Plan during Construction prepared by Contractor 	Project Site	Once	Contractor
Social Environment - Involuntary Resettlement, - Living and Livelihood	 Monitoring of the implementation status of Resettlement works such as provision of assistance package for project affected persons, and common assets 	Project Site and Relocation Site	Once	TSMC
- Vulnerable Group, - Cultural Heritage/ Asset	Monitoring of the implementation status for CSR activities such as community support program	Around Project Site	Once/year	TSMC
Existing social infra- structures and services	- Securing of community accessibility	Around Project Site	Once	Contractor

Table 13: Environmental Monitoring Plan (Construction Phase)

Category	Item	Location	Frequency	Responsible Organizations
Common	- Monitoring of mitigation measures (as shown in Table 10)	Each location	Once/month	Contractor
Air Quality	- NO ₂ , SO ₂ , CO, PM _{2.5} , PM ₁₀	Construction site (1 point)*	1 week/3 months	Contractor
Water Quality	- Water temperature, pH, SS, DO, BOD ₅ , COD, coliforms, oil and grease, chromium	- Outflow of construction site to the creek (at least 3 sampling points/mixing point: i) discharge water, ii) upstream water, and iii) downstream water) ** - Well near the construction site (1 point)	Once/2 months	Contractor
Waste	- Amount and kind of solid waste	Construction site	Once/3 months	Contractor
Noise and Vibration	- Noise and vibration level - Traffic count	Preservation area such as residence around the proposed construction site (at least 1 point)	Once (24 hours)/3 months	Contractor
		Preservation site such as residence along the route for on-site vehicles (1point for noise and vibration and 2 points for traffic count)	Once (24 hours)/3 months	Contractor
Hydrology	Groundwater levelGround elevation level	Well near the construction site	Once/ months	Contractor

Category	Item	Location	Frequency	Responsible Organizations
	- Consumption of groundwater amount			
Living and Livelihood/ Vulnerable Group/ Misdistribution of Benefit and Damage/ Children's Right	- The implementation status for CSR activities such as community support program	Around Project Site	Once/year	Project Proponent
Risks for Infectious Disease such as AIDS/HIV	- Awareness of infectious diseases	Construction site	Once/month	Contractor
Occupational Health and Safety	- Record of accidents and infectious diseases	Construction site	Once/month	Contractor
Community Health and Safety	- Record of accidents and infectious diseases related to the community	Around construction site	Once/month	Contractor
	- The implementation status for CSR activities such as community support program	Around Project Site	Once/year	Project Proponent

Note: *Air quality monitoring site in the construction area should be selected in consideration of keeping the same location during construction phase.

** Water quality monitoring location should be selected at least three points for one discharge point to confirm the impact of the

Table 14: Environmental Monitoring Plan (Operation Phase)


Survey Item	Item	Location	Frequency	Responsible Organizations
Common	- Monitoring of mitigation measures (as shown in Table 11)	Project site	Quarterly (3 years after operation) Yearly (after 3 years operation)	Project Proponent
Air Quality	- NO ₂ , SO ₂ , CO, PM _{2.5} , PM ₁₀	Representative point inside the project area	1 week each in the dry and rainy seasons (first 3 years after starting of the operation stage)	Project Proponent
Water Quality	- Water temperature, pH, SS, DO, BOD ₅ , COD, color and odor, Total Nitrogen, Total Phosphorus, Sulphide, HCN, Oil, Grease, Formaldehyde, Phenols, Free chlorine, Zinc, Chromium, Arsenic, Copper, Mercury, Cadmium, Barium, Selenium, Lead, and Nickel	- Outflow of retention pond to the creek (at least 3 sampling points/mixing point: discharge water, upstream water, and downstream water)	Every 2 month: Water temperature, pH, SS, DO, BOD ₅ , COD, color and odor, Every 6 month :all parameters	Project Proponent
Waste	Amount of non-hazardous waste management Amount of hazardous waste management	Each tenant	Twice/year (submission of the environmental report by the tenants)	Tenants
Soil Contamination	- Status of control of solid and liquid waste which causes soil contamination	Each tenant	Twice/year (submission of the environmental report by the tenants)	Tenants
Noise and Vibration	Noise level at the monastery and residences Traffic count	Tenants including Project Proponent	One time each in the dry and rainy seasons (first 3 years after starting the operation stage)	Tenants including Project Proponent
Offensive Odor	- Status offensive odor control by the tenants	Each tenant	Twice/year (submission of the environmental report by tenants)	Tenants
Bottom Sediment	- Water quality monitoring (as indicator of the pollution of the bottom sediment)	Same as the water quality monitoring	- Additional analysis on the bottom sediment of creek, in case of finding continuous high concentration	Project Proponent
Hydrological Situation	- Checking the function of retention pond at heavy rain.	Retention pond	When the heavy rain	Project Proponent
Living and Livelihood/	- The implementation status for	Around Project Site	Once/year	Project

effluent water from the project site to the existing canal.

Survey Item	Item	Location	Frequency	Responsible Organizations
Vulnerable Group/ Misdistribution of Benefit and Damage/ Children's Right	CSR activities such as community support program			Proponent
Risks for Infectious Disease such as AIDS/HIV	- Status of measures against infectious diseases	Each tenant	Twice/year (Submission of the environmental report by the tenants)	Tenants including Project Proponent
Occupational Health and Safety	- Record of accidents and infectious diseases	Work site and office	Twice/year (Submission of the environmental report by the tenants)	Tenants including Project Proponent
Community Health and Safety	- Record of accidents and infectious diseases related to the community	Around the project site	Twice/year (Submission of the environmental report by the tenants)	Project Proponent
	- The implementation status for CSR activities such as community support program	Around Project Site	Once/year	Project Proponent
Usage of Chemicals	- Record of the type and quantity of chemicals and implementation status of control measures through self-inspection	Each tenant (that uses chemicals)	biannually	Tenants

12. Institutional Arrangement

The organizational structure during the pre-construction, construction and closing phases for the Project is proposed as shown in Figure 7. The project proponent (MJTD) will outsource a contractor to implement the detailed design, construction and demolition work during the pre-construction, construction, phase and closing phase. The outsourced contractor will establish a project office (Zone B Project Office) to undertake the implementation of the detailed design and construction/closing works together with the environmental mitigation and management plan and the environmental monitoring, while the project proponent will supervise their works.



Source: EIA Study Team

Figure 7: Proposed Organizational Structure for Environmental Management of the Project during the Pre-construction, Construction, and Closing Phases

The organizational structure during the operation phase is proposed as shown in Figure 8. Each tenant will implement EMP and EMoP for each business and submit the environmental monitoring report to the One Stop Service Center (OSSC) of TSMC and copy to MJTD. On the other hand, MJTD will submit the monitoring report based on the results of implementation of EMP and EMoP for the project prepared by the contractor.




Figure 8: Proposed Organizational Structure for Environmental Management of the Project during the Operation Phase

13. Public Consultation and Public Disclosure

(1) Scoping Stage

In the scoping stage, three sessions of public consultation meeting (PCM) and public disclosure (PD) were conducted as shown in the following tables.

Table 15: Summary of Public Consultation Meeting for EIA at the Scoping Stage

Item	Description
Time and	(1) Saturday, 19 December 2015; 1st session: 9:30AM to 10:45AM
Date	(2) Tuesday, 22 December 2015; 2nd session: 9:30AM to 10:45AM, 3rd session: 3:00PM to 4:15PM
3.7	Convention Hall, Department of Human Settlement and Housing Development, Thilawa SEZ Management
Venue	Committee Office (Temporary), Thanlyin Township near Thilawa SEZ
	- Director, Environmental Conservation Department in Yangon Division, MOECAF
	- Deputy Commissioner, General Administration Dept., Yangon Southern District
	- Officers, General Administration Dept. in Thanlyin and Kyauktan townships
	- Officers, Housing Department, Ministry of Construction, Thanlyin Township
	- Township officers, Municipal Dept. and Rural Development Dept., Dept. of Health in Thanlyin Township
Invitees	and Kyauktan Township
	- Officers, Myanmar Port Authority, Ministry of Transportation
	- Relevant companies/factories in Thilawa SEZ
	- Local residents in and around Thilawa SEZ area
	- Project Proponent/developer and related government organizations (e.g., TSMC, MJTD)
	- Other organizations and individuals who are interested in the project
	1st session:347 people (men: 234, women: 113)
Attendee	2nd session: 35 people (men: 30, women: 5)
	3rd session: 48 people (men: 34, women: 14)
	- Brief explanation on the past EIA-related studies
Agenda	- Project brief on the industrial area, residential and commercial area and logistic area planned in Zone B area
Agenda	- Major positive and negative findings on the draft scoping results, scope of the EIA study
	- Further schedule of EIA
Language	In local language, Myanmar language
used	
Q & A	In total, eight questions were raised from the participants and discussed with the project proponent and
session	coordinating organization.
Feedback	In total, 18 comments in the three PCM sessions were submitted. Major comments and opinions are summarized
sheet	below.

Table 16: Main Questions in PCM at the Scoping Stage and Further Responses

No.	Comment	Further Response*
1	Request for clarification on the impact of the development of Zone B area on the road	To be considered as one of
	condition in this EIA study	CSR activities to plan.
2	Inquiry regarding the places where to submit the suggestions or comments of the public	Answered at PCM and no
3	Request for clarification on the impacts on air and soil due to the disposal of wastes by	further response required
	migrated workers	in EIA
4	Request for additional distribution of the summary of the scoping report	Considered in EIA stage
5	Inquiry regarding the area where the EIA study is implemented whether it is 700 ha or	Answered at PCM and no
	the entire area in Thilawa SEZ	further response required
6	Inquiry regarding the project plans for power supply and water supply in Thilawa SEZ	in EIA
	area	
7	Request for the arrangement of other resettlement site	
8	Inquiry regarding the impact on the health issue of local community by the	
	development of Zone B area in this EIA study	

Note: "Further Response" describes the necessity of additional response and the taken correspondence by the project proponent to the received comments or requests, opinion during PCM as of December 2015. Chapter number refers to the draft EIA report.

Table 17: Main Comment in Feedback Form at the Scoping Stage and Further Response

No.	Comment	Further Response
1	Request for assessing the impact on social environment adequately including indirect	Considered in draft EIA
	impacts to the local people	report (Chapter 7 & 9)
2	Clarification on the environmental mitigation measures and request for conducting	Considered in draft EIA
	appropriate environmental management	report (Chapter 7)
3	Degreest for taking the comments and original of the level residents into consideration	Considered in EIA stage
	Request for taking the comments and opinions of the local residents into consideration in the whole process of project	and in draft EIA report
	in the whole process of project	(Chapter 9)
4	Request for explaining the situation on natural environment periodically in the project	Considered in draft EIA
	Request for explaining the situation on flatural environment periodicarry in the project	report (Chapter 9)
5	Request for establishing a mutual understanding by direct discussions between the	Considered in draft EIA
	project developer and local people.	report (Chapter 10)
6	Appreciation for the increase in job opportunity caused by the Project.	Not required

Source: EIA Study Team

Note: "Further Response" describes the necessity of additional responses and the taken correspondence by the project proponent to the received comments or requests, opinion from feedback form as of December 2015. Chapter number refers to the draft EIA report.





Figure 9: Pictures of PCM at the Scoping Stage

Table 18: Summary of Public Disclosure for EIA at the Scoping Stage

Item	Description	
1.Disclosure period	Thursday, 31 December 2015 to Thursday, 14 January 2016 (ten working days)	
2.Disclosure place	A total of 12 places	
3.Comment submission method	Comments can be submitted with the comment form provided at the disclosure places or by e-mail either in Myanmar or English language.	

Item	Description	
4.Language used	In local language, Myanmar and English language	
5.Comments Two letters were received from the public. Major comments and opinions are summarized		

Table 19: Main Comment in PD at the Scoping Stage and Further Response

No.	Comment	Further Response
1	Clarification on the impact on the environment for public health concerns and the	Considered in draft EIA
	impact of air pollution and odor caused by the Project	report (Overall, Chapter 9)
2	Appreciation for the increase in job opportunity caused by the Project	Not required
3	Request for disclosure of the report for industrial area and logistic, residential and	Considered in EIA stage
	commercial areas in Zone B at the same time	
4	Request for inclusion of necessary information on the wastewater treatment to	Considered in draft EIA
	implement EIA in the report	report (Chapter 3)
5	Request for more explanation on the environmental and social issues at the closing	Considered in draft EIA
	phase	report (Chapter 7 & 8)
6	Request for preparing the report based on the results of field survey	Considered in draft EIA
		report (Chapter 6 & 7)
7	Request for inclusion of precaution plan against infectious diseases in the EIA report	Considered in draft EIA
	Request for inclusion of precaution plan against infectious diseases in the ETA report	report (Chapter 7 & 9)
8	Request for inclusion of information about the methods for prevention, management	Considered in draft EIA
	and punishment regarding waste management in the EIA report	report (Chapter 9)
9	Request to consider the impact on farmers (e.g., loss of income source) by the	Considered in draft EIA
	Project	report (Chapter 7)
10	Request for clarifying the impact on cultural heritage	Considered in draft EIA
	request for clarifying the impact on cultural heritage	report (Chapter 7)
11	Request for clarifying the impact on involuntary resettlement during construction	Considered in draft EIA
	work	report (Chapter 7)

Note: "Further Response" describes the necessity of and the taken correspondence by the project proponent to the received comments or requests, opinion during PD as of December 2015. Chapter number refers to the draft EIA report.

Source: EIA Study Team

(2) Draft EIA Stage

In the scoping stage, three sessions of public consultation meeting (PCM) and public disclosure (PD) were conducted as shown in the following tables.

Table 20: Summary of Public Consultation Meeting for EIA at the Draft EIA Stage

Item	Description		
Time and	(1) Saturday, 2 April 2016		
Date	1st session: 10:00 AM to 11:30 AM		
	(2) Thursday, 7 April 2016		
	2nd session: 10:00 AM to 11:30 AM, 3rd session: 1:30 PM to 3:00 PM		
Venue	Convention Hall, Department of Human Settlement and Housing Development, Thilawa SEZ Management		
	Committee Office (Temporary), Thanlyin Township near Thilawa SEZ		
Invitees	- Director, Environmental Conservation Department in Yangon Division, MOECAF		
	- Deputy Commissioner, General Administration Department, Yangon Southern District		
	- Officers, General Administration Dept. in Thanlyin and Kyauktan townships		
	- Officers, Housing Department, Ministry of Construction, Thanlyin Township		
	- Township officers, Municipal Dept. and Rural Development Department, Department of Health in		
	Thanlyin Township and Kyauktan Township		
	- Officers, Myanmar Port Authority, Ministry of Transportation		
	- Relevant companies/factories in Thilawa SEZ		
	- Local residents in and around Thilawa SEZ area		
	- Project proponent/developer and related government organizations (e.g., TSMC, MJTD)		
	- Other organizations and individuals who are interested in the Project		
Attendee	1st session: 110 people (men: 68, women: 42)		
	2nd session: 65 people (men: 39, women: 26)		
	3rd session: 2 people (men: 2, women: 0)		
Agenda	- Outline of the Thilawa SEZ Project (Zone B)		
	- Results of Baseline survey		
	- Results of Impact assessment results		

Item	Description	
- Proposed mitigation measures, environmental management and monitoring plans		
- Institutional Arrangements		
	- Public consultation and public disclosure	
	- Conclusion and Further EIA schedule	
Language	In local language, Myanmar language	
used		
Q & A	In total, nine questions were raised from the participants and discussed with the project proponent and	
session	coordinating organization.	
Feedback	In total, seven feedback sheets were submitted in the three PCM sessions. Major comments and opinions	
sheet	are summarized below.	

Table 21: Main Questions in PCM at the Draft EIA Stage and Further Responses in EIA

No.	Comment	Further Response
1	Request for provision of the extra volume of water to religious places and local	To be considered as one of CSR
1	people around the project area	activities to plan
2	Request for description of the long-term plan for industrial waste management	Considered in EIA report
	and detail explanation about the domestic waste management.	(Chapter 3 &7)
	Request for detail description of the impact and mitigation measures of	Considered in EIA report
3	HIV/AIDS and chemical usage, environmental management plan, closing system	(Chapter 10)
3	and the employment contract, the organization structure, responsibility, members	
	of monitoring system in pre-construction and operation phase.	
4	Request for simple explanation about the impact on air quality so that local	Answered at PCM and no
_	people can understand.	further response required
5	Question about job opportunity for the affected vulnerable people, Request for	Considered in EIA report
	monitoring continuously for the vulnerable people even in the closing phase.	(Chapter 7&10)
6	Concern about too much watering that might cause accidents.	
7	Request for visiting house by house and explain this report to the people who	Answered at PCM and no
,	cannot attend today.	further response required
		- To forward the comment to the
8	Worry about no electricity along the Dagon-Thilawa road that might cause	related department
	accident.	- To be considered as one of CSR
		activities to plan.
9	Question about the housing plan for workers.	Answered at PCM and no further
9	Question about the housing plan for workers.	response required

Note: "Further Response" describes the necessity of additional responses and the taken correspondence by the project proponent to the received comments or requests, opinion during PCM as of April 2016.

Table 22: Main Comment in Feedback Form at the Draft EIA Stage and Response in EIA

No.	Comment	Further Response in EIA
1	Request for implementation of planting program	Planting program will be planned by the project proponent
2	Clarification on disadvantages of environment to the community definitely.	Considered in EIA report (Chapter 7)
3	Request for considering the issues regarding health, social and other of local people in the surrounding area of Thilawa SEZ.	The project proponent will plan health care program.
4	Request for implementation of the project effectively.	Not required
5	Agree. Good.	Not required
6	Expectation of job opportunity for local people by the project.	Not required
7	Concern about drainage system that might cause some risk in rainy season	The improvement of drainage system
	if it is not properly set.	will be planned by the project proponent
8	Agree with the project that will provide job opportunity to the local people.	Not required
9	Request for implementation of EIA according to the international standards.	Not required
10	Request for provision of educational program to local people.	Not required
11	Worry about no electricity along the Dagon-Thilawa road that might cause accident.	The comment is forwarded to MOC. To be considered as one of CSR activities to plan.
12	Question if there is any plans to protect workers from the heat.	Announcement to construction contractor will be given for the prevention of heat stroke by the project

No.	Comment	Further Response in EIA	
		proponent	

Note: "Further Response" describes the necessity of additional responses and the taken correspondence by the project proponent to the received comments or requests, opinion from feedback form as of April 2016 Source: EIA Study Team

Table 23: Summary of Public Disclosure for EIA at the Draft EIA Stage

Item	Description	
1.Disclosure period	Thursday, 24 March 2016 to Saturday, 23 April 2016 (one month)	
2.Disclosure place	A total of 16 places 1) Yangon Southern District General Administration Office 2) Thanlyin Township General Administration Office 3) Kyauktan Township General Administration Office 4) Thilawa SEZ Management Committee Office (Temporary) near Thilawa SEZ; and 5) Myanmar Japan Thilawa Development Limited Office in Thilawa SEZ 6) Seven (7) Village Tracts/Ward Office in Thanlyin and Kyauktan Township; - Hpa Yar Kone Village Tract Office - Let Yet San Village Tract Office - Ah Lun Soke Village Tract Office - Aye Mya Thi Dar Ward Office - Shwe Pyi Thar Yar Ward Office - Thi Tar Myaing Ward Office - Shwe Pyauk Village Tract Office 7) 100 household head's and other villager's house (4 places)	
3.Comment submission method	Comments can be submitted with the comment form provided at the disclosure places or by e-mail either in Myanmar or English language.	
4.Language used	In local language, Myanmar and English language	
5.Comments	One letter was received from the public. The comments and opinions are summarized below.	

Source: EIA Study Team

Table 24: Main Comment and Response in PD at the Draft EIA Stage

Comment	Further Response
Request for explanation of the EIA procedure to local people to understand easily and more	Follow up meetings were
clearly.	organized as shown Table
Request for sending the related EIA documents before public consultation meeting in order	19 and the result was
to secure enough time to review these documents.	considered in EIA report
Request for simple explanation in EIA documents with simple words for better	•
understanding.	
Request for extension of the disclosure period.	

Note: "Further Response" describes the necessity of additional responses and the taken correspondence by the project proponent to the received comments or requests, opinion during PD form as of May 2016

Source: EIA Study Team

In response to the public comment that requests for more simple and clear explanation, the follow up meetings were organized two times in 10 and 18 May 2016 in order to have the opportunity to discuss and solve question and problem with villagers. The outline of the follow up meetings is summarized in Table 20. Through the follow up meeting, a lot of questions were raised and it was answered by MJTD and OSSC, EIA Study Team. Unclear points from villagers were mostly disappeared and better understanding among stakeholders was established.

Table 25: Summary of Follow-up Meetings

Item	1 st Follow-up meeting	2 nd follow-up meeting
Time & Date	Tuesday, 10 May 2016, 10:30 -12:30	Wednesday, 18 May 2016, 15:00 -17:00
Venue	Meeting room of MJTD	Meeting room of TSMC
No. of Attendee	Total 5 people	Total 19 people
Main	- Thilawa Social Development Group	- Thilawa Social Development Group
Participant	- Community Relation Department, MJTD	- Environmental Section of OSSC, TSMC
Farticipalit	- EIA Study Team	- Community Relation Department, MJTD

Item	1st Follow-up meeting	2 nd follow-up meeting
		- EIA Study Team
Main Discussion	- Expected impact of air pollution, waste water, chemical usage, solid waste, involuntary resettlement, and vulnerable group by the Project - Expected impact of each tenant depending on the type of business - Activities of environmental management in Zone A	- Process of EIA, IEE, EMP described in EIA Procedure - Activities on Environmental Protection in OSSC - Methodology and result of Field Survey - Arrangement of PCM and PD - Treatment system of wastewater - Issue on involuntary resettlement - Example case of other industrial areas

The following three comments were proposed from villagers for taking into consideration as much as possible and to describe in the EIA report.

Table 26: Summary of Comment and Correspondence in Follow-up Meeting

No.	Comment	Correspondence
1	To consider public involvement on the environmental	The plan for public involvement is described in
	monitoring during construction phase and operation phase.	Chapter 11 as Stakeholder Engagement Plan in Section
		11.1.3.
2	To add more description and explanation in Chapter 7 for	Additional description is added regarding involuntary
	Environmental and Social Impact Assessment especially for	resettlement in Section 7.13.
	Involuntary Resettlement.	
3	To disclose the information of each tenant regarding EIA/	TSMC will consider the availability of the information
	IEE requirement, the contents of EIA, the situation and	disclosure regarding IEE/EIA for each tenant.
	condition on the approval of EIA to the public.	

Source: EIA Study Team

(3) Public Consultation and Public Disclosure for the Resettlement Work Plan (RWP)

A series of PCMs and PD is planned to be implemented based on the Framework of Resettlement Works for the 2,000 ha Development Area of Thilawa Special Economic Zone (SEZ) released by TSMC in February 2016. In the framework, the 2,000 ha of the development area is broadly divided into Area 1 to Area 6 and moreover, some RWP areas are divided into small parts in terms of the smooth implementation of resettlement works and the timing of the actual development.

The industrial area is composed of 4 RWP areas which are Area 2-1, a part of Area 2-2 and 2-3, and Area 4-1. The resettlement works for Area 2-1 already started to implement as the first step since Area 2-1 is currently determined as the initial development area. Based on the situation above, two times of PCM for Area 2-1 at the draft RWP stage were implemented in 14 February and 27 March 2016. The summary of the PCM is described in Table 27. Afterwards, the draft RWP for Area 2-1 disclosed from 29 February 2016 to 8 April 2016 for forty days in nine places in and around Thilawa SEZ. In addition, the draft RWP both in English and Myanmar language was uploaded on the website of TSMC. Public comments were collected with the comment form at the disclosure places or by e-mail either in Myanmar language or in English.

PCM and PD for the other RWP areas will be implemented according to the actual development schedule step by step.

Table 27: Summary of PCM for the Draft RWP (Area 2-1)

Items	1st PCM	2nd PCM
1. Date and time	14:00 – 16:30, Sunday, 14 February 2016	9:00AM- 10:30AM, Sunday, 27 March 2016
2. Venue	Ordination Hall, Aye Myar Thida Ward (Phalan),	Ordination Hall, Aye Myar Thida Ward (Phalan),
	Kyauktan Township	Kyauktan Township
3. Invitee	PAHs for Area 2-1	PAHs for Area 2-1
4. Participant	Approximately 95 persons	30 PAHs and 41 other participants; 71 persons
		as a total

Items	1st PCM	2nd PCM		
5.Main	· Administrator, General Administration Department, Thanlyin Township			
invitees/partic	· Administrator, General Administration Department, Kyauktan Township			
ipants from	Village Administrator, Shwe Pyi Thar Yar Village Tract			
government/o	 Village Administrator, Aye Mya Thida Ward 			
thers	• 100/10 household head leader, Shwe Pyi Thar Y			
	• 100 /10 household head leader, Aye Mya Thida			
	 Villagers from Shwe Pyi Thar Yar Village Tract 			
	· Villagers from Aye Mya Thida Ward			
	 Other organizations and individuals who are interest 			
6. Agenda	Background and RWP activities	Background and RWP activities		
	2) Area of 100 ha for initial development area	2) Summary of the past consultation meetings incl.		
	(Area 2-1)	village level meetings		
	3) Eligible households for Area 2-1,	3) Eligible households for Area 2-1		
	4) Proposed compensation and assistance package	4) Proposed compensation and assistance package with detailed assistance allowances		
	5) Planned implementation organization	5) Possible resettlement sites		
	Planned grievance redress mechanism	Planned IRP activities		
	7) Possible relocation sites	7) Planned implementation organization		
	8) Further steps	Proposed grievance redress mechanism		
	9) Q & A session	9) Further steps and expected timeline for Area		
		2-1		
		10) Other activities for Area 2-1 in the near future		
		11) Q & A		
7. Major	1) Inquiry on the status of the affected cemetery	1) Request for the implementation about the entire		
opinions and	located inside Area 2-1 by the development	700ha together with 100ha.		
comments	2) Inquiry on the status of the affected cows	2) Request for the explanation of land		
from the participants	raising on pasture land inside Area 2-1 by the development	compensation of local people from the 200ha of Thilawa SEZ (from area 6).		
	3) Request for clarification on the area and	3) Inquiry regarding the name of ownership.		
	situation of the land acquisition process and	4) Request for the relocation together with the		
	La Na-39	cemetery and big tree to the place nearby.		
	4) Inquiry on the reason to pay the tax for land	5) Inquiry regarding the land compensation for		
	even after La Na-39 was issued	farm land and garden land.		
	5) Request for proceeding land acquisition,	6) Request for the IRP planned before		
	resettlement, and income restoration program	resettlement.		
	not only for 100 ha (Area 2-1) but also for	7) Request for the implementation of the project in		
	262 ha	accordance with 2012 farm land law.		
	6) Request for answering to the request letter	8) Complain related with their farmland not to		
	which was submitted three months ago to	accept for the construction of living structure.		
	TSMC but has not been replied yet			
8. Feedback	No comments and opinions were submitted in the	Fours comments and opinions were submitted in		
form	collected feedback form.	the collected feedback form.		

Source: Thilawa SEZ Management Committee, Resettlement Work Plan (RWP) for Development of Area 2-1 (100ha) of Thilawa Special Economic Zone (Draft) February, 2016





Source: Thilawa SEZ Management Committee, Resettlement Work Plan (RWP) for Development of Area 2-1 (100ha) of Thilawa Special Economic Zone (Draft) February, 2016

Figure 10: Pictures of PCM for RWP of Area 2-1

14. Comments from TSMC

TSMC issued an approval letter (Ref: TSEZ-EIA-003) of the Scoping Report on Environmental Impact Assessment for Development of Industrial Area of Zone B in the Thilawa Special Economic Zone on 26 February 2016 with terms and conditions. The Project Proponent prepared the draft EIA report which corresponds to these terms and conditions as shown in Table 28.

Table 28: Correspondence to the Terms and Conditions from TSMC (Scoping Report)

No.	Terms and Condition from TSMC	Correspondence
(i)	You shall describe the contact address, profile, and relevant	Information of the implementation organizations of
	experience of the organization which has been conducting the	EIA was described in Chapter 1 of the draft EIA
	EIA study as well as information on environmental, social,	report. CVs of each experts of the EIA Study Team
	and health experts as key personnel including each person's	were attached in Annex.
	experience in the field of environmental, social, and health	
	impacts assessment, academic credentials, and relevant	
	certificates and accreditations.	
(ii)	You shall describe international conventions, treaties, and	Major international conventions, treaties, and
	agreements related to your project as the project's policy and	agreements that the Myanmar government has ratified
	legal framework.	related to the Project were described in Chapter 2 of
		the draft EIA report.
(iii)	You shall set project's target levels for environment taking	Taken into account the Myanmar National
, ,	into consideration the Myanmar National Environmental	Environmental Quality (Emission) Guideline, the
	Quality (Emission) Guidelines issued by the Ministry of	project's target levels were revised and described in
	Environmental Conservation and Forestry on 29 December	Chapter 2 of the draft EIA report.
	2015 and conditions of surrounding area.	
(iv)	You shall describe the institutional arrangement for	Institutional arrangements for environmental
	environmental management by your organization including	management for two stages; (i) pre-construction,
	the organizational chart, a section in charge of environment,	construction and closing stages and (ii) operation stage
	and its role and responsibility in construction stage and	were summarized in Chapter 2 of the draft EIA report.
	operation stage at least.	•
(v)	You shall describe the detailed project information in order to	Detailed project information was presented in Chapter
	assess the environmental, social, and health impacts properly.	3 of the draft EIA report.
(vi)	You shall include socio-economic components such as access	Impact on accessibility to public services and natural
	to public services and natural resources in the TOR for the	resources was included in the TOR for the EIA
	EIA investigation in order to assess social impacts properly.	investigation and assessment in Chapter 7 of the draft
		EIA report.
(vii)	You shall conduct scoping evaluation for impacts on soil	Impacts on soil erosion, usage of chemicals, and
	erosion, usage of chemicals, and earthquakes, and shall	earthquakes were considered for scoping and
	conduct its impact assessment if needed.	evaluated in Chapter 7 of the draft EIA report.
(viii)	You shall conduct scoping evaluation for residual impact in	Residual impacts in the stage after project closure
	the stage after project closure and conduct impact assessment	were considered in Chapter 8 of the draft EIA report.
	if needed.	
(ix)	In addition to the impact assessment for the development of	Cumulative impacts of the development of Zone A
	the industrial area of Zone B, you shall assess cumulative	were taken into consideration when impacts of the
	impact including the development of Zone A and the	Project were assessed in Chapter 7 of the draft EIA
	development of the logistic area and residential and	report.
	commercial areas of Zone B.	Impacts which should be assessed cumulatively such
		as air and noise/vibration were evaluated in
		consideration of Zone B development including
		logistic, residence and commercial area.
(x)	You shall reflect all of the above comments to the draft EIA	The comments received from TSMC were considered
	report.	to be reflected in the draft EIA report.
	EIAG. 1 FE	•

Source: EIA Study Team

The Thilawa SEZ Management Committee (TSMC) issued a notification (TSEZ-EIA-005) regarding the comments for the draft EIA Report on Environmental Impact Assessment for Development of Industrial Area of Zone B in the Thilawa Special Economic Zone on 17 May 2016. The project proponent prepared the final EIA report which corresponds to the terms and conditions as shown in Table 29.

Table 29: Correspondence to the Comments from TSMC (OSSC) (Draft EIA Report)

	Chapter/ Section	Findings	Comments	Correspondence
1	Common	-	Names of the Ministry and numbers of ministry which reformed in April 2016 shall be revised in the Final EIA report	In accordance with the comments, names of the ministry and numbers of ministry are modified in the final EIA report.
2	Common	A letter of endorsement by the Project Proponent is not attached in the draft EIA Report.	The project proponent shall issue a letter of endorsement and attach in the Final EIA Report.	A letter of endorsement issued by the project proponent is attached in the final EIA report.
3	Common	EIA study team has not registered to the Environmental Conservation Department (ECD) of Ministry of Natural Resources and Environmental Conservation for undertaking EIA.	EIA study team shall submit application form for registration of undertaking EIA to the ECD before submission of the Final EIA Report.	Nippon Koei Co, Ltd., that EIA Study team belongs to, submitted the application form for registration to the ECD and the ECD received it on May 11, 2016.
4	Common	Resettlement Work Plan (RWP) including Income Restoration Plan (IRP) for PAHs are prepared and will be implemented by TSMC. The project proponent is a position to wait for completion of resettlement before signing "Land Lease Agreement" and start construction. After land lease agreement, the project proponent is a position to support income restoration for PAHs indirectly through TSMC after the Land Lease Agreement.	It is recommended that finalization of the RWP and completion of the signing compensation/ assistance with PAHs shall be a condition in the approval letter of EIA to start construction work.	The project proponent will follow the comment.
5	Common	Cumulative impact assessments are implemented for only air, water, noise, and vibration. The impacts on flora/ fauna and biodiversity, and community health and safety are not described.	The cumulative impact on flora/ fauna and biodiversity, and community health and safety, and traffic (for both construction and operation stages) shall be described in the Final EIA Report.	In accordance with the comments, the cumulative impact on flora/ fauna and biodiversity due to the clearing of vegetation land are added in Section 7.9 (p.7-52– p.7-54), and the cumulative impact on public safety and security due to the increase of traffic and population among local community are added in Section 7.25 (p.7-91 – p.7-92). In addition, new chapter for the cumulative impact assessment, as Chapter 8, is added and explains environmental items, basic concept and reference section of Chapter 7 of Final EIA report.(p.8-1 and p.8-2)
6	Common	Proper environmental management mechanism by tenant and sub-zone development shall be secured.	It shall be described in the Final EIA Report that ECPP (kind of EMP), IEE or EIA for each projects/factories in Zone B shall be conducted.	In accordance with the comments, contents of ECPP, IEE or EIA that should be conducted by each projects/factories is described in Section 2.7.1. (p.2-20 – p.2-24).
7	Common	Project Commitments is not clearly mentioned in the draft EIA Report.	The Project Proponent should provide a clear list of commitments that the Project will undertake. This includes compliance with the relevant laws and standards and all proposed mitigation measures to be undertaken. This should include the provision of adequate services for the workers on the SEZ (which may include medical services and other services). It would	In accordance with the comments, commitments that the Project will undertake including relevant laws, standards, and proposed mitigation measures to be conducted is summarized in Annex 10-1. On the other hand, activities of CSR are described in Section 2.7.3(3) (p.2-27 — p.2-28)

	Chapter/ Section	Findings	Comments	Correspondence
			also include any mitigation measures to be carried out for the whole SEZ, including waste management and landscaping. CSR should be treated as a separate component. It is not to be considered as a part of the requirements of the EIA. It may be included but separate from the Project Commitments.	
8	Common	The results of PCM are not mentioned in Executive Summary.	The results of PCM shall be added to Executive Summary in the Final EIA Report.	In accordance with the comments, the results of PCM at draft EIA stage are summarized in the Executive Summary. Moreover, the further responses to the received comments are briefly described.
9	Executive Summary Table 6	Living and livelihood: Impacts and mitigation must be considered as part of EIA not as CSR.	Wording of results of impact assessment shall be reconsidered in the Final EIA Report.	In accordance with the comments, wording of results of impact assessment is revised in the Executive Summary.
10	Executive Summary Table 6	Flood risk-low impact due to EL – 5m	It shall be described in the Final EIA Report how have climate change impacts been modeled and considered over life of project including increase floods, cyclones and sea level rise.	In accordance with the comments, consideration of climate change impacts, increasing of floods, cyclone and sea level rise for setting the elevation level are added in Section 3.4. (p.3-6)
11	Executive Summary Table3-8	Impacts and mitigation measures	Does not address existence of vulnerable and near threatened species of fauna.	Considerations for existence of vulnerable and near threatened species of fauna are mentioned in the Executive Summary and Section 7.9.5. (p.7-4, p.7-52– p.7-54)
12	Chapter 2	-	Proponent's corporate environmental and social policies should be provided in detail (if available).	In accordance with the comments, it is described in Section 2.1 that the project proponent joins UN Global Compact which focuses on the areas of Human Rights, Labor, Environment and Anti-corruption. (p.2-1)
13	Chapter 2 2.1.2 Fundamental Laws and Regulations related to Environmental and Social Consideration	- It is described the fundamental laws and regulations related to the environmental and social considerations in Myanmar. But, some related laws are needed to mention in table 2.1-1 and summary of related laws Some of the laws referred in some chapters of the report are not described in table 2.1-1.and summaries of key laws, such as the Shops and establishment Act (2051) and The Factories Act (2051) Prevention of Hazard from chemicals and related substances law was enacted in 2013, not in 2003.	The following modification shall be implemented in the Final EIA Report. - To change the enacted year of Prevention of Hazard from Chemical and Related Substances Law. (not in 2003, enacted in 2013) - To describe some internal laws in table 2.1-1 and summarize some important laws such as: - Prevention of Hazard from Chemical and Related (2013) - Substances Law (2013) - Labour Dispute Settlement Law (2012) - Foreign investment law (2012) - Myanmar Citizen Investment Law - Social Security Law (2014) - Boiler Law (2015) - Export and Import Law	In accordance with the comments, the said laws and acts were added in Section 2.2.2 (p.2-1 – p.2-7).

	Chapter/ Section	Findings	Comments	Correspondence
14	Chapter 2 2.1.2 Fundamental Laws and Regulations related to	- It is described about the major international agreements and Treaties that the Myanmar has ratified related to environment and social considerations in table 2.1-2.	(2012) - Electricity Law(2015) - Labour Organization Law(2011) - Workmen Compensation Act(1955) - The Prevention and Control of Communicable Diseases Law - Payment of Wages Law/Rules - Factory Act (1951) - The Explosive Act(1987) - The Explosive Substances Act(1908) - Heritage Goods Protection Law(2015) - The Conservation of Water Resources Law(2006) - The Conservation of Water Resources Rules(2013) - The Shops and Establishment Act(1951) - Leaves and Holidays Act (1951) - Minimum Wages Law and Rules (2013) - Employment and skill development law (2013) The following international conventions and treaties shall be added. a) Vienna Convention (1985) b) Montreal Protocol (1989)	In accordance with the comments, the said laws and acts were added in Section 2.2.2. (p.2-3)
15	and Social Consideration Chapter 2 2.2.1 Air Quality	Target level of emission gas is not described. Some tenants have a plan to install small-medium combustion facilities such as boiler and melting furnace.	Besides target level of ambient air quality, target level of emission gas shall be set taking into consideration of National Environmental Quality (Emission) Guidelines.	In accordance with the comments, target level of emission gas as well as ambient air quality set in National Environmental Quality (Emission) Guidelines is added in Section 2.4.1. (p.2-8 – p.2-10)
16	Chapter 2 2.2.1 Air Quality	In 2.2.1, it is described that there is no ambient air quality standard in Myanmar. But, ambient air quality standards are mentioned in MEQG. In table 2.2-2, there is no MEQG value in parallel with other standards.	In table 2.2-2, MEQG value should be added in order to correlate the other standards.	In accordance with the comments, NEQG value is added in Section 2.4.1 and the tentative target value of the Project is reconsidered. (p.2-8 – p.2-10)
17	Chapter 2 2.3 Institutional Arrangement	-	Remaining ministries at the OSSC, such as Central Bank, Ministry of Industry, etc shall be added.	In accordance with the comments, members of OSSC are modified in Section 2.6.1. (p.2-18)
18	Chapter 2 2.3 Institutional Arrangement	-	Table 2.3-5 shall be included more detailed information CSR activities by the Project Proponent (list of activities with date, number of participants, etc.), describe the effective period of the CSR activities	In accordance with the comments, detailed information of CSR activities by the project proponent are added in Section 2.7.3(3). (p.2-27 – p.2-28)

	Chapter/ Section	Findings	Comments	Correspondence
19	Chapter 3	Project development and implementation time schedules are not described (It is required by EIA Procedures.).	Project development and implementation time schedules shall be described in the Final EIA Report.	In accordance with the comments, project development and implementation time schedule are added in Section 3.12. (p.3-22)
20	Chapter 3 3.4 Land reclamation	Detailed information on materials for land reclamation from outside is not clear.	For the land reclamation plan, estimates of the amount of materials (rock, gravel, and sand) from outside, source, and expected mitigation measures in sourcing, transporting, placing shall be described if available.	The excavated volume and embankment volume are planned to be balanced in the development area. Since the land reclamation plan including the amount of materials will be prepared by the construction contractor in the construction phase, the land reclamation plan is not described in the final EIA report.
21	Chapter 3 3.6 Drainage Plan	The capacities of retention pond and retention canal for prevention of flood are not found. It is difficult to assess flood risk inside of the Project Site.	The capacities of retention pond and retention canal for prevention of flood shall be described in the Final EIA Report.	In accordance with the comments, the capacities of retention pond and retention canal are added in Section 3.6. (p.3-10 – p.3-11)
22	Chapter 3 3.7.2 Water Supply Distribution System	Capacity of the existing centralized wastewater treatment system of Zone A and estimated wastewater volume from Zone A are not described. Thus it is difficult to evaluate whether the treatment system still have enough capacity of receiving wastewater from Zone B tenants in the initial phase.	The capacities of existing treatment system and estimated wastewater volume from the Zone A at the timing of starting operation of Zone B shall be described.	In accordance with the comments, The capacities of existing treatment system and estimated wastewater volume from the Zone A at the timing of starting operation of Zone B is added in Section 3.7.2. (p.3-13 – p.3-14)
23	Chapter 3 3.8.2 Wastewater Treatment Plant	Target parameters of design wastewater quality are only BOD and SS (Table 3.8-2). However some parameters after primary wastewater treatment (Table 2.2-4) such as iron, silver, total phosphorus, ammonia, and fluoride are not covered compare with the target wastewater quality discharging to water body (Table 2.2-7). It is not clear that which treatment facilities (pre-treatment by tenant or centralized wastewater treatment) will treat these parameters.	The design wastewater quality and diagram of wastewater treatment or target level of wastewater quality after primary wastewater by tenant shall be revised to archive the target wastewater quality discharging to water body. In addition, information on the location of waste water treatment plant and mention more clearly about treatment plant capacity, facilities and final discharge system shall be described.	In accordance with the comments, the target level of wastewater quality after primary wastewater treatment is modified in Section 2.4.2. (p.2-11-p.2-14)
24	Chapter 3 3.10 Solid Waste Management	It is described that the waste which cannot be reused or recycled may be managed by the waste treatment firm in Zone A or through public service such as by the Pollution Control and Cleansing Department of the Yangon City Development Committee (YCDC).	Are there any internal regulations for tenants particularly regarding the disposal of hazardous waste? If there is no instruction to tenants, it may be arisen an issue due to improper disposal ways particularly for hazardous waste.	There is a regulation for disposal of hazardous waste in the proposed internal regulation for the Industrial area. In accordance with the comments, the proposed internal regulations for tenants particularly regarding the disposal of hazardous waste is added in Section 3.10. (p.3-19 – p.3-20)
25	Chapter 3 3.10 Solid Waste Management	In figure 3.10-1, type of treatment will not be representing the solid waste management of project proponent.	The solid waste management of industrial area by the project proponent should be mention clearly. Need to provide the detailed information on the estimate annual amount of hazardous wastes (if possible) and disposal system.	In accordance with the comments, the solid waste management of the industrial area by the project proponent is added in Figure 3.10-1. (p.3-20) The detailed information on the disposal system are described in Section 4.3.7 (3). (p.4-21 – p.4-24) However, the estimated annual amount of hazardous wastes is not described in final EIA report. Because type of tenant has not been fixed at

	Chapter/ Section	Findings	Comments	Correspondence
				this stage. The project proponent will monitor the amount and type of waste from each tenant in all phases. It is described in Section 10.2 (p.10-13)
26	Chapter 3 3.11 Greening Plan	The area information of greening is not described in this section. The information will be a basic indicator of mitigation measures for flora, fauna, and ecosystem.	Area information of greening in the non-sales area shall be added to Section 3.11 and monitored as a part of environmental monitoring plan.	In accordance with the comments, the area information of greening in non-sales area is added in Section 3.11. (p.3-20 – p.3-21)
27	Chapter 4	The SEZ is one of the large areas located on the bank of Yangon River. Baseline information on river water quality and biodiversity of the river.	Baseline survey for river water quality is recommended to implement in order to identify impact on water pollution before and after development of SEZ.	In accordance with the comments, Yangon River water quality data is added in Section 4.1.2. (p.4-4 – p.4-5) However, it is expected that inflow impact of Yangon River will not present clearly, because Yanon River average flow rate is estimated over seven hundred times larger than that of Shwe Pyauk Creek crossing Thilawa SEZ including maximum wastewater from Zone A and Zone B. In addition baseline data in Yangon River would be not stable and change depending on time or location, because Yangon River is mixed by tidal influence and its basin has a lot of pollutant source such as industry, agriculture, residence and transportation of tanker. In consideration of situation above, Shwe Pyauk Creek was set as the forecast area and survey point, in order to identify and evaluate the impact on water body due to the implementation of the Project.
28	Chapter 4	Public health components (Infant mortality rate, Maternal Mortality Rate, Crude Death Rate, morbidity, occurrence of diseases, Communicable diseases Incidence under DUNS, accidents and injuries, and social health determinants) are not mentioned.	Public health components shall be included in the Final EIA Report.	In accordance with the comments, current situation regarding public health components around the project area is added in Section 4.3.8. (p.4-28 – p.4-30)
29	Chapter 4 4.1.4	Existing noise assessment: The ambient noise measures taken in April 2013 show that the noise level during daytime along the road is above the criteria. The noise levels are acceptable level during nighttime. It is proposed to increase this level from 58 dB(A) to 70 dB(A) along the roadway. See Table 2.2-11 at page 2-12. No justification has been provided for this.	Results of noise monitoring shall be reconsidered to make consistency.	Noise level from traffic is different characteristic from ambient noise, and generally higher. Though the target noise level for living area (Table 2.4-7) is set in NEQG, there is no target level specified for traffic noise along the road in NEQG. Therefore, tentative target levels for traffic noise along the road are set in accordance with the Japanese traffic noise target level (Table 2.4-10), in this EIA study. In accordance with the comment, target values for noise are installed in Table 4.1-8, which was referred to the EIA Report for the Thilawa SEZ Class A development project (September 2013). (p.2-14 – p.2-16, p.4-6)
30	Chapter 4 4.2.6 Flora, Fauna, and Biodiversity	Information of natural conservation area such as reserved forests in the surrounding area of the Project	Information on natural conservation area such as reserved forests shall be added to Section 4.2.6. The impact	There is no protected area including natural reserve, national park, wildlife sanctuary and bird sanctuary around Thilawa SEZ. On the other hand,

	Chapter/ Section	Findings	Comments	Correspondence
		site is not described. This information is a basic information to assess impact on flora, fauna, and ecosystem.	on flora, fauna, and ecosystem shall be assessed based on the information if necessary.	there is a reserved forest (553 acer) located around Ban Bwe Gon Dam in Kyauktan Township, 3km away from Thilawa SEZ. There is no impact on this reserved forest due to the implementation of the Project. In accordance with the comments, information on reserved forest is added in Section 4.2.6. (p.4-12 – p.4-14)
31	Chapter 4 4.3.6 Livelihood	Not mention about the Livelihood of people relying on the creeks	Information on the livelihood of those persons using the creeks to access the agriculture land shall be added in the Final EIA Report.	In accordance with the comments, the information on the livelihood of those persons who are using the creeks to access the agriculture is added in Section 4.3.6. (p.4-16 – p.4-17)
32	Chapter 4 6.3 Noise	Tables 2.2-10 and 2.2-11 The noise levels set in the MEQS related to impact at receptors. The MEQS would apply unless the project can justify why any level should be chosen. The receptor should be the most sensitive point at the location closest to the source. In the case of traffic there needs to be an assessment of the number and type of vehicles and the transport routes to be taken. Noise assessments within the SEZ are likely to be high. Whilst each tenant will be required to adopt noise mitigation measures and provide hearing protection where required, this should also be a requirement of the TSMC.	The justification of the reason why tentative target noise level from traffic in the Table 2.2-11 shall be described in the Final EIA Report.	Noise level from traffic is different characteristic from ambient noise, and generally higher. Though the target noise level for living area (Table 2.4-7) is set in NEQG, there is no target level specified for traffic noise along the road in NEQG. Therefore, tentative target levels for traffic noise along the road are set in accordance with the Japanese traffic noise target level (Table 2.4-10), in this EIA study. In accordance with the comment, the justification of the reason why tentative target noise level from traffic is described in Section 2.4.3 of the Final EIA Report. (p.2-14 – p.2-16)
33	Chapter 7 7.1 Summary of Environmental and Social impact Assessment	In table 7.1-1, it is described that increasing of traffic volume might be affect the safety of children and project proponent shall design the mitigation measures for security of school children. It is also not link with 7.17.1 Forecast Item of Children's Rights. But in chapter (9), there is no mitigation measure for that and also need to link with 7.17.1.	Consistency among Section 7.1 (summary of impact assessment), Section 7.17 (Forecast Results) and Section 9.1 (Mitigation Measures) shall be ensured in the Final EIA Report.	In accordance with the comments, Section 7.1 and 10.1 are modified in order to ensure the consistency regarding Section 7.18. For the impact on the traffic safety for children due to the increase of traffic volume is considered and described in Section 7.25.(p.7-91 – p.7-92) In addition, the other section is also clarified to ensure the consistency among Section 7.1, forecast results in each section and Section 10.1 of the Final EIA Report.
34	Chapter 7 7.2 Air Quality	In the note in Page 7-8, it is understandable that NO2 is representative parameter for impact assessment on air quality from vehicle among NO2, SO2, and CO. However, it is not clear why impact on PM is not described. Some impact may be occur due to construction activities in and around Thilawa SEZ.	Impact on PM from vehicle shall be assessed in the Final EIA Report	In accordance with the comments, impact on PM10 from vehicle is added in Section 7.2. (p.7-13, p.7-18 – p.7-22)
35	Chapter 7 7.2 Air Quality	With respect to impact from tenants in Industrial and Logistic Area, some tenants in Zone A have already had a plan to install small-medium combustion facilities such as boiler and melting furnace. Impact assessment shall be implemented	Impact assessment on emission from tenants in Industrial and Logistic Area shall be implemented taking into consideration of Internal Regulations of Zone A and Appraisal of ECPP by OSSC/ TSMC.	In accordance with the comments, impact of emission from tenants in the industrial area and the logistic area is assessed taking into consideration of proposed internal regulations of Zone B and appraisal of ECPP by OSSC/TSMC in Section 7.2.5, 2). (p.7-23)

	Chapter/ Section	Findings	Comments	Correspondence
		taking into consideration of Internal Regulations of Zone A and Appraisal of ECPP by OSSC/ TSMC.		
36	Chapter 7 7.3 Water Quality	Clarify the approach for the impacts on water quality. Verify that Shwe Pyauk Creek is the only tidal river and stream that will be affected by discharges from the Industrial estate. Indicate the reason that data on the actual flow in Shwe Pyauk Creek was not collected and used for the impact assessment. Indicate why the impacts on water quality in Yangon River were not considered by the EIA. Estimate the water quality impacts on Shwe Pyauk Creek assuming rainy season flow conditions and dry season flow conditions.	The reason why water quality survey and impact assessment was not taken into account of tidal affect from Yangon River shall be described in the Final EIA Report.	In accordance with the comments, the reason of selection of the forecast area of water quality is described in Section 7.3.2. (p.7-24 – p.7-25)
37	Chapter 7 7.3 Water Quality	Total wastewater from Zone A and Zone B are exceeded total water supply volume. Water demand shall be reconsidered taking into account of actual and planned information of Zone A.	Water demand shall be reconsidered taking into account of actual and planned information of Zone A.	In accordance with the comments, water demand taking into account of actual and planned information of Zone A is considered in Section 7.3.5.(p.7-28)
38	Chapter 7 7.3 Water Quality/ 7.8 Bottom Sediment/ 7.19 Water Use	Forecast of water quality is only targeting BOD. If same methodology is applied for forecasting heavy metals and toxic substance, some parameters of forecasted surface water quality will exceed the target level of ambient water quality because volume of wastewater from Industrial Area of Zone A and Zone B more than existing flow rages. On the other hands, it is not realistic that concentration of heavy metals of treated wastewater to water body will be same as its target level as long as tenants comply with target level for primary wastewater.	Measures for compliance of target level of ambient water quality shall be re-considered and described in the Final EIA Report.	The concentration of heavy metals and toxic substance of treated wastewater from tenants is not known concretely, at the present moment. The tenants will submit the future water demand plan to the project proponent, and the project proponent would prepare the adequate wastewater treatment measures adjust to the tenant's activities. Basically, it is expected that concentration of wastewater is diluted by mixing with stormwater through the retention pond and creek flow. In case that large amount discharge which includes heavy metals and toxic substance is expected and especially low flow season, the project proponent would review the internal target value and set strict standard for pre-treatment, if necessary. (p.7-28, p.7-50 – p.7-51, p.7-79)
39	Chapter 7 7.4 Solid Waste Management	It is described that the operator of SWM facilities checks the waste sample the generators want to dispose of and conduct sample analysis to evaluate whether the waste can be received and managed properly. The assessment of waste is not clear as no details have been provided of the estimated number of people on site or the possible tenants. No details have been provided in the EIA (except references to the DOWA Eco-system and Table 4.3-13 at page 4-20) that there is a	What are the restrictions for types of wastes which can be managed properly by the SWM Company? If the waste is not accepted by the SWM company, how such wastes will be controlled? There should be a clear letter of intent that the land-fill site will accept the waste, including hazardous waste.	In accordance with the comments, the restrictions for types of waste which can be managed properly by the SWM Company are added in Section 4.3.7. (p.4-21 – p.4-25) The measure for wastes which is not accepted by SWM company is described in Section 7.4.5 (2), p.7-31)

	Chapter/ Section	Findings	Comments	Correspondence
		suitable facility for the disposal of hazardous and dangerous waste in accordance with the laws of Myanmar.		
40	Chapter 7 7.4 Solid Waste Management	For hazardous waste management during construction and operation stages should be fully considered the facts that in proper recycling of hazardous wastes, hazardous wastes neither Golden Dowa Ecosystem Myanmar nor YCDC can treat (eg. PCB, infectious waste).	Treatment methodology of hazardous waste which neither Golden DOWA Ecosystem Myanmar nor YCDC can treat shall be described in the Final EIA Report.	In accordance with the comments, the detailed information of treatment methodology of hazardous waste by Golden DOWA Ecosystem Myanmar and YCDC is added in Section 4.3.7 and 7.4.5. (p.4-22, p.7-31—p.7-32)
41	Chapter 7 7.4 Solid Waste Management	For non-hazardous wastes during construction and operation stages should be considered the facts that to collect the public wastes from out of service area in Thilawa SEZ, domestic wastes from Zone A and Zone B, Construction worker's waste outside of Zone A and Zone B and other waste from surrounding area.	The countermeasures of illegal dumped waste generated in the surrounding area related to Zone A and Zone B shall be described in the Final EIA Report.	In accordance with the comments, the countermeasures of illegal dumped waste generated in the surrounding area of Zone A and Zone B is added in Section 7.4.5 (3) (p.7-35)
42	Chapter 7 7.5 Soil Contamination	Actual mitigation measures to prevent infiltration of wastewater to ground such as installation of water proof floor, enough thickness of floor, and adequate drainage to divide water use area and non-water use area are not described.	Actual mitigation measures to prevent infiltration of wastewater to ground shall be added to the Final EIA Report taking into consideration of Zone A Internal Regulations.	In accordance with the comments, actual mitigation measures to prevent infiltration of wastewater to ground taking into consideration of proposed internal regulations of Zone B are added in Section 7.5.5. (p.7-36 – p.7-37)
43	Chapter 7 7.6 Noise and Vibration	More than large-scale machinery such as grinding/ milling machines are planned to install by some tenants. In case that, control methodology of noise and vibration by the project proponent together with TSMC shall be required.	Measures for compliance of target level of noise and vibration in operation phase shall be re-considered and described in the Final EIA Report in case that more than expected large-scale machinery will be installed.	In case that more than expected large-scale machinery will be installed, the tenants shall analyze and evaluate the impact of noise and vibration. Noise and vibration emitted from any source within the land of the tenant shall be effectively controlled by its own arrangement, if necessary. In accordance with the comments, considerations above are added in Section 7.6.6. (p.7-44—p.7-48)
44	Chapter 7 7.6 Noise and Vibration	The forecast result at Section 7.6.6 needs further justification. The management option at page 7-34 to halt work 30m from impacted homes during the day and 200m from impact homes during the night requires detailed investigation to identify how many homes will be impacted. It may be better to provide a buffer zone and landscaping.	Arrangement of lot layout plan to allocate the tenant and installation of buffer zone with less noise and vibration impacts to the surrounding sensitive receivers (monastery, houses etc.) shall be considered taking into account of actual and planned information of Zone A.	In accordance with the comments, feasible mitigation measures are added in Section7.6.6. (p.7-46)
45	Chapter 7 7.7 Offensive Odor	Actual mitigation measures to prevent offensive odor such as installation of deodorization system, ventilation system are not described.	Actual mitigation measures to prevent offensive odor shall be added to the Final EIA Report taking into consideration of Zone A Internal Regulations.	In accordance with the comments, actual mitigation measures to prevent offensive odor taking into consideration of proposed internal regulations of Zone B are added in Section 7.7.5. (p.7-49)
46	Chapter 7 7.9 Flora/ Fauna and Biodiversity	With respect to assessment of biodiversity and ecosystem, land use change, remaining area of natural area in and around the SEZ, and mitigation measures	Land use change, remaining area of natural area in and around the SEZ, and mitigation measures such as greening shall be added to	In accordance with the comments, greening plan is added to the assessment of biodiversity and ecosystem in Section 7.9.5. (p.7-52—

	Chapter/ Section	Findings	Comments	Correspondence
	12 1 2 1 2	such as greening are unconsidered.	assessment of biodiversity and ecosystem.	p.7-54)
47	Chapter 7 7.10 Hydrology	With respect to assessment of surface water flow, drainage plan of boundary of the project site is not clear to prevent generation of backwater from surrounding area in rainy season.	Drainage plan of boundary of the project site to prevent generation of backwater from surrounding area shall be added in the Final EIA Report.	The drainage plan of boundary of project site will be prepared by construction contractor in during construction phase. For the reference, the drainage plan of boundary of the industrial area of Zone A is described in Section 7.10.5. The drainage plan of boundary of the Project will be prepared in the same manner of Zone A. (p.7-56)
48	Chapter 7 7.11 Soil Erosion	Mitigation measures of prevention of soil erosion caused by discharging storm water from retention pond are not clear.	Impact assessment on soil erosion shall be implemented taking into consideration of mitigation measures of prevention of soil erosion caused by discharging storm water from retention pond.	In accordance with the comments, the mitigation measure of prevention of soil erosion caused by discharging storm water from retention pond is added in Section 7.11.5. (p.7-58—p.7-59)
49	Chapter 7 Social Impact (Direct Impact to PAPs)	The Resettlement Work Plan by Myanmar Government should be provided with the EIA. It must have had extensive public consultation. In addition, given the recommendations made by the JICA Reviewers, the RAP needs to be revisited to ensure compliance with best practice and the EIA Procedure 2015.	Outline of Resettlement of Work Plan by Myanmar Government such as clarification of responsibilities for the Plan, cost for implementation of the Plan, and measures on maintaining current livelihood of PAPs shall be summarized in the Final EIA Report.	As outline of Resettlement of Work Plan, responsibilities and implementation structure is described in Section 2.6.3. (p.2-19—p.2-20) The contents of assistance packages (items of costs for the implementation) and the detail (measures on maintaining current livelihood of PAPs) are summarized in Section 7.12. (p.7-60—p.7-62)
50	Chapter 7 7.20 Cultural Heritage/ Asset	One cemetery and one temple are located in the Project Site but it is not clear that actual relocation method has not been decided. Clear provision needs to be made for an assessment of the cultural values of the assets identified in 6.7.1.	It is recommended that completion of actual implementation of relocation of cemetery and temple with agreement of PAH shall be a condition in the approval letter of EIA to start construction work.	The Project Proponent will follow the comments.
51	Chapter 7 7.21 Landscape	It is described the tenant industry shall be responsible for landscaping the plot and maintaining the same in a well-kept condition. But not limited to trimming, watering and fertilization. Tenants will have to follow the internal regulations of MJTD.	It is need to mention how much area will be maintained for landscaping and greening after the Zone A and Zone B development? The estimated area which will be maintained as landscaping and greening should calculate and mention in this section.	In accordance with the comments, the information of landscaping and greening area of Zone A and Zone B industrial area is added in Section 7.22. (p.7-82— p.7-83)
52	Chapter 7 7.22 Risks for Infection Diseases such as AIDS/HIV	It is mentioned about that the risk for infectious disease and only described the management of AIDS/HIV as an example.	Shall be mentioned other infectious disease such as Hepatitis C, Hepatitis B, and outbreak prone diseases such as Diarrhoea, food poisoning, meningitis etc. Shall be mentioned on other communicable diseases such as malaria, dengue, tuberculosis, sexually transmitted diseases. Shall include diseases preventable by immunization such as diphtheria, measles etc Shall set up health education program, early reporting and referral system, and immunization program for	In accordance with the comments, infectious disease and outbreak prone diseases and other communicable diseases other than AIDS/HIV are described additionally in Section 7.23. (p.7-84) Accordingly, the profile of health is enclosed as public health components in Section 4.3.8. (p.4-28–p.4-30) In addition, health education and reporting system, immunization program to be recommended to establish are described in Section 7.23. (p.7-85)

	Chapter/ Section	Findings	Comments	Correspondence
			under 5 years old children from family at construction site and tenants.	
53	Chapter 7 7.23 Occupational Health and Safety	Concrete activities on occupational health and safety stipulated in IFC General EHS Guidelines are not described. For any workers living on the SEZ, there is a need to undertaken an assessment based on the IFC General EHS Guidelines. This should also be the minimum standard if any tenants also provide worker accommodation. No assessment has been made on the number of workers for Zone B.	Mass casualty events and disaster should be mentioned and preparedness and response plan should be developed. Snake bite should be mentioned. Concrete activities on occupational health and safety stipulated related to the Project in IFC General EHS Guidelines and labour related laws and regulations in Myanmar shall be added. The following facts should be considered in EIA study according to the labour related laws and regulations in Myanmar: 1) labour rights 2) contract between tenants and labours which includes working hours, working days and other negotiations. 3) safety awareness and health check 4) safety health plan 5) work place diseases and accidents 6) accommodation facilities for the workers with family. A Grievance Mechanism needs to be established to assist in the resolution of disputes during construction and operation of the Zone B. This should enable disputes to be resolved quickly and easily to promote harmonious relationships between the communities and the TSMC. Once tenants are on the site they should be involved with the Dispute Resolution	Preparedness and response plan for mass casualty events and disaster are mentioned in Section 7.27. (p.7-94) In accordance with the comments, additional contents such as snake bite, concrete activities for OHS stipulated in IFC General EHS Guidelines and law and regulation in Myanmar related occupational health are described in Section 7.24. In addition, the facts mentioned in the left column are incorporated in Section 7.24 (p.7-86—p.7-90) as well. As a function of grievance mechanism, the process of dispute settlement in current situation is described in the paragraph of (2) Impact on Labor Right in Section 7.24.5. (p.7-89)
54	Chapter 7 7.24 Community Health and	Concrete activities on community health and safety stipulated in IFC General EHS Guidelines are not described.	Committee if required. Safe water supply should be mentioned. Mass casualty events and disaster should be mentioned	Preparedness and response plan for mass casualty events and disaster are mentioned in Section 7.27. (p.7-94)
	Health and Safety	described.	and preparedness and response plan should be developed. Concrete activities on community health and safety stipulated related to the Project in IFC General EHS Guidelines shall be added. Security safety for community, the following facts should be considered: 1) Traffic accidents 2) Increase of crime,	Safe water supply is described in Section 7.20 (p.7-77– p.7-79) as one of the contents for water usage. In accordance with the comments, concrete activities for CHS stipulated in IFC General EHS Guidelines are described in Section 7.25. (p.7-91 – p.7-92) In addition, the facts mentioned in the left column except "2) infectious diseases such as Hepatitis C, Hepatitis B, Diarrhoea etc." are incorporated in Section 7.24 as well. (p.7-86 – p.7-90) For the contents regarding infectious

	Chapter/ Section	Findings	Comments	Correspondence
			infectious diseases such as Hepatitis C, Hepatitis B, Diarrhoea etc. 3) Utilization of worker's accommodation	diseases, it is described in Section 7.23 (p.7-84 – p.7-85)
55	Chapter 7 7.25 Usage of Chemical	Actual/ planned control measures of usage of chemical in Zone A such as preparation of list of chemical and its Material Safety Data Sheet (MSDS), monitoring of amount and control measures, and implementation of self-inspection are not described.	Actual/ planned control measures of usage of chemical in Zone A such as preparation of list of chemical and its Material Safety Data Sheet (MSDS), monitoring of amount and control measures, and implementation of self-inspection shall be described in the Final EIA Report taking into consideration of Zone A Internal Regulations and SOPs of TSMC.	In accordance with the comments, several control measures of usage of chemical that can be applied to the project area taking into consideration of the proposed internal regulation of Zone B and EHS Guidelines are added in Section 7.26.(p.7-93) and 10.2 (p.10-14)
56	Chapter 7 7.26 Flood Risks	Setting elevation of flood risk is only taking into consideration of the highest level of MITT but not clear of highest date. It is not consideration of past flood and cyclone.	The elevation shall be set taking into consideration of not only the highest level of MITT but also past flood and cyclone.	In accordance with the comments, setting the elevation level taking into consideration of past flood and cyclone is added in Section 3.4. (P. 3-6) and Section 7.27 (p.7-94).
57	Chapter 7 7.28 Earthquake	With respect to forecasting impact on earthquake in operation phase, there is no description about measures on infrastructure of the Project such as canal, pond, and road.	Impact assessment on earthquake for infrastructure facilities shall be included in the Final EIA Report.	In accordance with the comments, mitigation measure for earthquake impact on infrastructure facilities in the project area is added in Section 7.29. (p. 7-97 – p.7-98)
58	Chapter 7 7.29 Global Warming	Concrete activities on minimization of GHGs emission by tenant in their operation are not clear. Identify all emissions sources and their locations. Provide estimates (tonnes per year) of GHG emissions (e.g., CO ₂ , NO ₂ , SO ₂ , CH ₄ , VOC).	Concrete activities on minimization of GHGs emission by tenant in their operation shall be added taking into consideration of actual activities in Zone A.	In accordance with the comments, some activities for minimization of GHGs emission are added, such as usage of solar power to the street lamp, usage of LED and recommendation of usage of energy-saving equipment to the tenants in Section 7.30. (p.7-99—p.7-100)
59	Chapter 9 9.1 Environmental Mitigation and Management Plan	Need to link with Chapter 2. Provide a description of the Proponent staff that will be responsible for supervision and implementation of the Environmental Management Plan. Please indicate the responsibilities of construction contractors for implementation of environmental management plans. Please clarify that independent monitoring consultants and agencies will conduct environment monitoring programs. Include the Proponent's responsibilities for monitoring and reporting under EIA Procedure Chapter IX. Monitoring. Include who will be responsible for ensuring/monitoring compliance by individual tenants. Similarly, who will be aggregating the monitoring	Environmental mitigation measures and management plan shall be revised in the Final EIA Report as much as possible taking into consideration of the finding in the left column:	As for the project proponent, environmental management system was already established during development of Zone A. The current staff will hold the additional post for Zone B. Implementing organization and responsible organization for environmental management plan are mentioned in Table 10.1-1-Table 10.1-3. (p.10-2—p.10-11) And implementation structure of the project proponent and main tasks for environmental and social considerations in the project proponent are added in Section 10.5. (p.10-16) Responsible organization for monitoring plan is mentioned in Table 10.1-1-Table 10.1-3. On the other hand, each tenant will implement EMP and EMOP for each business and submit the environmental monitoring report to OSSC of TSMC and the project

	Chapter/ Section	Findings	Comments	Correspondence
		reports from individual tenants. The role and responsibilities of the Environmental Conservation Department (ECD) including the Yangon Region ECD needs to be described.		proponent based on its IEE/EIA. Mitigation measures and monitoring plan will be conducted by own expense based on its IEE/EIA In accordance with the comments, the role and responsibilities of the Environmental Conservation Department (ECD), as a member of OSSC, is added in Section 10.5. (p.10-16)
60	Chapter 9 9.1 Environmental Mitigation and Management Plan	Specific EMPs are not mentioned. Need to mention the following points in detail: 1) Verify the items in each of the environmental mitigation and management plans in Table 9.1-1, 9.1-2, 9.1-3. 2) Each plan needs staffing requirements, cost estimation, and capacity development and training should be separated for mitigation and monitoring programs. 3) plans to address full implementation of the IRP and to include details of the programcensus of PAPs, budget estimates, time frame, institutional arrangements and reporting. 4) plans to address mitigation measures and monitoring requirements for incineration, common waste water treatment plant, sludge disposal facilities, hazardous wastes management sits etc. 5) the mechanism for grievance redress and community outreach efforts to deal with any complaints from nearby residents. 6) Plan for compensation for land disturbance and land acquisition should be provided attached with Resettlement Plan 7) Plans for consultation, grievance redress, and disclosure during implementation is needed to prepare. 8) plan for supervision and monitoring for the compliance and EMP implementation needed to be prepared.	Environmental mitigation measures and management plan shall be revised in the Final EIA Report as much as possible taking into consideration of the finding in the left column:.	1) Based on the proposed environmental mitigation and management plans in Table 10.1-1, 10.1-2, 10.1-3., contractor/tenants will select adequate /feasible measures or add better measurement depending on the situation. 2) Environmental management system was already established during development of Zone A. The current staff will hold the additional post for Zone B. On the other hand, environmental management staff of contractors/tenant will be proposed by contractor/tenants 3) In accordance with the comments, the detail contents of IRP are added in Section 7.12. (p.7-60- p.7-62) 4) plans to address mitigation measures and monitoring for incineration, common waste water treatment plant, sludge disposal facilities, hazardous wastes management site will be prepared by Private Solid waste management company in ZoneA. 5) In accordance with the comments, the mechanism for grievance redress and community outreach efforts is described as a part of stakeholder engagement plan in Chapter 11. (p.11-2) 6) In accordance with the comments, the plan for land compensation is added in 7.12 (p.7-60 - p.7-62). 7) In accordance with the comments, plans for consultation, grievance redress, and disclosure are described as a part of stakeholder engagement plan in Chapter 11. (p.11-2) 8) In accordance with the comments, implementation organization structure including tenants and project proponents for environmental management is added in Section 10.5
61	Chapter 9 9.1 Environmental Mitigation and Management Plan	Staffing Requirements and Terms of Reference for key positions are needed, including: 1) environmental staffing requirements for the Proponent Environmental Management Staff 2) Contractors environmental management staff	Environmental mitigation measures and management plan shall be revised in the Final EIA Report as much as possible taking into consideration of the finding in the left column:	(p.10-17). 1) Environmental management system was already established during development of Zone A. The current staff will hold the additional post for Zone B. Main tasks for environmental and social considerations of the project proponent are added in Table

	Chapter/ Section	Findings	Comments	Correspondence
		3) TOR for third party environmental consultants involved in preparation and implementation of environmental management sub plans.		10.5-1(p.10-17). 2) Contractor's environmental management staff will be proposed by the contractor under requirement from the project proponent 3) TOR for third party's environmental consultants in monitoring is shown in Annex 10-2, including monitoring points, items, monitoring form and contents of monitoring reports
62	Chapter 9 9.1 Environmental Mitigation and Management Plan (page9-1)	Mitigation measures on water use, social infrastructure are not described even there are impacts to some extent.	Mitigation measures on water use, social infrastructure shall be described in the Final EIA Report.	In accordance with the comments, the mitigation measures on water use and existing social infrastructure are added in Section 10.1. (p.10-2 – p.10-11)
63	Chapter 9 9.1 Environmental Mitigation and Management Plan	In table 9.1-3, under Pollution, proposed mitigation measures and environmental management for air quality is only emphasize to control the emission from vehicles, not include to control the emission from various kinds of factory in Zone B.	It should be mentioned that the implementation organization including tenants and project proponents have to control the emission from factory with proper management plan.	In accordance with the comments, implementation organization structure including tenants and the project proponents for environmental management is added in Section 10.5. (p.10-16 – p.10-17)
64	Chapter 9 9.1 Environmental Mitigation and Management Plan (page9-2 to page 9-5)	Some mitigation measures are not clear.	Mitigation measures on water use, social infrastructure shall be described specifically as much as possible in the Final EIA Report.	In accordance with the comments, the mitigation measures on water use and existing social infrastructure are added in Section 10.1. (p.10-3 – p.10-4, p.10-8)
65	Chapter 9 9.2 Environmental Monitoring	Monitoring plans for some elements (category) which assessed in Chapter 7 are not described.	All of the elements (category) which assessed in Chapter 7 shall be included in the monitoring plan.	In accordance with the comments, all of the elements (category) which assessed in Chapter 7 are included in the monitoring plan in Section 10.2. (p.10-12 – p.10-14)
66	Chapter 9 9.2 Environmental Monitoring	As the results of findings and comments regarding section 7.3 Water Quality, frequency of water quality monitoring at outlet of centralized wastewater may be insufficient.	Water quality monitoring at outlet of centralized wastewater is recommended from every two months to every month (basic parameter) and from every six months to every three months (toxic and heavy metals).	In accordance with the comments, water quality monitoring at outlet of centralized wastewater is revised from every two months to every month (basic parameter) and from every six months to every three months. (p.10-13)
67	Chapter 9 9.2 Environmental Monitoring	Monitoring plan for activities on social aspect is not clear.	Results of activities on community support programs related to EIA shall be including the Environmental Monitoring Report.	In accordance with the comments, the implementation status of CSR activities such as community support program are added as monitoring item for applicable categories in Section 10.2. (p.10-12 – p.10-14)
68	Chapter 9 9.3 Budget for the Environmental Management	Wastewater treatment will be treated by the central wastewater treatment plant in Zone A for the time being, but there is no mentioned about operation and maintenance cost of the plant in Zone A.	The operation and maintenance cost shall be added in the Final EIA Report.	It is difficult to present the operation and maintenance cost of the wastewater treatment plant at the present moment because the cost is depending on the capacity/quality of the system and volume of treatment water.
69	Chapter 9 9.3 Budget for the Environmental Management	A budget is needed with: 1) costs for establishment and operation of the Proponents environmental management system; 2) costs for Third Party Environmental Consultant	Budget plan shall be revised in the Final EIA Report as much as possible taking into consideration of the finding as shown in the left column.	1) Environmental management system was already established during development of Zone A. The current staff will hold the additional post for Zone B. There is no additional cost for establishment. Cost of operation is included daily work.

	Chapter/ Section	Findings	Comments	Correspondence
	Section	services; 3) cost of monitoring and reporting for compliance with the ECC and EMP; 4) costs of further preparation, training, and implementation of environmental mitigation and management plans for; (i) preconstruction phase (Table 9.1.1); (ii) construction /closing phase (Table 9.1.2); and operation phase (Table 9.1.3.); 5) costs for Land Acquisition and Resettlement; 6) the costs for construction and operation of the central waste water treatment plant.		2) There is no cost estimation because there is no concrete TOR for third party's Environmental Consultant services. 3) Cost of monitoring and reporting are added in Table 10.3-2 (p.10-15). 4) Mitigation measures will be designed by contractor or tenants by own expense. 5) Items of costs for land acquisition and resettlement are described in Section 7.12. (p.7-60 – p.7-62) 6) It is difficult to present the operation and maintenance cost of wastewater treatment plant at the present moment because the cost is depending on the capacity/quality of the system and volume of treatment
70	Chapter 10	Public consultation meeting: Chapter 10 provides a listing and summary of the issues and concerns raised by the communities and the public. Many responses the questions, implied that the issues would be addressed in the EIA Report	For each issue, explain how the Project and/or the Proponent are addressing the issue. Need to consider and mention the solutions to solve the request from the public at PCM. The public consultation process shall be continued periodically. Key elements are required to ensure that the public consultation achieves a minimum acceptable level: 1) A stakeholder engagement plan shall be developed to ensure engagement with PAP, PAH and civil society. 2) The PAP and PAH need to be consulted on the mitigation measures for noise and traffic safety. 3) The PAP and PAH need to be consulted on the RAP and should provide comments and feedback for consideration 4) There should be consultation in particular on the air quality and waste issues to ensure that this can be addressed. 5) The community of Township (using Cemetery) need to be consulted and approval received to relocate the ceremony. This must be done in accordance with any conditions required by that community.	In accordance with the comments, the further responses to the public comments and requests by the project/the project proponent are described in Chapter 11. (p.11-1-p.11-20; Table 11.2-2, 11.2-4, 11.2-6, 11.3-2 to 11.3-4, 11.3-6, 11.3-8) In addition, stakeholder engagement plan, which includes the process of public consultation in case that any environmental and social, health issue occurs among local community, is described in Chapter 11 considering the comments in the left column. (p.11-1- p.11-20)

Source: EIA Study Team

15. Conclusion

As to the results of the EIA study for the Industrial area of Thilawa SEZ project, the following items are found:

- 1) In terms of living environment, most of the impacts are controlled and limited in and around the project area. The key negative impacts such as emission of gas and dust, deterioration of water quality, generation of noise and vibration are expected. However, implementation of appropriate mitigation and management plan, such as to spray water to bare areas for dust prevention and to avoid the incentive operation of the construction machinery for prevention of emission gas, noise and vibration during construction phase, and to provide the commuter bus by tenants and to comply with the tentative target value of effluent water flowing out of the wastewater treatment plant by tenants including the project proponent during operation phase, will minimize these impacts.
- 2) In terms of natural environment, the key negative impact is the clearance of existing vegetation during construction phase, though there is no sensitive ecological protection area. However, implementation of appropriate mitigation measures, such as planting trees, vegetation and sodding of public spaces as soon as possible and keeping the environmental conditions along the existing canal will minimize the impact on the ecosystem.
- 3) In terms of social environment, land acquisition and some scale of involuntary resettlement are expected. Impact on livelihood of the project-affected persons (PAPs) including vulnerable people and children is also expected during the pre-construction, construction and operation phase. Toward this issue, the resettlement framework of the Thilawa Special Economic Zone (SEZ) (2,000 ha) was prepared that includes compensation and assistance package and income restoration program for the PAPs and will be conducted by Thilawa SEZ Management Committee (TSMC), that will mitigate the impacts of the Project on social environment.
 - On the other hand, some positive impacts of the Project such as increase in job opportunity and improvement of social infrastructure are also expected.
- 4) In terms of health and safety, some impacts on occupational/community health and safety and increase in number of accidents are expected. However, implementation of appropriate mitigation and management plan, such as to manage working conditions during the construction work and to provide security and maintain safety prevention measures during construction/operation phase will minimize these impacts.
- 5) In consideration of the result of the EIA study for the Project, the Environmental Management Plans (EMPs) including adequate mitigation measures to reduce the negative impacts and Environmental Monitoring Plan (EMoP) are proposed for each phase of the Project: pre-construction phase, construction/closing phase, and operation phase.

It was confirmed that the environmental, social and health impacts of the Project were assessed and the Environmental Management Plan was formulated properly. In the process of EIA, opportunity of public involvement was ensured and comments from the public, TSMC and MONREC were reflected into the final EIA Report. Thus the EIA was completed in accordance with the requirements of the EIA Procedure properly in case that project proponent will follow EMP accordingly.

CHAPTER 1: INTRODUCTION

1.1 Project Proponent

Project Proponent: Myanmar Japan Thilawa Development Limited (MJTD)

Address: Corner of Thilawa Development Road and Dagon-Thilawa Road, Thilawa Special Economic Zone (SEZ), Thanlyin Township, Myanmar

1.2 Purpose of the Study

This Study is to assess the environmental and social impacts caused by the industrial area development project in Thilawa SEZ (approximately 262 ha) (hereinafter referred to as "the Project") by MJTD and consider the Environmental Management Plan (EMP) including mitigation measures to reduce and minimize the negative impacts caused by the Project.

1.3 Implementation Organization for Environmental Impact Assessment

The organizations in-charge of the implementation of the environment impact assessment (EIA) (hereinafter referred to as the "EIA Study Team") is presented in Table 1.3-1. The members of the EIA Study Team are listed in Table 1.3-2. The profile of each organization and the curriculum vitae of the key experts of the EIA Study Team are attached in Annex 1-1.

Table 1.3-1 Implementation Organization of EIA

	Organization	Responsibility
International	Nippon Koei Co., Ltd., Tokyo, Japan (NK)	Overall management and
Lead Consultant		technical aspect of EIA
Local Consultant	Myanmar Koei International Co., Ltd. (MKI)	Field survey
	Resource and Environment Myanmar Ltd.	Field survey and
	(REM)	public consultation meeting

Source: EIA Study Team

Table 1.3-2 Members of the EIA Study Team

Name of Organization	Name	Position	Background	Years of Experience
Nippon Koei	Mr. Tomoaki Tanabe	Team Leader	B. Eng. (Civil & Environmental)	20 years
Co., Ltd.	Ms. Naoko Katashima	Sub-Team Leader Social and Health Expert,	M. Sc. (Environmental Science) B. Sc. (Public Affairs)	15.5 years
	Mr. Kensaku Kawai	Urban Planning Expert	B. Sc. (Agricultural Technology)	22 years
	Mr. Shinji Tanaka	EIA Expert (Air)	B. Eng. (Civil Engineering)	14 years
	Mr. Atsushi Minami	EIA Expert (Water)	M.Sc. (Human Environment) B. Sc. (Human Environment)	9 years
	Mr. Kengo Naganuma	EIA Expert (Waste)	M. Sc. (Environmental Management and Conservation for Soil and Water Resource) B. Sc. (Environmental Management and Conservation for Soil and Water Resource)	23 years
	Mr. Satoshi Miyaichi	EIA Expert (Noise and Vibration)	M. Eng. (Urban and Environmental Engineering) B. Eng. (Civil Engineering)	12 years
	Ms. Sachiko Sakurai	EIA Expert (Natural Environment)	M. Eng. (Social Engineering) B. Eng. (Social Engineering)	6 years

Name of Organization	Name	Position	Background	Years of Experience
	Ms.Junko Masaki	Social Impact Assessment Expert	M. Sc. (Environmental Science) B. Sc. (Biological Resources	12 years
		Assessment Expert	Engineering)	
	Ms. Maki Ikuse	Social Impact Assessment Expert	M. Sc. (Frontier Science) B. Agr. (Agriculture)	2 years
	Mr. Tung Xuan Bui	EIA Expert (Field Survey Analysis)	Ph.D. (Environmental Science and Engineering) M. Sc. (Environmental Science and Engineering) B. Sc. (Chemistry)	12 years
Myanmar Koei	Mr. Htein Lin	Team Leader of Noise and Vibration Survey	M. Agr. (Agriculture) B. Agr. Sc. (Agriculture)	8 years
International Co., Ltd.	Mr. Aung Thu	Coordinator/ Noise and Vibration Survey	B. A. (Economic)	9 years
Resource and Environment	U Zaw Naing Oo	Team Leader of Water, Soil, Air Quality Baseline Survey	M. Sc. (Geology) B. Sc. (Geology)	19 years
Myanmar Ltd.	U Thura Aung	Water Quality and Soil Quality Survey	M. Sc. (Geology) B. Sc. (Geology)	11 years
	U Soe Yu Tun	Air Quality Survey	B. Sc. (Geology)	5 years

Source: EIA Study Team

1.4 Overall Schedule of Environmental Impact Assessment

The Environmental Impact Assessment Procedure (No.616/2015) (hereinafter referred to as "EIA Procedure"), which was issued by the Ministry of Environmental Conservation and Forestry (MOECAF) (predecessor of Ministry of Natural Resources and Environmental Conservation (MONREC)) on 29 December 2015 defines the detailed legal process regarding EIA procedures including preparation of EIA/IEE report, environmental management plan (EMP), public involvement, approval of EIA/IEE report by MOECAF, and monitoring process in accordance with the EIA report. In this EIA Procedure, "Industrial Zone Construction and Development (all sizes)" projects are requested to conduct full EIA study. Therefore, the project proponent has conducted EIA based on the EIA Procedure.

On the other hand, Presidential Decree No.49/2015 was enacted and this defines the transfer of power related to administrative procedures in SEZ. According to Thilawa SEZ Management Committee (TSMC), TSMC started to develop a procedure related to environmental management for investors as well as zone development in Thilawa SEZ based on the Decree from October 2015. In February 2016, TSMC finalized a procedure of appraisal of EIA for zone development and issued the approval letters of the scoping reports submitted by the project proponent to it on 26th February 2016.

For the appraisal of the EIA study for Zone B development, a mobile review team, which is composed of staff from Environmental Conservation Department (ECD) of Ministry of Natural Resources and Environmental Conservation, Ministry of Industry, Ministry of Health, and Ministry of Labor, Immigration and Population, was established in January 2016 to review the draft EIA report. To review the draft EIA report submitted by the project proponent on 22 March 2016, EIA Review Committee was held on 5 and 6 May 2016 and TSMC together with the mobile review team released comments on the draft EIA Report on 17 May 2016. The project proponent has revised and finalized the EIA Report by reflecting the comments and submitted it to TSMC for approval.

EIA schedule of the Project is shown in Table 1.4-1.

Table 1.4-1 EIA Schedule of the Project (as of May 2016)

		2015				2016		
Item	September /October	November	December	January	February	March	April	May
1. Examination of the Project Plan								
2. Scoping								
Preparation of the Draft Scoping Report								
Public Consultation Meeting (PCM)			A					
Public Disclosure (PD)								
Submission of the Final Scoping Report					A			
Approval of Final Scoping Report by TSMC					•			
3. Field Survey								
Field Survey during the Rainy Season								
Field Survey during the Dry Season								
4. EIA								
Preparation of the Draft EIA Report								
Submission of the Draft EIA						A		
Public Consultation Meeting (PCM)							A	
Public Disclosure (PD)								
EIA Review Committee								A
Comments Letter of Draft EIA Report								A
Submission of the Final EIA Report	T	,						A

Source: EIA Study Team

CHAPTER 2: POLICY OF ENVIRONMENTAL AND SOCIAL CONSIDERATIONS

2.1 Corporate Environmental and Social Policies

The project proponent has participated in the UN Global Compact since 30 October 2015, which is the largest Corporate Social Responsibility Initiative in the world and focuses on the areas of Human Rights, Labor, Environment and Anti-corruption. The project proponent is committed to making the Global Compact and its principles part of the strategy, culture and day-to-day operations. The ten principles of UN Global Compact are shown in Table 2.1-1.

Table 2.1-1 Ten Principles of UN Global Compact

Area		Principals
Human Rights	Principle 1:	Businesses should support and respect the protection of internationally proclaimed
		human rights; and
	Principle 2:	make sure that they are not complicit in human rights abuses.
Labour	Principle 3:	Businesses should uphold the freedom of association and the effective recognition of the
		right to collective bargaining;
	Principle 4:	the elimination of all forms of forced and compulsory labour;
	Principle 5:	the effective abolition of child labour; and
	Principle 6:	the elimination of discrimination in respect of employment and occupation.
Environment	Principle 7:	Businesses should support a precautionary approach to environmental challenges;
	Principle 8:	undertake initiatives to promote greater environmental responsibility; and
	Principle 9:	encourage the development and diffusion of environmentally friendly technologies.
Anti-Corruption	Principle 10:	Businesses should work against corruption in all its forms, including extortion and
		bribery.

Source: UN Global Compact

2.2 Myanmar Regulatory Framework

2.2.1 Institutional Setting of the National Level

Myanmar has 21 ministries under the Office of the President as of May 2016. The leading ministries in-charge of environmental and social considerations are the Environmental Conservation Department of the Ministry of Natural Resources and Environmental Conservation (MONREC), that was reorganized Ministry of Environmental Conservation and Forestry (MOECAF) in April 2016.

2.2.2 Fundamental Laws and Regulations Related to Environmental and Social Considerations

The fundamental laws and regulations related to the environmental and social considerations and health in Myanmar are shown in Table 2.2-1. In addition, major international agreements and treaties that the Myanmar government has ratified related to the environmental and social considerations are shown in Table 2.2-2.

Table 2.2-1 Fundamental Laws and Regulations Related to Environmental and Social Considerations and Health in Myanmar

No.	Laws and Regulations as of May 2016						
Enviro	Environmental Framework						
1	The National Environment Policy (1994)						
2	The Environmental Conservation Law (2012)						
3	The Environmental Conservation Rule (2014)						

No.	Laws and Regulations as of May 2016
	Environment
4	The Underground Water Act (1930)
5	The Territorial Sea and Maritime Zone Law (1977)
6	The Law on Aquaculture (1989)
7	The Conservation of Water Resources and Rivers Law (2006)
8	The Conservation of Water Resources and River Rules (2013)
9	ry/Biodiversity The Forest Law (1992)
10	The Protection of Wildlife and Wild Plants and Conservation of Natural Areas Law (1994)
	nvironmental Standards EIA Procedures (December 2015)
11	,
12	National Environmental Quality (Emission) Guidelines (December 2015)
Land U	
13	The Land Acquisition Act (1894)
14	The Farmland Law (2012)
15	The Farmland Rules (2012)
16	The Vacant, Fallow and Virgin Lands Management Law (2012)
17	The Vacant, Fallow and Virgin Lands Management Rules (2012)
Heritag	
18	The Protection of Preservation of Cultural Heritage Region Law (1994)
19	The Heritage Goods Protection Law (2015)
Public	
20	The Public Health Law (1972)
21	The Prevention and Control of Communicable Diseases Law (1995, revised in 2011)
	rial Law
22	The Explosive Act (1884)
23	The Explosive Substances Act (1908)
24	The Marine Fisheries Law (1990)
25	The Freshwater Fisheries Law (1991)
26	The Prevention of Hazard from Chemicals and Related Substances Law (2013)
27	The Business for Ozone Depleting Substances: Notification No.37/2014
	g Environment
28	The Worker's Compensation Act (1923)
29	The Payment of Wages Act (1936)
30	The Factory Act (1951)
31	The Shops and Establishment Act (1951)
32	The Leave and Holiday Act (1951, partially revised in 2014)
33	The Labour Organization Law (2011)
34	The Social Security Law (2012)
35	The Labour Organization Rule (2012)
36	The Labour Dispute Settlement Law (2012)
37	The Employment and Skill Development Law (2013)
38	The Minimum Wage Law/Rules (2013)
	ructure/Economic Development
39	The Foreign Investment Law (2012)
40	The Export and Import Law (2012)
41	The Myanmar Citizen Investment Law (2013)
42	The Electricity Law (2014)
43	The Boiler Law (2015)
	ules for SEZ
44	Myanmar Investment Commission: Notification No. 1/2013 and No.50/2014 (Economic activities which
	require environmental impact assessment)
45	The Myanmar Special Economic Zone Law (2014)
46	Ministry of National Planning and Economic Development: Notification No. 81/2014 (for the issuance of
	permit on the application to invest in the Thilawa Special Economic Zone)
47	The Special Economic Zone Rules (2015)
48	TSEZMC Notice to Ensure the Responsible Investment in the Thilawa SEZ (August 2015)
49	Standard Operation Procedures for Investors in Thilawa SEZ (December 2015)

Source: EIA Study Team

Table 2.2-2 Major International Agreements and Treaties that the Myanmar Government has Ratified Related to Environmental and Social Considerations

	International Agreements and Treaties	Date Ratified
1	Ramsar Convention (Convention on Wetlands of International Importance Especially as Waterfowl Habitat), 1971	2005
2	Convention on International Trade in Endangered Species of Wild Fauna and Flora, Washington, D.C., 1973; and this convention as amended in Bonn, Germany, 1979	1997
3	Vienna Convention for the Protection of the Ozone Layer, 1985	1993
4	Basel Convention, 1989	2015
5	Montreal Protocol on Substances that Deplete the Ozone Layer, 1989	1993
6	London Amendment to the Montreal Protocol on Substances that Deplete the Ozone Layer, London, 1990	1993
7	United Nations Framework Convention on Climate Change (UNFCCC), New York, 1992	1994
8	Convention on Biological Diversity, Rio de Janeiro, 1992	1994
9	Stockholm Convention on Persistent Organic Pollutants (POPs), 2001	2004 (Accession)

Source: The Republic of the Union of Myanmar, National Biodiversity Strategy and Action Plan (2011), Website of the Basel Convention (http://www.basel.int/Countries/StatusofRatifications/PartiesSignatories/tabid/4499/Default.aspx) (As of May 2016)

The following are summaries of the key laws related to the natural and social environment in Myanmar that will likely be relevant to the Project.

Environmental Framework

The Environmental Conservation Law (ECL) (2012) and Environmental Conservation Rules (ECRs) (2014)

The Environmental Conservation Law (ECL) was enacted in March 2012. This law is the fundamental law of environmental management and environmental conservation in Myanmar prepared by MOECAF. Subsequently, the Environmental Conservation Rules (ECRs) were enacted in June 2014 as the detailed enforcement regulations for ECL. ECL stipulates MOECAF's responsibility for environmental policy and administration, formulation of environmental management plan, implementation of environmental monitoring, setting of environmental standards, management of hazardous waste, and formulation and implementation of EIA, among others.

With regard to related special economic zone (SEZ) articles, Article 16 in ECL stipulates the responsibilities of the business owner of an industrial estate or business in SEZ on environmental conservation as follows:

- To be responsible to carry out by contributing the stipulated cash or kind in the relevant combined scheme for environmental conservation including the management and treatment of waste;
- To contribute the stipulated user's charges or management fees for the environmental conservation according to the relevant industrial estate, special economic zone, and business organization; and
- To comply with the directives issued for environmental conservation according to the relevant industrial estate, special economic zone, or business.

Moreover, ECRs stipulate the basic policy and concept of EIA application for the development of projects (Article 55).

- To prepare the environment impact assessment system and submit to the Ministry (Article 55 (a) in ECRs); and
- To implement and carry out environmental management plan within the time stipulated by the Ministry and submit the performance situation to the Ministry (Article 55 (b) in ECRs).

Water Environment

The Conservation of Water Resources and Rivers Law (2006)

The aims of this law are as follows: (a) to conserve and protect the water resources and river system for the beneficial utilization of the public; (b) to enable smooth and safe waterways navigation along

rivers and creeks; (c) to contribute to the development of the state economy through improving water resources and river system; and (d) to protect environmental impact.

However, this law is under the jurisdiction of the Ministry of Transport. This law focuses on transportation safety and its development. However, it lacks actual numerical criterion for natural environment.

Forestry/Biodiversity

The Protection of Wildlife and Wild Plants and Conservation of Natural Areas Law (1994)

The objectives of this law are to implement the Government policy for wildlife protection and natural areas conservation, to carry out in accordance with the relevant International Conventions, to protect endangered species of wildlife and their natural habitats, to contribute for the development of research on natural science, and to protect wildlife by the establishment of zoological/botanical gardens. It prescribes the formation of the committee for protection of wildlife and natural areas with its function and duties and the determination of natural areas and endangered species of wild animal which are to be protected.

EIA/Environmental Standards

The EIA Procedure (2015)

The EIA Procedure formulated by MOECAF in coordination with the Asian Development Bank (ADB) was enacted in December 2015. This EIA Procedure covers the following contents: screening of projects, qualification for conducting the initial environmental examination (IEE)/EIA, categorization of projects for IEE/EIA/environmental management plan (EMP), preparation of IEE/EIA report and EMP, public involvement, procedure on how to get the approval of IEE/EIA report from the Environmental Conservation Department (ECD) under MOECAF, environmental compliance certificate (ECC), and monitoring process after getting the approval of the IEE/EIA report.

National Environmental Quality (Emission) Guidelines (2015)

MOECAF formulated the National Environmental Quality (Emission) Guidelines (NEQG) in coordination with ADB in December 2015. The NEQG determines the guideline values for general emission such as air emissions, wastewater, noise levels, odor, and those for sector-specific emission such as emission from forestry, agribusiness/food production, chemicals, oil and gas, infrastructure, general manufacturing, mining, and power.

Land Use

The Land Acquisition Act (1894)

The Land Acquisition Act (1894) serves as the fundamental law for land acquisition in Myanmar that sets out the procedure of land acquisition and compensation. The act further outlines relevant procedures, including notice periods, procedures for objections to acquisition (Article 5), method of valuation of land, process for taking possession of land (Article 16 and 17), court processes and appeals (Article 18 and 24), procedures for the temporary occupation of land (Article 35), and the acquisition of land for companies (Article 38). The act requires that compensation 'at market value' is provided to those from whom the land is acquired (Article 23).

The Farmland Law and Rules (2012)

The law determines the land use rights of farmland and the granting of land use rights to eligible farmers. It allows the right to sell, mortgage, lease, exchange, and give either whole or part of the right to use the farmland. The law determines the formation as well as the roles/responsibilities of farmland administrative bodies at various levels. The Farmland Law and Rules determine procedures such as the application for farmland registration and obtaining land use certificates, application of transfer of farmlands for other purposes, and indemnities and compensation.

Heritage

The Protection of Preservation of Cultural Heritage Region Law (1994)

This law prescribes the determination of cultural heritage regions for protection and preservation so as not to deteriorate due to natural disaster or man-made destruction.

Public Health

The Public Health Law (1972)

It is concerned with protection of people's health by controlling the quality and cleanliness of food, drugs, environmental sanitation, epidemic diseases and regulation of private clinics.

The Prevention and Control of Communicable Diseases Law (1995, revised in 2011)

This law describes functions and responsibilities of health personnel and citizens in relation to prevention and control of communicable diseases. It also describes measures to be taken in relation to environmental sanitation, reporting and control of outbreaks of epidemics and penalties for those failing to comply. The law also authorizes the Ministry of Health to issue rules and procedures when necessary with approval of the government.

Industrial Law

The Explosive Act (1884)

The Explosive Act stipulates the prohibitions on production, possession and use of explosives without permission.

The Explosive Substances Act (1908)

The Explosive Substance Act stipulates the prohibitions on production, possession and use of explosives without permission

The Prevention of Hazard from Chemical and Related Substances Law (2013)

The Prevention of Hazard from Chemical and Related Substances Law, the central law of chemicals management in Myanmar enacted in 2013, stipulates that when chemicals and related substances is to be transferred, stored, used, or disposed, operating approval certificate should be obtained in accordance with the regulations based on the international treaties.

Working Environment

The Worker's Compensation Act (1923)

It stipulates that employer is required to make payments to employees who become injured or who die in any accidents arising during and in consequence of their employment. Such compensation also must be made for diseases which arise as a direct consequence of employment, such as carpal tunnel syndrome.

The Payment of Wages Act (1936)

The Payment of Wage Act defines the payment obligation to the workers employed in the factories or railway administration. It stipulates the method of payment stating that the payment should be made in cash on a regular payday, and allows legal action against delayed payment or un-agreeable deduction.

The Factory Act (1951)

The Factory Act stipulates the work condition of the workers in the factory such as working hours, worksite safety and health measures. According to the act, worker at age 18 or over shall not work exceed 8 working hours per day or 44 hours per week, and the working days shall not exceed 6 days per week. As for worksite safety, the factory shall be kept clean with proper ventilation, light and heat and the workspace shall be situated away from drains, latrines or other things which create a bad or unhealthy smell.

The Shops and Establishment Act (1951)

It stipulates the payment of wage, work hours, holidays at shops and commercial establishment.

The Leave and Holidays Act (1951, partially revised in 2014)

This act has been used as the basic framework for leaves and holidays for workers with minor amendment in 2006 and 2014. This defines the public holidays that every employees shall be granted with full payment. It also defines the rules of leaves for workers including medical leave, earned leave and maternity leave.

The Labour Organization Law (2011)

The Labour Organization Law replaced the Trade Union Act enacted in 1927 for protecting the rights of the workers, having good relations among the workers or between the employer and the worker, and for forming and carrying out the labour organizations systematically and independently. Under the law, the labour organization has the right to carry out freely in drawing up their constitution and rules. It has the right to negotiate and settle with the employer if the workers are unable to obtain the right of the workers contained in the labor laws. On the other hand, the employer shall recognize the labour organizations and assist as much as possible if the labour organizations request for help for the interest of his workers.

The Social Security Law (2012)

The Social Security Law, enacted in 2012, was amended the Social Security Act in 1954. It stipulates the formation and implementation of social security systems.

The Labour Dispute Settlement Law (2012)

This law was enacted for safeguarding the right of workers or having good relationship between employer and workers and making peaceful workplace or obtaining the rights fairly, rightfully and quickly by settling the dispute of employer and worker justly. It stipulates that employer in which more than 30 workers are employed shall form the workplace coordinating committee consisting of the representatives of workers and the representatives of employer.

The Minimum Wage Law (2013)

The minimum wage law, passed in March 2013, was replaced the 1949 Minimum Wage Act. The law provides a framework for minimum wage determination: the presidential office establishing a tripartite minimum wage committee shall decide minimum wage with industrial variation based on a survey on living costs of workers possibly every two years. This also stipulates equal payment.

Infrastructure/Economic Development

The Foreign Investment Law (2012)

The Foreign Investment Law is set up to delineate the statutory characteristics of investment into Myanmar. There are specific requirements in the law that stipulate the protection of the environment. Furthermore, the following types of investments are restricted or prohibited under the law:

- Business which can affect the traditional culture and customs of the national races within the Union:
- Businesses which can affect public health;
- Businesses which can cause damage to the natural environment and ecosystem;
- Businesses which can bring hazardous or poisonous wastes into the Union;
- Factories which produce or businesses which use hazardous chemicals under international agreements;

The Export and Import Law (2012)

In 2012, the Export and Import Law was enacted and the Control of Imports and Exports Act (1947) was abolished. It aims to implement the economic principles of the State successfully, to lay down the policies to export and import that support the development of the State; and that are to be in conformity with the international trade standards.

The Myanmar Citizen Investment Law (2013)

The New Citizens Investment Law was enacted in 2013, repealing the Myanmar Citizens Investment Law of 1994. This law is to promote the inducement of domestic investment so as to lead to promotion of production and exports by the private sector.

The Electricity Law (2014)

In 2014, the Electricity Law of 1984 was replaced by the new Electricity Law, a comprehensive piece of legislation covering licensing, a new regulatory commission, standards, inspection, tariff, and restrictions. The Electricity Law divides projects into "small" (up to 10 MW), "medium" (between 10 MW to 30 MW) and large (upwards of 30 MW); the states and regions can issue permits for small and medium power plants. In case these plants are not connected to the national grid, the Union

Government Ministry is not the primary authority involved. The authorities have a legal right to use land for the purpose of power plants under the Electricity Law, and have the right to expand and maintain their facilities. The law also provides that the authorities can build transmission lines in accordance with existing laws.

The Boiler Law (2015)

The Boiler Law was enacted for protection of the accidents related to the boiler, building up skill resources, and mitigation of the long-term environmental and health impacts generated from boilers. It is described that the boiler that is to be used should meet international requirements.

Law/Rules for SEZ

The Myanmar Special Economic Zone Law (January 2014)

Myanmar Special Economic Zone Law, which was enacted in 2013 and revised in January 2014, provides the basis for the government's establishment of SEZs to encourage economic growth and foreign investment through several incentives such as five-year tax exemption and 50% income tax relief on items exported overseas for five years. Article 35 of this law stipulates that investors shall abide by the environmental standards described in the Myanmar Environmental Conservation Law and international standards.

TSEZMC Notice to Ensure the Responsible Investment in the Thilawa SEZ (August 2015)

TSMC issued a notice to ensure the responsible investment in the Thilawa SEZ in August 2015 (TSEZMC Notice No.4/2015). TSMC notifies businesses investing and doing business in the SEZ, to ensure the following eight responsibilities; 1. Respect human rights, 2. Engage with stakeholders, 3. Support the rights of workers, 4. Build human capital, 5. Ensure effective grievance mechanisms, 6. Be transparent, and 7. Create shared value, and 8. Support the communities in which they operate.

Standard Operation Procedures for Investors in Thilawa SEZ (Version No.2 in October 2015)

The Thilawa SEZ Management Committee (TSMC) has prepared the Standard Operation Procedures (SOPs) for investors in Thilawa SEZ to get certification, approval, permit for starting their business from TSMC and One Stop Service Center (OSSC) under TSMC in accordance with SEZ law and SEZ rules. The SOPs include procedures to obtain investment license, company registration, building permit, fire safety certificate, approval of environmental conservation and prevention plan (ECPP), tax registration, labor registration, and so on.

As for the environmental protection by investors, investors are required to obtain approval of ECPP before starting construction, and to obtain approval of EIA/IEE before commencement of commercial operation, if required as judged by TSMC. Investors are also required to receive environmental inspection and submit monitoring report in accordance with their ECPP during the construction and operation phases.

2.3 Contractual and Other Commitments

Internal Regulation for the Tenants

The project proponent has been formulating the internal regulations for the industrial area of Zone B, like the Internal Regulations for Zone A formulated in January 2015, in order to operate the whole industrial area properly, and also manage and supervise the tenants entered in the industrial area of Zone B in compliance with the relevant laws and regulations.

The proposed internal regulations will have several obligations for the tenants such as;

- Protective controls/rules on construction
- Conditions on design, such as setback lines, landscaping, building, parking and fencing
- Water requirements, rainwater drainage system
- Effluent standards of wastewater and air quality
- Noise and vibration standard
- Solid waste management

2.4 Tentative Environmental Target Values for Consideration of Surrounding Environment

According to Article 10 of the Environmental Conservation Law, MOECAF shall set the following environmental quality standards, with the approval of the Union Government and the Committee:

- (a) Suitable surface water quality standards for the public usage of rivers, streams, canals, springs, marshes, swamps, lakes, reservoirs, and other inland water sources of the public;
- (b) Water quality standards for coastal and estuarine areas;
- (c) Underground water quality standards;
- (d) Atmospheric quality standards;
- (e) Noise and vibration standards;
- (f) Emissions standards:
- (g) Effluent standards;
- (h) Solid waste standards; and
- (i) Other environmental quality standards stipulated by the Union Government.

As of May 2016, emission guideline and target values of ambient air quality, air emission, wastewater, and noise levels were set in NEQG, while other standards have not been set yet by MOECAF. In the Project, the Project Proponent basically continues to apply quantitative target values that have already been set in the EIA report for Thilawa SEZ Development Project (Class A) (September 2013) (hereinafter referred to as "EIA report for Class A") and/or in the Internal Regulations of Zone A prepared by the Myanmar Japan Thilawa Development Limited (MJTD) on January 1, 2015 (hereinafter referred to as "IR-A"), while referring to the target values set in NEQG. The ones that are not set in the above documents have been set in this document. Each quantitative target value to be applied is described below.

- 2.4.1 Air Quality
- 2.4.2 Water Quality
- 2.4.3 Noise
- 2.4.4 Vibration

2.4.1 Air Quality

(1) Tentative Target Value of Ambient Air Quality

NEQG has set the ambient air quality in Myanmar as shown in Table 2.4-1. Table 2.4-1 also shows the ambient quality standards in Southeast Asia (e.g., Thailand, Vietnam), Japan, and World Health Organization (WHO), which the Environmental, Health, and Safety (EHS) Guidelines by International Finance Corporation (IFC) applies as reference.

Table 2.4-1 Ambient Air Quality Standards of Myanmar, Other Countries and WHO

Item	Average Period	Myanmar	Japan	Thailand	Vietnam	wно
	10 mins	0.5 mg/m^3	-	-	1	0.5 mg/m^3
	1 hour	ı	0.26 mg/m^3	0.78 mg/m^3	0.35 mg/m^3	-
SO_2	24 hours	0.02 mg/m^3	0.10 mg/m^3	0.3 mg/m^3	0.125 mg/m^3	0.125 mg/m ³ (InterimTarget-1) 0.05 mg/m ³ (InterimTarget-2) 0.02 mg/m ³ (Guideline)
	1 year	-	1	0.1 mg/m^3	0.05 mg/m^3	-
	1 hour	0.2 mg/m^3	-	0.32 mg/m^3	0.2 mg/m^3	0.2 mg/m^3
NO ₂	24 hours	-	0.07-0.11 mg/m ³	-	0.1 mg/m^3	-
	1 year	0.04 mg/m^3	-	0.057 mg/m^3	0.04 mg/m^3	0.04 mg/m^3
СО	1 hour	-	-	36.3 mg/m ³	30 mg/m^3	-

Item	Average Period	Myanmar	Japan	Thailand	Vietnam	WHO
	8 hours	-	22.5 mg/m ³	-	10 mg/m^3	-
	24 hours	-	11.3 mg/m ³	10.26 mg/m^3	-	-
	1 hour	-	-	-	0.3 mg/m^3	-
TSP	24 hours	-	-	0.33 mg/m^3	0.2 mg/m^3	-
	1 year	-	-	$0.10 \mathrm{mg/m}^3$	0.1 mg/m^3	-
	1 hour	-	0.2 mg/m^3	-	-	-
PM_{10}	24 hours	0.05 mg/m ³	0.1 mg/m ³	0.12 mg/m^3	0.15 mg/m ³	0.15 mg/m³ (InterimTarget-1) 0.10 mg/m³ (InterimTarget-2) 0.075 mg/m³ (InterimTarget-3) 0.05 mg/m³ (Guideline)
	1 year	0.02 mg/m ³	-	0.05 mg/m^3	0.05 mg/m^3	0.07 mg/m³ (InterimTarget-1) 0.05 mg/m³ (InterimTarget-2) 0.03 mg/m³ (InterimTarget-3) 0.02 mg/m³ (Guideline)
DM	24 hours	0.025 mg/m ³	0.035 mg/m ³	0.05 mg/m^3	0.05 mg/m ³	0.075 mg/m³ (InterimTarget-1) 0.05 mg/m³ (Interim Target-2) 0.0375 mg/m³ (Interim Target-3) 0.025 mg/m³ (Guideline)
PM _{2.5}	1 year	0.01 mg/m ³	0.015 mg/m ³	$0.025~\text{mg/m}^3$	0.025 mg/m ³	0.035 mg/m³ (InterimTarget-1) 0.025 mg/m³ (InterimTarget-2) 0.015 mg/m³ (InterimTarget-3) 0.01 mg/m³ (Guideline)
	1 hour	-	-	0.2 mg/m^3	0.2 mg/m^3	-
Ozone	8 hours	0.1 mg/m^3	-	0.14 mg/m^3	0.12 mg/m^3	0.16 mg/m ³ (InterimTarget-1) 0.1 mg/m ³ (Guideline)
	24 hours	-	-		0.0015 mg/m^3	
Pb	1 month	-	-	0.0015 mg/m^3		-
	1 year	-	-	-	0.0005 mg/m^3	-
Photochemical oxidants	1 hour	-	38.7 mg/m ³	-	-	-

Note 1: Photochemical oxidants are oxidizing substances such as ozone and peroxyacetyl nitrate produced by photochemical reactions (only those capable of isolating iodine from neutral potassium iodide excluding nitrogen dioxide)

Note 2: The value of SO₂ and NO₂, CO and Ozone of Japan and Thailand were converted to mg/m³ units from ppm.

Source: Myanmar: National Environmental Quality (Emission) Guidelines (December, 2015).

Japan: National Air Quality Standard in Japan (Circular No.25, 1973, originally), Ministry of Environment, Japan

Thailand: Notifications of National Environmental Board No.10, B.E 2538 (1995), No. 24, B.E. 2547 (2004), No. 28, B.E 2550 (2007), No. 33, B.E 2552 (2009), No. 36, B.E 2553 (2010) under the Enhancement and Conservation of National Environmental Quality Act B.E.2535 (1992).

Vietnam: National Technical Regulation on Ambient Air Quality (QCVN 05:2013/BTNMT), Ministry of Science and Technology in Vietnam.

WHO: WHO Air Quality Guidelines 2005.

On the basis of the above standards, the tentative target value for air quality in the Project, as shown in Table 2.4-2, has been set with the following considerations:

- Target parameters of ambient air quality in Myanmar's standards are applied if it has set (SO₂, NO₂, PM_{2.5}, and PM₁₀).
- The averaging period adopted is 24 hours, which could be measured using the available equipment in Myanmar whereas currently it is impossible to implement continuous measurement for one month or one year at the project site due to battery/electrical capacities.
- If there is no standard in Myanmar, then basically the strictest standard among the standards of Japan, Thailand, Vietnam, and WHO of interim target-1 are adopted.

 Table 2.4-2
 Tentative Target Value of Ambient Air Quality in the Project

Item	Average Period	Myanmar	Japan	Thailand	Vietnam	WНО	Tentative Target Value
SO ₂	24 hours	0.02 mg/m^3	0.10 mg/m^3	0.3 mg/m^3	0.125 mg/m^3	0.125 mg/m ³ (InterimTarget-1) 0.05 mg/m ³ (InterimTarget-2) 0.02 mg/m ³ (Guideline)	0.02 mg/m^3

Item	Average Period	Myanmar	Japan	Thailand	Vietnam	wно	Tentative Target Value
	1 hour	0.2 mg/m^3	-	0.32 mg/m^3	0.2 mg/m^3	0.2 mg/m^3	0.2 mg/m^3
NO ₂	24 hours	-	0.07-0.11 mg/m ³		0.1 mg/m ³	-	0.1 mg/m ³
СО	24 hours	-	11.3 mg/m ³	10.26 mg/m ³	-	-	10.26 mg/m ³
PM _{2.5}	24 hours	0.025 mg/m ³	$0.035 \\ mg/m^3$	0.05 mg/m ³	0.05 mg/m ³	0.075 mg/m³ (InterimTarget-1) 0.05 mg/m³ (Interim Target-2) 0.0375 mg/m³ (Interim Target-3) 0.025 mg/m³ (Guideline)	0.025 mg/m ³
PM ₁₀	24 hours	0.05 mg/m ³	0.1 mg/m ³	0.12 mg/m ³	0.15 mg/m ³	0.15 mg/m³ (InterimTarget-1) 0.10 mg/m³ (InterimTarget-2) 0.075 mg/m³ (InterimTarget-3) 0.05 mg/m³ (Guideline)	0.05 mg/m ³

Source: EIA Study Team

(2) Air Emissions Level

NEQG has set air emission level applicable to small-combustion facilities designed to deliver electrical or mechanical power, steam, heat, or any combination of these, regardless of fuel type, with a total, rated heat input capacity of 3-50 megawatt thermal as shown in Table 2.4-3.

Table 2.4-3 Air Emission Level set in NEQG

Combustion Technology/ Fuel	Particulate matter PM ₁₀	Sulfur Dioxide	Nitrogen Oxides
Gas	-	-	200^{10} mg/Nm^3
			$400^{2)} \text{mg/Nm}^3$
			$1,600^{3}$ mg/Nm ³
Liquid	100	3%	1,600-1,850 ⁴⁾ mg/Nm ³
Natural gas (3-<15 MW)	-	-	90 ⁵⁾ mg/Nm ³
			210^{6} mg/Nm^3
Natural gas (15-<50 MW)	-	-	50 mg/Nm ³
Fuel other than natural gas (3-<15MW)	-	0.5% sulfur	200 ⁵⁾ mg/Nm ³
			310^{6} mg/Nm^3
Fuel other than natural gas (15-<50MW)	-	0.5% sulfur	150 mg/Nm ³
Gas	-	-	320 mg/Nm^3
Liquid	150 mg/Nm ³	$2,000 \text{ mg/Nm}^3$	460 mg/Nm ³
Solid 7)	150 mg/Nm ³	2,000 mg/Nm ³	650 mg/Nm ³

Note: 1) spark ignition; 2) dual fuel; 3) compression ignition, 4) Higher value applies if bore size >400mm,

5) electric generation; 6) mechanical drive, 7) included biomass

Source: NEQG (December 2015)

On the other hand, IR-A stipulates that the tenants shall have its own arrangement to satisfy with the standard stipulated by the regulation in the Republic of the Union of Myanmar and IFC General ESH Guidelines.

2.4.2 Water Quality

(1) Tentative Target Value of Ambient Water Quality

Currently, there is no ambient water quality standard in Myanmar. Its target value wasn't set neither in the EIA report for Class A nor in the IR-A. In consideration of the above situation, the target value of ambient water quality for the Project is set in reference of the ambient quality standards in South-east Asia (e.g. Indonesia, Thailand and Vietnam) and Japan as shown in Table 2.4-4.

On the basis of the above standards, the tentative target value for ambient water quality in this project, as shown in Table 2.4-4, has been set with the following considerations.

- Target parameters of ambient water quality level were decided based on available measurement equipment in Myanmar.
- Basically each of target value has adopted the strictest one among the standards of Indonesia, Thailand, Vietnam and Japan.
- For tentative target value of DO, and BOD, SS, the current conditions were exceeded the strictest standards in Indonesia, Thailand, Vietnam and Japan. Thus, tentative target values were selected as the values which to be achieved with current conditions.

Table 2.4-4 Target Value of Ambient Water Quality

	Parameter	unit	Indonesia	Thailand	Vietnam	Japan	Tentative Target Value
1	DO	mg/L	3	2	4	2	4
2	BOD	mg/L	6	4	15	8	15
3	SS	mg/L	400	-	50	100	100
4	pН		6-9	5-9	5.5-9	6-8.5	6-8.5
5	COD _{Cr}	mg/L	50	-	30	-	30
6	Cyanide	mg/L	0.02	0.005	0.02	Not detectable	Not detectable
7	Phenol	mg/L	1	0.005	0.001	-	0.001
8	Zinc	mg/L	0.05	1.0	1.5	-	0.05
9	Chromium (VI)	mg/L	0.05	0.05	0.04	0.05	0.04
10	Arsenic	mg/L	1	0.01	0.05	0.01	0.01
11	Copper	mg/L	0.02	0.1	0.5	-	0.02
12	Mercury	mg/L	0.002	0.002	0.001	0.0005 (Alkyl mercury: not detectable)	0.0005
13	Cadmium	mg/L	0.01	0.005* 0.05**	0.01	0.003	0.003
14	Selenium	mg/L	0.05	-	-	0.01	0.01
15	Lead	mg/L	0.03	0.05	0.05	0.01	0.01
16	Nickel	mg/L	-	0.1	0.1	-	0.1
17	Manganese	mg/L	-	1.0	1	-	1.0
18	Iron	mg/L	1	-	1.5	-	1.5
19	NO ₃ as N	mg/L	20	5.0	10	10	5
20	NH ₃ as N	mg/L	-	0.5	0.5	-	0.5
21	Fluoride	mg/L	1.5	-	1,5	0.8	0.8
22	Oil and Grease	mg/L	1	-	0.1	-	0.1
23	Total coliform	MPN/100 ml	10,000	20,000	7,500	-	7,500

Note: If the results of current status are exceeded the tentative target value, target value should set that does not significantly worsen the current situation.

Source: Indonesia: Government Regulation No.82/2001, Class III: Water that can be used for freshwater fish aquaculture, animal husbandry, plantation irrigation purposes and/or other uses requiring the same water quality standards)

Thailand: Notification of the National Environmental Board, No. 8, B.E. 2537 (1994), issued under the Enhancement and Conservation of National Environmental Quality Act B.E.2535 (1992), published in the Royal Government Gazette, Vol. 111, Part 16, dated February 24, B.E.2537 (1994), Class 3: Medium clean fresh surface water resources used for : (1) consumption, but passing through an ordinary treatment process before using, (2) agriculture

Vietnam: National technical regulation on surface water quality (NTR 08:2008), Agricultural use in surface water quality standard (Class B1)

Japan: Agricultural use in river water quality standard (Class D)

(2) Tentative Target Value of Effluent Water Quality after Wastewater Pre-treatment by Tenant

The tentative target value of effluent water quality discharged from each tenant in the industrial area was set in consideration of National Environmental Quality (Emission) Guidelines (NEQG), the industrial wastewater effluent guideline value determined by the Ministry of Industry (MOI) and the designed treatment level of the central sewage treatment plant (STP).

The tenants shall install its own pre-treatment system (PTS) to comply with the target value as shown below table. The treated effluent water by PTS from tenants will be connected to the central STP in the industrial area of Zone A/Zone B that can treat to reduce BOD, COD and SS levels.

In consideration of the above condition, tentative target level shall be set by the following criteria;

- (1) Since BOD, COD, and SS will be treated at the central STP, the tentative target values of these three items were set in consideration of the designed treatment level of the central STP.
- (2) As for other items except the above three, tentative target values were selected from NEQG, which is the latest guideline of effluent water quality stipulated by MONREC. According to NEQG, the guideline value shall be applied to any project subject to EIA Procedure. Therefore, NEQG was selected as high priority. The parameters and its limited value is not set in NEQG but set in industrial wastewater effluent guideline of MOI, MOI guideline were selected additionally to the tentative target value.
- (3) The items such as Cyanide (as HCN) (free), Tar, Phenols (only), heavy metals (total), Insecticides and Radioactive materials are not common and not able to be measured in Myanmar. Therefore, Cyanide (as HCN) (total), Phenols and cresol were set as target items, instead. Since Tar, Heavy metals (total) and Radioactive materials have no alternative analysis items, Therefore, these parameters were removed from target item. For insecticides, it has not been clearly defined as a target substance of insecticide in guide line of MOI. Thus, it was also removed from target item.
- (4) The target value of Color and Odor and Total Nitrogen, those of which haven't set either in NEQG or in the wastewater effluent guideline of MOI, set as a voluntary target values by the project proponent.

Table 2.4-5 Tentative Target Value of Effluent Water Quality (EWQ) after Wastewater

Pre-treatment by Tenant

No.	Items	Unit	Target Value set by MOI ²	Guideline Value set in NEQG	Internal Regulations of Zone A	Tentative Target Value	Reason for selection
1.	BOD (5 days at 20 °C)	mg/L	20	50	200	200^{3}	(1)
2.	Suspended solids (SS)	mg/L	30	50	300	200^{3}	(1)
3.	Dissolved solids	mg/L	2,000	-	2,000	2,000	(2)
4.	pH Value	_	5 - 9	6 - 9	6.5 - 8.5	6 – 9	(2)
5.	COD _{Mn} Permanganate value	mg/L	60	-	150	150	(1)
6.	COD _{Cr} Dicromate value	mg/L	-	250	300	300^{3}	(1)
7.	Sulfide (as HS)	mg/L	1	1	1	1	(2)
8.	Cyanide (as HCN)	mg/L	0.2	0.1 (free) 1 (total)	0.2	1 (total)	(3)
9.	Oil and grease	mg/L	5	10	5	10	(2)
10.	Total coliform bacteria	MPN/100 mL	-	400	400	400	(2)
11.	Tar	-	None	-	None	-	(3)
12.	Formaldehyde	mg/L	1	-	1	1	(2)
13.	Phenols and cresols	mg/L	1	0.5 (Phenols only)	1	1	(3)
14.	Free chlorine	mg/L	1	0.2 (total residual)	1	0.2	(2)
15.	Heavy metals (total)	mg/L	-	10	-	-	(3)
16.	Zinc	mg/L	5	2	5	2	(2)
17.	Chromium (Total)	mg/L	0.5	0.5	0.5	0.5	(2)
18.	Chromium (Hexavalent)	mg/L	-	0.1	-	0.1	(2)
19.	Arsenic	mg/L	0.25	0.1	0.25	0.1	(2)
20.	Copper	mg/L	1.0	0.5	1	0.5	(2)

^{*}Above four reasons correspond to "reason for selection" of each item in Table 2.4-5.

No.	Items	Unit	Target Value set by MOI ²	Guideline Value set in NEQG	Internal Regulations of Zone A	Tentative Target Value	Reason for selection
21.	Mercury	mg/L	0.005	0.01	0.005	0.01	(2)
22.	Cadmium	mg/L	0.03	0.1	0.03	0.1	(2)
23.	Barium	mg/L	1.0	ı	1	1.0	(2)
24.	Selenium	mg/L	0.02	0.1	0.02	0.1	(2)
25.	Lead	mg/L	0.2	0.1	0.2	0.1	(2)
26.	Nickel	mg/L	0.2	0.5	0.2	0.5	(2)
27.	Insecticides	-	None	-	None	-	-
28.	Radioactive Materials	-	None	-	None	-	(3)
29.	Temperature	°C	40	<3 (increase)	35	<3 (increase)	(2)
30.	Color and Odor	Co-Pt	Not objectionable when mixed in receiving water	-	150	150	(4)
31.	Total Nitrogen	mg/L	-	-	80^{1}	80^{1}	(4)
32.	Ammonia	mg/L	=	10	-	10	(2)
33.	Fluoride	mg/L	=	20	-	20	(2)
34.	Iron	mg/L	=	3.5	ī	3.5	(2)
35.	Silver	mg/L	=	0.5	ī	0.5	(2)
36.	Total Phosphorus	mg/L	-	2	-	2	(2)

Note 1: This standard has been changed from 40 to 80 on July 7, 2015 by MJTD (Ref: MJTD/O/15-07-187, Notification: Standard of Wastewater Quality Changed on Thilawa Special Economic Zone (Zone A) Industrial Zone Internal Regulations

Note 2: The unit is changed to mg/L from ppm in the original source.

Note 3: Designed influent water quality at the central STP; BOD: 200 mg/L, SS:200 mg/L, COD_{Mn}:150 mg/L, COD_{Cr}:300 mg/L

Source: EIA Study Team

(3) Tentative Target Value of Effluent Water Quality after Wastewater Treatment at Centralized Sewage Treatment Plant (STP) by Project Proponent (MJTD)

The target value of effluent water quality after wastewater treatment at centralized STP by the project proponent was set, in consideration of National Environmental Quality (Emission) Guidelines (NEQG) and the industrial wastewater effluent guideline value determined by the Ministry of Industry (MOI) as shown in Table 2.4-6.

Therefore, the process of selection of the tentative target level is summarized as follows;

- (1) Target value of BOD, SS and COD that will be treated at the central STP of Zone A/Zone B set based on the designed treatment levels which are satisfied with the guideline values of NEQG and MOI.
- (2) As for other items except the above three, tentative target values of effluent water quality after treatment at the central STP are same as tentative target values of effluent water quality for tenants shown in Table 2.4-5.

Table 2.4-6 Tentative Target Value of Effluent Water Quality after Wastewater Treatment at Centralized Treatment plant by Project Proponent (MJTD)

No.	Items	Unit	Target Value set by MOI ²	Guideline Value set in NEQG	Tentative Target Value of EWQ after Wastewater Pre-treatment	Tentative Target Value	Reason for selection
1.	BOD (5 days at 20 °C)	mg/L	20	50	200	20^{3}	(1)
2.	Suspended solids	mg/L	30	50	200	30^{3}	(1)
3.	COD _{Mn} Permanganate value	mg/L	60	-	150	35 ³	(1)
4.	COD _{Cr} Dicromate value	mg/L	-	250	300	70^{3}	(1)
5.	Dissolved solids	mg/L	2,000	-	2,000	2,000	(2)

^{*}Above two reasons correspond to the "reason for selection" of each item in Table 2.4-6.

No.	Items	Unit	Target Value set by MOI ²	Guideline Value set in NEQG	Tentative Target Value of EWQ after Wastewater Pre-treatment	Tentative Target Value	Reason for selection
6.	pH Value	_	5 - 9	6 - 9	6 – 9	6 - 9	(2)
7.	Sulfide (as HS)	mg/L	1	1	1	1	(2)
8.	Cyanide (as HCN)	mg/L	0.2	0.1 (free) 1 (total)	1 (total)	0.2	(2)
9.	Oil and grease	mg/L	5	10	10	10	(2)
10.	Total coliform bacteria	MPN/100 mL	-	400	400	400	(2)
11.	Tar	-	None	-	-	-	(2)
12.	Formaldehyde	mg/L	1	-	1	1	(2)
13.	Phenols and cresols	mg/L	1	0.5 (Phenols only)	1	1	(2)
14.	Free chlorine	mg/L	1	0.2 (total residual)	0.2	0.2	(2)
15.	Heavy metals (total)	mg/L	ı	10	-	-	(2)
16.	Zinc	mg/L	5	2	2	2	(2)
17.	Chromium (Total)	mg/L	0.5	0.5	0.5	0.5	(2)
18.	Chromium (Hexavalent)	mg/L	ı	0.1	0.1	0.1	(2)
19.	Arsenic	mg/L	0.25	0.1	0.1	0.1	(2)
20.	Copper	mg/L	1.0	0.5	0.5	0.5	(2)
21.	Mercury	mg/L	0.005	0.01	0.01	0.01	(2)
22.	Cadmium	mg/L	0.03	0.1	0.1	0.1	(2)
23.	Barium	mg/L	1.0	-	1.0	1.0	(2)
24.	Selenium	mg/L	0.02	0.1	0.1	0.1	(2)
25.	Lead	mg/L	0.2	0.1	0.1	0.1	(2)
26.	Nickel	mg/L	0.2	0.5	0.5	0.5	(2)
27.	Insecticides	-	None	-	-	-	(2)
28.	Radioactive Materials	-	None	-	-	-	(2)
29.	Temperature	°C	40	<3 (increase)	<3 (increase)	<3 (increase)	(2)
30.	Color and Odor	Co-Pt	Not objectionable when mixed in receiving water	-	150	150	(2)
31.	Total Nitrogen	mg/L	-	-	80¹	80 ¹	(2)
32.	Ammonia	mg/L	-	10	10	10	(2)
33.	Fluoride	mg/L	-	20	20	20	(2)
34.	Iron	mg/L	-	3.5	3.5	3.5	(2)
35.	Silver	mg/L	-	0.5	0.5	0.5	(2)
36.	Total Phosphorus	mg/L		2	2	2	(2)

Note 1: This standard has been changed from 40 to 80 on July 7, 2015 by MJTD (Ref: MJTD/O/15-07-187, Notification: Standard of Wastewater Quality Changed on Thilawa Special Economic Zone (Zone A) Industrial Zone Internal Regulations

Note 2: The unit is changed to mg/L from ppm in the original source.

Note 3: Designed treated water quality at central STP: BOD :20 mg/L, SS:30 mg/L, COD_{Mn}:35 mg/L, COD_{Cr}:70mg/L

Source: EIA Study Team

2.4.3 Noise

(1) Noise Level Set in NEQG

In NEQG, the noise level is set as shown in Table 2.4-7 and noise prevention and mitigation measures should be taken by all projects where the predicted or measured noise impacts from a project facility or operation exceed the applicable noise level guideline at the most sensitive point of reception. Noise impact should not exceed the levels shown below, or result in a maximum increase in background levels of three decibels at the nearest offsite receptor location.

Table 2.4-7 Target Noise Level Set in NEQG

	One Hour LAeq (dBA)				
Receptor	Daytime (7:00-22:00) (10:00-22:00 for public holidays)	Nighttime (22:00-7:00) (22:00-10:00 for public holidays)			
Residential, institutional, educational	55	45			
Industrial, commercial	70	70			

Source: NEQG (December 2015)

(2) Tentative Target Noise Level during the Construction Phase and Closing Phase

Tentative target noise levels during the construction phase and closing phase are set as shown in Table 2.4-8. These levels are defined for construction noise in both EIA report for Class A and in the IR-A for tenants. The difference of the target level between them is the location of the evaluation point, i.e., at the boundary of the building of receptors under EIA report for Class A that will be applied to the EIA report for Zone B, while it is at the boundary of SEZ and tenant's property under IR-A. In the Project, tentative target noise level is set same as EIA for Class A.

Since demolition noise has the same characteristics as construction noise, the above target noise level is applied during the closing phase as well.

Table 2.4-8 Tentative Target Noise Level during the Construction Phase and Closing Phase

Category	Daytime (Leq) (7 am-7 pm)		Evening Time (Leq) (7 pm-10 pm)		Nighttime (Leq) (10 pm-7 am)	
	EIA ¹	Tenant ²	EIA	Tenant	EIA	Tenant
A side next to a residential house and monastery located less than 150 m	75 dB	75 dB	60 dB	60 dB	55 dB	55 dB
Other than above	75 dB	75 dB	65 dB	65 dB	65 dB	65 dB

Note: Evaluation point is at the boundary of building of receptors for EIA of Zone B and at boundary of SEZ and tenant's property.

- 1: Target noise level set in the EIA report for Class A
 - 2: Target noise level set in the IR-A for tenants in the industrial area

Source: The EIA report for Thilawa SEZ Development Project (Class A) (September 2013), summarized by the EIA Study Team

(3) Tentative Target Noise Level during the Operation Phase

Table 2.4-9 shows the target noise levels during the operation phase in the EIA report for Class A, IR-A, and NEQG. In the Project, tentative target noise level is set same as EIA for Class A because background noise level is already exceeded NEQG sometimes.

Table 2.4-9 Tentative Target Noise Level during the Operation Phase

Category	Г	Oaytime (Le (7 am-7 pm			ing Time (l pm-10 pm			ghttime (L 10 pm-7 ar	
Category	EIA ¹	Tenant ²	NEQG ³	EIA	Tenant	NEQG	EIA	Tenant	NEQG
A side next to sensitive area such as monastery, hospital, and school	60 dB	60 dB	55dB	55 dB	55 dB	55dB	50 dB	50 dB	45dB
A side next to residential area	65 dB	65 dB		60 dB	60 dB		55 dB	55 dB	
A side next to commercial and industrial areas including inside of Thilawa SEZ Zone A	70 dB	70 dB	70 dB	65 dB	65 dB	70 dB	60 dB	60 dB	70 dB

Note: Evaluation point is at the boundary of building of receptors for EIA of Zone B and at the boundary of SEZ and tenant's property, while at the most sensitive point of reception for NEQG.

- 1: Target noise level set in the EIA report for Class A
- 2: Target noise level set in the IR-A for tenants in the industrial area
- 3: In NEQG, the noise level should not exceed the levels shown in the table, or result in a maximum increase in background levels of three decibels at the nearest offsite receptor location during public holidays.

Source: The EIA report for Thilawa SEZ Development Project (Class A) (September 2013), summarized by the EIA Study Team

(4) Tentative Target Noise Level from Traffic

Noise level from traffic is different characteristic from ambient noise, and higher. Though the noise level for living area is set in NEQG (Table 2.4-7), there is no target level specified for traffic noise along the road in NEQG. Therefore, tentative target levels for traffic noise along the road are set in accordance with the Japanese traffic noise target level as shown in Table 2.4-10.

Table 2.4-10 Tentative Target Noise Level from Traffic

	Daytime (Leq) (6 am-10 pm)	Nighttime (Leq) (10 pm-6 am)
Target Noise Level (dB)*	75	70

Note *: Applied "proximity to major arterial roads"

Source: The Noise Regulation Law (Japan) (Law No. 98 of 1968, Latest Amendment by Law No.91 of 2000)

2.4.4 Vibration

(1) Tentative Target Vibration Level during the Construction Phase and Closing Phase

Tentative target vibration levels during the construction and closing stages applied the same levels as in the EIA Report for Class A. Target vibration level for tenants applied the same level since this was not defined in the IR-A. Only the evaluation points of EIA of Zone B and for tenants are different. In the Project, tentative target vibration level is set same as EIA for Class A.

Demolition vibration has the same characteristics as construction vibration. Therefore, the target levels shown in Table 2.4-11 can be adopted for both construction phase and closing phase.

Table 2.4-11 Tentative Target Vibration Level during the Construction/Closing Phase

Category		Daytime (La) I (7 am-7 pm)		Evening Time (La) (7 pm-10 pm)		Nighttime (La) (10 pm-7 am)	
	EIA ¹	Tenant ²	EIA	Tenant	EIA	Tenant	
A side next to residential house and monastery	65 dB	65 dB	65 dB	60 dB	60 dB	60 dB	
A side next to commercial and industrial areas including inside of Thilawa SEZ Zone A	70 dB	70 dB	70 dB	65 dB	65 dB	60 dB	

Note: Evaluation point is at the boundary of building of receptors for EIA of Zone B and at the boundary of SEZ and tenant's property.

- 1: Target vibration level set in the EIA report for Class A
- 2: Target vibration level set in the IR-A for tenants in the industrial area

Source: The EIA Report for Thilawa SEZ Development Project (Class A) (September 2013), summarized by the EIA Study Team

(2) Tentative Target Vibration Level during the Operation Phase

Tentative target vibration levels during the operation phase applied the same levels as in the EIA report for Class A and IR-A for tenants as shown in Table 2.4-12. In the Project, tentative target vibration level is set same as EIA for Class A.

Table 2.4-12 Tentative Target Vibration Level during the Operation Phase

Category	Daytime (La) (7 am-7 pm)		U	Time (La) -10 pm)	Nighttime (La) (10 pm-7 am)	
	EIA ¹	Tenant ²	EIA	Tenant	EIA	Tenant
Residential houses and monastery	65 dB	65 dB	60 dB	60 dB	60 dB	60 dB
Office, commercial facilities, and factories	70 dB	70 dB	65 dB	65 dB	65 dB	60 dB

Note: Evaluation point is at the boundary of the building of receptors for EIA of Zone B and at the boundary of SEZ and tenant's property.

- 1: Target vibration level set in the EIA report for Class A
- 2: Target vibration level set in the IR-A for tenants in the industrial area

Source: The EIA Report for Thilawa SEZ Development Project (Class A) (September 2013), summarized by the EIA Study Team

(3) Tentative Target Vibration Level from Traffic

Vibration level from traffic is different characteristic from ambient vibration level, and higher. Since there is no target level set in either the EIA report for Class A or IR-A, the tentative target vibration levels from traffic are set in accordance with the Japanese target level as shown in Table 2.4-13.

Table 2.4-13 Tentative Target Vibration Level from Traffic

	Daytime (L ₁₀) (6 am-10 pm)	Nighttime (L ₁₀) (10 pm-6 am)
Target Level (dB)*	65	60

Note *: Applied "Residential Area"

Source: The Vibration Regulation Law (Japan) (Law No. 64 of 1976, Latest Amendment by Law No.75 of 1995)

2.5 Social and Health Standards for the Project

IFC EHS Guidelines

The EHS Guidelines¹ by IFC are technical reference documents with general and industry-specific examples of Good International Industry Practice (GIIP), as defined in IFC's Performance Standard 3: Resource Efficiency and Pollution Prevention. The EHS Guidelines contain the performance levels and measures that are normally acceptable to IFC, and that are generally considered to be achievable in new facilities at reasonable costs by existing technology.

There are two kinds of guidelines, General EHS Guidelines and Industry Sector Guidelines. The General EHS Guidelines contain information on cross-cutting environmental, health, and safety issues potentially applicable to all industry sectors in the following section: (1) Environment, (2) Occupational Health and Safety, (3) Community Health and Safety, and (4) Construction and Decommissioning. Table 2.5-1 shows the contents of the section of Community Health and Safety.

Table 2.5-1 Community Health and Safety in IFC EHS Guidelines

Contents	Brief Description
Water Quality and Availability	Drinking water sources should at all times be protected so that they meet or exceed applicable national acceptability standards or in their absence the current edition of WHO Guidelines for Drinking-Water Quality. Project activities should not compromise the availability of water for personal hygiene needs and should take account of potential future increases in demand. The overall target should be the availability of 100 liters per person per day.
Structural Safety of Project Infrastructure	Reduction of potential hazards is best accomplished during the design phase when the structural design, layout and site modifications can be adapted more easily. The following issues should be considered and incorporated as appropriate into the planning, siting, and design phases of a project: 1) inclusion of buffer strips or other methods of physical separation around project sites to protect the public from major hazards associated with hazardous materials incidents or process failure, 2) incorporation of siting and safety engineering criteria to prevent failures due to natural risks posed by earthquakes, tsunamis, wind, flooding, landslides and fire, and 3) application of locally regulated or internationally recognized building codes.
Life and Fire Safety (L&FS)	All new buildings accessible to the public should be designed, constructed, and operated in full compliance with local building codes, local fire department regulations, local legal/insurance requirements, and in accordance with an internationally accepted life and fire safety (L&FS) standard. Sponsors should prepare a Life and Fire Safety Master Plan identifying major fire risks, applicable codes, standards and regulations, and mitigation measures.
Traffic Safety	Traffic safety should be promoted by all project personnel during displacement to and from the workplace, and during operation of project equipment on private or public roads. Prevention and control of traffic related injuries and fatalities should include the adoption of safety measures that are protective of project workers and of road users, including those who are most vulnerable to road traffic accidents.

_

¹ The EHS Guidelines are available at the following website of IFC. (As of May 2016) http://www.ifc.org/wps/wcm/connect/topics_ext_content/ifc_external_corporate_site/ifc+sustainability/our+approach/risk+m anagement/ehsguidelines

Contents	Brief Description
Transport of	Projects should have procedures in place that ensure compliance with local laws and international
Hazardous	requirements applicable to the transport of hazardous materials.
Materials	
Disease	Recommended interventions against the communicable diseases at the project level include 1) providing
Prevention	surveillance and active screening and treatment of workers, 2) preventing illness among workers in local
	communities by undertaking health awareness and education initiatives, training health workers in disease
	treatment and conducting immunization programs for workers, and 3) providing treatment through standard
	case management in on-site or community health care facilities.
Emergency	All projects should have an Emergency Preparedness and Response Plan that is commensurate with the
Preparedness	risks of the facility and that includes the following basic elements: 1) Administration (policy, purpose,
and Response	distribution, definitions, etc), 2) Organization of emergency areas (command centers, medical stations, etc),
	3) Roles and responsibilities, 4) Communication systems, 5) Emergency response procedures, 6)
	Emergency resources, 7) Training and updating, 8) Checklists (role and action list and equipment checklist),
	and 9) Business Continuity and Contingency.

Source: IFC, Environmental, Health, and Safety (EHS) Guidelines, General EHS Guidelines: Community Health and Safety (April 30, 2007)

2.6 Institutional Arrangement

2.6.1 Thilawa SEZ Management Committee

Thilawa SEZ Management Committee (TSMC) was established as per Article (5) of the Myanmar Special Economic Zone Law as the government's licensing body which approves the investment of both foreign and domestic investors to be located in the Thilawa SEZ.

Under the TSMC, One Stop Service Center (OSSC) was established as a single window for investors in the Thilawa SEZ, where they can get all of the necessary approvals and registrations done at one place. It is staffed by representatives of various ministries who are fully authorized to grant necessary licenses and approvals required by investors.

The One-Stop Service Center is currently staffed by representatives from:

- Commerce and Consumer Department, Ministry of Commerce
- Customs Department, Ministry of Planning and Finance
- Department of Internal Revenue, Ministry of Planning and Finance
- Department of Immigration and National Registration, Ministry of Labor, Immigration and Population
- Labor Department, Ministry of Labor, Immigration and Population Department of Human Settlement and Housing Development, Ministry of Construction
- Environmental Conservation Department, Ministry of Natural Resources and Environmental Conservation
- Directorate of Industrial Supervision and Inspection, Ministry of Industry
- Central Bank
- General Administration Department (GAD), Yangon Southern District
- Myanmar Port Authority
- Directorate of Investment and Companies Administration (DICA)

As for environmental management, two officers from Environmental Conservation Department of MONREC have been dispatched to the environment section in OSSC. As the regular tasks, the officers review application documents related to environment from investors, conduct environmental inspection during construction phase, before commencement of operation, and during operation.

2.6.2 Project Proponent

The project proponent (MJTD) consists of five departments/divisions as shown in Figure 2.6-1. Environment, safety and health section under operation team of operations division is responsible for

environmental, health and safety management. Community relation division under President and CEO directly is responsible for grievance adjustment, support of the community, CSR activities etc.




Figure 2.6-1 Organizational Structure of MJTD

Table 2.6-1 Main Tasks for Environmental and Social Consideration in MJTD


Division/ Section	Main Tasks
Environment, safety	1) Assisting tenants in the environmental assessment of factory development as follows:
and health section	- Providing information on environmental regulations and local consultants; and
	- Facilitating communication with TSMC for environmental and social issues.
	2) Monitoring the Thilawa SEZ Zone B industrial area operations according to EMP and EMoP, and;
	3) Submitting environmental monitoring reports to TSMC.
Community relation	1) Grievance Adjustment
division	- Handling complains/ claims/ requests from community and its response as necessary
	- Coordinating between tenant and community for grievance adjustment
	2) Planning and implementation of CSR activities
	3) Consultation with tenant related to community relation
	4) Job matching and assistance

Source: MJTD

2.6.3 Institution Structure for Involuntary Resettlement in Thilawa SEZ

Figure 2.6-2 shows the institutional structure of implementing resettlement works in Thilawa SEZ. Two committees, namely, Relocation Implementation Committee (RIC) and Income Restoration Program Implementation Committee (IRPIC), were established as the supporting organizations for implementing resettlement works, including IRP activities, of the entire Thilawa SEZ (2,400 ha) according to the decisions issued by the Yangon Region Government (YRG). These organizations will be in charge of the actual relocation and resettlement works in Thilawa SEZ.

While the two committees mentioned above play a role for supporting implementation, the Multi-Stakeholder Advisory Group (MSAG), which was established for resettlement works in Zone A of Thilawa SEZ development, supports by providing advice on the resettlement works. Broader stakeholder engagement will assist in expediting the progress of the resettlement works and resolving some of the challenges, as well as providing lessons learned from Zone A in the case of 2,000 ha. In the two committees and MSAG, selected representatives from the villages will be involved and will act as members to reflect the public opinion into the resettlement process.



Source: Thilawa SEZ Management Committee, Framework of Resettlement Works for the 2,000 ha Development Area of Thilawa Special Economic Zone (SEZ), February 2016

Figure 2.6-2 Implementation Structure of Resettlement Works in Thilawa SEZ

2.7 Environmental Management in the Thliawa SEZ


2.7.1 Environmental Management Framework of Thilawa SEZ

(1) EIA Procedure for the Project Proponent

As described in Chapter 1, a procedure of environmental management for zone development was established in February 2016 as shown in Figure 2.7-1². The project proponents of zone development are required to submit scoping report, draft EIA report, and final EIA report, and conduct public consultation meetings and disclosures at scoping stage and draft EIA report stages. For the appraisal of the EIA study for zone development, a mobile review team, which is composed of staff from MONREC and relevant ministries, is established to review the draft EIA report. TSMC together with the mobile review team will make comments on the draft EIA Report through EIA Review Committee. After issuing comments on the draft EIA Report, the project proponent finalizes the EIA report based on the comments from TSMC as well as the public for appraisal of the final EIA Report by TSMC.

After approval of the Final EIA Report, the project proponent will be requested to conduct environmental monitoring during construction, operation, closing phases based on Environmental Management Plan (EMP) developed based on the results of environmental impact assessment.

² From the technical view point of EIA, the requirement of EIA study in the Thilawa SEZ will follow the EIA Procedures.



Source: Thilawa SEZ Management Committee

Figure 2.7-1 Procedure for EIA Appraisal for Zone Development


(2) Environmental Management for Investors

As for environmental management for setting up a business and commencement of commercial operation by an investor in Thilawa SEZ, the following actions are requested in the three stages; "Preparatory stage for starting construction (Before construction)", "Construction stage", and "Regular operation stage" as shown in Figure 2.7-2. Standard operating procedures related to application and approval process of ECPP, IEE and EIA can be downloaded from the following link in the website of TSMC³.

http://www.myanmarthilawa.gov.mm/environmental-protection-ecpp-iee-and-eia

This procedure was prepared for Zone A development, but it will apply to Zone B as well.

3



Note: This procedure was prepared for Zone A development, but it will apply to Zone B as well.

Source: Thilawa SEZ Management Committee

Figure 2.7-2 Overall Procedures for Environmental Management in Thilawa SEZ

1) Preparatory Stage for Starting Construction

Environmental Conservation and Prevention Plan (ECPP)

In accordance with the Notification No.81/2014 of the Ministry of National Planning and Economic Development, it is required to prevent and conserve the surrounding environment in Thilawa SEZ. Hence, every applicant needs to prepare and submit Environmental Conservation and Prevention Plan (ECPP), which includes the plan for environmental management, mitigation measures and monitoring to be conducted, for its business operation. All investors shall obtain approval of ECPP from TSMC before commencing the construction works at the project site.

Environmental Impact Assessment (EIA)/ Initial Environmental Examination (IEE)

Some investors which may cause adverse environmental impacts may be required to conduct IEE or EIA. TSMC judges necessity of IEE or EIA based on the draft ECPP prepared by Applicants in accordance with the following criteria as shown in Table 2.7-1.

Criteria for Necessity of IEE/EIA

No. Criteria Item

1 Requirement of IEE or EIA in accordance with existing criteria (EIA Procedures, IFC production area, etc.

1	with existing criteria (EIA Procedures, IFC EHS Guidelines, EU Directive 2008/1/EC concerning integrated pollution prevention and control)	(a)	production area, etc.
2	Facing to Residential and Monetary Area	(a)	Facing or Not facing
3	Air pollution	(a)	Installation of combustion facilities such as boilers, furnaces, engines etc.
		(b)	Materials used for combustion facilities
		(c)	Generation capacity of combustion facilities
		(d)	Amount of Emission Gas

No.	Criteria	Item		
4	Water Pollution	(a) Amount of wastewater discharge		
		(b) With toxic or Without toxic		
5	Soil Contamination	(a) Possibility of infiltration or leaking of toxic substances		
6	Noise and Vibration	(a) Facing to residential area or Monastery area with heavy		
		machinery operation or without heavy machinery operation		
		(b) Not facing to residential area or Monastery area with heavy		
		machinery operation or without heavy machinery operation		
7	Odor	(a) Facing residential area and using odor substances		
		(b) Not facing residential and monastery area but using odor		
		substance		
8	Hazardous and Chemical Substance	(a) Amount of hazardous and chemical usage		
9	Occupational Health & Safety	(a) Including dangerous works		
		(b) Using VOC		
		(c) Using toxic substances		
10	Other environmental element founded by	(a) Based on International Guidelines		
	Expert	(b) Practical experiences		

Source: Thilawa SEZ Management Committee

As of the end of April 2016, TSMC approved 34 ECPPs, 1 EIA, and 1 IEE as shown in Table 2.7-2.

Table 2.7-2 List of Approved ECPP, EIA, and IEE in Thilawa SEZ (As of the end of April 2016)

Approve Approval Number Date		Sector	Main Business Activities	EIA/ IEE Requirement	Current Status
1	2014/11/25	Automobile	Manufacturing Radiator	None	Operation
2	2014/11/26	Textile	Sewing shirts	None	Before Operation
3	2014/12/23	Waste management	Industrial Waste Management	EIA (Approved)	Operation
4	2015/1/14	Textile	Knitting glove	None	Before Operation
5	2015/1/29	Administration	Industrial park center	None	Open
6	2015/1/30	Acoustic instrument	Manufacturing speaker, headphone	None	Operation
7	2015/2/23	Bottle manufacturing	Pet bottle manufacturing	None	Operation
8	2015/2/25	Textile	Sewing stuffed toys	None	Operation
9	2015/3/20	Bottle manufacturing	Aluminum can manufacturing	None	Before Operation
10	2015/3/30	Metal-processing	Manufacturing steel pipes	None	Before Operation
11	2015/4/9	Logistic	Logistic	None	Operation
12	2015/4/29	Textile	Sewing underwear	None	Before Operation
13	2015/5/19	Human resource services	Vocational training	None	Before Operation
14	2015/6/12	Food	Instant noodles making	IEE (Approved)	Before Operation
15	2015/7/3	Cement	Manufacturing Portland cement	EIA	Before Operation
16	2015/7/13	Metal-processing	Manufacturing steel structure frame	None	Before Operation
17	2015/9/4	Metal-processing	Coil Center	None	Before Operation
18	2015/9/12	Logistic	Logistic	None	Before Operation
19	2015/10/9	Textile	Sewing underwear	None	Before Operation
20	2015/10/16	General manufacturing	Design and manufacturing machines	None	Before Operation
21	2015/10/23	Paper	Manufacturing Corrugated boxes	None	Before Operation
22	2015/10/23	Metal-processing	Manufacturing pressure vessels, columns, drums	None	Before Operation
23	2015/10/23	Textile	Sewing underwear, knitwear	None	Before Operation

Approve Approval Number Date		Sector	Main Business Activities	EIA/ IEE Requirement	Current Status
24	2015/10/23	Pharmaceutical industry	Manufacturing medicines	IEE	Before Operation
25	2015/11/16	Automobile	Manufacturing automotive parts	None	Before Operation
26	2015/12/17	General manufacturing	Manufacturing tripods for cameras	None	Before Operation
27	2015/12/17	Paint	Manufacturing paints	IEE	Before Operation
28	2015/12/29	Rental factory	Rental factory	None	Before Operation
29	2016/1/5	Nursing care instrument	Manufacturing wheel chair	None	Before Operation
30	2016/1/25	Agricultural machinery	Importing, assembling agricultural machinery	None	Before Operation
31	2016/2/2	Construction	Manufacturing cement brick	None	Before Operation
32	2016/2/26	Cement	Re-packing cement	None	Before Operation
33	2016/2/26	General manufacturing	Manufacturing polyurethane foam	IEE	Before Operation
34	2016/2/26	Fertilizer	Importing, blending, re-packing fertilizer	None	Before Operation
35	2016/3/7	Manufacturing	Steel structure fabrication	None	Before Operation
36	2016/3/15	Manufacturing	Edible oil packaging	None	Before Operation
37	2016/3/15	Services/ Real Estate Development	Shop house	None	Before Operation
38	2016/3/28	Services/Real Estate Development	Worker accommodation	None	Before Operation
39	2016/4/4	Manufacturing	Manufacturing of aluminum products (doors, window frame)	None	Before Operation
40	2016/4/28	Services/ Trading	Maintenance, services and trading of agriculture machines	None	Before Operation

Source: Thilawa SEZ Management Committee

2) Construction Stage

During construction stage, construction contractor shall implement environmental mitigation measures and submission of monitoring report in accordance with the submitted ECPP and receives two or three times inspections; inspection(s) at construction stage (after 4 months from the start of construction and incase of the after 12 months) and inspection at before commencement of commercial operation.

3) Regular Operation Stages

During regular operation stage, investors shall implement environmental mitigation measures and submission of monitoring report biannually in accordance with the submitted ECPP and shall receive the first inspection after 4-6 months from the start of commercial operation and additional inspection after the first inspection as necessary.

2.7.2 Social Consideration Framework of Thilawa SEZ

(1) Social Consideration Policy of TSMC

TSMC issued a notice to ensure the responsible investment in the Thilawa SEZ in August 2015 (TSEZMC Notice to Ensuring the Responsible Investment in the Thilawa SEZ No.4/2015) for all companies, Myanmar and foreign, who are investing and doing business in the Thilawa Special Economic Zone, including subcontractors of investor companies. This guidance on responsible business conduct is intended to be supplemented by more specific guidance from the SEZ

Management Committee on issues such as health, safety and environment, security, labor law, human resources and recruitment, social and community relations, and reporting/transparency. This guidance will highlight relevant Myanmar laws which all businesses in the SEZ must comply with, as well as relevant international standards to which they are encouraged to adhere, such as those of the IFC and the International Labor Organization (ILO).

TSMC notifies businesses investing and doing business in the SEZ, to ensure the eight responsibilities as shown in Table 2.7-3

Table 2.7-3 Eight Responsible Investment in Thilawa SEZ stipulated in TSEZMC Notice No.4/2015

Items of Responsible Investment	Description
1. Respect human rights	Companies should ensure that their operations, conduct, and activities respect the human rights of workers, the communities where they operate, their consumers, and Myanmar society as a whole.
2. Engage with stakeholders	Companies should consult with all those affected by their activities, operations, and impacts, be they workers, consumers, or communities, as well as other stakeholders, so that companies have access to accurate and useful information about their actions and can create a two-way dialogue.
3. Support the rights of workers	Companies should familiarize themselves with, and fully respect, all Myanmar labor laws, including those which provide for independent trade unions, collective bargaining and workplace coordination committees. Companies can play an important role in ensuring equal opportunity for employment by addressing discrimination in hiring and in working conditions.
4. Build human capital	The SEZ Management Committee encourages companies to offer training programs to workers, and those entering the workforce, to improve their skills and to prepare them for supervisory, administrative, managerial or technical roles.
5. Ensure effective grievance mechanisms	Those affected adversely by a company's activities need access to effective remedies. This includes establishing grievance mechanism(s) that are accessible (including in the local language) to individuals, workers, consumers, and communities and the company's participation in and cooperation with the grievance mechanism. Companies can refer to Guiding Principles 29 and 31 of the UN Guiding Principles for Business and Human Rights for further information. Grievance mechanism should be legitimate, accessible, predictable, equitable, transparent, rights-compatible, and a source of continuous learning. They should be designed in collaboration with potential users of the grievance mechanism.
6. Be transparent	The SEZ Management Committee supports companies' initiatives to ensure that their conduct is as open and transparent as possible (subject to the need for commercial confidentiality). It also encourages companies to communicate with stakeholders about actions that affect them or about which they have raised concerns. It is important for companies to report publicly on the steps they have taken to ensure that their conduct respects and supports human rights in Myanmar.
7. Create shared value	The SEZ Management Committee believes that creating shared value can address social needs in a way that is commercially viable for businesses. Creating shared value for communities, workers and consumers is not corporate philanthropy, but a way in which to achieve economic success and win-win situations for businesses and society, including the poor.
8. Support the communities in which they operate	Companies are encouraged to undertake or participate in activities beneficial to the communities in which they operate and Myanmar society as a whole, both through creating shared value and through philanthropic initiatives. In doing so companies should consult the intended beneficiaries about their needs, be transparent about what they are able to provide, be clear about how long the service will be provided or the project developed, and deliver what they have promised. If the company is not able to fulfill its promise, it should inform the community early and explain the reasons why. Companies can also include credible local organizations, including civil society groups, in designing, operating, and monitoring the progress of such projects and establish effective mechanisms to receive and act on feedback.


Source: Thilawa SEZ Management Committee

2.7.3 Environmental Management by the Project Proponent

(1) Overall Structure during the Pre-construction and Construction Phases

The organization structure during the pre-construction and construction phases for the Project is proposed as shown in. Figure 2.7-3. The project proponent (MJTD) will outsource a contractor to

implement the detailed design and construction during the pre-construction and construction phases. The outsourced contractor will establish a project office (Zone B Project Office) to undertake the implementation of the detailed design and construction works together with the environmental mitigation and management plan and the environmental monitoring, while the project proponent will supervise their works. Institutional arrangement in the closing phase will be also same structure as pre-construction and construction phases.



Source: EIA Study Team

Figure 2.7-3 Proposed Organizational Structure for Environmental Management of the Project during the Pre-construction and Construction Phases

The project office of the outsourced contractor will be responsible in dealing with environmental and social issues arising during related phases. Major tasks of the project office relevant to environmental management are listed as follows:

- 1) Implementation of the EMP
- 2) Monitoring of the construction work according to environmental monitoring plan (EMoP);
- 3) Provision of the technical support of the project proponent (MJTD) in coordination with relevant government organizations regarding environmental and social issues;
- 4) Resolution of the environmental and social issues arising during the construction and closing phases of the Project; and
- 5) Submission of environmental monitoring reports to the project proponent (MJTD).

On the other hand, major task of the project proponent relevant to environmental management are listed as follows:


- 1) Guidance and supervision of implementation of the EMP and environmental monitoring
- 2) Review of the environmental monitoring reports submitted by the contractor
- 3) Preparation and submission of the environmental monitoring reports based on contractor's environmental monitoring reports to TSMC

(2) Overall Structure during the Operation Phase

The organizational structure during the operation phase is proposed as shown in Figure 2.7-4. Each tenant will implement EMP and EMoP for each business and submit the environmental monitoring report to OSSC of TSMC and the project proponent (MJTD) based on its IEE/EIA. The project proponent (MJTD) will submit the monitoring report based on the results of implementation of EMP and EMoP for the Thilawa SEZ Zone B industrial area development.

The project proponent (MJTD) will be in charge of the overall operation of the Thilawa SEZ Zone B industrial area. Firstly, the project proponent will formulate the internal regulations for the industrial

area of Zone B, like the Internal Regulations for Zone A formulated in January 2015 that stipulates several obligations such as effluent standards of wastewater and air, noise standard, and regulation of protective controls to the tenants.



Source: EIA Study Team

Figure 2.7-4 Proposed Organizational Structure for Environmental Management of the Project during the Operation Phase

(3) Activities on Community Support Programs by the Project Proponent

The project proponent has been implementing community support programs as one of the Corporate Social Responsibility (CSR) activities under the following objectives;

- To establish harmonious relationship with the host communities and help to improve the living conditions of families within the communities.
- To balance the social, environmental and economic impacts of the economic zone by playing an active and positive role as neighbor by contributing to human development by emphasizing education and the strengthening of local skills and capacities.

In order to secure sustainable implementation of sustainable community support progreams, MJTD has established a community fund by collecting community relation fees from the tenants of the Ind im su an im

as established a community range of continuity relation recommends or the
ndustrial Zone. Each tenant pays a certain amount monthly and all of the money are allocated to
mplementation of community support programs and other CSR programs. Target communities to be
upported are not only for Project Affected Household (PAH) but also for surrounding communities in
nd around Thilawa SEZ. Until now, the following community support programs have been
mplemented for student support and local community support as shown in Table 2.7-4.

Programs	Date	Number of Participants	Activities
Thilawa SEZ	12th July 2015	Around 350 student	About 350 students received school supplies
neighboring	1st June 2015	11 student	Scholarship for 11 outstanding students for 6 academic year
students	13th October 2015	-	Supported excursion trip to the students
Support	1st June 2015	Around 600 student	Job Seminar and knowledge sharing program at Thanlyin
Program			Technological University to be persued as an Engineering career
	23th November 2015	Around 400 student	Health education and nutrition program at Myaing Tharyar
			school
	25th May 2015	Around 400 student	School stationeries donation to the students
Local	12th July 2015	-	Donated an assembly hall at Moe Kyo Swan Monastery

Table 2.7-4 Current Corporate Social Responsibility Activities by MJTD

Programs	Date	Number of Participants	Activities
Community	(Hand over date)		compound located near Thilawa SEZ
Support Program	During 2015	-	Multi-stakeholders meetings for transparency and dialogue with authorities, local community, investors and stakeholders
	During 2015	-	Support vocational training programs for the development of local communities which is about security, basic knowledge of calculations and health and safety of personnel
	During 2015	-	Assistance to the water flood victims
	During 2015	-	Arrange excursion for the local communities to visit around THILAWA SEZ to share the updated situations of the THILAWA SEZ project
	March. 2016	9 persons	Assistance to the handicapped persons who are from TSEZ surrounding area
	During 2015	-	Contribute and support infrastructure improvements to the host community
	March to June 2015	50 students	Organizer of free English Language class for the local community
	6th April 2016	65 persons	Novitiation ceremony for 65 novices
	4th May2016	-	Rubbish collection for Alwan Sut Village

Source: MJTD

In addition to the current community support programs, the project proponent (MJTD) is planning to implement new community support programs for contribution to improvement of life of communities continuously within budget of the community fund as follows;

- Improvement of public health in the communities
- Improvement of community infrastructure
- Improvement of community safety

The planned community support programs will be prioritized taking into consideration of needs and request from the communities.

2.8 JICA Guidelines for Environmental and Social Considerations

As described in Chapter 3, the Project is expected to be funded by the Japan International Cooperation Agency (JICA). Therefore, the Project is required to comply with the JICA Guidelines for Environmental and Social Considerations (April 2010) (hereinafter referred to as "the JICA Guidelines").

The objectives of the JICA Guidelines are to encourage project proponents to have appropriate consideration for environmental and social impacts, as well as to ensure appropriate information disclosure to the public. According to the JICA Guidelines, the "Environmental and Social Considerations Studies" means studies including socio-economic and natural environment baseline surveys, predicting and evaluating adverse impacts and likely impacts that projects are to cause on the environment and local society, and mitigation measures to avoid and minimize these impacts.

Since the Project is classified as Category A, which is likely to have significant adverse impacts on the environment and society, information disclosure and consultation with stakeholders are mandatory to be held in the course of the EIA study of the Project.

Comparison between the JICA Guidelines and the relevant regulations in Myanmar is presented in Annex 2-1. As for EIA, there is no critical gap between the EIA Procedure in Myanmar and the JICA Guidelines. Since the JICA Guidelines require that the documents used in the public consultation meetings are written in the official language or in a language widely used in the country, Myanmar language was used for the documents provided at the public consultation meetings in the Project.

On the other hand, since there is no comprehensive law stipulating land acquisition and resettlement regulations, most of the mandates in the JICA Guidelines, such as sufficient compensation and support for project-affected peoples (PAPs), preparation of resettlement action plan, consultations with PAPs, and appropriate and accessible grievance mechanisms, have not been regulated in Myanmar. Therefore, in the Project, the resettlement works have been conducted by considering the measures to fill the gaps between the JICA Guidelines and the relevant regulations in Myanmar as shown in Annex 2-1. For example, assistance in improving or restoring livelihood to at least the pre-project level has been planned and provided. In addition, the Resettlement Work Plan (RWP) has been prepared in consultation with PAPs and disclosed to the public.

CHAPTER 3: PROJECT DESCRIPTION

3.1 Project Outline

3.1.1 Background

The Myanmar government has placed high priority on foreign direct investment as a key factor for the development of the nation. In particular, the government expects the Thilawa Special Economic Zone (SEZ), located in the outskirts of Yangon, to play an important role in economic development. Under this circumstance, The Myanmar Government and the Japanese Government signed the Memorandum on the Cooperation (MOC) for the development of Thilawa SEZ in December 2012.

In January 2014, the Myanmar Japan Thilawa Development Limited (MJTD) was established as a joint venture among MMS Thilawa Development Company (MMST), Thilawa SEZ Management Committee (TSMC), and Myanmar Thilawa SEZ Holdings Public Limited (MTSH) to do business as operator and developer of the Thilawa SEZ Zone A, which is an early development area that covers 396 ha of the Thilawa SEZ¹.

The construction of Zone A started in January 2014 after the completion of the feasibility study (F/S) and approval of the environmental impact assessment (EIA) report by TSMC. Its operation started in August 2015. In addition, MJTD has started to plan the development of another 700 ha in Thilawa SEZ together with MTSH as "Zone B", which includes about 262 ha of industrial area, 267 ha of logistic area, and 169 ha of residential and commercial areas.


In response to this, the EIA study has been started in parallel to evaluate the environmental and social impacts caused by the development of Zone B, and consider the mitigation measures and environmental management plan. Since these three areas have different project proponents, the EIA process is going to be done separately by each project proponent. This scoping report is targeted for the industrial area development project (approximately 262 ha) (hereinafter referred to as "the Project") whose project proponent is MJTD².

3.1.2 Location of Thilawa SEZ

The Thilawa SEZ is located in Southern District, Yangon Region and about 23 km southeast of Yangon City as shown in Figure 3.1-1.

Note: Japan International Cooperation Agency (JICA) participated in this joint venture later.

² Other development areas of Zone B, namely, logistic area and residence and commercial area, will be developed, operated, and managed by the Thilawa Property Development Ltd. (TPD) that was established jointly by MTSH and TSMC.



Source: Thilawa Special Economic Zone Development Project (Class A) Environmental Impact Assessment Report (September 2013)

Figure 3.1-1 Location of Thilawa SEZ

3.2 Land Use Plan of Zone B


Land use plan of Zone B is shown in Figure 3.2-1. Zone B will be developed by dividing the three areas, namely: industrial area, logistic-dependent industrial area, and residence and commercial areas. The Project Proponent of each area is shown in Table 3.2-1.

Table 3.2-1 Land Use Plan of Zone B

Land Use	Area (ha)	Project Proponent
Industrial Area	Approx. 262	MJTD
Logistic Area	Approx. 267	TPD
Residence & Commercial Area	Approx. 169	TPD
Total	Approx. 700	

Note: Above figures may change in the later stage.

Source: EIA Study Team prepared on the basis of the information from the project proponent



Source: EIA Study Team prepared on the basis of the information from the project proponent

Figure 3.2-1 Land Use Plan of Zone B

3.3 Selection of Alternative

3.3.1 Policy of Alternative Study

In order to consider the project area and the shape of the industrial area of Zone B, two alternatives were compared comprehensively from the viewpoint of technical aspect, economical aspect, safety, and social and environmental consideration. The alternatives were set under the following conditions:

- (a) Project site should be inside of the Thilawa SEZ excluding Zone A (2,000 ha in total).
- (b) SEZ excluded area that belongs to the ministries other than MOC should not be included.
- (c) Public area (public road and canal) should not be included.
- (d) Existing houses and paddy field should be eliminated as much as possible.
- (e) Shape of the development area should be simple as much as possible like a rectangle for easy development.

Taking into account the above conditions, the two alternatives shown in Table 3.3-1 were chosen considering the efficiency of the industrial area in Thilawa SEZ. Therefore, the location of the industrial area of Zone B in the two alternatives was selected to be adjacent to the Zone A area.

As a result of the alternative study shown in Table 3.3-1, Alternative A was selected as the priority option because it has advantages from the viewpoint of technical aspect, economical aspect, safety, and environmental/social consideration as follows:

- Technical aspect: higher ground elevation
- Economic aspect: less construction cost
- Safety: less traffic volume during construction
- Environment/social consideration: less scale disruption of nature and less number of project-affected households (PAHs)

Alternative A Project site is adjacent to the SEZ outer road in the east.
Development area is about 270 ha.
There is no creek in the Alternative A area.

Project site is adjacent to the SEZ outer road in the north and west, and links to the Zone A area.
Development area is abWout 200 ha.
Existing creek is located in the Alternative B area.

Table 3.3-1 Result of Alternative Study

Project Plan	Trians BEZ Zoon A Logend Logend Logend Trians BEZ Zoon A Rose Bridgers Alen Control of the control of t

Alternative	Alternative A	Alternative B	
Technical Aspect	 Since ground elevation is higher than in Alternative B on the average, land reclamation work is simpler than in Alternative B. 	 Ground elevation is not high on average in this area and earth filling work is necessary to satisfy the elevation level of +5.0 m. The area includes a small creek running into the Yangon River. Therefore, it is needed to adjust the creek and install a drainage system in order to run the water from the development area into the creek. 	
Economic Aspect	 Since earthwork volume is smaller than in Alternative B, construction cost is estimated to be less and construction period is estimated to be shorter than in Alternative B. Since the number of PAHs will be less than in Alternative B as stated in the environmental/social consideration below, the compensation for resettlement will be reduced. 	 Since earthwork volume is larger than in Alternative A, construction cost is estimated to be higher and construction period is estimated to be longer than in Alternative A. Since the number of PAHs will be more than in Alternative A as stated in the environment/social consideration below, the compensation for resettlement will be increased. 	
Safety	 As transportation of soil for land reclamation is basically done inside the project site, the risk of traffic accident occurring outside of the project site is not increased. 	 Since it is necessary to transport the soil for land reclamation from outside of the project site, the risk of traffic accident is increased. Possibility of flood risk might be increased in the upper course of the creek due to heavy rain and/or inappropriate maintenance of drainage system. 	
Environment /Social Consideration	 Since the traffic volumes resulting from the earthwork transportation during the construction phase are estimated to be smaller than in Alternative B, exhaust gas from the vehicular traffic will be less than in Alternative B. According to the project description, the modification in the creek is not expected. Therefore, the negative impact on natural environment is forecasted as less than Alternative B. Around 100- 150 households might be resettled in the Alternative A area, which is about 150-200 less than in Alternative B. Therefore, the social impact will be lesser than that of Alternative B. 	 Since the traffic volumes resulting from the earthwork transportation during the construction phase are estimated to be larger than in Alternative A, exhaust gas from the vehicle traffic will be more than in Alternative A. According to the project description, the modification in the creek is expected. Therefore, the negative impact on natural environment, Flora/Fauna and Ecosystem is expected. Around 300 households might be resettled in Alternative B area, which is about 150-200 more than in Alternative A. Therefore, the social impact will be greater than that of Alternative A. 	
Evaluation	• Compared with Alternative B, Alternative A has advantages from the viewpoint of technical aspect, economical aspect, safety aspect, and environmental/social consideration. Therefore, Alternative A is chosen as the preferred option.		

Source: EIA Study Team prepared on the basis of the information from the project proponent

3.3.2 Zero Option

• In Thilawa SEZ, development of Zone A (approximately 400 ha) and infrastructure development around the Thilawa SEZ are ongoing. Therefore, "zero option" scenario in this report should be based on the current condition, i.e., with the development of Zone A and infrastructure, but without the development of Zone B. The study of the zero option is shown in Table 3.3-2 below. As a result of this study, it is judged that the implementation of the Project should be undertaken because of some advantages in terms of effective urban development and economic development of the country and region including infrastructure development around Thilawa SEZ. In addition,

anticipated negative impacts could be avoided or minimized by taking the appropriate countermeasures.

Table 3.3-2 Study of Zero Option

Aspect	Condition Without the Project	Condition With the Project
Technical Aspect	 Random development might be implemented without any plan for overall area development. Then, the future development plan might be restricted after disorderly development. 	Zone B would be developed efficiently in accordance with the planned area development plan.
Economical Aspect	 Job opportunity would not increase from the current situation. Economic development of the entire Thilawa SEZ would be limited. 	 A series of infrastructure development project (water supply, port, and power supply) has been ongoing around the Thilawa SEZ for Zone A development. Cost-effectiveness of these projects would be increased if Zone B would also be developed. Job opportunities would increase for local residents.
Environment/ Social Consideration	 Involuntary resettlement might not occur. Impact on natural and social environment that might be caused by the development of Zone B will not occur. Issues of environmental and social consideration might be more complicated and segmented in case random developments are conducted in and around Zone B. 	 Impact on natural environment and pollution caused by the construction work and operation of Zone B, and impact on social aspect such as involuntary resettlement would occur. Planned area development would effectively and comprehensively address environmental and social consideration issues. Living environment for local residents would be improved due to the development of the surrounding infrastructure.

Source: EIA Study Team prepared on the basis of the information from the project proponent

3.4 Land Reclamation Plan

To set the design elevation of land, the following three simulation results/ conditions were taken into consideration for prevention of flood.

Case 1) Storm surge simulation in Yangon River (In the case of a simulation result of assumed strongest cyclone in the future taking into consideration of climate change): E.L: 5.2 m

Case 2) Flood analysis (100 years return rainfall): E.L: 4.9 m. and

Ccse 3) The highest water level at Myanmar International Thilawa Terminal (MITT) in the past: E.L: 4.24 m

On the bases of the above information, the Project proponent sets E.L 5.5m as the target elevation of land of Industrial Area by adding to 0.3 m as allowance height for safety from the Case 1.

The land elevation of whole the project site is set from E.L.5.5 m to E.L. 7.0 m in accordance existing elevation to reduce construction soil to be excavated.

Table 3.4-1 Concept of Land Reclamation in the Industrial Area

	Industrial Area
Elevation	EL +5.5-7.0 m

Source: EIA Study Team prepared on the basis of the information from the project proponent

3.5 Road System

3.5.1 Road Plan

Figure 3.5-1 shows the road plan of the industrial area (Zone B). Main road is planned in order to connect the main gate to the main points in the industrial area. Sub-road is planned as access road for small-scale plots and mid-scale plots from the main road.




Figure 3.5-1 Road Plan in the Industrial Area (Zone B)


3.5.2 Road Section


Typical sections of the main roads and sub-roads are shown in Figure 3.5-2 and Figure 3.5-3, respectively. Main roads have retention canal in the center in order to control rainwater and buffer zone at both sides. Large or mid-size lots are located along the main road. Sub-roads have buffer zone at both sides. Small or mid-size lots are located along the sub-road. Table 3.5-1 shows the description of main roads and sub-roads.


Table 3.5-1 Description of Road

Item	Main Road	Sub-road
Right of Way (ROW)	56 m	26 m
Lanes/width of pavement	4 lanes/16 m	2 lanes/10 m

Source: Feasibility Study for the Thilawa SEZ Zone B Development (General Study)









Source: Feasibility Study for the Thilawa SEZ Zone B Development (General Study)

Figure 3.5-2 Typical Section of Main Road



TYPICAL CROSS SECTION OF TEMPORARY ACCESS ROAD




Source: Feasibility Study for the Thilawa SEZ Zone B Development (General Study)

Figure 3.5-3 Typical Section of Sub-road

3.6 Drainage Plan

Drainage plan in the industrial area (Zone B) is shown in Figure 3.6-1. Drainage water from the industrial area will run through the drainage ditch and retention pond and will be discharged to Shwe

Pyauk Creek that connects to the Yangon River. Section of drainage ditch is shown in Figure 3.5-2 and Figure 3.5-3.



Source: EIA Study Team prepared on the basis of the information from the project proponent

Figure 3.6-1 Drainage Plan in the Industrial Area (Zone B)

Discharged water volume outside of the industrial area is controlled at the retention pond. Table 3.6-1 and Table 3.6-2 show the design criteria for drainage ditch and retention ponds, respectively.

Drainage Ditch (Capacity: Approximately 70,000 m³)

Retention Pond (Capacity: Approximately 70,000 m³)

Table 3.6-1 Design Criteria for Drainage Ditch

	Item	Description	
1.	Design stormwater flow (DSWF)	$Q = C \cdot q \cdot A$ (Rational formula)	
		Where, Q: Design stormwater flow (m ³ /sec)	
		C: Runoff coefficient	
		q: Rainfall intensity (mm/sec/ha)	
		A: Drainage area (ha)	
2.	Rainfall intensity	: Intensity formula	
3.	Return period	: 5 years for stormwater collection culvert	
4.	Overall runoff coefficient	: 0.30 before development, 0.85 after development	
		$Q = A \cdot V$, $V = (1/n) \cdot R^{2/3} \cdot I^{1/2}$: Manning's formula	
-	5 Uvdmaylia design of sever	Where, Q: Stormwater discharge (m ³ /sec)	
٥.	Hydraulic design of sewer	A: Sectional area of pipe (m ²)	
		V: Mean velocity (m/sec)	

Item	Description
	n : Roughness coefficient
	R: Hydraulic radius (m)
	I : Hydraulic gradient
6. Type of stormwater collection sewers	: Pipes, box culverts, ditches and open channels
7. Allowable flow velocity	: 0.8 - 3.0 m/sec
8. Minimum size of pipe	: 300 mm
9. Allowance of sewer capacity	: 10%-20% of design stormwater flow
10. Minimum earth covering	: 1.0 m
11. Maximum manhole interval	: 50 m for less than D300 mm of inlet pipe
12. Sewer connection method	: Sewer bottom connection or water surface connection
13. Material of inlet pipe	: Hume concrete pipe
14. Material of ditch and box culvert	: Reinforced concrete
15. Material of open channel	: Earth canal with sodding
16. Roughness coefficient	: 0.013
17. Hydraulic gradient	: 2.0% for less than D500 mm, 1.0% for box culvert, ditch, and open channel

 $Source: Feasibility\ Study\ for\ the\ Thilawa\ SEZ\ Zone\ B\ Development\ (General\ Study)$

Table 3.6-2 Design Criteria for Retention Ponds


Item	Description				
1. Design return period	: 10 years				
2. Type of pond	: Digging type with gate and spillway				
	$: Q = [Q_{10} - Q_a/2] \cdot T \cdot 60$				
	Where, Q: Design capacity of retention pond (m3)				
3. Capacity of retention pond	Q10: Design stormwater flow (m ³ /sec)				
	Qa: Allowable discharge flow (m ³ /sec)				
	T: Concentration time (minute)				
4. Volume of sedimentation	: 1.5 m ³ /ha/year and 10 years period				
	$: Q_0 = \mathbf{C} \cdot \mathbf{B} \cdot \mathbf{d} \cdot [2 \cdot \mathbf{g} \cdot \mathbf{H}_1]^{0.5}$				
	Where, Q ₀ : Discharge flow (m ³ /sec)				
	C: Coefficient of correlation between H ₁ /d and H ₂ /d				
5 December of the Control of the Con	B: Width of gate (m)				
5. Regulating gate	d : Opening height of gate (m)				
	g: Gravitational constant (9.8 m/sec ²)				
	H ₁ : Upstream water height (m)				
	H ₂ : Downstream water height (m)				
	$: Q_c = C \cdot L \cdot h^{0.5}$				
	Where, Q _c : Overflow (m ³ /sec)				
6. Spillway	C Overflow coefficient				
	L: Width of trough (m)				
	h: Water height of trough (m)				

Source: Feasibility Study for the Thilawa SEZ Zone B Development (General Study)

3.7 Water Supply System

3.7.1 Water Sources

The location maps of water sources for Thilawa SEZ are shown in Figure 3.7-1 and Figure 3.7-2. Water sources will be the Zamani Reservoir and Lagunbyin Reservoir for development of Thilawa SEZ.



 $Source: Preparatory\ Study\ on\ Thilawa\ SEZ\ Infrastructure\ Development\ in\ the\ Republic\ of\ the\ Union\ of\ Myanmar\ \ (2014)$

Figure 3.7-1 Location of Water Source for Thilawa SEZ



Source: Prepared by the EIA Study Team based on the map from Myanmar Information Management Unit

Figure 3.7-2 Location of Water Source for Thilawa SEZ

3.7.2 Water Supply Distribution System

Water supply system in the industrial area (Zone B) is shown in Figure 3.7-3. Design concept for the water supply distribution system from water purification plant to tenants is shown in Table 3.7-1.

Table 3.7-1 Summary of Design Concept

Item	Description
Unit volume of water supply (Daily maximum water flow)	$: 80 \text{ m}^3/\text{ha/day}$
Water connection point	: Minimum distance 100 m
Water pressure	: 15 m for normal condition and 10 m for firefighting
Flow velocity	: Design standard from 0.5 m/sec to 1.5 m/sec
Interval of hydrant	: 300 m
Internal distribution system	: Distribution network (Reticulated pipeline)

Source: Feasibility Study for Thilawa SEZ Zone B Development (General Study)

Water from Zarmani Reservoir is planned to be transmitted to the water purification plant (WPP) (Q=6,000 m³/day) established in Zone A through a pipe by pumping. The treated water from WPP is distributed to each tenant. Meanwhile, an ongoing Japanese ODA loan project3 which will install the public water supply pipe from Lagunbyin Reservoir to Thilawa SEZ will make it possible to supply 42,000 m³/day of water to Thilawa SEZ by around 2019.

Considering the progress of the above project, the water supply plan in Zone B industrial area is prepared in stages as shown in Table 3.7-2.

Table 3.7-2 Water Supply Plan in the Industrial Area

Timing	Water Supply Plan		
Before around 2019	Distribute water to each tenant from water purification plant (WPP) in		
(Before the water supply pipe has been installed)	Zone A by pumping from Zamami Reservoir		
After around 2019	Distribute water to each tenant from water purification plant (WPP) i		
(After the water supply pipe has been installed)	Zone A by pumping from Zamami Reservoir		
	Connect to the public water supply pipe from Lagunbyin Reservoir		
	and distribute water to each tenant		

Source: EIA Study Team prepared on the basis of the information from the project proponent



Source: EIA Study Team prepared on the basis of the information from the project proponent

Figure 3.7-3 Water Supply Plan in the Industrial Area (Zone B)

-

³ Yangon Urban Water and Sewage Improvement Project

3.8 Sewage System

3.8.1 Sewage System

Sewage system in the industrial area (Zone B) is shown in Figure 3.8-1.

In the initial stage of Zone B development (Stage-1 sewage system in Zone B industrial area), since the total amount of wastewater generated from tenants in Zone B is estimated to be few, wastewater will be transferred to the sewage treatment plant (STP) in Zone A and then will be treated.

In the Stage-2 of sewage treatment system, STP in Zone A area will be extended the capacity. The land for extension of STP has been secured in sewage treatment plant in Zone A industrial area.

In the final stage, wastewater generated in Zone B will be treated in STP in Zone B. In beginning of year, project proponent collects the water demand from each tenants and estimates amount of wastewater of next year. If the predicted amount of wastewater exceeds capacity of the existing STP, the existing STP will be extended by next years. Therefore, the amount of waste water is not to exceed the capacity of the STP.



Figure 3.8-1 General Plan of Sewage System in the Industrial Area (Zone B)

The design criteria for sewage system are shown in Table 3.8-1.

 Table 3.8-1
 Design Criteria of Sewage System

Item	Description
1. Wastewater yield ratio to water supply	: 80% of water demand
2.Collection system	: Separate system with monitoring pit and sewer
3. Wastewater treatment method	: Standard Activated Sludge Method (Treated level: BOD 20 mg/L)
4.Capacity of sewage treatment plant	: Stage-1 (Current status of STP in Zone A industrial aera): 4.800 m ³ /day Stage-2 (Extended STP in Zone A industrial aera): 20,000 m3/day Stage-3 (Extended STP in Zone A industrial aera and newly established STP): 35,000 m3/day *The expected sewage amount from Zone A industrial area in 2018 are maximum 4,600 m3/day.
5.Hydrological calculation	: Manning's formula
6.Roughness coefficient of pipe	: 0.013
7.Allowable flow velocity	: 0.6 ~ 3.0 m/sec
8.Hydraulic gradient	: Considered same as the gradient of sewer pipe (in full capacity condition)
9. Allowance of sewer capacity	: 100% of design HMWF
10.Interval of manholes	: 50 m to 100 m
11.Relay pumping stations	: Submersible pumps and manhole type pit located at the sidewalks or in green areas
12.Receiving water bodies	: Yangon River via stream

Source: Feasibility Study for Thilawa SEZ Zone B Development (General Study)

3.8.2 Wastewater Treatment Plant

(1) Design Wastewater Quality

The design wastewater quality is estimated by the experience of previous project. The pollutant load in Zone B is shown in Table 3.8-2. Items of influent wastewater quality and treated wastewater quality are summarized from Table 2.4-5 and Table 2.4-6 respectively. Regarding design of influent wastewater quality, if any target value of parameter stipulated in the Table 2.4-5 has discrepancy with the laws and regulation in Republic of the Union of Myanmar, the laws and regulations, the standard of which is stricter, shall prevail.

Table 3.8-2 Summary of Design Wastewater Quality

Item	Description	Target Value
1. Influent Wastewater Quality	a) BOD (mg/L)	200-500*
	b) SS (mg/L)	200
2. Treated Wastewater Quality	a) BOD (mg/L)	20
	b) SS (mg/L)	30

Note*: This target value could be relaxed.


Source: Feasibility Study for Thilawa SEZ Zone B Development (General Study)

(2) Wastewater Treatment Method

The sewage treatment process in Zone B industrial area is shown in Figure 3.8-2. All of the industrial and domestic wastewater will be treated at the central STP in Zone B industrial area. Before the central STP, each tenant shall install its own Pre Treatment System (PTS) if the wastewater quality does not meet the influent wastewater quality.

Considering the characteristics of wastewater volume and quality, a conventional activated sludge process is adapted for wastewater treatment in Zone B. With regard to the sludge treatment process, a gravity thickener and mechanical dewatering process are recommended. An outline of the treatment process is shown in Figure 3.8-3.


Depending on the composition of the waste water, there is also a plan to extend the functionality of the future wastewater treatment plant. The process of coagulating sedimentation would be installed in the existing waste water treatment plant.



- *1: Target value of effluent water quality after wastewater pre-treatment by tenant (Table 2.4-5) is adapted in this point.
- *2: Target value of effluent water quality after wastewater treatment at centralized treatment plant by Project Proponent (Table 2.4-8) is adapted in this point.
- *3: Target value of ambient water quality (Table 2.4-4) is adapted in this point.

Source: EIA Study Team prepared on the basis of the information from the project proponent

Figure 3.8-2 Wastewater Treatment Process in Zone B Industrial Area



 $Source: Feasibility\ Study\ for\ Thilawa\ SEZ\ Zone\ B\ Development\ (General\ Study)$

Figure 3.8-3 Diagram of Conventional Activated Sludge Process

3.9 Power Supply Plan

3.9.1 Power Demand in Zone B

Power demand in Zone B is forecasted considering the estimated necessary capacity of the facility (transformer) of a maximum 105 MVA (262 ha x 0.8 (ratio of plot) x 0.5 MVA/ha).


Table 3.9-1 Condition of Power Demand Forecast

No.	Item	Figures
1	Factor of Power Supply	0.2-0.5 /MVA/ha (* Industrial area)
2	Power Ratio	0.85
3	Amount of Power Supply (MW)	Electrical Demand (MVA) x Power Ratio

Source: Feasibility Study for Thilawa SEZ Zone B Development (General Study)

3.9.2 Power Supply Distribution System

Figure 3.9-1 shows the power supply system in Thilawa by around 2020.



Source: Prepared by EIA Study Team based on the Preparatory Study on Thilawa SEZ Infrastructure Development in the Republic of the Union of Myanmar (2014)

Figure 3.9-1 Power Supply System in Thilawa SEZ

3.9.3 33 kV Distribution Plan

The general plan of the 33 kV distribution system in Zone B is shown in Figure 3.9-2. The networks for 33 kV are designed by applying the ring loop system, which is an electric power supply network securing looping and double supply as precautions in the event of some accident. Each loop distribution line is connected to feeders of the different banks. Even if an accident happens somewhere on a distribution line or bank, power can be supplied from the other live distribution line. In Zone B, a maximum of four loops are assumed.





Figure 3.9-2 General Plan of 33 kV Distribution System in the Industrial Area (Zone B)

3.10 Solid Waste Management

Industrial waste generated from the industrial area will be re-used or recycled as much as possible by collecting the waste separately. This sorting out process is handled by each tenant and project proponent respectively. The waste which cannot be re-used or recycled may be managed by the waste treatment firm in Zone A or through public service such as by the Pollution Control and Cleansing Department of the Yangon City Development Committee (YCDC). In accordance with proposed internal regulations for Zone B industrial area, each tenant shall make sufficient provision for the safe and efficient disposal of all wastes, including, but not limited to, pollutants generated from its Plot. In addition, project proponent and each tenant must strictly comply with applicable laws, regulations, and notices. And at its sole responsibility and expense, shall treat, safety manage, eliminate or dispose of all dangerous or hazardous materials and waste including but not limited to industrial waste.

The expected process of solid waste management in Zone B industrial area is shown in Figure 3.10-1. Each tenant will generate industrial waste. These wastes will be sorted out into each category and will be treated. The project proponent will only generate business-related waste from the office located in Zone A. The incineration facility may be installed at the waste treatment firm in Zone A in the near future.

The current condition of solid waste management is described in section 4.3.7. In addition, the expected solid waste management process flow is described in section 7.4.




Source: EIA Study Team

Figure 3.10-1 Expected Process of Solid Waste Management in Zone B Industrial Area

3.11 Greening Plan

In order to create green space for the living conditions of flora and fauna, landscape, and employee's comfort, trees and sodding are arranged in the project area. Furthermore, each tenant will prepare green space inside its plot.

Figure 3.11-1 shows the greening plan in the project area. The planned green area covers about 20.2 ha, approximately 7.7% of the total area of the project area. Different kinds of trees are located on the sidewalk and retention canal along the main road. Bushes are located on the sidewalk along the sub-road. Surface of the sidewalk along the main road and sub-road will be covered by 8 m of sodding. Retention canal is located in the middle of the main road. Sodding is spread on the surface of the slopes along the project boundary fence. The greening plan for Zone B industrial area will follow the same plan of Zone A industrial area such as similar interval of planting and same proportion of sodding area. Figure 3.11-2 shows the state of green space of the Zone A industrial area. In the Zone A industrial area, greening area is planned to be covered about 21.7 ha, approximately 5% of the total area, that includes green space along main road, retention pond and sub road.



Note: The design of the greening plan may slightly be changed during the construction phase. Source: EIA Study Team prepared on the basis of the information from the project proponent

Figure 3.11-1 Greening Plan in the Industrial Area (Zone B)



Figure 3.11-2 State of Green Space of Zone A Industrial Area

3.12 Tentative Implementation Schedule

For the implementation of the project, the project area will be developed in several phases. The first phase is approx. 100 ha, and its implementation schedule is shown in Table 3.12-1.

Table 3.12-1 Implementation Schedule of First Phase

Item	2015		2016		2017			2018						
EIA Study			•											
Pre-construction Phase														T
Construction Phase														•
Operation Phase														ļ

Note: The above implementation schedule is as of May, 2016

Source: EIA Study Team

The implementation of the remaining phases is not yet scheduled as of June 2016.

CHAPTER 4: CURRENT ENVIRONMENTAL AND SOCIAL CONDITION

4.1 Living Environment


The overall conditions of air quality, water quality, soil quality, and noise levels are quoted from the Environmental Impact Assessment (EIA) Report for the Thilawa Special Economic Zone (SEZ) Class A Development Project by Myanmar and Japan Thilawa Development Ltd., which was approved by the Thilawa SEZ Management Committee (TSMC) based on the comments of the Ministry of Environmental Conservation and Forestry (predecessor of MONREC). The summary of the field survey for overall conditions is shown in Table 4.1-1. The location of the environmental survey for overall conditions is shown in Figure 4.1-1.

In addition, Yangon River water quality, which was measured in the Preparatory Survey for the Project for Expansion of Yangon Port in Thilawa Area, is shown in Table 4.1-6.

Table 4.1-1 Summary of Environmental Survey for Overall Conditions under the EIA Study of Class A

Category	Item	Description					
	A : O1:4	Parameter	1) Sulfur dioxide (SO ₂), 2) Carbon monoxide (CO), 3) Nitrogen dioxide (NO ₂), 4) PM10				
	Air Quality	Period	Two points in the dry and rainy seasons (two samples in total)				
		Location	Along the road				
Environmental Conditions (quoted from	Water Quality	Parameter	31 parameters for natural and living environment: 1) Temperature, 2) Odor, 3) Color, 4) Electrical conductivity (EC), 5) Hardness, 6) pH, 7) Turbidity, 8) SS, 9) DO, 10) COD _{Cr} , 11) TOC, 12) BOD ₅ , 13) Oil and Grease, 14) Total Coliforms, 15) NH ₄ -N, 16) NO ₂ -N,17) NO ₃ -N, 18) T-N, 19) T-P, 20) Cu, 21) Zn, 22) Cd, 23) Pb, 24) Hg, 25) Ni, 26) Mn, 27) Cr (VI), 28) Fe, 29) CN, 30) Sulfide, 31) Sulfate				
the existing data from EIA		Frequency	Monthly (some main parameters sampled from March to August 2013 and all parameters sampled from June to August 2013)				
studies near		Location	Surface water				
the Project site)	Soil Quality	Parameter	Total of 11 parameters: 1) Cadmium (Cd) 2) Chromium (Cr v _I) 3) pH 4) Mercury (Hg) 5) Lead (Pb) 6) Arsenic (As) 7) Zinc (Zn) 8) Nickel (Ni) 9) Manganese (Mn) 10) Iron (Fe) 11) Copper (Cu)				
		Period	One time sampling at one point				
		Location	Paddy field				
		Parameter	LAeq (A-weighted loudness equivalent)				
	Noise Level	Period	72-hour survey during weekday and weekend				
		Location	Two locations				

Source: EIA Report for the Thilawa SEZ Class A Development Project (September 2013)



Source: EIA Report for Thilawa SEZ Class A Development Project (September 2013)

Figure 4.1-1 Location of Environmental Survey for Overall Conditions under the EIA Study of Class A

4.1.1 Air Quality

Table 4.1-2 and Table 4.1-3 show the results of air quality survey conducted in April and June 2013 for TAN01 and TAN02.

Table 4.1-2 Results of Air Quality Survey in 2013 (TAN01)

Parameter (Unit)	Date	Season	Res	Tentative Target Value under the Project*	
	9 to 12 April	Dry	Daily Average	0.015	
SO_2	2013	Diy	Minimum - Maximum	0.012 - 0.019	0.02 mg/m^3
(ppm)	22 to 29 June	Rainy	Daily Average	0.020	(0.008 ppm)
	2013	Kaiiiy	Minimum - Maximum	0.0085 - 0.053	
	9 to 12 April	Derry	Daily Average	0.4305	
CO	CO 2013 (ppm) 22 to 29 June	Dry	Minimum - Maximum	0.3414 - 0.5070	10.26 mg/m^3
(ppm)		Rainy	Daily Average	0.3618	(9 ppm)
	2013		Minimum - Maximum	0.22 - 0.46	
	9 to 12 April	Derry	Daily Average	0.036	
NO_2	2013	Dry	Minimum - Maximum	0.033 - 0.040	0.1 mg/m^3
(ppm)	22 to 29 June	Doing	Daily Average	0.022	(0.05 ppm)
	2013	Rainy	Minimum - Maximum	0.0090 - 0.033	
	9 to 12 April	Derry	Daily Average	0.13	
PM10	2013	Dry	Minimum - Maximum	0.11 - 0.14	0.05 mg/m ³
(mg/m^3)	22 to 29 June	Doiny	Daily Average	0.039	0.05 mg/m^3
	2013	Rainy	Minimum - Maximum	0.028 - 0.051	

Note*: The tentative target value was set under the Project. (See Section 2.4.1)

Source: EIA Report for the Thilawa SEZ Class A Development Project (September 2013)

Table 4.1-3 Results of Air Quality Survey in 2013 (TAN02)

Parameter (Unit)	Date	Season	Res	Tentative Target Value under the Project*	
	9 to 12 April	Desc	Daily Average	0.016	
SO_2	2013	Dry	Minimum - Maximum	0.015 - 0.018	0.02 mg/m^3
(ppm)	22 to 29 June	Doing	Daily Average	0.0038	(0.008 ppm)
2013		Rainy	Minimum - Maximum	0.00050 - 0.0088	
CO	9 to 12 April	Dry	Daily Average	0.44	10.26 mg/m ³

Parameter (Unit)	Date	Season	Res	Tentative Target Value under the Project*	
(ppm)	2013		Minimum - Maximum	0.43 - 0.46	(9 ppm)
	22 to 29 June	Rainy	Daily Average	0.31	
	2013	Kailiy	Minimum - Maximum	0.25 - 0.42	
	9 to 12 April	Desc	Daily Average	0.041	
NO_2	2013	Dry	Minimum - Maximum	0.038 - 0.048	0.1 mg/m^3
(ppm)	22 to 29 June	Rainy	Daily Average	0.035	(0.05 ppm)
	2013		Minimum - Maximum	0.034 - 0.035	
	9 to 12 April	Desc	Daily Average	0.082	
PM10 (mg/m ³)	2013	Dry	Minimum - Maximum	0.057 - 0.10	0.05 mg/m^3
	22 to 29 June	Rainy	Daily Average	0.048	0.05 mg/m
	2013	Kailiy	Minimum - Maximum	0.038 - 0.060	

Note*: The tentative target value was set under the Project. (See Section 2.4.1)

Source: EIA Report for the Thilawa SEZ Class A Development Project (September 2013)

4.1.2 **Water Quality**

EIA Study of Class A (1)

Tables 4.1-4 and Table 4.1-5 show the results of the water quality survey at TW1 located in Zarmani Reservoir and TW2 located on the small stream running to the Yangon River. In Zarmani Reservoir, the results showed that pH was 5.8-9.3, BOD₅:1.5-3.5 mg/l, SS:159-1,230 mg/l, DO:4.06-7.70 mg/l, Total coliform:100-3,000 MPN/100 ml, and COD:0.368-5.52 mg/l. On the other hand, the results at TW2 showed that pH was 7.21-7.4, BOD₅:2.5-3 mg/l, SS:73-272 mg/l, DO:4-4.6 mg/l, Total coliform:400-1,700 MPN/100 ml, and COD:0.736-2.36 mg/l.

Table 4.1-4 Results of Water Quality Survey at TW1 (April-August, 2013)

Parameters (Unit)	March	April	May	June	July	August	Tentative Target Value under the Project*
Temperature (°C)	30.1	37.3	29.5	28.22	27.58	28.50	-
Taste and Odor			Not ob	jectionabl	e		-
Color	Clear	Clear	Clear	Clear	Clear	Clear	-
Electrical Conductivity (µS/cm)	57	48	63	47	28	39	-
pH	5.8	6.2	9.3	7.5	7.6	8.9	6-8.5
BOD ₅ (mg/L)	2.5	2.5	3	3.5	1.5	2.5	15
SS (mg/L)	1,200	160	180	270	160	170	100
DO (mg/L)	4.1	7.0	4.4	4.5	6.8	7.7	4
Fecal Coliform (MPN/100 ml)	1×10^{2}	-	3×10^{3}	3×10^{2}	4×10^{2}	-	-
Total Coliform (MPN/100 ml)	1×10^{2}	-	3×10^{3}	3×10^{2}	4×10^{2}	-	7,500
COD (mg/l)	3.7	0.4	0.4	2.4	1.8	5.5	30
Total Nitrogen (mg/L)	7.6	13.28	13.3	12.9	12.7	13.4	1
Total Phosphorous (mg/L)	2.6	ND	ND	ND	0.2	0.2	1
Total Organic Compounds (mg/L)	6.5	7.9	10	13	6.4	5.0	-
Turbidity (FNU)	42.2	0.1	90.5	55.6	46.6	54.6	-
Hardness (mg/L)	40	32	14	60	80	10	-

Note: The results were rounded up or rounded off using an appropriate number of significant figures for each parameter.

Note *: The tentative target value was set under the Project. (See Section 2.4.2)

Source: EIA Report for the Thilawa SEZ Class A Development Project (September 2013)

Table 4.1-5 Results of Water Quality Survey at TW2 (April-August, 2013)

Parameters (Unit)	March	April	May	June	July	August	Tentative Target Value under the Project*
Temperature (°C)	-	-	-	27.39	27.25	26.5	-
Odor	-	-	-	No	ot objection	able	-
Color	-	-	-	Clear	Clear	Clear	-
Electrical Conductivity (µS/cm)	-	-	-	48	53	62	-
pH	-	-	-	7.2	7.3	7.4	6-8.5

Parameters (Unit)	March	April	May	June	July	August	Tentative Target Value under the Project*
BOD ₅ (mg/L)	-	-	-	3.0	2.5	2.5	15
COD _{Cr} (mg/L)	-	-	-	2.4	0.74	1.1	30
SS (mg/L)	-	-	-	91	73	270	100
Turbidity (NTU)	-	-	-	240	98	650	-
Hardness (mg/L)	-	-	-	120	100	20	-
DO (mg/L)	-	-	-	4	4.6	4.5	-
Total Coliform (MPN/100 ml)	-	-	-	1.7×10^3	-	4.0×10^{2}	7,500
Total Nitrogen (mg/L)	-	-	-	8.1	8.2	8.1	-
Nitrite (NO ₂ -N) (mg/L)	7.6	ND	13	15	13	13	-
Nitrates (NO ₃ -N) (mg/L)	ND	ND	ND	4.2	ND	ND	5
Ammonium Nitrogen	ND	ND	0.25	ND	ND	ND	
$(NH_4-N) (mg/L)$	ND	ND	0.23	ND	ND	ND	-
Total Phosphorous (mg/L)	-	-	-	ND	ND	ND	-
Oil and Grease (mg/L)	<1	2	<1	<1	1	2	0.1
Sulfide (mg/L)	ND	ND	ND	ND	ND	ND	-
Sulfate (mg/L)	100	100	100	ND	5	40	-
Total Organic Carbon (mg/L)	-	-	-	4.9	5.3	4.1	-
Cyanide (CN) (mg/L)	< 0.05	< 0.005	< 0.05	< 0.05	< 0.05	< 0.05	Not detectable
Mercury (Hg) (mg/L)	ND	0.0002	0.0011	0.0001	0.0009	0.0021	0.0005
Lead (Pb) (mg/L)	0.003	ND	0.062	0.009	0.05	0.010	0.01
Cadmium (Cd) (mg/L)	0.0044	0.0007	ND	0.0013	0.0152	0.0004	0.003
Hexavalent Chromium (Cr(VI)) (mg/L)	ND	ND	ND	ND	ND	ND	0.04
Copper (Cu) (mg/L)	0.04	ND	0.28	0.18	ND	ND	0.02
Zinc (Zn) (mg/L)	ND	ND	ND	ND	ND	ND	0.05
Nickel (Ni) (mg/L)	< 0.01	0.01	0.01	< 0.01	0.01	< 0.01	0.1
Manganese (Mn) (mg/L)	ND	0.1	0.1	ND	ND	ND	1.0
Iron (Fe) (mg/L)	0.001	5	0.094	0.05	0.05	4	1.5

Note: The results were rounded up or rounded off using an appropriate number of significant figures for each parameter.

ND; Not Detected

Note \ast : The tentative target value was set under the Project. (See Section 2.4.2)

Source: EIA Report for the Thilawa SEZ Class A Development Project (September 2013)

(2) Yangon River

Table 4.1-6 shows data of water quality in Yangon River. SS showed high values at all sites ranging from 260-320 mg/l. SS at the bottom layer tended to be higher value than at the surface layer. DO ranged between 5.5-9.0 mg/l. BOD showed high values at all sites ranging from 128-288 mg/l. The values differed from site to site and no specific trend emerged. Location of monitoring points in Yangon River is shown in Figure 4.1-2.

Table 4.1-6 Water Quality in Yangon River (August, 2012)

Site		S1 16°40' 59" N 96°13' 59" E	S2 16°39' 36" N 96°15' 08" E	S3 16°38' 01" N 96°15' 50" E	S4 16°36' 54" N 96°15' 28" E	S5 16°39' 38" N 96°14' 21" E	Tentative Target Value
Date		14-8-2012	14-8-2012**	13-8-2012	13-8-2012**	15-8-2012	under the
Hour		7:30	8:00	6:50	7:30	9:00	Project*
Depth(m)		6	13	3	24	8	
Tomporoture (9C)	Surface	24.0	24.2	22.8	24.0	24.5	-
Temperature (°C)	Bottom	24.0	24.4	22.8	25.6	24.4	
ъU	Surface	7.6	7.8	7.8	6.1	7.5	6-8.5
pH	Bottom	7.5	7.7	6.5	7.8	7.6	
SS (mg/l)	Surface	310	325	260	290	282	100
55 (mg/1)	Bottom	300	330	288	308	320	
The state of the s	Surface	250	268	240	270	265	-
Turbidity (NTU)	Bottom	245	316	250	300	288	
DO (mg/l)	Surface	6.0	8.0	7.0	6.0	6.0	4
DO (IIIg/I)	Bottom	8.0	7.6	5.5	7.8	7.6	

Site		S1 16°40' 59" N 96°13' 59" E	S2 16°39' 36" N 96°15' 08" E	S3 16°38' 01" N 96°15' 50" E	S4 16°36' 54" N 96°15' 28" E	S5 16°39' 38" N 96°14' 21" E	Tentative Target Value	
Date		14-8-2012	14-8-2012**	13-8-2012	13-8-2012**	15-8-2012	under the	
Hour		7:30	8:00	6:50	7:30	9:00	Project*	
BOD ₅ (mg/l)	Surface	288	160	192	128	240	15	
BOD5(IIIg/I)	Bottom	192	288	160	240	288	13	
Coliform bacteria	Surface	>16	>16	>16	>16	>16		
(MPN/100 ml)	Bottom	>16	>21	>16	>17	>16] - !	
Total Nitrogen	Surface	0.55	0.61	0.55	0.55	0.54		
(mg/l)	Bottom	0.77	0.75	0.51	0.86	0.59	_	
Total	Surface	0.185	0.170	0.173	0.184	0.189		
Phosphorous (mg/l)	Bottom	0.303	0.298	0.204	0.323	0.271	-	

Note *: The tentative target value was set under the Project. (See Section 2.4.2)

**:Water samples at bottom layer were collected on 30th August at S2 and S4.

Source: Original data was obtained from JICA Report, The Urgent Project for Rehabilitation of Yangon Port and Main Inland Water Transport, January 2015.



Source: Original data was obtained from JICA Report, The Urgent Project for Rehabilitation of Yangon Port and Main Inland Water Transport, January 2015.

Figure 4.1-2 Location of Yangon River Water Sampling

4.1.3 **Soil Quality**

The results of soil quality analysis are presented in Table 4.1-7. Copper, lead, and zinc were detected at 0.004-0.007 mg/kg, 80-83 mg/kg, and 105-115 mg/kg, respectively, while chromium and mercury were detected at 10 and 0.002-0.004 mg/kg, respectively or not detected at all.

No.	Parameter	Dry Seaso	on (April)	Rainy (July)	Unit
		ST1 ST2		ST1	
1	Cadmium (Cd)	0.004	0.006	0.007	mg/kg
2	Chromium (VI)	ND	ND	10	mg/kg
3	pН	6.2	6.5	6.3	-
4	Mercury (Hg)	0.002	0.004	ND	mg/kg
5	Lead (Pb)	80	83	80	mg/kg
6	Arsenic (As)	ND	ND	ND	mg/kg
7	Zinc (Zn)	105	110	115	mg/kg
8	Nickel (Ni)	10	12	7	mg/kg
9	Manganese (Mn)	15	18	14	mg/kg
10	Iron (Fe)	5,280	5,310	5,010	mg/kg
11	Copper (Cu)	80	85	110	mg/kg

Table 4.1-7 Results of Soil Quality Analysis at ST2 (2013)

Remarks: ND: Not Detected

Source: 1) Standard of Soil Contamination Countermeasures Act, 2002, Japan

- 2) Environmental Quality Standards for Soil Pollution, 1994, Japan
- 3) Soil Quality Standard for Other Purposes, 2004, Thailand
- 4) Regulation for Implementing the Law on Soil Contamination Countermeasures QCVN 03: 2008/BTNMT, Vietnam. It is applied as "farmland"

4.1.4 Noise Level

The results of noise levels (Leq) in April 2013 are shown in Table 4.1-8. The noise levels at TAN01 located along the road was at 58.3~61.1 dB(A) during daytime (6:00-22:00), and at 42.7~47.6 dB(A) during nighttime (22:00-6:00). On the other hand, the noise levels at TAN02 located in front of a monastery and about 131 m away from the road was at 53.2~59.8 dB(A) during daytime, and at 51.8~55.1 dB(A) during nighttime.

Table 4.1-8 Results of Noise Levels in April, 2013 (Dry Season)

Únit: dB(A)

	Date		N01 the Road)	TAN02 (Living Environment)			
		Daytime	Nighttime	Daytime	Nighttime		
1	07-08 April 13	58.9	47.6	53.2	53.7		
2	08-09 April 13	61.1	42.7	59.8	51.8		
3	09-10April 13	58.3	46.7	54.5	55.1		
Tentative Target	Residential, institutional, educational	75	70	55	45		
Value*	Industrial, commercial			70	70		

Note: Daytime and nighttime under the survey indicate 6:00-22:00 and 22:00-6:00 respectively, while daytime and nighttime under the NEQG indicate 7:00-22:00 and 22:00-7:00 respectively.

Note*: Along the Road: The Noise Regulation Law (Japan) (Law No.98 of 1968, Latest amendment by Law No.91 of 2000)

Living Environment: National Environmental Quality (Emission) Guidelines (2015) (See Section 2.4.3)

Source: EIA Report for the Thilawa SEZ Class A Development Project (September 2013)

4.2 Natural Environment

4.2.1 Meteorology

Greater Yangon has a tropical monsoon climate characterized by altering the rainy season (from May to October) and the dry season (from November to April). Table 4.2-1 shows the amount of monthly rainfall and maximum, minimum, and mean temperature averaged from 1981 to 2010 observed at the Kaba-aye Meteorological Station, which is the nearest station from Thilawa SEZ.

The mean monthly temperature is highest in April at 30.7 °C and lowest in January at 25.0 °C. Except in December and January, the monthly temperatures are above 25.0 °C. The southwest monsoon wind is the main source of rain, and the Yangon area receives rain during the period from May to October.

The average annual amount of rainfall is 2,787 mm. Rainfall sharply decreases from November and continues to be less than 10 mm from December to February.

Table 4.2-1 Monthly Maximum, Minimum, Mean Temperatures, and Rainfall at Kaba-aye Station in Yangon City (1981-2010)

Month	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Average/ Total
Max. Temp. (°C)	33.2	35.2	36.8	37.5	34.1	30.8	30.3	30.0	31.0	32.2	33.1	32.5	33.1
Min. Temp. (°C)	16.7	18.3	21.1	23.8	24.3	23.6	23.2	23.3	23.2	23.1	21.3	17.7	21.6
Mean Temp. (°C)	25.0	26.8	29.0	30.7	29.2	27.2	26.8	26.7	27.1	27.7	27.2	25.1	27.4
Rainfall (mm)	1	4	12	38	325	566	608	571	393	201	61	7	2787


Source: Data of the Department of Meteorology and Hydrology, Kaba-aye Station, Yangon

Table 4.2-2 shows the maximum day of rainfall recorded in a year at Kaba-aye station from 2002 to 2013. In May 2008. The maximum rainfall was recorded 344 mm/day in May 2007. Cyclone Nargis brought 220 mm rainfall in a day.

Table 4.2-2 Maximum Rainfall Recorded at Kaba-aye Station in Yangon City (2002-2013)

	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013
Maximum Rainfall (mm/day)	115	82	107	94	92	344	220	180	100	99	108	143
Recorded Month	Sep	Aug	Jun	Sep	Aug	May	May (Cyclone Nargis)	Sep	Jun	Jun	Aug	Aug

Source: Data of the Department of Meteorology and Hydrology, Kaba-aye Station, Yangon



Source: Data of the Department of Meteorology and Hydrology, Kaba-aye Station, Yangon


Figure 4.2-1 Climograph of Kaba-aye Station in Yangon City (1981-2010)

4.2.2 Hydrological Situations

The main river around Thilawa SEZ is the Yangon River, which is a large tidal river in the region running on the west side of Thilawa SEZ. The data on the tide levels of the Yangon River as observed at elephant point (see Figure 4.2-2) by the Ministry of Port Authority (MPA) are shown in Table 4.2-3. The elephant point is located at the mouth of the Yangon River, 32 km south from the Yangon Port. The data of MPA are converted in accordance with Myanmar's standard sea level.

In Thilawa SEZ, there are six tidal rivers and small streams. Four of them, namely: Ah Lun Sake Creek, Shwe Pyauk Creek, Pa Lan Creek, and small creek flow into the Yangon River. In the south area of Thilawa SEZ, Gway Creek and Kayat Creek flow into the Hmawwun River, which flows from east to west and reaches the Yangon River.

In and around Thilawa SEZ, there are three major water reservoirs, namely: Zarmani Reservoir, Bant Bwaykone Reservoir and Thilawa Reservoir.



Source: JICA Preparatory Study on Thilawa SEZ Infrastructure Development in the Republic of the Union of Myanmar (March 2014)

Figure 4.2-2 Location of Rivers and Elephant Point

Table 4.2-3 Hydrological Data on the Yangon River

Description Data of Sounding at Elephant

Highest HWL (September 1930) +4.390

Description	Data of Sounding at Elephant Point (m)
Highest HWL (September 1930)	+4.390
MWL in Bo Aung Kyaw Wharf	+0.856
MWL in Pilaket Creek	+0.591
Zero of Tide Gauge in Yangon	-2.265
Lowest LWL (February 1888)	-2.265
High Tide Duration	1.2 hr

Source: JICA Preparatory Study on Thilawa SEZ Infrastructure Development in the Republic of the Union of Myanmar (March 2014)



Source: Preparatory Study on Thilawa SEZ Infrastructure Development in the Republic of the Union of Myanmar(2014)

Figure 4.2-3 Surface Water in and around Thilawa SEZ

4.2.3 Topography

The Thilawa SEZ Zone B is part of the Ayeyarwaddy and Sittaung deltas. The ridges exist on both sides of Thanlyin-Kyauktan Bridge and Thilawa Road. The distinct physiographic units are as follows:

(1) Ridges


The dominant physical features of the region where the project is located are the three ridges namely: the Yangon Ridge in the northern part, the Thanlyin Anticlinal Ridge in the eastern part, and the Kawhmu Ridge in the western part of the region. Other parts are flat lowlands. These ridges are the southern continuation of the Pegu Yoma. The Yangon-Mingaladon Ridge is an anticlinal ridge but morphologically it looks like a homoclinal ridge. The highest elevation is about 68 m above sea level with 30 m base height and the regional slope is towards the south. The Thanlyin Ridge is also an anticlinal ridge and covered with thick lateritic soil. The highest elevation of the entire region is about 50 m mean sea level (msl) and base height is about 21 m above sea level. The Kawhmu Ridge is a dome shaped and covered with thick lateritic soil. The highest point is about 60 m and the basement of this ridge is about 20 m. This ridge is wide at about 34 km from the north of Twentay Town to the south of Kawhmu Town. Further in the western part along the Thanlyin-Kyauktan Highway and the western part of Nyaungwine Village Tract, Shwebyauk Village, Thanlyin Township, and Kyauktan Township are situated. The elevation of the ridges is above 17 m and is located at the border of Thanlyin Township and Kyauktan Township along the road between Ahle Village of Thanlyin Township and Thilawa Village of Kyauktan Hmawwun by the side of Thilawa Road. The ridges are covered with dense forest vegetation and boundaries and are composed of laterite. These ridges are gently sloping southward.

(2) Alluvial Plain

The alluvial plain is widespread and a vast agricultural land is found in the study area. This plain is built up with alluvial deposits from the Hlaing and Bago rivers. The general elevation of the alluvial plain is generally less than 6.6 m above mean sea level. In the rainy season, the plain is usually flooded, thus, it permits old alluvial soil to be deposited in its banks. The plain is rather swampy in some places.

(3) Costal Lowland

The coastal zone exists in the southern and southeastern parts of Thanlyin Township and Kyauktan Township. These coastal zone structures are from Mibya, Zwebagon, Shan Chaung, and Sinmakwe villages in the southern part up to the Mottama Sea. Large swampy lowlands are found in the lower part of the coastal region where the Hmawwun River, Kondon Creek, and Kawdaun Creek flow into the Yangon River. The drain empties very slowly, thus, this part is unsuitable for agriculture and fishing industries. The western portion of these townships is drained by a lot of tidal rivers and creeks. The main drainage is the Hmawwun River, which flows from east to west and drains into the Yangon River. Some creeks flow into the Yangon River, some into the Hmawwun River, and some directly into the Gulf of Mottama (e.g., Kanaung, Myagaing, and Tummyaung).



Source: Resource Environmental Myanmar Ltd.

Figure 4.2-4 Physiographic Features in the Yangon Area


4.2.4 Geographical Features

The regional geomorphic features of the entire area include ridges and deltaic lands lying south of the Pegu Yoma between the Sittaung River in the east and the Irrawaddy River in the west. This area is in a north-south trending sedimentary basin containing thick sedimentary deposits from the Tertiary to Quaternary periods. The Tertiary deposits are strongly folded into narrow en echelon anticlinal folds such as the Yangon Ridge, the Thanlyin-Kyauktan Ridge, and the Twentay-Kawhmu Ridge. All these ridges are trending south towards the Gulf of Martaban. Rocks of the Tertiary Period contain well consolidated marine sandstone and shale of the Pegu Group and semi-consolidated, continental deltaic, and marginal marine deposits of the Irrawaddy Formation. The synclinal valley or through west of the Yangon Anticlinal Ridge is filled with unconsolidated deposits from the Quaternary Period. There forms a wedge-shaped alluvial accumulation, ranging in thickness from a few feet near the ridge up to 100 m in the synclinal valley. The wedge-shaped form of these sediments extends both in the east-west and north-south directions and shows thickening toward the south and west. These sediments include clay, silt, sand, and very coarse-grained gravel.

Lithostratigraphic Units Geological Age **Physical Parameter** Recent Alluvial Recent Clay and silt with trace sand Pleistocene Valley-filled Deposits Clay, silt, sand, and very coarse-grained gravel Reddish brown, grey to blue, laminated clays, with interbedded sand-rocks Danyingon Clay Yellowish grey to bluish grey sand-rock, fine to coarse-grained, sometimes Pliocene Arzanigon Sand-rock very coarse-grained, sometimes very coarse to gritty with intercalated clay and mudstone/siltstone Besapet Alternation Miocene Alternation of shale and argillaceous sandstone Thadugan Sandstone Well consolidated, jointed argillaceous sandstone Generally indurated shale Hlawga Shale Oligocene

Table 4.2-4 Geological Survey of the Region Located in and around the Yangon Area

Source: Data from the Geology Department




Note: Scale is not applicable Source: Data from the Geology Department

Figure 4.2-5 Geological Map in and around the Yangon Area

4.2.5 Soil Erosion

The main types of soil are Ferrosols, Gleysols, Solovechaks, and Arenesols. Ferrosols (plinthic) or lateritic soils are found on low hills along Thanlyin-Kyauktan. The soil is good for growing rubber and vegetables and for gardening. Gleysols (dystric) or meadow gley soils occupy much of the area in this township as shown in Figure 4.2-6. About 90% of these soils are composed of silt and clay, but humus content varies from place to place. These soils are favorable for paddy cultivation. The main problem, however, is the poor drainage and water logged conditions. Meadow Solonchak are usually found in lowlands under impeded drainage. In the rainy season, they are covered with flood water. Because of the high content of clay, these soils become very dry and crack in the dry season. Solonchaks (gleyic) or saline swampy gluey soils are found along the coastal area. These soils develop from sediments transported and deposited in the estuaries of the Yangon River.



Note: Scale is not applicable

Source: Data from the Land Use Division, Myanmar

Figure 4.2-6 Soil Map of Yangon Area

4.2.6 Flora, Fauna, and Biodiversity

According to the results of Flora and Fauna Survey in 2013¹, there were 139 flora species in the dry season and 181 species in the rainy season in the Thilawa SEZ Zone A area and the downstream near the Yangon River. The listed and recorded plant species were checked with the International Union for Conservation of Nature (IUCN) Red List of threatened species. However, none of those species were found in the IUCN Red List.


The fauna survey was also conducted in 2013 in and around the Thilawa SEZ Zone A. A total of 13 butterfly species were recorded in the study area during the survey period. All the recorded butterfly species were common species. A total of 18 bird species, which belong to 13 families, were recorded in the survey area. A total of four mammal species categorized as Least Concern (LC) by IUCN Red List were recorded during the survey period. Some species such as the white-bellied rat, *Niviventer fulvscens*, and greater bandicoot rat, *Bandicota indica*, were found mainly in the rice fields, whereas the grey squirrel *Callosciurus pygerythrus* was found in both scattered trees and scrubland areas.

¹ EIA Report for the Thilawa SEZ Class A Development Project (September 2013)

A total of 18 reptilian species and seven amphibian species were recorded in the survey area during the survey period and the total 18 species in the dry season and eight species in the rainy season had the Lc status in the IUCN Red List. The reptile species, *Calotes versicolor*, was observed in areas with mixed vegetation and scattered trees. Among the recorded species, the paddy frog, *Fejervarya limnocharis*, was found as a very common species. The frog species, *Holobatrachus tigerinus* was also common in the area and distributed in many parts of the area in the wet season. A total of 15 fish species were recorded during the survey period. The fishes are important for the ecosystem of the canal and rice field water body. The fish species, *Mystus cavasius* and *Puntius chola*, were found as the most common species in the Thilawa SEZ Zone A. The fish species, *Mystus bleekeri* and *Labeo calbasu*, were also abundant in the aquatic habitat. As a result of the survey, endangered (EN) species, vulnerable (VU) species by IUCN Red List, and prohibited species, which need to be conserved by implementing a no hunting, trading, and no disturbance by the Myanmar Law, were not identified by the Flora and Fauna Survey in 2013.

4.2.7 Protected/Reserved Area

There is no protected area including natural reserve, national park, wildlife sanctuary and bird sanctuary around Thilawa SEZ^2 . On the other hand, there is a reserved forest (553 acer) about three km away from Thilawa SEZ as shown in Figure 4.2-7, located around Ban Bwe Gon Dam in Kyauktan Township and administrated by the Forest Department.



Note: Accurate boundary of the reserved forest is unknown, while white boundary in the map shows Ban Bwe Gon Dam. Source: Website of Forestry Department (http://www.fdmoecaf.gov.mm/eng/node/9641)

Figure 4.2-7 Location of Ban Bwe Gon Dam (Reserved Forest)

.

² Source: Institute Oikos and BANCA (Biodiversity And Nature Conservation Association), Myanmar Protected Areas Context, Current Status and Challenges, 2011

 $http://www.istituto-oikos.org/files/download/2012/Myanmar Protected Areas. Context_Current Status and Challenges.pdf$



Bank Bway Gone Reservoir designated forestry area (Area-553 Acre)





The board is for raising awareness to the public for environmental conservation



Ban Bwe Gon Dam

Source: EIA Study Team

Figure 4.2-8 Photo of Ban Bwe Gon Dam (Reserved Forest)

4.3 Social Environment

4.3.1 Population

Thilawa SEZ is located across Thanlyin and Kauktan townships in Yangon Region. In 2015, there are about 268,000 people in Thanlyin Township and 133,000 in Kyauktan Township as shown in Table 4.3-1. The percentage of urban population is about 32% in both townships.

Table 4.3-1 Population of Thanlyin and Kyauktan Townships

		Total (Mal	e/Female)		Tota	al (Urban/R	Rural)	
Town ship	Male	Female	Total	Sex Ratio	Urban	Rural	Urban Population (%)	Household s
Thanlyin	130,537	137,526	268,063	94.9	86,065	181,998	32.1	61,597
Kyauktan	64,378	68,387	132,765	94.1	42,778	89,987	32.2	32,976

Source: Department of Population, Ministry of Immigration and Population "The 2014 Myanmar Population and Housing Census—The Union Report- Census Report Volume 2" May 2015

4.3.2 Ethnicity

The races residing in Thanlyin and Kyauktan townships are shown in Table 4.3-2. Most of the people who live in these townships are Bamar, followed by Kayin, Rakhine, and Indian people. A small number of Pakistani and Bangladeshi live in Thanlyin Township.

No	Race	Towns	hip
No.	Kace	Thanlyin	Kyauktan
1	Kachin	52	3
2	Kayar	2	2
3	Kayin	1,573	224
4	Chin	224	12
5	Mon	415	8
6	Bamar	198,494	120,110
7	Rakhine	1,183	90
8	Shan	133	3
9	China	371	330
10	Indian	7,090	4,140
11	Pakistan	64	0
12	Bangladeshi	425	0
13	Others	2,615	0
	Total	212 641	124 922

Table 4.3-2 Races in Thanlyin and Kyauktan Townships (2014)

Remark: The total number in each township is different from the total population which is mentioned in Table 4.3-1 because of the limitation of data collection.

Source: Thanlyin and Kyauktan Township Administrative Offices

4.3.3 Religion

The different kinds of religion present in Thanlyin and Kyauktan townships are shown in Table 4.3-3. More than 90% of the people living in the two townships are Buddhists. There are more Hindus and Muslims living in Kyauktan Township than in Thanlyin Township.

Table 4.3-3 Religion in Thanlyin and Kyauktan Townships (2014)

Township	Religion	Buddhist	Christian	Hindu	Muslim	Total
Thanlyin	Number	120,110	1,220	3,232	360	124,922
	(%)	96.2	0.9	2.6	0.3	100.0
Kyauktan	Number	202,076	1,853	3,760	3,200	212,641
	(%)	93.7	0.9	2.8	2.4	100.0

Remark: The total number in each township is different from the total population which is mentioned in Table 4.3-1 because of the limitation of data collection.

Source: Thanlyin and Kyauktan Township Administrative Offices

4.3.4 Land Use

Land use in Thanlyin and Kyauktan townships are shown in Table 4.3-4. Both townships mainly use its land for agriculture followed by water area. In Thanlyin Township, settlement land covers 10.6% (3,936 ha) which is comparatively large. It is considered that Thanlyin Township is a kind of bed-town for laborers who go to Yangon to work.

Table 4.3-4 Land Use of Thanlyin and Kyauktan Townships (2012/2013)

Land Catagory	Than	lyin	Kya	yautan	
Land Category	ha	%	ha	%	
Agricultural Land	24,762.3	66.4	62,882.9	74.5	
Forest and Natural Area	51.4	0.1	225.4	0.3	
Road and Railway	803.7	2.2	1,097.5	1.3	
Water Area	5,064.6	13.6	12,087.2	14.3	
Industrial Land	2,108.0	5.7	794.4	0.9	
Settlement Land	3,936.0	10.6	3,840.9	4.6	
Other	565.3	1.5	3,442.7	4.1	
Total Area	37,291.3	100.00	84,371.0	100.00	

Source: JICA/Sanyu Consultants Inc., Data Collection Survey on Water Resources Potential for Thilawa Special Economic Zone and Adjoining Areas Final Report, September 2014

4.3.5 Water Usage

The sources of drinking water and non-drinking water in Thanlyin and Kyauktan townships are shown in Table 4.3-5 and Table 4.3-6, respectively. More than 60% of the households in Thanlyin Township are using water for drinking and non-drinking purposes from wells, while about 70% of households

are using water from the pool/pond/lake in Kyauktan Township. On the other hand, as shown in Figure 4.3-1, most of the wells in Thanlyin Township are located outside of Thilawa SEZ.

Table 4.3-5 Source of Drinking Water in Thanlyin and Kyauktan Townships


Township	Source of Water	Tap Water/ Piped	Tube Well, Borehole	Protected Well/Spring	Unprotected Well/Spring	Pool/Pond/ Lake	River/Stream /Canal	Waterfall/ Rainwater	Bottled Water Purifier	Tanker/ Truck	Other	Total
Thonlyin	Number	1,392	24,925	10,389	3,602	14,190	33	185	5,595	91	1,195	61,597
Thanlyin	(%)	2.3	40.5	16.9	5.8	23.0	0.1	0.3	9.1	0.1	1.9	100.0
Kyauktan	Number	1,804	2,171	3,961	1,092	22,833	14	103	864	5	129	32,976
	(%)	5.5	6.6	12.0	3.3	69.2	0.04	0.3	2.6	0.02	0.4	100.0

Source: Department of Population, Ministry of Immigration and Population "The 2014 Myanmar Population and Housing Census—The Union Report- Census Report Volume 2" May 2015

Table 4.3-6 Source of Non-Drinking Water in Thanlyin and Kyauktan Townships

Township	Source of Water	Tap Water/ Piped	Tube Well, Borehole	Protected Well/Spring	Unprotected Well/Spring	Pool/Pond/ Lake	River/Stream /Canal	Waterfall/ Rainwater	Bottled Water/Water Purifier	Tanker/ Truck	Other	Total
Thanlyin	Number	3,062	29,188	9,770	3,618	14,545	60	5	63	19	1,267	61,597
Hamym	(%)	5.0	47.4	15.9	5.9	23.6	0.1	0.01	0.1	0.03	2.1	100.0
Kyauktan	Number	2,292	3,376	3,183	995	22,935	15	3	34	2	141	32,976
	(%)	7.0	10.2	9.7	3.0	69.6	0.05	0.01	0.1	0.01	0.4	100.0

Source: Department of Population, Ministry of Immigration and Population "The 2014 Myanmar Population and Housing Census—The Union Report- Census Report Volume 2" May 2015



Source: JICA/Sanyu Consultants Inc., Data Collection Survey on Water Resources Potential for Thilawa Special Economic Zone and Adjoining Areas Final Report, September 2014

Figure 4.3-1 Distribution of Tube and Dug Wells in Thanlyin and Kyauktan Townships

4.3.6 Local Economy and Livelihood

The main sources of livelihood in the two townships are agriculture, fishing, and official employment in the government. In Thanlyin Township, other sources of earning are livestock breeding, fish

farming, casual labor, and betel leaf and coconut plantations as well as small-to-medium-size businesses. In Kyauktan Township, other livelihood activities include livestock breeding, fish farming, and betel leaf and coconut plantations. Most of the casual laborers are employed in the agricultural sector. According to the survey results of Resettlement Framework for 2,000 ha, it is confirmed that more or less 10 households are engaging in the aquaculture in and around Thilawa SEZ, and the fishponds are mainly located along Alunsut Creek. In addition, about 20 households are cultivating not only monsoon paddy fields but also summer paddy fields by utilizing the irrigated water from the existing water source including creeks which flows in and around Thilawa SEZ.

Table 4.3-7 Existing Status of Local Livelihoods in Thanlyin and Kyauktan Townships (2014)

	Type of Workers (Person)									
Township	Government Staff	Service Staff	Agriculture	Livestock	Trader	Factory	Odd Job	Others		
Thanlyin	7,436	2,675	6,650	175	21,003	6,230	41,972	21,623		
Thamyin	(6.9%)	(2.5%)	(6.2%)	(0.2%)	(19.5%)	(5.8%)	(39.0%)	(20.1%)		
Kyauktan	4,305	11,000	4,307	8,706	6,637	5,378	6,569	35,851		
	(5.2%)	(13.3%)	(5.2%)	(10.5%)	(8.0%)	(6.5%)	(7.9%)	(43.3%)		

Source: Thanlyin and Kyauktan Township Administrative Offices

4.3.7 Social Infrastructure and Service

(1) Access Road

Figure 4.3-2 shows the current main roads that connect Yangon City to Thilawa SEZ, i.e., the road that passes through Thanlyin Bridge (Bridge No. 1) and the road that passes through Dagon Bridge (Bridge No. 2). The peripheral road of Thilawa SEZ is paved with concrete while the road between Thanlyin Bridge and Thilawa SEZ is paved with asphalt. Majority of the pavement is made with concrete because concrete is relatively inexpensive there while there is insufficient asphalt factories which provide good-quality asphalt. On the other hand, most of the roads connected into the villages are still unpaved. Currently, the expansion of connection road from Thanlyin Bridge to Thilawa SEZ has been planned under the support of JICA³.

_

³ Infrastructure Development Project in Thilawa Area Phase 2 (Yen Credit)



Source: Preparatory Study on Thilawa SEZ Infrastructure Development in the Republic of the Union of Myanmar (2014)

Figure 4.3-2 Present Conditions of the Main Roads to Thilawa SEZ

(2) Water Storage Reservoirs

a) Major Water Reservoirs in and around Thilawa SEZ

Major water reservoirs in and around Thilawa SEZ are as follows:

Zarmani Reservoir: It is a reservoir for agricultural purposes and the reservoir serves mainly for irrigation. In addition, the reservoir water is sold as drinking and domestic water to the nearby industrial area and port.

Bant Bwaykone Reservoir: It is a reservoir for agricultural purposes. The reservoir water is supplied for irrigation and sold to Kyauktan Township. A small portion is sold as drinking and domestic water to a nearby port.

Thilawa Reservoir: This reservoir's water is supplied to nearby factories and is used for irrigation, and sold to a nearby port.

Since water right for surface water belongs to the Ministry of Agriculture and Irrigation (MOAI), the Zarmani Reservoir and Bant Bwaykone Reservoir are managed by MOAI. On the other hand, the water right of Thilawa Reservoir belongs to the Ministry of Industry (MOI) and the Ministry of Construction (MOC).

The location of the above reservoirs is presented in Figure 4.2-3. Table 4.3-8 and Table 4.3-9 show outline and situation of utilization of the three reservoirs.

Table 4.3-8 Existing Three Reservoirs in and around Thilawa SEZ

No	Content	Bant Bwaykone	Zarmani	Thilawa
1	Location (Township)	Kyauktan	Thanlyin	Thanlyin
2	Name of Source Creek	Par Da	Myayaryoe	-
3	Catchment Area (km ²)	2.25	7.25	0.93
4	Gross Storage Capacity	2,140	6,616	1,363
5	Full Water Level (EL m)	7.92	7.01	9.75
6	Completion Year	June 1994	June 1995	1986

Source: Preparatory Study on Thilawa SEZ Infrastructure Development in the Republic of the Union of Myanmar (2014), and JICA/Sanyu Consultants Inc., Data Collection Survey on Water Resources Potential for Thilawa Special Economic Zone and Adjoining Areas Final Report, September 2014

Table 4.3-9 Utilization of Three Reservoirs in and around Thilawa SEZ (2003-2011)

Unit: 1,000 m³/year

	Bant Bwaykone	Zarmani	Thilawa
1. Irrigation Water (average)	1,299	2,455	The amount of irrigation, domestic,
Maximum (1999-2011)	2,620	5,222	and drinking water (2007-2011):
Minimum (1999-2011)	1,023	752	1,371
2. Domestic, Drinking Water	37	9	
(average: - 2011)*1			
(average: 2002 - 2003)*2	2,187	23,719	
Average water consumption	1,336	2,464	1,371
(1+2)(average: - 2011) *3			

^{*1:} The average except from 2002 to 2003.

b) Future Reservoir for Water Usage in Thilawa SEZ

Currently, the development of Lagunbyin Water Supply System has been planned by the Yangon City Development Committee (YCDC) in cooperation with JICA. The source of water is Lagunbyin Reservoir which was constructed by the Ministry of Agriculture and Irrigation in 2000, located 70 km north of Thilawa SEZ on the border of Yangon District and Bago District. Figure 4.3-3 shows the location while Table 4.3-10 shows the specification.

^{*2:} The water from Zarmani and Bant Bwaykone was supplied to a nearby construction project in 2002-2003; it was different from the normal year.

^{*3:} In the Thilawa Reservoir, the operational record before 2006 did not remain with the administrator (SHESAKA Factory).

Source: JICA/Sanyu Consultants Inc., Data Collection Survey on Water Resources Potential for Thilawa Special Economic Zone and Adjoining Areas Final Report, September 2014



Source: Prepared by the EIA Study Team based on the map from Myanmar Information Management Unit

Figure 4.3-3 Location of Lagunbyin Reservoir

Table 4.3-10 Specification of Lagunbyin Reservoir

	Subject	Lagunbyin Reservoir
1	Catchment Area	42 square-mile (108.78 km ²)
2	Average Annual Rainfall (Inch)	100 inch (2,500 mm)
3	Average Annual Inflow (Ac-ft)	126,000 Ac-ft (155.418 MCM)
4	Type of Dam	Earth Dam
5	Height of Dam	62 ft (18.89 m)
6	Length of Dam	5,180 ft (1578.8 m)
7	Storage Capacity of Full Tank (Ac-ft)	148,800 Ac-ft (183.512 MCM)
8	Dead Storage Capacity (Ac-ft)	5,250 Ac-ft (6.476 MCM)
9	Water Spread Area of F.T.L (Acre)	6,700 Acre (27 km ²)


Source: JICA/Sanyu Consultants Inc., Data Collection Survey on Water Resources Potential for Thilawa Special Economic Zone and Adjoining Areas Final Report, September 2014

The Lagunbyin Water Supply System managed by YCDC is planned to cover the four townships of East Dagon, North Dagon, South Dagon, and Dagon Seikkan, located in the east of Yangon City and Thilawa SEZ with a capacity of 40 MGD. The water amount allocated by the Irrigation Department will be 30 MGD for the four townships in Yangon City and 10 MGD in Thilawa SEZ.

(3) Solid Waste Management

a) Solid Waste Management in Yangon City

The Pollution Control and Cleansing Department (PCCD) of YCDC is in charge of solid waste management of 33 townships in Yangon City. The flow of solid waste from generation to final disposal in Yangon City is illustrated in Figure 4.3-4.



Source: The Project for the Strategic Urban Development Plan of the Greater Yangon (JICA) 2014

Figure 4.3-4 Flow of Solid Waste Management in Yangon City

The waste collection system in Yangon City is a combination of primary waste collection method, waste temporary storage and secondary waste collection (waste transportation). The PCCD personnel collects solid waste directly from waste generation sources such as households, shops and businesses using push carts or trucks. The PCCD also collect waste from waste bins placed on the corner of the street in which waste generator discharge. In addition, there is another type of collection, so-called "on call". Waste generators make a phone call for waste collection to a township office or a district office. A PCCD truck goes and collects waste directly from large amount waste generators such as industries, embassies, and institutions.


There are two main final disposal sites (FDS) operated by the PCCD. One is Htantabin final disposal site and the other one is Htawe Chaung final disposal site. These two FDSs are open and receive wastes for 24 hrs/day. Additionally, some small and temporary landfill sites are operated.

Table 4.3-11 outlines the existing final disposal sites in Yangon city, while Figure 4.3-5 shows these location. All final disposal sites are currently operated as open dumping sites. No soil covering on the dumped waste, collection/treatment of leachate, nor control of landfill gas have been carried out.

Name	Township/District	Area [ha]	Year of Starting Service	
Disposal site				
Htanbin	Hlaing Tharyar/ West	61	2002	
Htawe Chaung	North Dagon/ East Dagon	Dagon/ East Dagon 60		
Temporal site				
Shwe Pyi Thar	Shwe Pyi Thar/ West	1	1998	
[Kyun Chaung]	•			
Seikgyikhanaungto	Seikgyikhanaungto / South	0.1	1962-	
Dala	Dala/ South	1	1950	

Table 4.3-11 Existing Final Disposal Site in Yangon City

Source: YCDC



Source: Prepared by EIA Study team based on information from PCCD

Figure 4.3-5 Location of the Existing Disposal Sites in Yangon City

As for the infectious waste, the PCCD has collected them separately by compactor trucks and then incinerated them at the furnace equipped in the cemetery located at the nearby Htantabin FDS. The furnace of Htantabin Crematorium is used for infectious wastes every afternoon after completion of funerals.

As for management of disposed hazardous materials, the PCCD has treated and disposed waste which are recognized and classified as hazardous wastes like the expired medicines, residual paints and mercury. In most cases, these materials are sealed into concrete containers or encapsulated and placed into a protected deep trench. Since hazardous wastes have not been regulated by legislation in Myanmar, responsibility of treatment and disposal as well as method for treatment is not clear.

b) Solid Waste Management in Thanlyin and Kyauktan Townships

Solid waste management facilities in Thanlyin and Kyauktan townships are shown in Table 4.3-12. In Thanlyin Township, the Sanitary Department is in-charge of waste management and collects waste

from all wards. On the other hand, the Sanitary Section of the Administration Department is in-charge of waste management in Kyauktan Township. As shown in Figure 4.3-6, each of the two townships has operated its own final disposal site as open dumping.

Table 4.3-12 Solid Waste Management in Thanlyin and Kyauktan Townships


Township	Department in Charge of Solid Waste Management	Waste Collection Amount [t/d]	Equipment[Vehicles, Machinery]	Collection Area	Area of Present Disposal Site [ha]
Thanlyin	Sanitary Department	60	Truck: 5	16 of 17 wards	1.6
			(3.5 to 4.0 ton truck)	and 2 villages	
Kyauktan	Sanitary Section of the Administration	5	Truck: 2 (1 ton truck) Push cart: 3	6 of 9 wards	2.0
	Department				

Source: Thanlyin Township and Kyauktan Township Administrative Office



Figure 4.3-6 Location of the Existing Disposal Sites in Thanlyin and Kyauktan Townships







Final Disposal Site in Kyauktan Township

Figure 4.3-7 West Dumping Condition in Thanlyin and Kyauktan Townships

c) Waste Management Facility in Zone A of Thilawa SEZ

The solid waste management company has been located in Zone A of Thilawa SEZ as one of the tenants, which area is about 40 ha at the corner of Thilawa Development Road and Dagon-Thilawa

Port Road in Thanlyin Township. The specifications of the facility and the layout plan are shown in Table 4.3-13 and Figure 4.3-8 respectively.


The target wastes of the facility are industrial waste, which will be generated in Thilawa SEZ as primary and outside of Thilawa SEZ as secondary. The expected volume of waste is approximately 22,100 t/year, which are about 60 % (13,260 t/year) hazardous waste and 40 % (8,840 t/year) non-hazardous waste.

In terms of waste weight for each treatment process, approximately, 6,100 t/year for sorting, 6,600 t/year for incineration, 4,100 t/year for fuel conversion, 2,700 t/year for landfilling, 2,600 t/year for stabilization, and tens of t/year for wastewater treatment are planned.

Table 4.3-13 Waste Management Facility in Zone A of Thilawa SEZ

Facilities	Specification and Function
Laboratory Analysis	This facility is for analyzing waste for acceptance inspection and leachate, wastewater,
(Inspection) Facility	and exhaust gas for environmental monitoring and so on.
Sorting Facility	This facility receives and inspects waste from generators. After separating cleaning and
	segregating waste, valuables will be sold to demanders and non-valuables will be
	transferred to the other facilities for treatment and disposal considering the
	characteristics of the waste.
Stabilization Facility	This facility mixes waste with agents such as cement so as to prevent elution of
	hazardous substances from waste. Besides, this facility has the function of moisture
	control for landfill waste with high water content.
Fuel Conversion Facility	This facility mixes waste and adjusts the characteristics and concentration of hazardous
	substances so as to produce fuel for cement factories.
Incineration Facility	This facility is for volume reduction, stabilization, and detoxification of waste. Exhaust
(to be installed)	gas treatment equipment (chemical baghouse filter) will be installed so as to satisfy the
	target level of emission gas.
Final Disposal Facility	The landfill shall equip a liner facility to strictly intercept waste and leachate from
	entering the surrounding environment. Leachate discharged from the landfill shall be
	adequately treated by the wastewater treatment facility. During waste disposal, only a
	limited area will be opened to activate disposal and another area will be covered by a
	sheet to prevent odor. After waste disposal, soil covering and liner covering shall be
	applied and landfill gas shall be captured and combusted to prevent air pollution and
	odor. At first, two landfill cells for non-hazardous and hazardous wastes will be
	constructed individually for the first ten years of operation. Each cell will be expanded
	after they get filled up. In total, eight landfill cells (four for non-hazardous waste and
	four for hazardous waste) will be constructed.
	It is planned to be operated for 60 years.
Wastewater Treatment	This facility is for neutralization, solid-liquid separation, and biological treatment of
Facility	wastewater generated from the project facilities. Effluent shall be discharged into the
	retention canal of the industrial park by satisfying the target level of wastewater
	quality.
Other Facilities	Other small-scale and supporting facilities such as office, security house, power
	receiving house, parking, car washing facility, and truck pool will be set up.

Source: DOWA/Golden Dowa Eco-System Myanmar Co., Ltd., Project on Construction of Solid Waste Management Facilities in the Thilawa Zone A Final Environment Impact Assessment Report, June 2015)



Source: DOWA/Golden Dowa Eco-System Myanmar Co., Ltd., Project on Construction of Solid Waste Management Facilities in the Thilawa Zone A Final Environment Impact Assessment Report, June 2015)

Figure 4.3-8 Perspective Image (Upper: Starting Operation, Lower: Completion of Operation)

(4) Drainage and Sewage

The destination of rainwater drainage in Thilawa SEZ is the Yangon River and Hmawwun Creek. Rainwater in Thilawa SEZ and eastern sub-basins is collected by drainage facilities consisting of culverts and canals installed along the road. The rainwater then flows into the Yangon River through the existing creeks. Even in urban areas such as Yangon City, sewerage systems have not been established and both rainwater and sewage water are collected together by using the same canals.

(5) Electricity

Three substations, namely: Thanlyin Substation, Thaketa Substation, and Kamarnat Substation are located in the surrounding area of Thilawa SEZ as shown in Table 4.3-14. Among them, the Thanlyin Substation is the closest one from Thilawa SEZ about 10 km to the north.

Table 4.3-14 Grid Substation near Thilawa Grid Substation

	No. of 230 kV Feeder Bays	Substation Voltage	230 kV Transformer Capacity
Thanlyin Substation	2	230/33/11 kV	100 MVA (100 MVA x 1 unit)
Thaketa Substation	2	230/33/11 kV	300 MVA (100 MVA x 3 units)
Kamarnat Substation	5	230/33/11 kV	100 MVA (100 MVA x 1 unit)

Source: Preparatory Study on Thilawa SEZ Infrastructure Development in the Republic of the Union of Myanmar (2014)

Table 4.3-15 shows the number of conventional households by main source of lighting in Thanlyin and Kyauktan townships according to the result of the census in 2014. Around 47.7 % and 33.1 % of households use electricity in Thanlyin and Kyauktan townships, respectively.

Table 4.3-15 Conventional Households by Main Source of Lighting

		Total	Electricity	Kerosene	Candle	Battery	Generator (Private)	Water Mill (private)	Solar System/ Energy	Other
Thanl	yin	61,597	29,199	2,784	5,689	16,023	5,710	81	1,723	388
Kvauk	tan	32,976	10,914	4.617	4,436	8.218	2.057	13	1,793	928

Source: Department of Population, Ministry of Immigration and Population "The 2014 Myanmar Population and Housing Census—The Union Report- Census Report Volume 2" May 2015

(6) School

Location of major schools, i.e. basic education primary school (B.E.P.S.), basic education middle school (B.E.M.S), basic education high school (B.E.H.S) and university, near Thilawa SEZ in Thanlyin and Kyauktan townships are shown in Figure 4.3-9 and Figure 4.3-10, and the name and the located village tract/ ward of schools are described in Table 4.3-16 and Table 4.3-17.





Figure 4.3-9 Location of Major Schools near Thilawa SEZ in Thanlyin Township



Source: EIA Study Team

Figure 4.3-10 Location of Major Schools near Thilawa SEZ in Kyauktan Township

Table 4.3-16 List of Major Schools near Thilawa SEZ in Thanlyin Township

Sr. No.	Name of School	Location
1	Co-operative University	Nyaung Thone Pin Village Tract
2	B.E.H.S (Branch) Jamar	Seikkyi Village Tract
3	Su Htoo Pan Monastery School	Aye Myitta Ward
4	B.E.P.S Phan Chat	Phan Chat Ward
5	B.E.P.S (146) Battalion School	Pha Yar Kone Village Tract
6	B.E.H.S Kyauk Yay Twin	Hpa Yar Gone Village Tract
7	B.E.P.S Jamar	Aung Chan Thar Ward
8	B.E.M.S (Branch) Htaw Watt	Aung Chan Thar Ward
9	B.E.M.S (Branch) Nyaung Thone Pin	Ah Mhu Htan Ward
10	B.E.H.S (2) Thanlyin	Myo Thit (East) Ward
11	B.E.H.S (3) Thanlyin	Htan Pin Gone Village Tract
12	B.E.H.S (1) Thanlyin	Oak Pho Su Village Tract
13	B.E.H.S (4) Thanlyin	Bago Su Ward
14	B.E.H.S (Branch) Kyaung Gone Seikkyi	Kyaung Gone Seikkyi Village Tract
15	B.E.P.S Aye Thit Sar	Aye Thit Sar Ward
16	B.E.M.S Kon Chan Kone	Kon Chan Kone Village Tract
17	B.E.P.S Nga Pa	Nga Pa Village Tract
18	Myanmar Maritime University	Hpa Yar Gone Village Tract
19	East Yangon University	Hpa Yar Gone Village Tract
20	Government Technological University	Lat Yat San Village Tract

Source: EIA Study Team

Table 4.3-17 List of Major Schools near Thilawa SEZ in Kyauktan Township

Sr. No	Name of School	Location
1	B.E.P.S Phan Lan	Aye Mya Thida Ward
2	B.E.M.H Battalion (7)	Aye Mya Thida Ward
3	B.E.P.S Shwe Pyi Thar Yar No.2	Shwe Pyi Thar Yar Ward
4	B.E.P.S Shwe Pyi Thar Yar No.3	Shwe Pyi Thar Yar Ward
5	B.E.P.S Shwe Pyi Thar Yar No.1	Shwe Pyi Thar Yar Ward
6	B.E.P.S Ka Yat	Thidar Myaing Ward
7	B.E.P.S Gway Pin	Thidar Myaing Ward
8	B.E.P.S Banbwe Kone No.1	Myaing Thar Yar Ward
9	B.E.M.S Myaing Thar Yar (Branch)	Myaing Thar Yar Ward
10	B.E.P.S Shan Su	Myaing Thar Yar Ward
11	B.E.P.S Banbwe Kone No.2	Myaing Thar Yar Ward
12	B.E.P.S Nyaung Wyne	Myaing Thar Yar Ward
13	B.E.H.S (1) Kyauktan	San Chain Mhee Ward
14	B.E.M.S Myo Ma	Ah Lal Ward
15	B.E.H.S (2) Thaw Ka School	San Chain Mhee Ward

Source: EIA Study Team

(7) Medical Facilities/Services

Location of major medical facilities and service near Thilawa SEZ in Thanlyin and Kyauktan townships are shown in Figure 4.3-11, and the name and the located village tract/ ward of hospitals are described in Table 4.3-18.




Figure 4.3-11 Location of Major Medical Services near Thilawa SEZ in Thanlyin and Kyauktan Townships

Table 4.3-18 List of Major Medical Services near Thilawa SEZ in Thanlyin and Kyauktan Townships

Sr. No.	Name of Hospital	Location
1	Chan Myae Myitta Private Hospital	Thanlyin Township
2	Thanlyin General Hospital	Thanlyin Township
3	Rural Health Department	Lat Yat San Village Tract, Thanlyin Township
4	Rural Health Department	Hpa Yar Gone Village Tract, Thanlyin Township
5	Sub - Rural Health Department	Kon Chan Gone Village Tract, Thanlyin Township
6	Kyauk Tan General Hospital	Kyauktan Township
7	Rural Health Department	Nyaung Wine Village Tract, Kyauktan Township
	(Myaing Thar Yar)	
8	Mother & Child Care	Ah Lal Ward Village Tract, Kyauktan Township
9	Mother & Child Care	San Chain Mhee Ward, Kyauktan Township

Source: EIA Study Team

4.3.8 Public Health

Table 4.3-19 shows morbidity and mortality of diseases and accidents in Thanlyin and Kyauktan townships in 2015. It shows high morbidity of Acute Respiratory Infections (ARI) under 5 year-old and diarrhea disease in both townships.

 Table 4.3-19
 Morbidity and Mortality of Diseases and Accidents (2015)

Disease/Accident	Thanly	in Township	Kyauktan Township		
Disease/Accident	Morbidity	Mortality	Morbidity	Mortality	
Malaria (per 100,000 Pop)	NA	0	0.9	-	
ARI (per 100,000<5 children)	935	2	10,500	-	
Diarrhea (per 100,000 Pop)	1,966	0	10,774	-	
TB (Sputum+) (per 100,000 Pop)	295	0	79.65	-	
Snake Bite (per 100,000 Pop)	54	2	35.9	3.6	
Transport Accident	4.3 (per 1000 Pop)	12.4 (per 100,000 Pop)	2.5 (per 1000 Pop)	5.5 (per 100,000 Pop)	

NA: Data is not available

Source: Township Health Profile 2016 of Thanlyin Township and Kyauktan Township

According to the Township Health Profile 2015 of Thanlyin and Kyauyktan townships, most immunization rates for the major diseases cover more than 90% and some exceeds 100% in both townships, as shown in Table 4.3-20.

Table 4.3-20 Expanded Programme on Immunization (2015)

	Thanlyin Township	Kyauktan Township
BCG	103	100.8
DPT (Diphtheria, Pertussis, Tetanus) 3 or Penta 1	101	100.7
OPV (Oral polio vaccine) 3	97	101.1
Hepatitis B3 or Penta 3	97	-
Measles 1 or 2	92	88.5
TT (tetanus toxoid) 1 or 2	100	97.1

Source: Township Health Profile 2016 of Thanlyin Township and Kyauktan Township

Health Impact Indicators of both townships show that mortality rate in 2015 declines from that in 2013, except Under 5 mortality rate (U5 MR) in Kyauktan Township and maternal mortality rate (MMR) in both townships. On the other hand, population growth rate also decreases in both townships as shown in Table 4.3-21

Table 4.3-21 Health Impact Indicator

Thanlyin Township		Kyauktai	n Township
2013	2015	2013	2015
1.79	1.2	0.87	0.7
14.4	7	14	5
17.3	4.3	2.9	12.8
0.9	1.3	0.04	1.4
	2013 1.79 14.4 17.3	2013 2015 1.79 1.2 14.4 7 17.3 4.3	2013 2015 2013 1.79 1.2 0.87 14.4 7 14 17.3 4.3 2.9

Source: Township Health Profile 2016 of Thanlyin Township and Kyauktan Township

Other parameters related to public health in both townships summarize in Table 4.3-22.

Table 4.3-22 Other Parameters related to Public Health (2015)

	Thanlyin Township	Kyauktan Township
Nutrition		
Underweight Children (< 1 yr) (%)	1.7	-
Underweight Children (<5 yr) (%)	0.5	1.4^{1}
Reproductive Health		
% of home deliveries (Basic Health Staff: BHS)	24.8	25.2
% of home deliveries (Auxiliary Midwife: AMW)	2	5.53
% of deliveries at Rural Health Center (RHC) delivery room	71	22.62
Law birth weight (%)	1.4	2.47
School Health		
Coverage of Students examined (%)	100	91.7
Coverage of Schools with Sanitary Latrine (%)	100	100
Coverage of Schools with safe Water Supply (%)	100	100
Environmental Health		
Coverage of Sanitary Latrines (%)	95.4	98

Note1: data in 2014

Source: Township Health Profile 2016 of Thanlyin Township and Kyauktan Township





National Tuberculosis Prevention Program

Immunization Program of Measles and Polio

Source: EIA Study Team

Figure 4.3-12 Major National Program for Prevention of Infectious Disease

According to the information of Ministry of Health⁵, the National Tuberculosis (TB) Program has been implemented for 2011-2015 in order to control expansion of TB in the whole Myanmar. Currently, government supports TB patients with free of charge by distributing medicine in clinic and hospital. In addition, prevention program of the Measles and Polio has been conducted with targeting children under 5 years old. The posters for these national programs are shown in Figure 4.3-12.

4.3.9 Cultural Heritage/Asset

There is no cultural heritage site designated by the United Nations Educational, Scientific and Cultural Organization (UNESCO) or the Myanmar government in Thilawa SEZ. There are two cemeteries, one is found in the industrial area of Zone B in Kyauktan Township and the other one is found in the logistic area of Zone B in Thanlyin Township. There is also a small Hindu temple found in the residence and commercial areas of Zone B in Thanlyin Township.

4.3.10 Landscape

The project site and its surrounding area are composed of flat plains and typical rural landscapes of urban neighborhood.

4.3.11 Emergency Risk

(1) Natural Hazard

The "Hazard Profile of Myanmar" prepared by the five government ministries and departments of Myanmar and four non-governmental agencies in July 2009 describes the nine types of disasters in Myanmar, as follows: 1) Cyclone, 2) Drought/Dry Zone, 3) Earthquake, 4) Fire, 5) Flood, 6) Forest Fire, 7) Landslide, 8) Storm, and 9) Tsunami. Among these, some notable natural hazards are described below.

(2) Flood

Flood in Greater Yangon can be classified into three types: i) river flood; ii) localized flood inundation in urban areas due to the combination of factors such as cloudburst, poor infiltration rate, poor drainage infrastructure (possibly due to climate change, heat island phenomenon); and in rural areas due to decrepit dams, dikes and levees, and iii) flood due to cyclone and storm surge.

Past major flood events from 1997 to 2007 are described in the "Hazard Profile of Myanmar", but there are only a few flood events recorded in and around Greater Yangon as shown in Table 4.3-23.

⁵ Expanded Program on Immunization Multi Year Plan 2012-2016, Ministry of Health (http://www.nationalplanningcycles.org/sites/default/files/country_docs/Myanmar/cmyp_2012-2016_12_nov_11_.pdf)

Ta	ble 4.3-23 Pas	e 4.3-23 Past Major Floods in Yangon Region (1997-2007)						
ion	Date	No. of Affected Households	Affected Population	Deaths	Remark			

Location	Date	No. of Affected Households	Affected Population	Deaths	Remark
Kayan Township	7 June 1997	1,189	5,878	0	North part of the region
Hta/16 Ward, Shwe Pyi Thar Township	8 September 2002	886	4,541	0	Along the left bank of the Hlaing River in Greater Yangon

Source: Hazard Profile of Myanmar, July 2009

Large-scale floods rarely happen since the area is protected due to the construction of banks along the Yangon River and the Bago River. The bank elevation is more than 3.83 m. However, small-scale floods inside the SEZ happen every year due to the poor drainage system and the influence of high tide at lowland areas near the Yangon River. According to the result of the interview survey on flooding targeting households living in Thilawa SEZ and along the outer boundary of Thilawa SEZ conducted from 17 to 20 September 2012 under the JICA Study⁶, 35% of the population have experienced flood at least once as shown in Table 4.3-24.

Table 4.3-24 Flood Experience of Residents

Frequent Flooding Experiences	Number of Samples	Percentage (%)
Yes	49	35
(1) Every year	5	10
(2) Sometimes (every 6-10 years or more)	1	2
(3) Only once as far as they know	43	88
No	91	65
Total	140	100

Source: JICA Preparatory Study on Thilawa SEZ Infrastructure Development in the Republic of the Union of Myanmar (March 2014)

Table 4.3-25 shows the duration of inundation. The residents who answered that flooding occurred every year reported that the duration of inundation is below 30 min. For the residents who answered that they experienced flooding once a year, 46% of them answered that the duration of inundation is one day. In addition, 26% of the residents answered that the duration of inundation is from one to three days, and 28% experienced more than three days of inundation.

Table 4.3-25 Inundation Duration Report of Residents Who Experienced Flooding Only Once

Duration of Inundation	Number of Samples	Percentage (%)
30 min to 1 hour	6	14%
More than 1 hour	1	2%
Half day to 1 day	13	30%
1 to 3 days	11	26%
3 to 5 days	7	16%
More than 6 days	5	12%
Total	43	100%

Source: JICA Preparatory Study on Thilawa SEZ Infrastructure Development in the Republic of the Union of Myanmar (March 2014)

(3) Cyclone

Cyclones that originate from the Bay of Bengal generally move westward to India and then turn toward Bangladesh and Myanmar. Severe cyclones tend to occur either during the pre-monsoon season from April to May or the post-monsoon season from October to November.

Cyclones have three destructive forces, namely: i) storm surge, ii) heavy rainfall, and iii) strong winds. According to the "Hazard Profile of Myanmar", 1,248 tropical storms formed in the Bay of Bengal

⁶ JICA Preparatory Study on Thilawa SEZ Infrastructure Development in the Republic of the Union of Myanmar (March 2014)

during the period from 1887 to 2005, of which 80 storms (6.4% of the total) hit Myanmar's coast. In total, 12 cyclones caused severe damage in Myanmar mainly due to the accompanying storm surge, and the highest death or missing toll was at 138,373 caused by Cyclone Nargis in May 2008.

Cyclone Nargis also hit Greater Yangon and floodwater spread on a number of townships around Yangon City. Most of the inundated areas during Cyclone Nargis were the Dala, Twantay, Htantabin, and Hlegu areas.

(4) Earthquake

In the Bay of Bengal, west of Myanmar, there is the Andaman Trench, where the Indian Plate is moving northward and subducting underneath the Burma Plate from west to east. In east Myanmar, there is the Sagaing Fault, which is the boundary between the Burma Plate and Sunda Plate. Hence, a magnitude 7.0+ earthquake has occurred more than 16 times, and six earthquakes of around magnitude 7.0 hit the main cities along the Sagaing Fault such as Yangon, Bago, and Mandalay from 1930 to 1956. Significantly, Yangon experienced six huge earthquakes around the 1930s.

4.4 Results of Survey for Framework of Resettlement Works for the 2,000 ha

The Thilawa SEZ Management Committee (TSMC) released the Framework of Resettlement Works for the 2,000 ha⁷ Development Area of Thilawa Special Economic Zone (SEZ) (hereinafter referred to as the "Resettlement Framework for 2,000 ha") to the public in February 2016. The results of the detailed measurement survey, which was conducted to formulate the Resettlement Framework for 2,000 ha are summarized by areas such as industrial area, logistic area, and residence and commercial areas for the referential information of the following:

(1) Number of Households and Persons and Workers

Table 4.4-1 shows the number of project-affected households (PAHs), project-affected persons (PAPs) and workers. In total, 415 PAHs are estimated with the total of 1,629 persons. About 60 % of the total persons have income source from their work.

Table 4.4-1 Outline of PAHs/PAPs

Category	Households	Persons	No. of Workers
Industrial Area	161	611	295
Logistic Area	82	348	189
Residence and Commercial Area	172	670	435
Total	415	1629	919

Remark: The "Worker" in this analysis indicates a person who has income source.

Source: Thilawa SEZ Management Committee, Framework of Resettlement Works for the 2,000 ha Development Area of Thilawa Special Economic Zone (SEZ), February 2016

(2) Ethnicity and Religion

Table 4.4-2 shows the ethnicity and religion of PAHs. In total, around 82 % of the people are Burmese while around 15% are Indian. On the other hand, 90% are Buddhist and 8.2 % are Hindu.

.

⁷ 2,000 ha indicates the whole Thilawa SEZ excluded Zone A of 400 ha.

Table 4.4-2 Ethnicity and Religion of PAHs

Unit: households

Category		Ethnici	ty	Religion			
Category	Burma India		Others	Buddhist	Hindu	Others	
Industrial Area	131	24	6	141	16	4	
	(81.4%)	(14.9%)	(3.7%)	(87.6%)	(9.9%)	(2.5%)	
Logistic Area	61 (74.4%)	20 (24.4%)	(1.2%)	73 (89.0%)	9 (11.0%)	(0.0%)	
Residence and	150	16	6	157	9	6	
Commercial Area	(87.2%)	(9.3%)	(3.5%)	(91.3%)	(5.2%)	(3.5%)	
Total	342	60	13	371	34	10	
	(82.4%)	(14.5%)	(3.1%)	(89.4%)	(8.2%)	(2.4%)	

Source: Thilawa SEZ Management Committee, Framework of Resettlement Works for the 2,000 ha Development Area of Thilawa Special Economic Zone (SEZ), February 2016

(3) Literacy

Table 4.4-3 shows the literacy of PAHs. In total, around 46 % are able to speak, read, and write fluently while around 1 % cannot read and write.

Table 4.4-3 Literacy of People

Category	Not able to speak, read, and write		Able to speak, but not to read and write		Able to speak, but read and write a little		Speak, read and write fluently	
<u>.</u>	Households	%	Households	%	Households	%	Households	%
Industrial Area	3	1.9	22	13.9	58	36.7	75	47.5
Logistic Area	2	0.8	12	9.5	37	37.7	30	52.4
Residence and Commercial Area	0	0.0	18	10.5	69	40.4	84	49.1
Total	5	1.2	52	12.7	164	40.0	189	46.1

Remark: This information is not available at the five households in total.

Source: Thilawa SEZ Management Committee, Framework of Resettlement Works for the 2,000 ha Development Area of Thilawa Special Economic Zone (SEZ),) February 2016

(4) Major Income Source and Annual Income

Table 4.4-4 shows major income source and annual average of main income. Majority of the income sources are odd job workers, which dominate around 35 % to 45 % in each category. Average income is around 4,900,000 kyats/year.

Table 4.4-4 Major Income Source of Household Head

		Annual					
Category	Paddy Farmer	Vegetable Farmer	Odd Job Worker	Wage Worker	Self- Employed	Other	Average of Main Income (Kyats/year)
Industrial Area	14.3	12.9	37.4	5.4	19.7	10.2	4,864,427
Logistic Area	36.6	0.0	35.4	9.8	9.8	8.5	6,239,227
Residence and Commercial Area	15.2	5.8	45.0	5.3	14.0	14.6	4,293,660
Total	16.9	6.9	40.4	6.6	15.3	14.0	4,901,335

Remark

Source: Thilawa SEZ Management Committee, Framework of Resettlement Works for the 2,000 ha Development Area of Thilawa Special Economic Zone (SEZ), February 2016

(5) Vulnerable Households

The Resettlement Framework for 2,000 ha defines vulnerable households as household headed by women, disabled person, or elderly person (over 61 years old), a household including a disabled

^{1:} Amount of the income from main income source is according to the interview results.

^{2:} The information on the type of income source is not available at the 15 households in total.

^{3:} Annual average of main income is calculated based on the total amount of main income from all working members in a household.

person or a household below the poverty line⁸. Table 4.4-5 outlines vulnerable households in each category.

Table 4	4 4-5	Vulnerable Households	C

Category	Households Headed by Woman	Households Headed by Disable Person	Households Headed by Elderly	Households Below the Poverty Line	Households Including Members of Disabled Person	Total
Industrial Area	20	2	16	3	1	36
Logistic Area	9	0	7	2	9	26
Residence and Commercial Area	28	0	23	1	2	44
Total	57	2	46	6	12	106

Remark: Total number of vulnerable households is different from the sum of each category, because some HH fell into multiple categories.

Source: Thilawa SEZ Management Committee, Framework of Resettlement Works for the 2,000ha Development Area of Thilawa Special Economic Zone (SEZ), February 2016

4.5 Environmental Management Program in Thilawa SEZ ZoneA

(1) Environmental Monitoring

During the construction phase of Thilawa SEZ Development Project (Zone A), MJTD has conducted the environmental monitoring and submitted the report to TSMC in accordance with the Environmental Monitoring Plan of the EIA Report of Thilawa SEZ Development Project (Zone A), 2013.

The main environmental monitoring results during the construction of Thilawa SEZ Development Project (Zone A) are summarized in Table 4.5-1.

Table 4.5-1 Results of Monitoring of Thilawa SEZ Development Project (Zone A) during Construction

Survey item	Parameters	Summary of Result
Air Quality	- NO ₂ , SO ₂ , CO, TSP, PM10	Concentrations of all parameters were lower than the target
		ambient air quality level defined by EIA Thilawa SEZ
		Development Project (Zone A) during the monitoring period.
		Measured values (monitoring period means) are NO ₂ ; 0.02-0.04
		ppm, SO ₂ ; < 0.01 ppm, CO; 0.29-0.56 ppm, TSP; 0.05-0.19
		mg/m ³ , and PM ₁₀ ; 0.02-0.08 mg/m ³ .(as of June 2015)
Water Quality	- pH, SS, DO, BOD5, COD,	Monitoring points were set at several locations including upper
	Oil and Grease, Cr, Total	stream and downstream of the discharge point from Zone A.
	Coliforms	Based on the monitoring results, there was no significant
		difference of water quality among different points.
Noise	- Noise level	Noise level monitoring locations were set near the monasteries,
		university, and along the road. During the monitoring period,
		noise level at each monitoring point was lower than the target
		noise level.
Ground Subsidence	- Ground elevation	Based on the periodic monitoring, there was no significant change
	- Consumption of	in the ground elevation due to groundwater usage.
	groundwater amount	
Accident	- Existence of accident	No accidents nor incidents happened during the monitoring
		period.

Source: Environmental Monitoring Report, MJTD

_

⁸ Integrated Household Living Conditions and Survey in Myanmar (2009-2010) was conducted by UNDP, UNICF, SIDA and the Ministry of National Panning and Economic Development, and survey result was publicized as Poverty Profile in June 2011. Poverty line as of 2010 was defined as 376,151 kyats per adult equivalent per year in Poverty Profile, and this amount is referred as poverty line in many reports. This framework also regards 376,151 kyats per adult equivalent per year as the poverty line.

(2) Environmental Mitigation Measurement

MJTD has been conducting the environmental mitigation measurements in accordance with the Environmental Management Plan of the EIA Report of Thilawa SEZ Development Project (Zone A), 2013. Some of the mitigation measurements are as follows:



Sprinkler Truck



Tentative Drainage (to prevent soil erosion)



Retention Canal Source: MJTD and EIA Study Team



Planting Trees

Figure 4.5-1 Samples of Environmental Mitigation Measurement

CHAPTER 5: SCOPING AND TERMS OF REFERENCE FOR ENVIRONMENTAL IMPACT ASSESSMENT

5.1 Procedure of Scoping for Environmental and Social Impact Assessment

In order to assess the likely significant environmental and social impacts, potential environmental and social impacts of the Project were preliminary identified based on the project description and overall environmental and social conditions in and around Zone B. The impacts of pollution, natural environment and social environment, health and safety, emergency risk, and others were classified as A to D in accordance with the following criteria, assuming no specific measures toward the impacts are taken:

1) A-: Significant negative impact A+: Significant positive impact

2) B-: Some negative impact B+: Some positive impact

3) C: Impacts are not clear, need more investigation

4) D: No impact or impacts are negligible, no further study required

5.2 Results of Scoping for Environmental and Social Impact Assessment

Results of the scoping for environmental and social impact assessment are shown in Table 5.2-1. Scoping was conducted toward the development project in the industrial area of Zone B. These impacts were evaluated in each of the three phases separately, namely: pre-construction/construction phase, operation phase and closing phase. Even though the Project does not plan to close in the near future, the impact at the closing phase was estimated in case the Project should be closed due to unanticipated cases such as when the tenants in the industrial area terminate the operation of their business or when the industrial area will close after completion of the period for lease agreement.

Table 5.2-1 Results of Scoping for Environmental and Social Impact Assessment (Pre-Construction/Construction Phase (PC/CO), Operation Phase (OP) and Closing Phase (CLP))

Catagami	Cooning Itom		luatio	n	Desgang for Coming Evolution
Category	Scoping Item	PC/CO	OP	CLP	
Pollution	Air Quality	B-	B-	B-	CO/CLP: Impact on air quality due to operation of construction machineries
					and traveling of construction vehicles is expected.
					OP: Impact on air quality due to increase of vehicle traffic caused by the
					operation of the industrial area is expected. Exhaust gases would be
					generated from the tenants.
	Water Quality	B-	B-	B-	CO/CLP: Impact on water quality from muddy water flowing to the river due
					to land reclamation work is expected.
					OP: Impact on water quality of the surrounding water bodies is expected due
					to wastewater generated from the tenants.
	Waste	B-	B-	B-	CO: Construction waste soil will not be generated according to the
					construction plan. Waste would be generated from construction workers.
					OP: Industrial waste would be generated from the tenants.
					CLP: Demolition waste and waste from construction workers would be
					generated.
	Soil	B-	B-	B-	CO: Soil contamination would be diffused if the soil in the Project site is
	Contamination				originally contaminated.
					OP: Soil contamination would occur due to the inadequate operation of the
					tenants.
					CLP: Soil contamination would be diffused if the site becomes contaminated
					at the closing point.

C-4	G	Eva	luatio	n	Decree for Combactor
Category	Scoping Item	PC/CO	OP	CLP	Reasons for Scoping Evaluation
	Noise and Vibration	B-	В-	В-	CO/CLP: Increase of noise and vibration levels due to construction machineries and traveling of construction vehicle would temporarily
					occur. OP: Increase of noise and vibration levels due to the traveling of vehicle traffic and operation of the tenants would occur.
	Ground Subsidence	D	D	D	CO: Groundwater will be used during construction phase however, no impact is expected because there was no change of ground elevation as monitored by the Zone A Project and the same kind of construction
	200 1 01				works will be conducted in the project area. OP/CLP: No activities are planned that will cause ground subsidence.
	Offensive Odor	D	В-	D	CO/CLP: There is no factor to cause offensive odor OP: There is a possibility that offensive odor would be generated from some tenants.
	Bottom Sediment	D	В-	D	CO/CLP: No construction works are planned that will cause impact on bottom sediment. OP: Bottom sediment of the surrounding water bodies would be deteriorated
Natural Environment	Protected Areas	D	D	D	by wastewater generated from the tenants. Since no natural preservation area and national parks exist in and around Zone B, impact on protected areas is not expected.
Liiviioiiiieit	Flora/Fauna and Ecosystem	С	С	С	Since there is inadequate information about flora and fauna living in the development area, field survey will be done.
	Hydrology	В-	В-	В-	CO/CLP: Impact on hydrology is temporarily expected caused by land modification. OP: Impact on hydrology is expected caused by the existence of development
	Topography and Geology	D	D	D	area. CO/CLP: Since there is no unique topography and geology in this area, no impact caused by the construction is expected. OP: No activities are planned that will cause impact on topography and
	Soil Erosion	B-	B-	В-	geology. CO/CLP: Soil erosion would occur due to land reclamation work. OP: Drainage water from the industrial area will be discharged to Shwe
Social environment	Involuntary Resettlement	A-	A-	D	Pyauk Creek. This would cause the creek to erode. PC: Land acquisition will be required partially and some scale of involuntary resettlement is expected.
					OP: Impact on the livelihood of relocated households is expected. CLP: Since there is no residential area, involuntary resettlement will not be expected.
	Living and Livelihood	A-/B+		С	PC/CO: PAHs who earn income from paddy fields and/or vegetable fields might lose their income source. On the other hand, increase of job opportunity as construction workers or commercial opportunity targeted to the workers is expected. OP: Impact on the livelihood of relocated households is expected. On the other hand, increase of job opportunity as workers of the tenants or commercial opportunity targeted to these workers is expected. CLP: The possibility and conditions of the tenants in the industrial area is not clear during closing phase, although some workers would lose their income source in case of the closure of the industrial area.
	Vulnerable Group	A-/B+	A-/B+	D	 PC/CO: Vulnerable people in the project area would be affected. On the other hand, job opportunity and commercial opportunity would increase. OP: Vulnerable people would not be able to receive the benefits of the Project. On the other hand, job opportunity as workers of the tenants and commercial opportunity would increase. CLP: There is no factor to cause negative impact on vulnerable group.
	Local Conflict of Interest	A-	A-	D	PC/CO/OP: Local conflict of interest would happen if job opportunity increased by the Project is misdistributed to the community. In addition, conflict of interest would occur between the relocated households and the host community, or PAHs of Zone A and those of the Project. CLP: There is no factor to cause the local conflict of interest.
	Misdistribution of Benefit and Damage	B-	B-	D	PC/CO/OP: Misdistribution of benefits and damages would occur since there are PAHs who lose their income source, while there are people who would get job opportunity as construction workers and workers of the tenants. CLP: There is no factor to cause the misdistribution of benefits and damages.

G 4	Scoping Item	Evaluation		n	Reasons for Scoping Evaluation
Category		PC/CO OP CLP			
	Children's Right	В-	B-/B+		PC/CO/OP: Due to the relocation, children's education would be temporarily disrupted. On the other hand, children would be indirectly influenced by the improvement of social infrastructure in the region as a result of the
		D (D	D (D		Project. CLP: There is no activity that will cause impact on children's right.
	Existing Social Infrastructures and Services	B-/B+	B-/B+	D	CO: Traffic congestion due to increase of construction vehicles is expected. Accessibility to school, hospital, and shops would be changed for PAHs. On the other hand, social infrastructures would be improved in and around the project area. OP: Accessibility to school, hospital, and shops would be changed for PAHs.
					On the other hand, positive impact is expected by the development of traffic network and improvement of social infrastructure related to the Project. CLP: There is no factor to cause the negative impact on the existing social infrastructures and services.
	Water Usage	С	С	D	Since existing information of water usage is not enough and the detailed plan of water usage has not been prepared, the impact on water usage is not clear.
	Cultural Heritage/Asset	B-	D	D	Two areas of the cemetery found in the development area would be affected by the development.
	Landscape	D	B-/B+	D	OP: Landscape would be changed by semi-urbanization of the Project area and its surrounding area.
Health and Safety	Risks for Infectious Disease such as AIDS/HIV	В-	В-	В-	CO/CLP: There is a possibility to increase the risks of infectious diseases due to influx of construction workers into the Project area. OP: There is a possibility to increase the risks of infectious diseases due to influx of workers of the tenants and the semi-urbanization of the Project
	Occupational	B-	B-	B-	area and its surrounding area. CO/CLP: Impact on the working conditions of workers is expected.
	Health and Safety	-	-	D	OP: Impact on the working conditions of workers of the tenants is expected.
	Community Health and Safety	B-	В-	В-	CO/CLP: Impacts on community health and safety are expected due to influx of construction workers, increase of vehicle traffic, and operation of construction machineries. OP: Impacts on community health and safety are expected due to influx of workers, increase of vehicle traffic, and semi-urbanization of the Project area and its surrounding area.
	Usage of Chemicals	D	В-	D	CO/CLP: There is no plan to use chemicals during the construction phase. OP: There is a possibility that some chemicals would be used by the tenants during the operation phase.
Emergency Risk	Flood Risk Risk of Fire	B- B-	B- B-	B- B-	There is a possibility of flood caused by rainstorm and cyclone. CO/CLP: There is a possibility for the risk of fire to increase due to the construction work. OP: There is a possibility for the risk of fire to increase due to economic activities.
	Earthquake	В-	В-	В-	CO/CLP: There is a possibility that structures for construction works would collapse if earthquake occurs. OP: There is a possibility that buildings and structures in the industrial area would collapse if earthquake occurs.
Other	Global Warming	В-	В-	B-/ B+	CO: Emission of greenhouse gases (GHGs) would be generated from construction machineries and vehicle traffic due to the Project. OP: Emissions of GHGs would be generated from vehicle traffic due to the Project and the operation of tenants. CLP: Emission of GHGs would be generated from construction machineries and vehicle traffic caused by the Project. On the other hand, emissions of GHGs would be reduced from operation activities.

Evaluation: A-: Significant Negative Impact

A+: Significant Positive Impact

B-: Some Negative Impact B+: Some Positive Impact

C: Impacts are not clear, need more investigation

D: No impacts or impacts are negligible, no further study is required

Source: EIA Study Team

The project proponent does not expect to close and terminate the operation of industrial activities at this moment. On the other hand, in case closure and termination of tenants in the industrial area of Zone B will occur, the tenants will take necessary environmental mitigation measures. The project

proponent will confirm their performance of environmental mitigation measures especially in soil remediation and treatment of chemical and hazardous substances after termination of the tenant.

5.3 Terms of Reference for Environmental Impact Assessment

Investigation of environmental impact assessment will be conducted for the environmental and social contents that would be affected by the project implementation as shown above. The survey for involuntary resettlement will be implemented by the Government of Myanmar and the results will be provided.

As to the terms of reference (TOR) for investigation of environmental impact assessment, the survey items and method of each impact evaluation item, which was identified as A, B, or C by scoping as described in Section 5.1, are shown in Table 5.3-1. Among the items of this survey, baseline values of air quality, water quality, soil quality, noise level, flora/fauna, cultural heritage and hydrology are being confirmed through laboratory analysis and field survey.

5.3.1 Field Survey Methodology

In order to forecast and evaluate the environmental and social impacts caused by the Project appropriately, the following field survey is planned to be conducted.

Table 5.3-1 Field Survey Methodology

Field Survey	Location of Survey Point	Period	Survey Items and Methods
Air Quality	3 spots	2 times (Rainy Season	Survey Items
	(see Figure 5.3-1)	and Dry Season)	1) Nitrogen dioxide (NO ₂), 2) Nitrogen monoxide (NO), 3)
		Continuously for 1	Sulfur dioxide (SO ₂), 4) Carbon monoxide (CO), 5) PM2.5, 6)
		week (7 days)	PM10
			Survey Methods
			USEPA reference methods or equivalent methods
Water Quality	For surface water	Surface water:	Survey Items
(Surface Water	: 5 spots	2 times (Rainy Season	For surface water:
and	For groundwater	and Dry Season, total	1) Temperature, 2) pH, 3) Dissolved oxygen (DO),
Groundwater)	: 2 spots	13 samples)	4) Electrical conductivity (EC), 5) Odor, 6) Color,
	(see Figure 5.3-1)	Groundwater:	7) Hardness, 8) Suspended solid (SS), 9) BOD ₅ ,
		2 times (Total 4	10) COD, 11) Total nitrogen, 12) Total phosphorous,
		samples)	13) Oil and grease, 14) Arsenic (As), 15) Mercury (Hg), 16)
			Lead (Pb), 17) Cadmium (Cd), 18) Hexavalent chromium
			(Cr(VI)), 19) Copper (Cu), 20) Zinc (Zn),
			21) Manganese (Mn) 22) Nickel (Ni), 23) Iron (Fe),
			24) Cyanide (free and total), 25) Fluoride, 26) Nitrates
			(NO ₃ -N), 27) Ammonium nitrogen (NH ₄ -N), 28) Total
			coliform, 29) Nitrite (NO ₂ -N), 30) Barium,
			31) Selenium, 32) Formaldehyde, 33) Phenol,
			34) Sulfide, 35) Chlorine
			For groundwater:
			1) Temperature, 2) Odor, 3) Color, 4) Electrical conductivity,
			5) Hardness, 6) pH, 7) BOD5, 8) SS, 9) DO, 10) COD, 11)
			Total nitrogen, 12) Total phosphorous, 13) Oil and grease, 14)
			Turbidity 15) Arsenic (As), 16) Mercury (Hg), 17) Lead (Pb),
			18) Cadmium (Cd), 19) Hexavalent chromium (Cr(VI)), 20)
			Copper (Cu), 21) Zinc (Zn), 22) Manganese (Mn) 23) Nickel
			(Ni), 24) Iron (Fe), 25) Cyanide (CN), 26) Fluoride, 27)
			Nitrates (NO ₃ -N, NO ₂ -N), 28) Ammonium nitrogen (NH4-N),
			29) Total coliform

Field Survey	Location of Survey Point	Period	Survey Items and Methods
			Survey Methods
			International standard methods or equivalent methods
Noise and	Roadside: 2 spots	One time (Dry Season)	Survey Items
Vibration Level	(noise and	at 5 points for 24 hours	1) Environmental/roadside noise level : LAeq (dB)
	vibration)	duration of weekday	(A-weighted loudness equivalent),
	Environment: 3	and 24 hours of	2) Roadside vibration level :Lv
	spots (noise)	weekend	Survey Methods
	(see Figure 5.3-1)		International standard methods or equivalent methods
Traffic Volume	Two sections, Same as the noise and vibration roadside survey (see Figure 5.3-1)	24 hours duration of weekday and 24 hours of weekend	Survey Items Number of vehicles. Vehicles are classified into four types:1) Motorbike, 2) Ordinary vehicle, 3) Heavy vehicles, and 4) Others (Tractor and others) Survey Methods Manual count
Soil	3 spots (see Figure5.3-1)	Dry Season: 1 time	Survey Items 1) Mercury (Hg), 2) Arsenic (As), 3) Lead (Pb), 4) Cadmium (Cd), 5) Copper (Cu), 6) Zinc (Zn), 7) Chromium (Cr VI), 8) Iron (Fe), 9) Manganese (Mn) Survey Methods International standard methods or equivalent methods
Flora and Fauna	Thilawa SEZ area	Rainy Season:	Survey Methods
	and its	1 time (List of Flora	1) Interview survey
	surrounding area	and Fauna)	2) Plot survey and line census survey
	(about 1.0 km in	Dry Season:	Survey Result to be prepared
	various	1 time (List of Flora	List of flora and fauna, vegetation maps in Thilawa SEZ and
	directions)	and Fauna, and	its surrounding area
	(see Figure 5.3-2)	Vegetation Maps)	
Cultural Assets	Zone B site and	One time	Survey Methods
	its surrounding		1) Interview survey
	area		2) Field observation
Hydrology	Zone B and its	One time	Survey Methods
(Topography)	surrounding area		1) Interview survey
	(about 500 m in		2) Field observation
	various		
	directions)		

Source: EIA Study Team




Figure 5.3-1 Field Survey Spots for Air, Water, Soil, Noise/Vibration and Traffic Volume




Figure 5.3-2 Field Survey Area (Flora and Fauna)

5.3.2 Methodology of Forecast and Evaluation

Based on the current situation of environmental and social condition collected through the existing materials and field survey, the contents and volume of the environmental and social impacts caused by the Project will be forecasted and evaluated. The basic concept of forecast and evaluation methodology is shown in Table 5.3-2.

Table 5.3-2 Basic Concept of Forecast and Evaluation Methodology

Content	Item	Methods of Forecast and Evaluation		
Pollution	Air Quality	CO/CLP: Impact on air quality along the roadside is qualitatively forecasted and evaluated based on the results of the field survey and the estimated number of construction vehicles. Impact on air quality caused by the operation of construction machineries is qualitatively forecasted and evaluated. OP: Impact on air quality along the roadside is quantitatively forecasted and		
		evaluated based on the results of the field survey and estimated number of vehicles. Impact on air quality caused by the generation of effluent gas from the tenants in the industrial area is qualitatively forecasted and evaluated with reference to the generating condition of effluent gas from similar facilities.		
	Water Quality	CO/CLP: Generation of water pollutant and its impact is qualitatively forecasted and evaluated based on the results of the field survey and the construction method estimated from similar cases. OP: Occurrence of water pollutant is quantitatively forecasted and evaluated		
	Waste	based on the results of the field survey and existing data. CO: Impact of waste generation from construction workers is qualitatively forecasted and evaluated with reference to the current condition of waste collection and disposal and similar cases.		
		OP: Impact of waste generation (domestic waste, industrial waste, and hazard waste) is qualitatively forecasted and evaluated with reference to the current condition of waste collection and disposal, and similar cases. CLP: Volume of demolition waste is qualitatively forecasted based on similar		
	Soil Contamination	cases. CO/CLP: Impact is qualitatively forecasted and evaluated based on the result of the field survey, existing data, and similar cases. OP: Impact is qualitatively forecasted and evaluated referring to the management situation of pollutants and amount generated by similar kinds of tenants.		
	Noise and Vibration	CO/CLP: Noise and vibration along the roadside are qualitatively forecasted based on the results of the field survey and estimated number of construction vehicles. Noise and vibration increase due to the operation of construction machineries is qualitatively forecasted and evaluated. OP: Equivalent sound level along the roadside is quantitatively forecasted and evaluated based on the results of the field survey and estimated number of vehicles generated by the Project. Noise and vibration increase due to the operation of tenants and relevant facilities is qualitatively forecasted and evaluated.		
	Offensive Odor	OP: Impact is qualitatively forecasted and evaluated based on existing data and similar cases.		
	Bottom Sediment	OP: Impact is qualitatively forecasted and evaluated based on existing data and similar cases.		
Natural	Flora/Fauna and Ecosystem Hydrology	Impact is qualitatively forecasted and evaluated based on the results of the field survey, existing data, and reference to the project plan and similar cases. Impact is qualitatively forecasted and evaluated based on existing data and similar		
	Soil Erosion	cases. Impact is qualitatively forecasted and evaluated based on the site investigation and project plan.		
Social	Involuntary Resettlement	Number of PAHs and their properties are quantitatively estimated. The impact is qualitatively forecasted based on the results of the detailed measurement survey provided by TSMC.		
	Living and Livelihood	Impact is qualitatively forecasted and evaluated based on the information about livelihoods of PAHs provided by TSMC, existing data, and similar cases.		
	Vulnerable Group (Gender, Poor, Disabled People)	Impact is qualitatively forecasted and evaluated based on the information about the vulnerable group provided by TSMC, existing data, and similar cases.		
	Local Conflict of Interest	Possibility that local conflict of interest would happen is qualitatively forecasted and evaluated based on the current situation and similar cases.		

Content	Item	Methods of Forecast and Evaluation
	Misdistribution of	Possibility that misdistribution of benefits and damages would occur is qualitatively
	Benefit and Damage	forecasted and evaluated based on the current situation and similar cases.
	Children's Right	Possibility of disruption of children's education and indirect influence to children
		by improvement of social infrastructure is qualitatively forecasted and evaluated
		based on the current situation and similar cases.
	Existing Social	Impact is qualitatively forecasted and evaluated based on the existing situation of
	Infrastructure and Services	social infrastructure, existing data and similar cases.
	Water Usage	Impact is qualitatively forecasted and evaluated based on existing data and similar cases.
	Cultural Heritage/	Impact is qualitatively forecasted and evaluated based on the result of interview
	Asset	survey and field observation.
	Landscape	Impact is qualitatively forecasted and evaluated based on the result of field
		observation and facility plan.
Health	Risks for Infectious	Impact is qualitatively forecasted and evaluated with reference to the construction
and Safety	Diseases such as AIDS/HIV	plan and similar cases.
	Occupational Health and Safety	Impact is qualitatively forecasted based on the construction plan and similar cases.
	Community Health	Impact is qualitatively forecasted and evaluated with reference to the
	and Safety	construction/operation plan and similar cases.
	Usage of Chemicals	Impact is qualitatively forecasted and evaluated based on existing data and similar cases.
Risk	Flood Risk	Impact is qualitatively forecasted and evaluated based on the results of the field
		observation, interview with the relevant organizations and people, and existing data.
	Risk of Fire	Impact is qualitatively forecasted and evaluated based on existing data and similar
		cases.
	Earthquake	Impact is qualitatively forecasted and evaluated based on existing data and similar
		cases.
Other	Global Warming	Impact is qualitatively forecasted and evaluated based on existing data and similar
		cases.

Note: PC: Pre-Construction, CO: Construction Phase, OP: Operation Phase, CLP: Closing Phase Source: EIA Study Team

CHAPTER 6: FIELD SURVEY

6.1 Air Quality

6.1.1 Survey Item

The parameters for air quality survey were SO₂, NO₂, NO, CO, PM_{2.5}, and PM₁₀.

NO was measured as the reference parameter to grasp the balance of NO₂ and NO at different three conditions, since NO₂ is generated by oxidizing NO in accordance with the time and distance from exhaust gas sources (e.g. chimney of combustion facility, vehicles, etc.) in ambient air.

6.1.2 Survey Location

The air quality survey was carried out during both the dry season and the rainy season. There were three survey sites corresponding to two kinds of environment. AQ-1 and AQ-2 were located along the road, while AQ-3 was placed inside the paddy field. The details of the location of air quality survey points are presented in Table 6.1-1 and Figure 6.1-1.




Figure 6.1-1 Location of Air Quality Survey Station

In consideration of the estimated future trip distribution and transportation route from/to Thilawa SEZ (as shown in Figure 7.2-2) and land use, two survey locations along the road were selected in order to measure current baseline data and to forecast the future impact.

Table 6.1-1 Location of Air Quality Survey Station

Survey Point	Coordinates	Type of Survey Point	Detailed Description of Survey Point
AQ-1	16°43′17.6″N, 96°15′48.3″E	Along the road	Beside the Thanlyin-Thilawa Road and near Kyaikkhauk Pagoda, Thanlyin Township
AQ-2	16°40′49.6″ N, 96°17′53.2″E	Along the road	Beside the Dagon-Thilawa Road, Thanlyin Township
AQ-3	16°39′13.6″ N, 96°16′50.6″E	Paddy field	East of Phalan Ywa Haung Monastery, Kyauktan Township

Source: EIA Study Team

(1) AQ-1 (along the road)

This station was installed in a flat area, located beside Thanlyin-Thilawa Road and about 1.5 km away from the junction of Thanlyin-Thilawa Road and Thanlyin-Kyauktan Road. The Thilawa SEZ development areas are located southwest of this station. As there are no residential houses or buildings nearby this station, the possible emission source is mostly from running vehicles on Thanlyin-Thilawa Road, as shown in Figure 6.1-2.



Source: EIA Study Team

Figure 6.1-2 Air Quality Survey at AQ-1

(2) AQ-2 (along the road)

This station was also installed in a flat area, located beside Thilawa Road and about 1.3 km away from the junction of Dagon-Thilawa Road and Thanlyin-Kyauktan Road. The industrial area of Thilawa SEZ Zone B is located southwest of AQ-2 and the Thilawa SEZ Zone A area lies to the west of the station. Htamalone Village is situated about 3 km to the north of the station. As there are no residential houses or buildings nearby this station, the possible emission source is mostly from running vehicles on Dagon-Thilawa Road and vehicles used for construction activities in Zone A, as shown in Figure 6.1-3.



Figure 6.1-3 Air Quality Survey at AQ-2

(3) AQ-3 (paddy field)

This station was installed in a paddy field located to the east of the monastery compound of Old Phalan Village, Kyauktan Township. The New Phalan Village area is situated about 1 km to the east of AQ-3. The surrounding area of AQ-3 is paddy field with few residential houses, as shown in Figure 6.1-4. AQ-3 is located just outside of the industrial area of Zone B. Possible emission sources are from human activities in nearby villages.



Source: EIA Study Team

Figure 6.1-4 Air Quality Survey at AQ-3

6.1.3 Survey Period

Air quality survey was conducted for seven consecutive days during the rainy season (September to October 2015) and dry season (December 2015). The measurement duration is shown in Table 6.1-2.

Table 6.1-2 Sampling Duration for Air Quality Survey

Sampling Point	Rainy Season	Dry Season
AQ-1	30 (Wed) September - 7 (Wed) October 2015	10 (Thu) - 17 (Thu) December 2015
AQ-2	30 (Wed) September - 7 (Wed) October 2015	10 (Thu) - 17 (Thu) December 2015
AQ-3	30 (Wed) September - 7 (Wed) October 2015	10 (Thu) - 17 (Thu) December 2015

6.1.4 Survey Method

Sampling and analysis of ambient air quality were conducted by referring to the recommendation of the United States Environmental Protection Agency (U.S. EPA). The Haz-Scanner Environmental Perimeter Air Station (EPAS) was used to collect ambient air survey data. Sampling rate or air quality data were measured automatically every one minute and directly read and recorded onsite for measured parameters (SO₂, NO₂, NO, CO, PM₁₀, PM_{2.5}) as shown in Table 6.1-3. Sampling pump was operated at 2 L/min. Different analysis methods are integrated in the instrument, such as Particulates 90° Infrared Light Scattering for particulate matters (PM₁₀, PM_{2.5}) and electrochemical sensors for toxic gases (CO, NO₂, NO, SO₂).

Table 6.1-3 Sampling and Analysis Method for Air Quality

No.	Parameter	Analysis Method
1	Sulfur dioxide (SO ₂)	On site reading
2	Nitrogen dioxide (NO ₂)	On site reading
3	Nitrogen monoxide (NO)	On site reading
4	Carbon monoxide (CO)	On site reading
5	Particulate matter 2.5 (PM _{2.5})	On site reading
6	Particulate matter 10 (PM ₁₀)	On site reading

Source: EIA Study Team

6.1.5 Survey Result

The air quality survey results obtained every minute at each survey site were combined to make daily average values (24 hours) for further evaluation and comparison with corresponding standard values.

(1) AQ-1 (along the road)

Results of ambient air quality measured at AQ-1 are presented in Table 6.1-4. It is obvious that the concentrations of NO_2 , CO, and especially $PM_{2.5}$ and PM_{10} during the dry season were higher than those during the rainy season. Comparing with the tentative target value, the concentration of all pollutants except SO_2 during the rainy season complied with the standard. During the dry season, concentrations of NO_2 and CO were lower than the standard, whereas SO_2 , $PM_{2.5}$ and PM_{10} measured for one week exceeded the tentative target value.

Table 6.1-4 Ambient Air Quality (Daily Average) at AQ-1

Season	Date	SO_2	NO ₂	NO	CO	PM _{2.5}	PM ₁₀
Season	Date	ppm	ppm	ppm	ppm	mg/m ³	mg/m ³
	30 Sep-1 Oct	0.022	0.042	0.171	0.33	0.021	0.021
	1-2 Oct	0.030	0.036	0.309	0.32	0.020	0.026
	2-3 Oct	0.030	0.036	0.287	0.31	0.021	0.022
Rainy	3-4 Oct	0.020	0.041	0.262	0.28	0.016	0.023
	4-5 Oct	0.014	0.040	0.240	0.25	0.014	0.016
	5-6 Oct	0.015	0.025	0.187	0.20	0.015	0.018
	6-7 Oct	0.016	0.025	0.215	0.23	0.012	0.016
	10-11 Dec	0.013	0.037	0.025	0.37	0.068	0.069
	11-12 Dec	0.017	0.047	0.024	0.60	0.077	0.086
	12-13 Dec	0.014	0.047	0.032	0.64	0.115	0.126
Dry	13-14 Dec	0.016	0.045	0.029	0.48	0.076	0.088
	14-15 Dec	0.017	0.043	0.042	0.63	0.080	0.083
	15-16 Dec	0.020	0.046	0.034	0.62	0.087	0.091
	16-17 Dec	0.012	0.050	0.035	0.52	0.093	0.096
Tentative Target Value		0.02 mg/m ³ (0.008 ppm)	0.1 mg/m ³ (0.05 ppm)	-	10.26 mg/m ³ (9 ppm)	0.025 mg/m ³	0.05 mg/m ³

(2) AQ-2 (along the road)

Results of ambient air quality measured at AQ-2 are presented in Table 6.1-5. The concentrations of PM_{10} and CO during the dry season were higher than those during the rainy season. Comparing with the tentative target value, concentrations of CO and $PM_{2.5}$ were lower than the standard in both rainy and dry seasons, while concentrations of SO_2 measured for one day in rainy season and two days during the dry season, concentrations of NO_2 measured in one day during the rainy season, and concentration of PM_{10} measured for three days during the dry season exceeded the tentative target value.

Table 6.1-5 Ambient Air Quality (Daily Average) at AQ-2

Coogen	Date	SO ₂	NO ₂	NO	CO	PM _{2.5}	PM_{10}
Season	Date	ppm	ppm	ppm	ppm	mg/m ³	mg/m ³
	30 Sep-1 Oct	0.006	0.037	0.032	0.22	0.020	0.018
	1-2 Oct	0.009	0.029	0.059	0.23	0.013	0.028
	2-3 Oct	0.006	0.030	0.071	0.18	0.012	0.017
Rainy	3-4 Oct	0.005	0.031	0.031	0.16	0.012	0.013
	4-5 Oct	0.005	0.034	0.026	0.16	0.012	0.011
	5-6 Oct	0.007	0.033	0.015	0.18	0.012	0.012
	6-7 Oct	0.006	0.061	0.493	0.13	0.018	0.017
	10-11 Dec	0.010	0.031	0.042	0.24	0.010	0.040
	11-12 Dec	0.007	0.036	0.053	0.36	0.011	0.040
	12-13 Dec	0.006	0.037	0.027	0.37	0.017	0.055
Dry	13-14 Dec	0.005	0.036	0.071	0.30	0.013	0.048
	14-15 Dec	0.010	0.031	0.025	0.41	0.009	0.053
	15-16 Dec	0.005	0.048	0.073	0.39	0.022	0.035
	16-17 Dec	0.005	0.036	0.024	0.36	0.008	0.054
Tentative Target Value		0.02 mg/m ³ (0.008 ppm)	0.1 mg/m ³ (0.05 ppm)	-	10.26 mg/m ³ (9 ppm)	0.025 mg/m ³	0.05 mg/m ³

Source: EIA Study Team

(3) AQ-3 (paddy field)

Results of ambient air quality measured at AQ-3 are presented in Table 6.1-6. It is obvious that the concentrations of all contaminants during the dry season were higher than those during the rainy season. Comparing with the tentative target value, the concentration of all pollutants during the rainy season complied with the standard. During the dry season, concentrations of CO were lower than the standard, whereas SO_2 measured for two days, NO_2 measured for six days, PM2.5 and PM_{10} for one week exceeded the tentative target value.

Table 6.1-6 Ambient Air Quality (Daily Average) at AQ-3

Sagan	Season Date		NO ₂	NO	CO	PM _{2.5}	PM ₁₀
Season	Date	ppm	ppm	ppm	ppm	mg/m ³	mg/m ³
	30 Sep-1 Oct	0.0006	0.038	0.027	0.10	0.006	0.012
	1-2 Oct	0.0036	0.034	0.043	0.15	0.016	0.033
	2-3 Oct	0.0036	0.030	0.008	0.11	0.007	0.016
Rainy	3-4 Oct	0.0005	0.030	0.002	0.09	0.005	0.012
	4-5 Oct	0.0010	0.025	0.031	0.09	0.004	0.015
	5-6 Oct	0.0018	0.027	0.021	0.14	0.005	0.017
	6-7 Oct	0.0026	0.032	0.004	0.16	0.008	0.020
	10-11 Dec	0.0147	0.050	1.008	0.18	0.033	0.099
	11-12 Dec	0.0030	0.062	1.013	0.19	0.043	0.106
	12-13 Dec	0.0040	0.066	0.736	0.24	0.057	0.161
Dry	13-14 Dec	0.0043	0.064	0.764	0.20	0.045	0.171
	14-15 Dec	0.0082	0.059	1.194	0.18	0.048	0.099
	15-16 Dec	0.0064	0.064	1.186	0.22	0.049	0.118
	16-17 Dec	0.0072	0.057	1.002	0.24	0.057	0.097
Tentative	Tentative Target Value		0.1 mg/m ³ (0.05 ppm)	-	10.26 mg/m ³ (9 ppm)	0.025 mg/m ³	0.05 mg/m ³

6.2 Water Quality

6.2.1 Survey Item

Parameters for surface water and groundwater survey are shown in Table 6.2-1.

Table 6.2-1 Parameters for Water Quality Survey

NT.	T4	Associated a Model of	Water (Quality
No.	Item	Analysis Method	Surface Water	Groundwater
1	Temperature	HI7609829-1 Sensor	✓	✓
2	pH	HI7609829-1 Sensor	✓	✓
3	Dissolved Oxygen (DO)	HI7609829-2 Sensor	√ (*)	~
4	Electrical Conductivity (EC)	HI7609829-4 Sensor	✓	✓
5	Odor	In-situ	√ (*)	✓
6	Color	APHA Platinum Cobalt Unit	√ (*)	✓
7	Hardness	EDTA Titrimetric Method	√ (*)	✓
8	Suspended Solids (SS)	Gravimetric Method	√ (*)	✓
9	BOD ₅	5210B. 5 Days BOD Test	√ (*)	✓
10	COD	Close Reflux, Titrimetric Method	√ (*)	✓
11	Total Nitrogen	APHA-AWWA-WEF Method	√ (*)	✓
12	Total Phosphorous	APHA-AWWA-WEF Method	√ (*)	✓
13	Oil & Grease	APHA-AWWA-WEF Method	✓	✓
14	Arsenic (As)	AAS – Graphite Hydride Method	√ (*)	✓
15	Mercury (Hg)	APHA-AWWA-WEF Method	√ (*)	✓
16	Lead (Pb)	AAS – Graphite Furnace Method	√ (*)	✓
17	Cadmium (Cd)	APHA-AWWA-WEF Method	√ (*)	✓
18	Chromium (hexavalent)	AAS – Graphite Furnace Method	√ (*)	✓
19	Copper (Cu)	AAS – Graphite Furnace Method	√ (*)	✓
20	Zinc (Zn)	AAS – Graphite Furnace Method	√ (*)	✓
21	Manganese (Mn)	AAS – Graphite Furnace Method	✓	✓
22	Nickel (Ni)	APHA-AWWA-WEF Method	√ (*)	✓
23	Iron (Fe)	AAS – Graphite Furnace Method	√ (*)	✓
24	Cyanide (CN)	APHA-AWWA-WEF Method	√ (*)	✓
25	Fluoride	APHA-AWWA-WEF Method	√ (*)	√

No.	Item	Analysis Mathad	Water C	uality
110.	Item	Analysis Method	Surface Water	Groundwater
26	Nitrate	APHA-AWWA-WEF Method	√ (*)	✓
27	Ammonium nitrogen	APHA-AWWA-WEF Method	√ (*)	✓
28	Total Coliform	APHA-AWWA-WEF Method	√ (*)	✓
29	Nitrite (*)	APHA-AWWA-WEF Method	√ (*)	
30	Barium (*)	APHA-AWWA-WEF Method	√ (*)	
31	Selenium (*)	APHA-AWWA-WEF Method	√ (*)	
32	Formaldehyde (*)	APHA-AWWA-WEF Method	√ (*)	
33	Phenol (*)	APHA-AWWA-WEF Method	√ (*)	
34	Sulfide (*)	APHA-AWWA-WEF Method	√ (*)	
35	Chlorine (*)	APHA-AWWA-WEF Method	√ (*)	

Note: (*) The parameters were surveyed only during the dry season at SW-1, SW-2, and SW-3 as shown in Table 6.2-2 and Figure 6.2-1. Source: EIA Study Team

6.2.2 Survey Location

There were five survey sites for surface water quality and two survey sites for groundwater quality. The brief description of sampling points is presented in Table 6.2-2 and their locations are shown in Figure 6.2-1. The details of each sampling point are described below.

Table 6.2-2 Sampling Points for Water Quality Survey

Category	Sampling Point	Coordinates	Description of Sampling Point
	SW-1	16° 41' 19.11" N	Ah Lun Soke Creek in Thilawa SEZ area
	5 11-1	96° 14' 38.19" E	All Luli Soke Creek iii Tilliawa SLZ area
	SW-2	16° 39' 28.20" N	Charle Drayle Create in Thilance CE7 area
	3W-2	96° 16' 06.52" E	Shwe Pyauk Creek in Thilawa SEZ area
Surface	CW 2	16° 38' 35.39" N	Do Lon (Day Dayle) Creak in Thilaya CE7 area
Water	Water SW-3	96° 16' 22.65" E	Pa Lan (Bay Bauk) Creek in Thilawa SEZ area
	SW-4	16° 37' 44.91" N	One and bearing the Kronites Term
	3W-4	96° 16' 17.31" E	One creek located west of Kyauktan Town
	CIVE	16° 36' 58.48" N	
	SW-5	96° 16' 39.13" E	Gway Creek located west of Kyauktan Town
	CW 1	16° 41' 01.2" N	Tub II in Ab I Caba William
Ground	GW-1	96° 15' 18.3" E	Tube well in Ah Lun Soke Village
water	CW 2	16° 39' 24.39" N	T. 11. 4. 1. D. 1. V.11
	GW-2	96° 17' 15.04" E	Tube well in monastery compound in Phalan Village




Figure 6.2-1 Location of Water Quality Sampling Points

(1) SW-1

SW-1 is located on Ah Lun Soke Creek where Thanlyin-Thilawa Road crosses the creek. The creek flows from northeast to southwest and joins the Yangon River at its end. The surrounding area of the sampling point is flat and paddy field, as shown in Figure 6.2-2. The width of the creek is about 8 m.





Figure 6.2-2 Surface Water Sampling at SW-1

(2) SW-2

SW-2 is located on Shwe Pyauk Creek where it crosses Thilawa Road. The creek flows from the east of the industrial area of Thilawa SEZ Zone B to the west and then enters into the Yangon River. The surrounding area of the sampling point is a paddy field and agricultural land, especially to the east of the site, as shown in Figure 6.2-3. The width of the creek is about 7 m.



Source: EIA Study Team

Figure 6.2-3 Surface Water Sampling at SW-2

(3) SW-3

SW-3 is located on Pa Lan (Bay Bauk) Creek where Thilawa Road crosses it. The creek flows from east to west and then enters into Yangon River. SW-3 is located within Thilawa SEZ Zone B area and about 1.7 km to the south of SW-2 along the road. The surrounding area of the sampling point is paddy field and agricultural land, as shown in Figure 6.2-4. The width of the creek is about 9 m.




Figure 6.2-4 Surface Water Sampling at SW-3

(4) SW-4

SW-4 is located at the crossing of a small creek and Thilawa Road. The creek flows east-west and finally discharges into the Yangon River. The sampling point is located inside Thilawa SEZ Zone B area and about 1.5 km to the south of SW-3 along the road. The surrounding area of the sampling point is a paddy field and agricultural land, as shown in Figure 6.2-5. The width of the creek is about 5 m.



Source: EIA Study Team

Figure 6.2-5 Surface Water Sampling at SW-4

(5) SW-5

SW-5 is located at the crossing of Gway Creek and Kyauktan-Thilawa Road. The creek runs north-south and finally joins into Hmaw Wun Chaung. The sampling point is located at the south edge of the entire Thilawa SEZ and about 1.5 km to the south of SW-4. The surrounding area of the sampling point is a paddy field and agricultural land, especially to the north of the station, as shown in Figure 6.2-6. The width of the creek is about 7 m.



Figure 6.2-6 Surface Water Sampling at SW-5

(6) GW-1

GW-1 sample was taken from one tube well located in Ah Lun Soke Village, Thanlyin Township, as shown in Figure 6.2-7. The depth of the tube well is about 30 m. Water from the well is utilized for washing, cooking, and planting. The water sample is highly transparent.





Source: EIA Study Team

Figure 6.2-7 Groundwater Sampling at GW-1

(7) GW-2

GW-2 sample was taken from one tube well located in the monastery compound in Phalan Village, as shown in Figure 6.2-8. GW-2 is located inside Thilawa SEZ Zone B area. The depth of the tube well is about 60 m. Water from the well is utilized especially for drinking. The water sample is highly transparent.






Figure 6.2-8 Groundwater Sampling at GW-2

6.2.3 Survey Period

Water quality survey was conducted two times during the rainy season and dry season, as shown in Table 6.2-3.

Table 6.2-3 Survey Time for Water Quality

Category	Survey Point	Rainy Season	Dry Season
	SW-1, SW-2, SW-3	6 Oct (2015)	15 Dec (2015)
Surface Water	3 W-1, 3 W-2, 3 W-3	0 Oct (2013)	2 Feb (2016)
	SW-4, SW-5	6 Oct (2015)	15 Dec (2015)
Groundwater	GW-1, GW-2	6 Oct (2015)	13 Jan (2016)

Source: EIA Study Team

6.2.4 Survey Method

(1) Sampling and Preservation Method

Water samples were taken by Alpha horizontal water sampler and collected in sterilized sample containers. Sampling was conducted strictly in accordance with recognized standard procedures. The parameters such as pH, temperature, dissolved oxygen (DO), electrical conductivity (EC), and turbidity were measured at each site concurrently with the sample collection. All samples were kept in iced boxes and transported to laboratories and stored at 2-4 °C. Detailed description of field equipment and containers used for water sampling and preservation method are described in the following tables.

Table 6.2-4 Field Equipment for Water Quality Survey

No.	Equipment	Manufacturer	Country of Origin	Model
1	Multiparameter (Temp., pH, EC, ORP, DO, TDS, Turbidity)	HANNA	USA	HI7609829 (with 3 sensors)
2	SmarTROLL multiparameter	In-situ Inc.	USA	-
3	Alpha Bottle (Water Sampler)	Wildlife Supply Company®	Indonesia	-

 Table 6.2-5
 Container and Preservation Method of Water Samples

No.	Parameter	Container	Preservation
1	Oil and grease	1,000 mL glass bottle	Sulfuric acid, Refrigerate
2	Chromium (Total)	1,000 mL plastic bottle	HNO ₃ , Refrigerate
3	Suspended solid	1,000 mL plastic bottle	Refrigerate
4	Heavy metals	3,000 mL plastic bottle	Refrigerate
5	Coliform	1,000 mL glass bottle	Refrigerate
6	Other	2,000 mL plastic bottle	Refrigerate

(2) Test Method

Water samples were sent to ISO Tech Lab, Agricultural Department, SGS Myanmar and SGS Thailand for laboratory analysis. The test method for each parameter is presented in detail in Table 6.2-1.

6.2.5 Survey Result

(1) Surface Water Quality

Results of surface water quality survey are shown in the following Table 6.2-6. The measured level of parameters was compared with the tentative target value. Table 6.2-6 shows that most of the measured parameters complied with the tentative target value during both dry and rainy seasons at all water sampling sites, except for SS, COD, Mn, Fe, CN and oil and grease.

Table 6.2-6 Survey Results of Surface Water Quality

		S	W-1	SV	W-2	S	W-3	SV	V-4	SV	V-5	Tentative
Parameter	Unit	rainy	dry	rainy	dry	rainy	dry	rainy	dry	rainy	dry	Target Value
Temperature	°C	27.1	28.2	26.7	27.0	28.1	30.0	28.4	28.9	27.7	28.7	-
pH	-	7.8	7.5	6.6	7.8	6.8	8.4	6.9	7.3	6.6	7.3	6 - 8.5
DO	mg/L	7.3	5.9	6.5	6.5	6.6	9.6	6.6	6.5	5.5	6.6	≥4
EC	μs	84	330	100	420	210	340	480	330	590	910	-
TSS	mg/L	-	430	-	490	-	240	-	-	-	-	100
BOD ₅	mg/L	-	3	-	8	-	9	-	-	-	-	15
COD	mg/L	-	1,400	-	810	-	1,300	-	-	-	-	30
Total Nitrogen	mg/L	-	1.4	-	1.1	-	<1	-	-	-	-	-
Total Phousphorous	mg/L	-	0.02	-	0.05	-	0.05	-	-	-	-	-
Oil & grease	mg/L	1.2	< 0.2	3.4	5.2	< 0.2	0.9	< 0.2	5.4	2	1.0	0.1
As	mg/L	-	< 0.002	-	< 0.002	-	< 0.002	-	-	-	-	0.01
Hg	mg/L	-	< 0.0005	-	< 0.0005	-	< 0.0005	-	-	-	-	0.0005
Pb	mg/L	-	< 0.01	-	< 0.01	-	< 0.01	-	-	-	-	0.01
Cd	mg/L	-	< 0.002	-	< 0.002	-	< 0.002	-	-	-	-	0.003
Cr (total)	mg/L	-	< 0.02	-	< 0.02	-	< 0.02	-	-	-	-	0.04 as Cr _(VI)
Cu	mg/L	-	< 0.1	-	< 0.1	_	< 0.1	-	-	-	-	0.02
Zn	mg/L	-	< 0.1	-	< 0.1	_	< 0.1	-	-	-	-	0.05
Mn	mg/L	< 0.1	1.4	< 0.1	0.6	< 0.1	< 0.1	< 0.1	0.5	< 0.1	1.1	1
Ni	mg/L	-	< 0.01	-	< 0.01	-	< 0.01	-	-	-	-	0.1
Fe	mg/L	-	6.9	-	8.2	-	1.4	-	-	-	-	1.5
CN	mg/L	-	0.009	-	< 0.004	-	< 0.004	-	-	-	-	Not detectable
Fluoride	mg/L	-	0.63	-	0.49	-	0.66	-	-	-	-	0.8
NO ₃ as N	mg/L	-	1.59	-	< 0.02	-	0.58	-	-	-	-	5
NH ₃ as N	mg/L	-	0.25	-	0.23	-	0.28	-	-	-	-	0.5
Total Coliform	MPN/ 100mL	-	1,100	-	490	-	130	-	-	-	-	7,500
NO ₂ as N	mg/L	-	< 0.02	-	0.17	-	< 0.02	-	-	-	-	-
Barium	mg/L	-	< 0.1	-	< 0.1	-	< 0.1	-	-	-	-	-
Selenium	mg/L	-	< 0.01	-	< 0.01	-	< 0.01	-	-	-	-	0.01
Formaldehyde	mg/L	-	< 0.01	-	< 0.01	-	< 0.01	-	-	-	-	-

		S	W-1	SV	N-2	S	W-3	SW	7-4	SV	V-5	Tentative
Parameter	Unit	rainy	dry	rainy	dry	rainy	dry	rainy	dry	rainy	dry	Target Value
Phenol	mg/L	-	< 0.001	-	< 0.001	-	< 0.001	-	-	-	-	0.001
Sulfide	mg/L	-	< 0.01	-	< 0.01	-	< 0.01	-	-	-	-	-
Chlorine	mg/L	-	0.03	-	0.03	-	0.02	-	-	-	-	-

(2) Groundwater Quality

Results of the groundwater quality survey are shown in Table 6.2-7. The measured level of parameters was compared with the standards of groundwater quality, QCVN 09:2008/BTNMT issued by the Ministry of Natural Resources and Environment of Vietnam. The table shows that most of the measured parameters complied with the standard during the rainy season at all water sampling sites, except for COD, ammonium, nitrate, nitrate nitrogen, hardness, and manganese. The concentrations of COD at GW-1 during the rainy season and at GW-2 during both the rainy and dry seasons were found to be higher than the standard. Some parameters related to nitrogen also exceeded the standards. The concentrations of ammonium nitrate during both the rainy and dry seasons, and nitrate nitrogen at GW-1 and GW-2 during the rainy season were found to be higher than the standard. Total hardness and manganese at GW-1 were found to be higher than the standard, whereas these parameters at GW-2 complied with the standard.

Table 6.2-7 Survey Results of Groundwater Quality

D	TT 14	GW	7-1	GV	N-2	Environmental
Parameter	Unit	Rainy	Dry	Rainy	Dry	Standard in Vietnam
Temperature	°C	28.5	28.5	28.5	28.7	-
Odor		None	None	None	None	-
Color	Pt.Co	<1	<1	<1	<1	-
pН		6.6	7.0	6.7	7.0	5.5-8.5
DO	mg/L	7.8	7.6	7.5	7.5	-
EC	μs	360	480	290	280	-
BOD ₅	mg/L	<2	<2	<2	<2	-
COD	mg/L	<10	50	11	38	4 (KMnO4)
TSS	mg/L	97	46	120	26	-
Total nitrogen (organic)	mg/L	< 0.6	1.1	< 0.6	<1	-
Ammonium NH ₄ -N	mg/L	0.13	0.73	0.24	0.38	0.1
Nitrite NO ₂ -N	mg/L	0.76	< 0.02	< 0.02	< 0.02	1.0
Nitrate NO ₃ -N	mg/L	16	0.03	15	0.88	15
Phosphorus	mg/L	0.03	0.02	0.39	0.34	-
Total hardness (as CaCO ₃)	mg/L	970	740	350	92	500
Cyanide	mg/L	< 0.01	< 0.01	< 0.01	< 0.01	0.01
Oil and grease	mg/L	< 0.2	< 0.5	< 0.2	< 0.5	-
Iron	mg/L	< 0.1	< 0.1	0.19	0.35	5.0
Copper	mg/L	< 0.1	< 0.1	< 0.1	< 0.1	1.0
Zinc	mg/L	< 0.1	< 0.1	< 0.1	< 0.1	3.0
Manganese	mg/L	5.7	6.5	0.23	0.25	0.5
Arsenic	mg/L	< 0.001	< 0.001	< 0.001	0.001	0.05
Cadmium	mg/L	< 0.001	< 0.001	< 0.001	< 0.001	0.005
Cr (VI)	mg/L	< 0.02	< 0.02	< 0.02	< 0.02	0.05
Fluoride	mg/L	0.55	0.63	0.25	0.26	1.0
Lead	mg/L	< 0.006	< 0.006	< 0.006	< 0.006	0.01
Mercury	mg/L	< 0.0005	< 0.0005	< 0.0005	< 0.0005	0.001
Nickel	mg/L	< 0.002	0.004	< 0.002	< 0.002	-
Total coliform	MPN/100 mL	>23	2.2	>23	>23	3

6.3 Noise and Vibration Level

6.3.1 Survey Item

The noise and vibration level survey items are shown in Table 6.3-1.

Table 6.3-1 Survey Parameters for Noise and Vibration Level

No.	Item	Parameter
1	Noise	A-weighted loudness equivalent (L _{Aeq})
2	Vibration	Vibration level, vertical, percentile (L _{V10})

Source: EIA Study Team

6.3.2 Survey Location

The description of their location is presented in Figure 6.3-1 and Table 6.3-2.




Figure 6.3-1 Location of Environmental Noise Survey Points

There were five survey points for noise and vibration, divided into two types of noise and vibration. The first two points were installed to monitor both noise and vibration generated along the roads. In consideration of the estimated future trip distribution and transportation route from/to Thilawa SEZ (as

shown in Figure 7.2-2) and land use, two survey locations along the road were selected in order to measure current baseline data and to forecast the future impact. These points were also combined to monitor traffic volume, as presented in detail in the next section. The three remaining survey points were established to measure environmental noise. The details of the survey points are presented below.

Table 6.3-2 Location of Noise and Vibration Survey Points

vey Point	Items	Coordinates	Description of Sampling Point
NV-1	Noise, Vibration and	16°43'33.99"N,	Beside Thanlyin-Thilawa Road from Kyaikkauk
IN V-1	Traffic Volume	96°16'02.99"E	to SEZ, 8 m away from the road

Surv Pagoda N Noise, Vibration and 16°40'49.93"N. NV-2 Beside Thilawa Road, 13.5 m away from the road Traffic Volume 96°17'53.37"E 16° 39' 13.47" N, To the east of Phalan Ywa Haung Monastery, Kyauktan N-3 Noise 96° 16' 51.11" E 16° 42' 11.90" N, N-4 Noise Near Thilawa SEZ Zone B area, Thanlyin Township 96° 15' 14.90" E 16° 37' 19.00" N, At the southernmost part of Thilawa SEZ area, Kyauktan N-5 Noise 96° 17' 6.40" E Township

Source: EIA Study Team

(1) Traffic Noise and Vibration

Two survey points for concurrent measurement of noise and vibration were named as NV-1 and NV-2.

There were five survey points for noise and vibration, divided into two types of noise and vibration. The first two points were installed to monitor both noise and vibration generated along the roads. These points were also combined to monitor traffic volume, as presented in detail in the next section. The three remaining survey points were established to measure environmental noise. The details of the survey points are presented below

(i) NV-1

Survey point NV-1 is located in an open area beside Thanlyin-Thilawa Road (8 m away from the road), as shown in Figure 6.3-2. The road is paved with asphalt; heavy vehicles use the road to go to Thilawa SEZ. Heavy vehicles such as wheel loader and heavy dump trucks were parking behind the field of the survey point. However, the survey point and the parking field are separated by 4 m high concrete fence and 6 m high bamboo trees. The survey point is located 3.7 m away from the fence. The nearest house is 30 m away from the survey point.




Figure 6.3-2 Location of Noise and Vibration Survey Point at NV-1

(ii) NV-2

The survey point NV-2 is almost identical with AQ-2. The survey point is located in an open area beside Thilawa Road and 13.5 m away from the road, as shown in Figure 6.3-3. The road is paved with concrete; light and heavy vehicles use the road to go to Thilawa SEZ. Works on one construction site have started during the survey period; this construction site is about 180 m away from the survey point. However, no significant noise and vibration are expected to be transmitted from the construction site. It is noted that sometimes some motorbike and dump trucks pass closely to the survey point.



Figure 6.3-3 Location of Noise and Vibration Survey Point at NV-2

(2) Environmental Noise

Three survey points for environmental noise were named as N-3, N-4, and N-5.

(iii) N-3

The location of N-3 is identical with the location of AQ-3. This survey point is surrounded by paddy field and few residential houses, as shown in Figure 6.3-4.





Source: EIA Study Team

Figure 6.3-4 Environmental Noise Survey at N-3

(iv) N-4

The survey point is located within Sanpoenar Village. There is a garment factory which is about 200 m northwest of N-4, as shown in Figure 6.3-5. The area is flat and paddy field to the east and there are residential houses of one village to the west. The dominant noise sources of this station are from daily human activities in the village and from motorbikes running along nearby local access roads.





Source: EIA Study Team

Figure 6.3-5 Environmental Noise Survey at N-4

(v) N-5

N-5 is located at the southernmost part of Thilawa SEZ area, Kyauktan Township, as shown in Figure 6.3-6. N-5 is 100 m away from Kyauktan-Thilawa Road whose traffic is not very high. The survey point is surrounded by paddy field to the north and crab breeding ponds to the south.





Source: EIA Study Team

Figure 6.3-6 Environmental Noise Survey at N-5

6.3.3 Survey Period

(1) Traffic Noise and Vibration

The noise and vibration level survey was conducted on two consecutive days (weekday and weekend) during the dry season in 2015. The details of the survey period are shown in Table 6.3-3.

Table 6.3-3 Survey Period for Traffic Noise and Vibration Survey

N	No.	Survey Point	Survey Period (Noise)	Survey Period (Vibration)
	1	NV-1	29 Nov (9 a.m.) – 01 Dec (9 a.m.)	31 Jan (1 p.m.) – 02 Feb (1 p.m.)
	2	NV-2	27 Nov (6 a.m.) – 29 Nov (6 a.m.)	29 Jan (10 a.m.) – 31 Jan (10 a.m.)

(2) Environmental Noise

The environmental noise survey was conducted on two consecutive days including one weekday and one weekend during the dry season in 2015. The measurement duration is shown in Table 6.3-4.

Table 6.3-4 Survey Period for Environmental Noise Survey

No.	No. Survey Point Survey Period		
1	N-3	11 Dec (7 a.m.) – 13 Dec (7 a.m.)	
2	N-4	11 Dec (7 a.m.) – 13 Dec (7 a.m.)	
3	N-5	11 Dec (7 a.m.) – 13 Dec (7 a.m.)	

Source: EIA Study Team

6.3.4 Survey Method

Measurement of noise and vibration level was conducted by referring to the recommendation of the Japanese Industrial Standard (JIS) and International Organization for Standardization (ISO), as detailed in Table 6.3-5.

Table 6.3-5 Methods for Noise and Vibration Measurement

No.	Parameter	Method
1	Traffic Noise Level (L _{Aeq})	JIS Z 8731:1999
2	Traffic Vibration Level (L _{v10})	JIS C 1510: 1995 (JIS C 1510: 1976)
3	Environmental Noise Level (L _{Aeq})	ISO 1996-1:2003 and ISO 1996-2:2007

Source: EIA Study Team

The instrument used for measurement of noise and vibration level is described in Table 6.3-6.

Table 6.3-6 Instrument for Measurement of Noise and Vibration Level

Parameter	Parameter Instrument		Manufacture	Note
Traffic Noise	Sound level meter	NL-42	Rion Co. Ltd. (Japan)	
Traffic Vibration	Vibration level meter	VM-53A	Rion Co. Ltd. (Japan)	Accompanied by a 3-axis accelerometer PV-83C (Rion Co. Ltd.)
Environmental Noise	Sound level meter	NM102	Noise Meter Inc. (USA)	Sound level meter with SD Card, Model SL-4023SD

Source: EIA Study Team

The instrument used for noise measurement was set at the height of 1.2 m. A-weighted loudness equivalent level was measured automatically every 10 minutes and recorded in a memory card.

The vibration instrument used was the VM-53A Vibration Level Meter (Rion Co. Ltd., Japan) accompanied by a 3-axis accelerometer PV-83C (Rion Co. Ltd.) which was placed on solid soil ground near the roads. Vertical vibration (z axis), L_v , was measured every 10 minutes and recorded to a memory card. L_v (dB) vibration levels were recorded as $L_{v,max}$, $L_{v,min}$, L_{v5} , L_{v10} , L_{v50} , L_{v90} , L_{v95} , and L_{veq} . L_{v10} was the vibration level used for this Project in accordance with Vibration Control Law of Japan.

6.3.5 Survey Result

(1) Traffic Noise

Noise level (L_{Aeq}) along the road during the dry season is presented in Table 6.3-7. Noise levels measured on both weekday and weekend at NV-1 and NV-2 were found to be lower than the tentative target value. It is obvious that noise levels measured at the same point on weekday were higher than those on weekend.

Table 6.3-7 Equivalent Noise Levels (L_{Aeq}) Monitored along the Road

			Equivalent Noise Level (LAeq, dB)			
Survey Point	Date	Type of Day	Daytime	Nighttime		
			(6 a.m. – 10 p.m.)	(10 p.m. – 6 a.m.)		
NV-1	29 Nov (Sun)	Weekend	66	59		
IN V-1	30 Nov (Mon)	Weekday	68	63		
NV-2	27 Nov (Fri)	Weekday	65	59		
IN V-2	28 Nov (Sat) Weekend		65	59		
Tentative Target Value			75	70		

(2) Environmental Noise

The noise level (L_{Aeq}) during the dry season at the three survey points is presented in Table 6.3-8. Most of the noise levels measured at the survey points on weekday and weekend complied with the tentative target value which is applied for the most sensitive case (monastery, hospital, school), except for only one case. Noise level recorded on a Friday evening at N-3 was slightly higher than the standard.

Table 6.3-8 Equivalent Noise Levels (L_{Aeq}) in the Surrounding Environment

Cumurau			Equivalent Noise Level (L _{Aeq} , dB)					
Survey Point	Date	Type of Day	Daytime	Evening Time	Nighttime			
1 OIIIt			(7 am - 7 pm)	(7 pm - 10 pm)	(10 pm - 7 am)			
N-3	11 Dec (Fri)	Weekday	46	57	45			
N-3	12 Dec (Sat)	Weekend	47	45	47			
N-4	11 Dec (Fri)	Weekday	47	52	53			
11-4	12 Dec (Sat)	Weekend	46	52	53			
N-5	11 Dec (Fri)	Weekday	44	41	43			
N-3	12 Dec (Sat)	Weekend	45	42	43			
Tentative T	arget Value*		60	55	50			
*: applied to	sensitive area (mo	nastery, hospital, scho	ool)					

Source: EIA Study Team

(3) Traffic Vibration

The vibration level (L_{V10}) along the road during the dry season is presented in Table 6.3-9. All vibration levels measured at the survey points on weekday and weekend were much lower than the tentative target value, which is applied for residential area and two-lane road.

Table 6.3-9 Vibration Levels (L_{V10}) Monitored along the Road

			Vibration level (L _{V10} , dB)		
Survey Point	Date	Type of Day	Daytime	Nighttime	
			(6 a.m. – 10 p.m.)	(10 p.m. – 6 a.m.)	
NV-1	31 Jan (Sun)	Weekend	42	33	
IN V-1	1 Feb (Mon)	Weekday	42	30	
NIV 2	29 Jan (Fri)	Weekday	36	28	
NV-2	30 Jan (Sat) Weekend		35	28	
Tentative Target Value			65	60	

Source: EIA Study Team

6.4 Traffic Volume

6.4.1 Survey Item

The survey items for traffic volume survey are number of vehicles, types of vehicles, and direction of vehicle movement when vehicles pass through the survey point.

6.4.2 Survey Location

Traffic volume survey was conducted at the same survey points as traffic noise and vibration survey points but 7 m away from noise and vibration meters. Traffic volume survey points were named as T-1 and T-2 and their description were described again in the following Table 6.4-1.

Table 6.4-1 Location of Traffic Volume Survey Points

Traffic Volume Survey Point	Coordinate	Detailed Description	Note
T-1	16°43'33.99"N,	Beside Thanlyin-Thilawa Road from Kyaikkauk	Same location
	96°16'02.99"E	Pagoda to SEZ, 8 m away from the road	of NV-1
T-2	16°40'49.93"N,	Beside Thilawa Road, 13.5 m away from the road	Same location
	96°17'53.37"E	Deside Tilliawa Koad, 15.5 ili away Ilolli die load	of NV-2

Source: EIA Study Team

The location of the survey points and their relationship with the transportation network in the area can be visualized in Figure 6.4-1.




Figure 6.4-1 Transportation Network and Traffic Volume Survey Points

6.4.3 Survey Period

The vehicle traffic survey was conducted for two consecutive days including a weekday and a weekend during the dry season in 2015 at the same time as the traffic noise and vibration level survey. Details of the survey period are shown in the following Table 6.4-2.

Table 6.4-2 Survey Period for Traffic Noise and Vibration Survey

No.	Survey Point	Survey Period
1	T-1	29 Nov (9 a.m.) – 01 Dec (9 a.m.)
2	T-2	27 Nov (6 a.m.) – 29 Nov (6 a.m.)

6.4.4 Survey Method

Manual direct observation and recording using tally counters were conducted to count the number of vehicles moving in each direction (e.g., from Thilawa SEZ or to Thilawa SEZ). Type of vehicles was also recorded concurrently. All vehicles were classified into four types as detailed in Table 6.4-3. Hourly quantities of each type of vehicle recorded by the tally counters were summarized and then the tally counters were reset for counting again.

Table 6.4-3 Classification of Vehicles Types

No.	Classification	Description
1	Two-wheeled vehicle	Motorbike, motorcycle taxi
2	Four-wheeled light vehicle	Pick-up car, jeep,taxi, saloon car, light truck (under 2 tons)
3	Four-wheeled heavy vehicle	Medium bus, express, big bus, medium truck, heavy truck
4	Others	Tractor

Source: EIA Study Team

6.4.5 Survey Result

Traffic volume recorded at the two survey points is presented in Table 6.4-4. The table shows that the number of all types of vehicle on a weekday is higher than that on a weekend at both survey points. Comparing the two survey points, the number of 2-wheel vehicles passing T-1 is significantly higher than that passing T-2. The number of 4-wheel light vehicles passing T-1 is also higher than that passing T-2, especially on weekday. However, the number of 4-wheel heavy vehicles running on Thanlyin-Thilawa Road (T-1) is similar to that on Thilawa Road (T-2).

Table 6.4-4 Vehicle Traffic Volume Recorded at T-1 and T-2

Unit: vehicles

Survey Point	Direction	Date	Weekday	2-wheel Vehicles	4-wheel Light Vehicles	4-wheel Heavy Vehicles	Others	Total
	To SEZ	20 Nov	Cum	4,125	800	478	46	10.552
TT 1	From SEZ	29-Nov	Sun	4,004	715	372	12	10,552
T-1	To SEZ	30-Nov	Mon	4,640	1,384	613	50	12 220
	From SEZ		30-NOV	MOII	4,458	1,544	522	17
	To SEZ	27-Nov	Fri	1,592	655	516	27	5.760
T-2 From SEZ	27-NOV	ΓΠ	1,540	788	626	16	5,760	
1-2	To SEZ	28-Nov	Sat	1,373	554	484	23	5,105
	From SEZ	20-NOV	Sat	1,450	626	577	18	3,103

Source: EIA Study Team

6.5 Soil Quality

6.5.1 Survey Item

Nine heavy metal parameters for soil quality survey were determined by referring to the relevant parameters for soil quality in Japan and neighboring countries, as shown in Table 6.5-1.

Table 6.5-1 Parameters for Soil Quality Survey

No.	Parameter
1	Arsenic (As)
2	Cadmium (Cd)
3	Chromium (Cr)
4	Copper (Cu)
5	Iron (Fe)
6	Lead (Pb)
7	Manganese (Mn)
8	Mercury (Hg)
9	Zinc (Zn)

6.5.2 Survey Location

There were four sampling points for soil quality survey. The description of the locations of the sampling points is presented in Table 6.5-2 and the detailed location of each sampling point can be found in Figure 6.5-1. Since past use of land, which is mainly composed of agricultural fields in and around project site, is assumed almost same, sampling points were selected one points per development area of Zone B.

Table 6.5-2 Sampling Points for Soil Quality Survey

Sampling Point	Coordinates	Description of Sampling Point
SO-1	16° 41' 56.00" N 96° 15' 43.10" E	Inside Thilawa SEZ Zone B area, Thanlyin Township
SO-2	16° 37' 54.40" N 96° 16' 26.00" E	Inside Thilawa SEZ Zone B area, Kyauktan Township
SO-3	16° 39' 59.10" N 96° 16' 54.30" E	Inside Thilawa SEZ Zone B area, Kyauktan Township
SO-4	16° 41' 6.70" N 96° 14' 49.20" E	Inside Thilawa SEZ Zone B area, northwestern part of Thilawa SEZ area, Thanlyin Township




Figure 6.5-1 Location of Soil Quality Survey Points

(1) SO-1

SO-1 is located inside a paddy field in the Thilawa SEZ Zone B area. The surrounding area is mainly flat and paddy field. The northern boundary of Thilawa SEZ Zone A area is about 1 km to the south of SO-1. Soil sample had gray to dark gray color, which can be roughly classified as silty clay.



Figure 6.5-2 Soil Quality Survey at SO-1

(2) SO-2

The survey point is located inside a paddy field and situated in the southern part of Thilawa SEZ Zone B area. The soil sample had gray color, which can be roughly classified as silty clay.



Figure 6.5-3 Soil Quality Survey at SO-2

(3) SO-3

The survey point is located in a paddy field and situated in the northern part of the industrial area of Thilawa SEZ Zone B. There are some bushes or shrubs around this sampling point. Thilawa Road is 500 m to the north of SO-3. The soil sample had yellowish brown color, which can be roughly classified as sandy clay.






Figure 6.5-4 Soil Quality Survey at SO-3

(4) SO-4

The sample is located in a paddy field and situated in the northwestern part of Thilawa SEZ area. The surrounding area is flat and paddy field. Thanlyin-Thilawa Road lies to the west of SO-4. The soil sample had light gray to gray color, which can be roughly classified as sandy clay.





Source: EIA Study Team

Figure 6.5-5 Soil Quality Survey at SO-4

6.5.3 **Survey Period**

Soil quality survey was conducted on 14 December 2015 during the dry season.

6.5.4 **Survey Method**

(1) Sampling and preservation method

For soil sampling, the standard agricultural sampler (soil auger) was employed. The sampler is a stainless steel tube that is sharpened on one end and fitted with a long, T-shaped handle. This tube has an inside diameter of about 3 inches. In order to refrain from contamination, about 20~30 cm of top soil were removed by the sampler before sampling. Then, sample was taken and collected in a cleaned plastic bag. Chemical preservation of soil is not generally recommended. Samples were cooled in an ice box whose temperature was under 4 °C. Samples were protected from sunlight to minimize any potential reaction.

(2) Analysis method

Soil samples were sent to the Applied Geology Department's laboratory for analysis. The analysis method for all concerned heavy metal parameters is Atomic Absorption Spectrophotometer (Aquaregia).

6.5.5 Survey Result

The result of soil quality analysis is presented in Table 6.5-3. All parameters showed significantly lower levels than the examined standards in Vietnam and Thailand. Therefore, the soil quality at the sampling sites is suitable for the project development.

Table 6.5-3 Soil Quality Survey Results

							Environmental Standard		
No.	Parameter	Unit	SO-1	SO-2	SO-3	SO-4	Vietnam (Industrial land)	Thailand (Not for habitat or agriculture)	
1	Arsenic (As)	mg/kg	ND	ND	ND	ND	12	27	
2	Cadmium (Cd)	mg/kg	0.007	0.006	0.006	0.005	10	810	
3	Chromium (Cr)	mg/kg	12	10	8	11	-	640	
4	Copper (Cu)	mg/kg	60	65	68	72	100	-	
5	Iron (Fe)	mg/kg	5,200	5,400	4,900	4,800	-	-	
6	Lead (Pb)	mg/kg	85	80	87	90	300	750	
7	Manganese (Mn)	mg/kg	10	8	12	9	-	32,000	
8	Mercury (Hg)	mg/kg	ND	ND	ND	ND	-	610	
9	Zinc (Zn)	mg/kg	75	70	80	78	300	-	

ND: Not detected

Source: Vietnam: QCVN 03:2008/BTNMT, "industrial land" class

Thailand: Notification of National Environmental Board No. 25, B.E. (2004), "other purpose" class

6.6 Flora and Fauna

6.6.1 Survey Item

The flora and fauna survey items are as follows:

- i) Vegetation
- ii) Flora species
- iii) Fauna species
- iv) Important species

6.6.2 Survey Area

The survey area is in and around the Thilawa SEZ Zone B area, focusing on areas marked by the green, blue, and cyan polygons, as shown in the following Figure 6.6-1.




Figure 6.6-1 Survey Area for Flora and Fauna

6.6.3 Survey Period

The flora and fauna field survey including interview survey was conducted both during the dry and rainy seasons. The survey duration is as shown in Table 6.6-1. Literature survey was conducted during 24-30 September, 2015.

Table 6.6-1 Field Survey Periods for Flora and Fauna Survey

Period
1st October, 2015 (one day)
10th December, 2015 (one day)

Source: EIA Study Team

6.6.4 Survey Method

(1) Vegetation Survey

The vegetation map was obtained by conducting field observation together with the use of secondary image from Google Earth and GIS software. At first, field observation was performed for the habitat survey at the project site to collect data using Garmin GPS. The data was then retrieved and processed


by the Map Info software. The Google images used were visually digitized based on the primary field survey. Finally, the vegetation map was formulated and analyzed based on both field survey and secondary image data from the Map Info software.

The materials and tools used for the field survey and formulation of the vegetation map include the following:

- i) Garmin GPS 62 cx
- ii) Map Info 11.0 and Discover
- iii) Google Earth software and Google Images
- iv) Field survey record

(2) Flora Species Survey

A global positioning system (GPS) was used to navigate and mark coordinates between the sample plots around the study area. Field observation was conducted in and around Zone B. In order to obtain essential ecological data for predicting flora of shrubs and herbs, $2 \times 20 \text{ m}$ belt transects were laid down and observed as shown in Figure 6.6-2. In each sub-plot, every plant species was listed and counted. For the tree species, $10 \times 10 \text{ m}$ quadrates (total of 10) were subjectively chosen and observed. In each sample plot, every living tree with girth at breast height (gbh) $\geq 10 \text{ cm}$ was measured, listed, and counted. In each sub-plot along the belt transect, every plant species was listed and counted. Care had been taken to cover different elevation, slope, aspect, drainage, and density gradients to study the overall spectrum of species diversity. In addition, all plant species (trees, shrubs, herbs, and cultivated crops) around the area were recorded and listed.



Source: EIA Study Team

Figure 6.6-2 Layout Design of the Belt Transect

Identification of plant and animal species was conducted with the assistance of skilled local people. The identified species were translated to scientific name with the assistance of senior researchers at Yangon University. The families were identified using a key to the families of the flowering plants, issued by the Department of Botany, Yangon University (1994). Specimen identification was performed using the literature by Backer *et al.*, 1963 and Kress *et al.*, 2003 and confirmed at the Herbarium in the Department of Botany, University of Yangon.

(3) Fauna Species Survey

Butterfly and dragonfly species were collected by aerial nets along the trail, packed by trasipaper (triangle paper), and placed in a plastic box together with mothball to keep the specimen for a long time. In addition, photos of butterflies were taken and used along with the specimen for identification of the species by examining using reference books.

Bird species were studied using binocular and camera. Photos of bird species were taken and then identified using reference books. The point count method was used for the bird survey in selected habitats. The species recorded by the point count method was examined and then identified using reference books.

Mammal species were confirmed by interview survey with the local people, because some mammals only lived in the survey area in the past and they were no longer found during the survey and in recent

time. Both observed and unobserved mammals were confirmed again through interview with experienced local people. All data recorded in the survey area were entered into the field data sheet.

Reptilian and Amphibian species were mainly collected by capturing them using the hands during the survey. Photos of reptiles and amphibians were taken as well. Information on some species was obtained from interviews with the local people.

Water bodies such as creeks, irrigation canal, lakes, and ponds were studied for aquatic fauna. Fishes were collected with the help of fishermen during the survey period. Traps were also used to get various types of fish like surface dwellers and bottom dwellers. The fishes were photographed soon after the collection and measurements were also taken for key characteristics. The fishes were then preserved in 10% formalin solution for further identification in the laboratory. The fishes were then identified according to Jayaram (1981) and Talwar and Jhingram (1991). In addition, fishermen were interviewed with regard to fishing gears, number of fishing time per day, and target species. The fishing gears were identified as trap, hook and line, and gill nets.

The list of instruments, tools, and materials used for the fauna survey is presented in Table 6.6-2 and some of their images are shown in Figure 6.6-3.

Table 6.6-2 Instruments, Tools, and Materials Used for Fauna Survey

No.	Instrument and Tool	Material
1	Camera (Nikon)	GPS map 62s (Garmin) for coordinates of collection
2	Binocular (Nikon)	Field guide to identify the species
3	Aerial net (PVC) net patch d1 millimetre, ring size 15 inches diameter made in Myanmar	Data sheet (to note the survey condition)
4	Plastic box, Mothball.	Vernier caliper and measuring tape to take the measurement

Source: EIA Study Team





Source: EIA Study Team

Figure 6.6-3 Instruments and Tools Used for Fauna Survey


(4) Interview and Literature Survey for Flora and Fauna

In addition to the field observation, secondary data were also surveyed by interviewing local residents (see Figure 6.6-4) and through literature review. In the interview survey, the surveyor visited the residents in and around the survey area and asked about the name of plants and animals existing in and around the area. Also, the past situation of flora and fauna, and the change in biodiversity and ecosystem in the area were asked.





Dry Season: 10th December, 2015







Rainy Season: 1st October, 2015

Rainy Season: 1st October, 2015

Source: EIA Study Team

Figure 6.6-4 Interview Survey with Local People

6.6.5 Survey Result

(1) Vegetation Survey

In the Thilawa SEZ Zone B area, four major habitat types were observed, namely: (1) patches of mixed vegetation with scattered trees, (2) cultivated land, (3) aquatic habitat, and (4) human habitation area. Vegetation map of Thilawa SEZ Zone B area is shown in Figure 6.6-5. The map shows clearly that the dominant areas are cultivated/agricultural land and grass and shrub land.




Figure 6.6-5 Vegetation Map of Thilawa SEZ Zone B Area

The vegetation types in the study area are herb land, shrub land, mangrove/swamp land, grass land, and paddy field. Sceneries of the survey area can be visualized in Figure 6.6-6.



Figure 6.6-6 Scenery of the Survey Area

(2) Flora

A total of 158 flora species were recorded in the survey area during the survey periods. (The list of flora species is presented in Annex 6-2.) The habitat of identified species consists of seven types, including tree, small tree, shrub, herb, creeper, climber, and grass. The recorded species were checked with the IUCN Red List of Threatened Species 2015-4 Version 3.1. All species were classified as either Not Evaluated (NE), Data Deficient (DD), or Least Concern (LC).

(3) Butterfly

A total of 71 butterfly species were recorded in the survey area during the survey periods. (The list of butterfly species is presented in Annex 6-2.) The habitat of identified species includes tree, shrub, bush, and trail. All recorded butterfly species were common species. Recorded species were checked with the IUCN Red List of Threatened Species 2015-4 Version 3.1. All species were classified as either NE or LC.



Peacock Pansy (Junonoa Almanac) Source: EIA Study Team

Common Tiger (Danus Genutia)

Figure 6.6-7 Butterfly Species Recorded in Thilawa SEZ Zone B

(4) Dragonfly

There were four dragonfly species observed during the survey. (The list of dragonfly species is presented in Annex 6-2.) All species were classified as LC according to the IUCN Red List of Threatened Species 2015-4 Version 3.1

(5) Birds

A total of 67 bird species were recorded in the survey area. (The list of bird species is presented in Annex 6-2.) The survey area is mainly characterized by grass land and scattered area; bird species common in this area are Black Drongo (*Dicrurus macrocercus*), Spotted Dove (*Spilopelia chinensis*), Barn Swallow (*Hirundo rustica*), and Common Myna (*Acridotheres tristis*). One species, White-throated Babbler (*Turdoides gularis*), was reported as Myanmar endemic species. Images of some bird species found in the area are shown in Figure 6.6-8. During the study period, some bird species were seen in all kinds of habitat showing their capability for wide distribution. Such commonly distributed species comprised insect eaters and some omnivores that have alternative food choices such as insects, flowers, seeds, and fruits.

Recorded species were checked with the IUCN Red List of Threatened Species 2015-4 Version 3.1. Most of the species were classified as NE and LC. There were two species, *Anhinga melanogaster* (Oriental Darter) and *Ploceus hypoxanthus* (Asian Golden Weaver), which were considered as Near Threatened (NT) species.



Asian Golden Weaver (Ploceus hypoxanthus)



Barn Swallow (Hirundo rustica)





Asian Pied Starling (*Gracupica contra* (*Sturnus contra*)) Source: EIA Study Team

Common Sandpiper (Actitis hypoleucos)

Figure 6.6-8 Some Bird Species Found in the Survey Area

(6) Mammals

A total of seven mammal species were recorded during the survey periods. (The list of mammals is presented in Annex 6-2.) Recorded species were checked with the IUCN Red List of Threatened Species 2015-4 Version 3.1. All species were classified as LC.

(7) Reptilian and Amphibian Species

There were a total of 13 reptilian and amphibian species recorded in the survey area during the survey periods. (The list of reptilian and amphibian species is presented in Annex 6-2.) The Garden Lizard (*Calotes versicolor*) was observed in the mixed vegetation with scattered trees area. Among the recorded species, the Paddy Frog (*Fejervarya limnocharis*) was found as a very common species. Recorded species were checked with the IUCN Red List of Threatened Species 2015-4 Version 3.1. Most of the species were classified as NE and LC. One species, *Ophiophagus hannah* (King Cobra), was considered as Vulnerable (VU).

(8) Fish

A total of 22 fish species were recorded during the survey period. (The list of fish species is presented in Annex 6-2.) The fishes are important for the ecosystem of the canal and rice field water bodies. The fish species such as Giant Snakehead (*Channa marulius*), Ceylon Snakehead (*Channa orientalis*), Gangetic mystus (*Mystus cavasius*), and Chola barb (*Puntius chola*) were found as very common species in the project area. Recorded species were checked with the IUCN Red List of Threatened Species 2015-4 Version 3.1. Most of the species were classified as NE and LC. There were three species classified as NT, including *Ompok bimaculatus* (Indian Butterfish), *Oreochromis mossambicus* (Mozambique Tilapia), and *Wallago attu* (Wallago).

(9) Important Species

The number of flora and fauna recorded in the survey area is summarized in Table 6.6-3. Some species were classified as vulnerable and near threatened species in accordance with the IUCN Red List of Threatened Species (2015-4 Version 3.1), as listed in Table 6.6-4. There were one threatened species (reptile) and five near threatened species including two birds and three fishes.

Table 6.6-3 Identified Species of Flora and Fauna during the Survey Period

	Number of Species					
	Total	IUCN Red List				
	Total	NE	DD	LC	NT	VU
Flora	158	139	3	16		
Butterfly	71	68		3		
Dragonfly	4			4		
Birds	67	1		64	2	
Mammals	7			7		
Reptilian and amphibian species	13	8		4		1
Fish	22	5	1	13	3	
Total	342	221	4	111	5	1

Note: NE: Not Evaluated; DD: Data Deficient; LC: Least Concern; NT: Near Threatened; VU: Vulnerable; EN: Endangered Source: Summarized by the EIA Study Team

Table 6.6-4 Threatened and Near Threatened Species Recorded during the Survey Period

No.	Scientific Name	Common Name	Family	IUCN (2015-4 Ver. 3.1)	Type of Species
A.	Threatened Species (CR: Critically	Endangered, EN: Endan	gered, VU: Vuln	erable)	
1	Ophiophagus hannah	King Cobra	Elapidae	VU	Reptile
В.	Nearly Threatened Species (NT)				
1	Anhinga melanogaster	Oriental Darter	Anhingidae	NT	Bird
2	Ploceus hypoxanthus	Asian Golden Weaver	Ploceidae	NT	Bird
3	Ompok bimaculatus	Indian Butterfish	Siluridae	NT	Fish
4	Oreochromis mossambicus (Tilapia mossambica)	Mozambique Tilapia	Cichlidae	NT	Fish
5	Wallago attu	Wallago	Siluridae	NT	Fish

Note: NT: Near Threatened; VU: Vulnerable; EN: Endangered

Source: EIA Study Team

6.7 Cultural Assets

6.7.1 Survey Item

Cultural survey was conducted to examine the existence of cultural assets in the project area. A list of survey items for cultural survey is presented in the following Table 6.7-1, including religious and non-religious items.

Table 6.7-1 Survey Items for Cultural Survey

Religious Items	Non-religious Items
Pagoda	Palace
Church	Architectural structures
Shrines	Sculpture
Stupas	Excavated building
Temple	Historic site
Monastery	Cultural landscape
Cemetery	Painting

Source: EIA Study Team

6.7.2 Survey Area

The cultural survey was carried out in and around the project area.

6.7.3 Survey Period

The cultural survey to collect cultural heritage data was implemented from 22 to 23 December 2015.

6.7.4 Survey Method

The survey method to identify cultural heritages in the project area is as follows:

Documentary survey and field investigation.

In the course of field investigation, various types of cultural assets were identified and noted. Local monks, wise men, and concerned elders were interviewed to obtain detailed information of the assets which were found inside the project area.

6.7.5 Survey Result


(1) Summary of Survey Results

There were 19 cultural structures and assets found within the whole Thilawa SEZ area and its surrounding area. There were three cultural assets in the Zone B area, namely: Own Maw Taw Temple, Phalan Cemetery, and another cemetery. The list and location of the cultural structures and assets are presented in Table 6.7-2.

Table 6.7-2 List of Cultural Structures and Assets Within or Around Thilawa SEZ

No.	Code	Coordinate	Name of Cultural Structure/Asset	Location	Remark
1	C-01	16°42'26.80"N 96°15'54.20"E	Phan Chat Taw Ya Monastery	Ah Lun Soke Village, Thanlyin Township	Excluded Area
2	C-02	16°42'17.39"N 96°15'36.29"E	Siri Sadal Mune Warat Temple (Hinduism)	Phan Chat Ward, Thanlyin Township	In Thilawa SEZ
3	C-03	16°42'10.89"N 96°15'9.54"E	Chapel (RWP6)	Ah Lun Soke Village, Thanlyin Township	In Thilawa SEZ
4	C-04	16°41'32.53"N 96°16'8.08"E	Own Maw Taw Temple (Hinduism)	Ah Lun Soke Village, Thanlyin Township	Inside Zone B (Residence and Commercial Area)
5	C-05	16°41'13.86"N 96°15'19.17"E	Siri Meriman Temple (Hinduism)	Ah Lun Soke Village, Thanlyin Township	Excluded Area
6	C-06	16°41'12.62"N 96°15'20.31"E	Phaung Taw-U Pagoda	Ah Lun Soke Village, Thanlyin Township	Excluded Area
7	C-07	16°41'9.37"N 96°15'23.34"E	Ah Lun Soke Monastery	Ah Lun Soke Village, Thanlyin Township	Excluded Area
8	C-08	16°41'8.70"N 96°15'10.86"E	Than Ann Nar Church (Catholic)	Ah Lun Soke Village, Thanlyin Township	Excluded Area
9	C-09	16°41'14.53"N 96°14'48.37"E	Cemetery	Ah Lun Soke Village, Thanlyin Township	Inside Zone B (Logistic Area)
10	C-010	16°40'53.07"N 96°15'25.12"E	Ah Lun Soke Cemetery	Ah Lun Soke Village, Thanlyin Township	In Thilawa SEZ
11	C-011	16°40'24.64"N 96°16'31.90"E	Moe Gyoe Swan Monastery (RWP3)	Ah Lun Soke Village, Thanlyin Township	Excluded Area
12	C-12	16°39'45.11"N 96°16'34.88"E	Phalan Cemetery	Phalan Village, Kyauktan Township	Inside Zone B (Industrial Area)
13	C-13	16°39'24.84"N 96°17'14.94"E	Phalan Ywa Haung Monastery	Phalan Village, Kyauktan Township	Excluded Area
14	C-14	16°39'17.43"N 96°16'49.79"E	Phalan Ywa-U Phayalay Monastery	Phalan Village, Kyauktan Township	Excluded Area
15	C-15	16°39'21.24"N 96°16'34.57"E	Hindu Temple	Phalan Village, Kyauktan Township	In Thilawa SEZ
16	C-16	16°38'36.56"N 96°16'58.87"E	Hindu Temple	Na Bal Sonn Village, Kyauktan Township	In Thilawa SEZ
17	C-17	16°38'50.03"N 96°17'27.13"E	Hindu Temple	Phalan Village, Kyauktan Township	Excluded Area
18	C-18	16°38'36.69"N 96°17'25.09"E	Monastery	Shwe Pyi Thar Yar Ward, Kyauktan Township	Excluded Area
19	C-19	16°38'13.17"N 96°17'43.70"E	Siri Rama Temple (Hinduism)	Shwe Pyi Thar Yar Ward, Kyauktan Township	Excluded Area

Source: EIA Study Team



Detailed location of the cultural structures and assets can be found in Figure 6.7-1.

Figure 6.7-1 Location of Cultural Structures/Assets In/Around Thilawa SEZ Area

(2) Description of Major Cultural Structure/Asset

Photos and some information related to major cultural structure/asset found in and around Thilawa SEZ are presented as follows:

Siri Sadal Mune Warat Temple (Hinduism) (C-02)

This temple is situated in Phan Chat Ward, Thanlyin Township, and belongs to the Hindus who are living nearby. This area is surrounded by the Myanmar Maritime University in the east, a glass factory (Ministry of Industry) in the north, and some paddy field in the west and south. The temple has been

established since 1991 and is made of bamboo and wood. The temple was damaged due to Cyclone Nargis in 2008. After that, it was renovated as a brick structure, which is its current appearance. Hindus usually celebrate their religious festival and traditional ceremony in this temple.





Own Maw Taw Temple (Hinduism) (C-04)

This small temple is located in the residence and commercial area of Zone B, Thanlyin Township. According to the villagers, it was founded in 1998 and used by around 35 households.



Cemetery (C-09)

This cemetery is located in the logistic area of Zone B, Thanlyin Township. According to the villager, it was founded over 100 years ago and it covers around 0.5 acres. Around 50 households are using it.





Phalan Cemetery (C-12)

Phalan Cemetery is located in the industrial area of Zone B, Kyauktan Township. Topographically, the cemetery is slightly higher than the surrounding area which is recognized as paddy field and cultivation

land. This cemetery mostly belongs to Phalan Village and local people bury or entomb corpse in this cemetery.





Phalan Ywa Haung Monastery (C-13)

This is located in the excluded area of Thilawa SEZ. According to a villager, it was founded in 1913 and around 200 households are using it.





Phalan Ywa-U Phayalay Monastery (C-14)

This is located in the excluded area of Thilawa SEZ. According to a villager, it was founded over 100 years ago and the whole village is using it.





6.8 Hydrology

6.8.1 Survey Item

The hydrology survey items include the following:

- i) Topography of Thilawa SEZ area
- ii) Surface water flow direction in the area

6.8.2 Survey Area

The topography and surface water flow survey area covers the entire Thilawa SEZ area and the 500-m buffer area which was determined as 500 m from the SEZ boundary, as shown in the following Figure 6.8-1.




Figure 6.8-1 Field Survey Area for Hydrology

6.8.3 Survey Period

The topography and surface water flow survey was carried out from 22 to 24 December 2015.

6.8.4 Survey Method

Firstly, the field survey was conducted using hand-held Garmin GPS instrument to estimate the elevation of the area and to record the practical observation of the water flow direction onsite. The field survey data was utilized to formulate ASTER image (15 m resolution) with 1.0-m interval contours by applying GIS software. Then, the water flow direction was visually digitized based on the topographic elevation of the contour interval. Water flow direction was again checked by practical observation during the survey.

The materials and tools used for the field survey and formulation of hydrology (topography) map include the following:

- i) ASTER image (15 m resolution)
- ii) Global Mapper 15 software
- iii) Map Info 11.0 and Discover
- iv) Garmin GPS 62 cx

6.8.5 Survey Result

(1) Topography Condition

According to the result generated by the GIS software, the topography of the Thilawa SEZ area is generally characterized by flat terrain with some changes in elevation from 3 m to 21 m, as shown in Figure 6.8-2.

(2) Surface Water Flow Direction

The figure shows that Thilawa SEZ area is characterized by higher areas in the middle and in the east and low-elevation land located in the west and south. Highest areas are found in the Thilawa SEZ Zone A area and in the industrial area of Thilawa SEZ Zone B. Pursuant to its topography, surface water flow in the main area of the SEZ is mostly from east to west and surface water flow in the southern part of the SEZ is from north to south. There are four creeks, running from east to west and discharging into the Yangon River, namely: Ah Lun Sake Creek, Shwe Pyauk Creek, Pa Lan (Bay Bauk) Creek, and another creek. There are two creeks, flowing from north to south and discharging into Hmaw Wunn River, namely, Gway Creek and Kayat Creek. Surface water runoff in adjacent areas of a creek flows in different directions, such as east-west, north-south, and south-north, but is directed to the creek. The watershed area of each creek has a span of less than 2 km, implying a length of 1 km in each side of the creek.




Figure 6.8-2 1-m Interval Contour Map with Water Flow Direction

CHAPTER 7: ENVIRONMENTAL AND SOCIAL IMPACT ASSESSMENT

7.1 Summary of the Environmental and Social Impact Assessment

Environmental and social impacts of the Project are predicted and evaluated based on the project description, results of baseline survey, and set target level. Table 7.1-1 shows the summary of the environmental and social impacts of the Project.

In this assessment of the Project, air quality, water quality, waste, noise and vibration, flora and fauna, biodiversity and community health and safety were identified as the items that should consider the cumulative impacts of other development projects in Thilawa SEZ, i.e. development project of Zone A and development project of Zone B that includes the development of the Project and the development of the logistic, residence and commercial area.

Table 7.1-1 Summary of the Environmental and Social Impacts of the Project (Industrial Area of Zone B)

		Sco	ping Re	sult	Asses	sment l	Result	
Category	Scoping Item	PC/ CO	OP	CLP	PC/ CO	OP	CLP	Reason for Assessment
Pollution	Air Quality	B-	B-	B-	B-	B-	В-	CO/CLP: Impact on air quality is expected to be limited because dust and emission gases from construction works will be within narrow area near the construction site. In addition, emission gas effect from construction vehicles travelling around the area will be little, comparatively limited vehicles are operating. OP: Impact on air quality is expected to be little, because roadside air quality is mitigated by commuter bus for workers. The tenants which may cause adverse impact to air condition by installing of combustion facilities be required to submit an EIA or IEE report with EMP including mitigation measures on air pollution to TSMC/OSSC. The proposed mitigation measures, such as energy use efficiency, process modification, selection of fuels or other materials, the processing of which may result in less polluting emission, application of emission control techniques, in necessary, in the EIA or IEE report shall be conducted by each tenant. Therefore, it is expected that the air pollution caused by the Thilawa SEZ Zone B operation would not cause any significant environmental impact on the surrounding area.
	Water Quality	B-	В-	В-	В-	В-	В-	CO/CLP: Impact on wastewater quality caused by construction/demolition work is expected to be limited because discharging muddy water from bare land of construction site will be temporary and wastewater from a construction camp will be treated by the septic tanks. OP: Impact on water quality is expected to be limited because water discharge from tenants will be treated at a treatment plant to comply with the industrial wastewater effluent guideline values stipulated by MOI and MOECAF and the proposed internal regulation. Basically, it is

		Sco	ping Re	sult	Asses	sment I	Result	
Category	Scoping Item	PC/ CO	OP	CLP	PC/ CO	OP	CLP	Reason for Assessment
								expected that concentration of wastewater is diluted by mixing with stormwater through the retention pond and creek flow. In case that large amount discharge which includes heavy metals and toxic substance is expected and especially low flow season, the project proponent would review the internal target value and set strict standard for pre-treatment, if necessary. Therefore, the impacts from wastewater to the surrounding environment would be less.
	Waste	В-	B-	B-	B-	B-		CO/CLP: The impact of the construction waste is expected to be limited because construction waste will be utilized to embankment work and scrap material by removal of structure will also be utilized as recyclable materials as much as possible. The rest of the waste will be treated by outsourcing to the private waste treatment firm in Thilawa SEZ which has functions of recycling, intermediate treatment, and the controlled landfill site or other proper waste treatment facilities outside of Thilawa SEZ. OP: Impact of industrial and business-related waste generated from the Project in addition to logistic and commercial areas of Zone B and Zone A is expected to be limited because a solid waste management facilities in Zone A which has functions of recycling, intermediate treatment, and the controlled landfill site and enough capacity of receiving waste from all of the industrial waste and business-related waste in Zone A and Zone B.
Pollution	Soil Contamination	B-	B-	B-	D	B-	D	CO: In the construction phase, all excavated soil would be backfilled into the Thilawa SEZ Zone B area as embankment soil. Excavated soil would not cause any soil contamination inside the industrial area and the surrounding area because soil quality of the industrial area as well as the entire area of Thilawa Zone B was observed complying with the relevant environmental standards. OP: Industrial wastewater discharged by the tenants would be collected and treated properly in the central wastewater treatment plant. Domestic wastewater would be treated by septic tanks at each tenant, while the pollution from stormwater runoff would be controlled and minimized as much as possible. With reference to the process of usage, producing, storing, disposing and handling of oil, chemical, dangerous or hazardous materials in the project area, the tenants must strictly comply with applicable laws, regulations at its sole responsibility and expense. The tenants shall treat the materials safety on the covered area to prevent infiltration of the materials to ground, and eliminate or dispose of all dangerous or hazardous materials and waste including, but not limited to, industrial waste to prevent from distributing to the soil environment. Hazardous waste (if any), industrial waste, and domestic waste would be well controlled and managed by each tenant. Solid waste receptacles or trash containers must be large enough to facilitate storage and collection and be installed within the land of

			ping Re	sult		sment I	Result	
Category	Scoping Item	PC/ CO	OP	CLP	PC/ CO	OP	CLP	Reason for Assessment
								tenant. Therefore, soil contamination caused by the tenants is estimated to be limited. CLP: Demolition work in the Project site and domestic activities during the period would not be expected to cause any pollution to the soil environment.
	Noise and Vibration	B-	B-	В-	B-	В-		CO/CLP: Impacts of noise and vibration from construction machineries are expected to be limited because noise and vibration caused by construction work are site specific and temporary events. Impact of noise and vibration from construction vehicles is expected to be limited because the construction vehicular traffic volume is estimated to be little compared with the present traffic volume. OP: Impacts of noise and vibration by tenants are expected to be limited because mitigation measures such as, sound—absorbing materials, installing the facility in the house, having the enough buffer zone for noise and installing vibration control devices for equipment, design of the structure to disconnect between the sources and ground for vibration, will be installed as necessary. In addition, the arrangement of the land allocation for each tenant and the installation of buffer zone with less noise and vibration impacts to the surrounding sensitive receivers (monastery, residence etc.) shall be considered by the project proponent, as possible. Impacts of noise and vibration from traveling vehicles are expected to be limited because noise and vibration levels are forecasted to be less than the target levels.
	Ground Subsidence	D	D	D	D	D		CO: Groundwater will be used during the construction phase; however, no impact is expected because there is no change in ground elevation as monitored by Zone A Project and the same kind of construction work will be conducted in the industrial area of Zone B. OP/CLP: No activities are planned that will cause ground subsidence.
	Offensive Odor	D	B-	D	D	B-		CO/CLP: There is no factor to cause offensive odor OP: With reference to usage, producing of disposing and handling of dangerous or hazardous materials in the project area, the tenants must, at its sole responsibility and expense, shall treat safety manage, eliminate or dispose of all dangerous or hazardous materials and waste to prevent from distributing to the offensive odor. Stack emissions of odor generally can be controlled using waste reduction, waste minimization and cleaner production principles or conventional emission control equipment. Therefore, odor caused by tenants is estimated to be limited.
	Bottom Sediment	D	В-	D	D	В-		CO/CLP: No construction works are planned that will cause impact on bottom sediment. OP: Impact on bottom sediment is expected to be limited because water discharge from the tenants will be treated at the treatment plant to comply with the industrial wastewater effluent guideline value stipulated by MOI and MOECAF and the proposed internal regulation. Basically, it is expected that concentration of wastewater is

			ping Re	esult		sment I	Result	
Category	Scoping Item	PC/ CO	OP	CLP	PC/ CO	OP	CLP	Reason for Assessment
								diluted by mixing with stormwater through the retention pond and creek flow. In case that large amount discharge which includes heavy metals and toxic substance is expected and especially low flow season, the project proponent would review the internal target value and set strict standard for pre-treatment, if necessary.
Natural Environment	Protected Areas	D	D	D	D	D	D	Since no natural preservation area and national parks exist in and around Zone B, impact on the protected
	Flora/Fauna and Ecosystem	C	C	С	B-	B-		areas is not expected. Based on the field survey, it was observed that biodiversity in the project area is not rich because of the fact that the area has been inhabited and cultivated by local people for a long time. In addition, the area, located near Yangon City, has been recently urbanized and strongly industrialized with the presence of industrial areas and deep terminals. The project area is not a special area in terms of biodiversity and ecosystem. Similar ecosystem and equivalent level of biodiversity would be found in nearby areas. There were 1 threatened species (1 reptile) and 5 near threatened species (2 birds and 3 fishes) recorded in the area. However, threatened species was interview information around 2008 and no information in recent years and this field survey. As for 2 birds, near threatened bird species are relatively common and observed in a wide area in Myanmar, though classified as NT by IUCN list. These bird species can easily move to other places, because they can find similar habitats such as near water, grassland, marshes, etc. in nearby areas. Clear marking of boundary of the project site to prevent the contractor from clearing the vegetation outside of the project site. Considering near threatened fish species, their habitats would remain unchanged as they can keep living in the existing creeks and lakes. Though clearing the vegetation due to the implementation of the project, greening of the public space along the main road, sub road and retention pond in the project area of Zone A and Zone B will help to mitigate the change of biodiversity and ecosystem. Therefore, the development of the project would not cause any significant impact on biodiversity and ecosystem of the region
	Hydrology	В-	В-	В-	В-	В-		PC/CO: Impact on hydrology is expected to be limited because the excavation and embankment work would be designed to minimize the excavation volume and embankment volume as much as possible, so that the water flow would not change significantly. OP: Impact on hydrology is limited because stormwater flow to the river will be equalized through retention ponds and minimized making changes to the water current and riverbed.
	Topography and Geology	D	D	D	D	D	D	CO/CLP: Since there are no unique topography and geology in this area, no impact from construction is expected. OP: No activities are planned that will cause impact on topography and geology.
	Soil Erosion	В-	В-	В-	В-	В-	В-	CO/CLP: Soil erosion in the bare area/bank would occur as a result of rainwater. OP: Impact of erosion on the creek is limited because the storm water and wastewater from the project site will be controlled by the

			ping Re	sult		sment I	Result	
Category	Scoping Item	PC/ CO	OP	CLP	PC/ CO	OP	CLP	Reason for Assessment
Social	Involuntary	A-	A-	D	A-	A-	D	designed retention pond and retention canals. PC:
Environment	Resettlement							Impact of Land Acquisition and Involuntary Resettlement Involuntary resettlement of 161 households is expected because the land acquisition of uncompensated land will be required partially for the implementation of the Project. However, the impact will be minimized by providing assistance for the loss of assets/income source and livelihood/relocation in kind or with cash based on Resettlement Framework for 2,000 ha prepared by TSMC. In addition, the relocation of the households currently living in the proposed relocation site is anticipated because of the development of the relocation site. However, TSMC will organize an adequate consultation with the households in a timely manner and provide compensation/ assistance as necessary. OP: Impact on Livelihood of Relocated Households Among the 161 households to be affected by the Project, 141 households are required to relocate from their current living place to other place. Therefore, it is expected the impact on the livelihood of relocated household is expected due to the changes more or less in their situation. However, the impact will be mitigated due to the implementation of an Income Restoration Program (IRP) based on the Framework
	Living and Livelihood	A-/ B+	A-/ B+	С	A-/B- /B+	A-/B- /B+	B- /B+	for 2,000 ha by TSMC. PC/ CO/ OP: Impact to PAHs by Land Reclamation (A-) Among the project affected households (PAHs), approx. 40% would lose their land-based income source and approx. 60% would lose their non land-based income source due to the resettlement through the land reclamation. However, the impact on PAHs will be minimized by providing assistance package based on the Resettlement Framework for 2,000 ha under the responsibility of TSMC. In addition, TSMC will provide IRP activities such as job matching and facilitation of job opportunity for some PAHs who would spend some time to restore their living after their resettlement. Furthermore, the project proponent will provide job opportunity and community support program as necessary together with TSMC in order to improve the situation on the living and livelihood in the community. CO/ OP/ CLP: Impact to Surrounding Community (B-) In construction and operation phase, unexpected impact on living and livelihood of the surrounding community would be arisen due to the construction work and the operation. In order to improve the situation on the living and livelihood, the project proponent will provide job opportunity and community support program targeting the surrounding community based on the request from the community. In closing phase, it is expected that some people who would lose their income source belonging to the Project due to the termination on the operation of tenants. Employment contract between tenants and workers is prepared under the supervision of OSSC labor section in order to secure the worker's

			ping Re	sult		sment I	Result	
Category	Scoping Item	PC/ CO	OP	CLP	PC/ CO	OP	CLP	Reason for Assessment
								labor right by confirming termination service. In case the termination service will be not preceded fairly, workers are able to request authorized labors officers of OSSC to settle and resolve the situation. In addition, the employment service will be provided with the cooperation and facilitation of Dept. of Labor for terminated worker's alternative livelihood. CO/ OP/ CLP: Impact on Improvement of Local Economy (B+) There will be the improvement of local economy due to the increase of job opportunity with the start of the construction/ demolished work and the operation by the Project.
	Vulnerable Group	A-/ B+	A-/ B+	D	A-/B- /B+	A-/B- /B+		PC/ CO/ OP: Impact to Vulnerable PAHs by Land Reclamation (A-) Among the PAHs, 36 households are defined as vulnerable people in the Project. In order to mitigate the impact, special attention will be given to them by providing additional assistance based on the Resettlement Framework for 2,000 ha under the responsibility of TSMC since they are more easily affected by the Project than non-vulnerable people. In addition, TSMC will provide IRP activities such as job matching and facilitation of job opportunity for some PAHs who would spend some time to restore their living after their resettlement. Furthermore, the project proponent will provide special support targeting vulnerable people based on their request as necessary in order to mitigate the impact on their living and livelihood. CO/ OP: Impact to Surrounding community (B-) Unexpected impact on vulnerable group of the surrounding community would be arisen due to the construction work and the operation. In order to improve the situation on their living and livelihood, the project proponent will provide job opportunity and community support program based on the request from the community. CO/ OP: Impact on Improvement of Local Economy (B+) There will be the improvement of local economy due to the increase of job opportunity with the start of the construction/ demolished work and the operation by
	Local Conflict of Interests	A-	A-	D	B-	B-		the Project. PC/CO/OP: Relocated PAHs and the host community in the relocation site In the proposed relocation site, sudden increase of the population is expected during the short period due to the relocation of PAHs. The host community will face more or less changes and inconvenience in various aspects of their life. Also, there would raise negative feeling to PAPs among host community. In response to the situation above, TSMC will consider planning the arrangement of necessary public facilities, and also will support to establishment the harmonization with host communities based on Resettlement Framework for 2000 ha to avoid the serious conflict. PAHs of Zone A and PAHs of the Project There is a possibility to occur complains regarding difference in compensation between PAHs of Zone A and the Project (Zone B). In this case, TSMC will

			ping Re	sult		sment I	Result	
Category	Scoping Item	PC/ CO	OP	CLP	PC/ CO	OP	CLP	Reason for Assessment
								provide enough explanation of the fairness in compensation in order to avoid serious conflict. Construction workers and local people It is expected to raise complain from local people against migrated construction workers because of worker's behavior such as disposing garbage and bad driving manner in community without any consideration etc. In this case, the construction contractor should provide necessary education and instruction to worker in order to avoid the conflict.
	Misdistribution of Benefit and Damage	В-	В-	D	B-	B-	D	PC/CO/OP: Impact of the assistance to be provided by TSMC Under the Project, the assistance for PAHs is basically designed to restore their livelihood to at least the pre-displacement level by mitigating the negative impact of the involuntary resettlement due to the change caused by the Project. Therefore, there is no misdistribution of benefit between PAHs and non-PAHs by the Project as a result of the assistance to be provided by TSMC. Impact on the living environment in the local community The living environment of local people would be directly or indirectly affected by the construction work or the operation of each tenant. In case of the problem, local people can communicate with the community relation department of the project proponent to solve the raised issues. In addition, the project proponent will implement community support programs as the one of CSR activities in order to help establishing harmonization with local communities and to balance the impacts of the Project. As a result, misdistribution of benefit and damage would be minimized by the effort of the project proponent.
	Children's Right	B-	B-/ B+	D	B-	B-/ B+	B-	Impact on Educational Opportunity of School Children in Relocated PAHs PC/CO: Since there are a total of 118 school children among the relocated PAHs, children's education would be temporarily disrupted due to relocation. In this case, TSMC will provide cash assistance for commuting to school and will consider measure as part of the IRP activities to minimize the impact based on the dialogue with PAHs. On the other hand, it is expected the educational opportunity will be provided more with the community support programs by the project proponent and also children would be indirectly influenced by the improvement of social infrastructure in the region as a result of the Project. Impact on Educational Opportunity of School Children of local community OP: So far, the project proponent has implemented "Thilawa SEZ neighboring students Support Program" and, around 1,000 students were benefited from this program. In addition, the project proponent will implement the educational programs continuously based on needs and requests from the community in the future. Therefore, it is expected that the educational opportunity will be improved by the effort of the project proponent by the Project. Impact on Increase of Child Labor CO/OP/CLP: Basically, children below 13 years old

			ping Re	esult		sment I	Result	
Category	Scoping Item	PC/ CO	OP	CLP	PC/ CO	OP	CLP	Reason for Assessment
								are not prohibited to work in any shop, commercial establishment or factory according to the labor law in Myanmar. As long as the Project and tenants keep laws in Myanmar, illegal child labor will be prevented in employment of labors. In addition, the labor section of OSSC will supervise tenants not to employ children as labors illegally at the time of each worker's registration for Thilawa SEZ. Therefore, child labor would be controlled well to prevent employing.
	Existing Social Infrastructures and Services	B-/ B+	B-/ B+	D	B-/ B+	B-/ B+	D	Impact to Relocated PAHs of the Project PC/CO: Accessibility of PAHs to social infrastructure/service would be affected more or less due to the relocation. On the other hand, the proposed relocation site will be arranged with basic social infrastructures as a part of the assistance by TSMC. Impact to Local People in the local Community of the project area CO: Accessibility of social infrastructure/ service will be affected due to the increase of construction vehicles. The traffic volume should be controlled by construction contractor to avoid serious traffic congestion. OP: Accessibility to social infrastructure would be limited by the existence of the tenants. On the other hands, it is planned to construct community road which has alternative function in order to keep the accessibility of the existing road for the local community. In addition, basic infrastructures such as the existing road and power supply will be improved due to the ongoing infrastructure development projects around Thilawa SEZ.
	Water Usage	С	С	D	В-	В-	D	CO: One pond and one water pump will not be able to use continuously due to the development. Basically it should be appropriately compensated under the compensation policy of YRG and TSMC. Moreover, the project proponent will arrange alternative pond near the pond for the community considering the situation as necessary. In addition, the deterioration of the local water resource such as adjacent wells and lake is expected due to the discharging water from construction site. However, it will be controlled well by installing settling ponds or simple turbid water treatment and septic tank. OP: The impact on the local water reservoir is not expected since the amount of water consumption for the Project will be managed and additional water supply source is planned to utilize. For the water quality in creek near the project area, it will be controlled well by managing drainage ditch and retention ponds. Basically, it is expected that concentration of wastewater is diluted by mixing with stormwater through the retention pond and creek flow. In case that large amount discharge which includes heavy metals and toxic substance is expected and especially low flow season, the project proponent would review the internal target value and set strict standard for pre-treatment, if necessary.
	Cultural Heritage/Asset	В-	D	D	B-	D	D	CO: One cemetery will be directly affected by the Project and some adjacent monasteries and

			ping Re	sult		sment I	Result	
Category	Scoping Item	PC/ CO	OP	CLP	PC/ CO	OP	CLP	Reason for Assessment
								Hindu temples will be indirectly affected due to the construction work. Therefore, it will be considered the several measure to keep this utility for the community under the understanding of local people by the adequate dialogue with them.
	Landscape	D	B-/ B+	D	D	B-/ B+		Impact of alteration of landscape resources (B-) OP: Since the late of 2013, the landscape has been already changed time by time since the construction work of Zone A. Moreover, 266ha of agricultural land will be cleared and altered to industrial area as the part of Zone B development. Therefore, the existing landscape is in the process of semi-urbanization due to Zone A development and it will push the semi-urbanization more and more due to the Project. Impact of Landscape design within the SEZ (B+) PP: Although semi-urbanization of landscape in and around Thilawa SEZ is inevitable, the development will be implemented under the project proponent internal regulation which rules to secure the environmental friendliness for users and residents, and harmonization with the surrounding area. In addition, greening area will be established in each plot and public space. Therefore, as long as the tenants follows the internal regulation and the project proponent will make effort to maintain the public area, the landscape of the project area is expected to be well-maintained semi-urbanized area
Health and Safety	Risks for Infectious Diseases such as AIDS/HIV	B-	B-	В-	B-	B-	В-	CO/OP/CLP: Risks for communicable and vector-borne disease are expected among workers and the surrounding local community due to the influx of labors from outside. In order to minimize the impact, preventive measures against such diseases, which is stipulated in the Environment, Health, and Safety (EHS) Guidelines of the International Finance Corporation (IFC), should be considered and implemented by construction contractor and each tenant in respective stage. In addition, existing public health care program will be utilized in cooperation with local government, and the project proponent will plan CSR activities regarding health care.
	Occupational Health and Safety	B-	B-	В-	B-	B-	В-	Impact on occupational health and safety CO/OP/CLP: Impacts on occupational health and safety (OHS) are inevitable due to the construction/demolished work, operation of tenants. In order to minimize the impacts, construction contractor/each tenant/ the project proponent shall take mitigation measures stipulated in EHS Guidelines of IFC Since the type of business is different in each tenant, the mitigation measure should be prepared considering the respective occupational risk under the respective impact assessment. Impact on labor right CO/OP/CLP: It is expected that labor rights for workers of the Project would be secured by construction constructor and each tenant with the related labor laws under the supervision of TSMC. In case of any disputes or conflicts between employee and employer, authorized

			ping Re	esult		sment l	Result	
Category	Scoping Item	PC/ CO	OP	CLP	PC/ CO	OP	CLP	Reason for Assessment
								labors officers of TSMC provide the coordination with employee to resolve the situation.
	Community Health and Safety	B-	В-	В-	В-	B-	B-	CO/CLP/OP: It is expected the impact on public safety due to the vehicle traffic, which is cumulatively increased by the surrounding development project, and the operation of heavy machineries. It is also expected the impact on public security due to the influx of labors and people for the implementation of the Project. To minimize impacts, the mitigation measures stipulated in the EHS Guidelines of the IFC should be taken by construction contractor/the project proponent. In addition, the project proponent will consider community health program as a part of CSR activities based on the request from the community regarding public safety and security.
Emergency Risk	Usage of Chemicals	D	B-	D	D	B-	D	OP: During the operation phase, some tenants would use chemical materials to be managed under specific condition. In addition, Material Safety Data Sheet (MSDS) will be utilized in order to let workers know about requirements and standards of the chemicals. Risk of chemical material is expected to be limited because the tenants will be required to prepare proper chemical substances management plan and to comply with applicable regulations/laws with reference to usage, producing, storing, disposing and handling of dangerous and hazardous materials as stipulated in the proposed internal regulation
	Flood Risk	В-	В-	В-	В-	В-	В-	CO/OP/CLP: Flood risks such as heavy rain, cyclone, and high tide are expected to be limited because land reclamation plan is prepared considering EL+5.5-7.0 m, which is higher than EL +4.24 m, 100 years return rainfall flood analysis of EL+4.9 m, storm surge simulation in Yangon River of E.L. +5.5.
Emergency Risk	Risk of Fire	B-	В-	B-	В-	B-		CO/CLP: Risk of fire is expected to be limited because the fire safety plan and equipment will be prepared by the project proponent to comply with the Building Construction and Fire Safety Rule regulated by TSMC. OP: Risk of fire is expected to be limited because the tenants shall install and maintain an effective fire alarm system and firefighting system for each building in the plot with reference to the TSMC rules and the proposed internal regulation.
	Earthquake	B-	B-	B-	B-	B-		CO/CLP: There is a possibility for an earthquake to occur. However, the contractor for construction and demolition work will prepare disaster prevention activities to minimize the damage. Therefore, the negative impact of the earthquake would be limited. OP: There is a possibility for an earthquake to occur. However, each tenant would design and construct properly to meet the required standard such as quake-resistance standard. Therefore, the negative impact of anon earthquake would be limited.

		Sco	ping Re	esult	Asses	sment l	Result	
Category	Scoping Item	PC/ CO	OP	CLP	PC/ CO	OP	CLP	Reason for Assessment
Other	Global Warming	B-	B-	B-/ B+	B-	B-		 CO: Emission of greenhouse gases (GHGs) would be generated from construction machineries and vehicular traffic caused by the Project. OP: Emissions of GHGs would be generated from vehicular traffic in the Project and operation of the tenants. CLP: Emission of GHGs would be generated from construction machineries and vehicular traffic caused by the Project. On the other hand, emissions of GHGs from operation activities would be reduced.

Note: PC: Pre-construction Phase, CO: Construction Phase, OP: Operation Phase, CLP: Closing Phase
Evaluation: A-: Significant Negative Impact
B-: Some Negative Impact
B-: Some Positive Impact
B-: Some Positive Impact

C: Impacts are not clear, need more investigation
D: No Impacts or impacts are negligible, no further study required
Source: EIA Study Team

7.2 Air Quality

7.2.1 Forecast Item

The following items were examined to forecast the impact:

- Air pollution along the main roads increased due to construction vehicles of the Project.
- Air pollution caused by construction work of the Project.
- Air pollution along the main roads increased during the operation phase of Zone B.
- Air pollution caused by the tenants during the operation phase in the Project.

7.2.2 Forecast Area

The area examined to forecast the impact was set around Thilawa SEZ.

The forecast points for the main roads nearby Thilawa SEZ were set as shown in Figure 7.2-1. These forecast points are located along the Thanlyin-Thilawa Road and Dagon-Thilawa Road.



Source: EIA Study Team

Figure 7.2-1 Forecast Points for Air Pollution along the Road

7.2.3 Forecast Period

As for the construction phase, the period examined to forecast the impact was set during the construction work period for the Project.

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases, i.e., when all the tenants in the industrial area and logistic area of Zone B as well as Zone A would start their operation.

7.2.4 Forecast Method

The forecast of air pollution impact was conducted as follows:

- To examine the air pollutant emission by considering the number of construction vehicles for the Project during the construction phase;
- To examine the air pollutant emission by considering the construction work plan for the Project during the construction phase;
- To estimate the NO₂ and PM₁₀ concentration¹ increase due to vehicle traffic generated in Zone B during the operation phase to assess its impact in the surrounding area; the prior development of Thilawa SEZ Zone A was also included; and
- To estimate the air pollutant emission by considering the possible tenants in the industrial and logistic area during the operation phase.

The methodology of the impact forecast is described below.

(1) Forecast Conditions

1) Road Traffic Volume from Thilawa SEZ during the Operation Phase

The traffic volumes on each forecast point during the forecast period were estimated based on the tentative road network system of Thilawa SEZ Zone A as reported in the Preparatory Study on Thilawa SEZ Infrastructure Development in the Republic of the Union of Myanmar (2013) and Final report of the preparatory survey for the project for expansion of Yangon Port in Thilawa area (2013). Basic concept is explained as follows:

Commuter Traffic Volume to Thilawa SEZ

The number of commuters from Thilawa SEZ Zone A and Zone B was assumed as 30,231. Basis for calculation is shown in Table 7.2-1. The numbers and percentages, such as unit number of labor per unit area and number of commuters out of SEZ, were utilized from the report of the JICA Preparatory Study on Thilawa SEZ Infrastructure Development in the Republic of the Union of Myanmar (2013).

_

 $^{^1}$ As a result of the field survey, SO₂ and CO levels during both rainy and dry seasons were less than half of the applied standards. Relatively high NO₂ and PM₁₀ concentration might be due to vehicle exhaust emission. In this connection, NO₂ and PM₁₀ were selected as a representative parameter to assess the environmental impact of air pollution due to the increase of traffic. PM2.5 was not selected as a representative parameter, because its production mechanism has not been elucidated vet

	Zone	Selling Area of Each Zone (ha)	Unit Number of Laborer per Unit Area (person/day·ha)	Number of Laborers (person/day) ③ =①×②	Number of Commuters Out of SEZ Zone A (person/day) (4=3×0.421)	Number of Commuters that will Use Car or Public Transport (person/day) (5=4) × 0.7 ²)
A	Industrial 284.0		200	56,800	23,856	16,699
В	Industrial Area	183.4	200	36,680	15,406	10,784
В	Logistics Area	186.9	50	9,345	3,925	2,748
	Total	-	-	102,825	43,187	30,231

Table 7.2-1 Estimation of Commuters Using Vehicles from Thilawa SEZ

The commuter traffic volume is assumed as 24,789. Basis for calculation is shown in Table 7.2-2.

Table 7.2-2 Traffic Volume of Commuting and Returning to/from SEZ

	Zone	Transportation	Commuting Rate of Each Vehicle ¹⁾	Number of Commuters Using Each Vehicle	Average Unit Number of Passengers	Generated and Attracted Traffic Volume
			(%)	(person/day)	(person/car)	(car/day)
			6	$7=5\times6$	8	9=7/8×2
	Industrial	Two-wheel Vehicle	38	6,346	1	12,692
Α	Area	Four-wheel Light Vehicle	2	334	2	334
		Four-wheel Heavy Vehicle	60	10,019	30	668
	Industrial	Two-wheel Vehicle	38	4,098	1	8,196
	Area	Four-wheel Light Vehicle	2	216	2	216
В		Four-wheel Heavy Vehicle	60	6,470	30	431
ь	Logistics	Two-wheel Vehicle	38	1,044	1	2,088
	Logistics Area	Four-wheel Light Vehicle	2	55	2	55
	Alea	Four-wheel Heavy Vehicle	60	1,649	30	110
						Two-wheel 22,976
	Total			30,231		Light Vehicle 605
	10141	-	-	30,231	_	Heavy Vehicle 1,209
						24,790

Note 1) Different from inner Yangon City, bus network is not well developed near Thanlyin and the area around Thilawa SEZ Zone A. The percentage of commuters using fixed route bus out of all commuters using vehicles and public transportation is set at 30%. The percentage of those using pickup bus is set as the same percentage as those using fixed route bus, i.e., 30%. Almost all workers cannot buy their own car; thus, persons who will use their own car are assumed only at 2% out of the remaining 40%. Thus, 38% of the workers will use their bicycle or bike.

Source: EIA Study Team

Trip Generation from Commercial Area

The amount of trip generation from the commercial area was assumed as 5,970 person/day. This estimate is based on the planning manual for urban transportation with large-scale development in Japan. Basis for calculation is shown in Table 7.2-3.

Note 1): Percentage of commuters outside of Thilawa SEZ was referred to Thilawa Special Economic Zone Development Project (Class A) Environmental Impact Assessment Report.

^{2):} According to a research on actual condition of commuting in South East Asia, about 30% of people whose wages are lower than USD 150/month commute by foot. Using this data, traffic volume after the development of Thilawa SEZ is estimated. Source: EIA Study Team

		Zone	Total Store Floor Area	Trip Generation Unit ¹⁾	Correction Factor ²⁾	Trip Generation	Customer Ratio from Outside of SEZ ³⁾	Generated and Attracted Trip
			(ha)	(person/ day•ha)	-	(person/day)	(%)	(person/day)
			1	2	3	4=1×2×3	5	6=4×5
	В	Commercial Area	16.1 ¹⁾	10,600 ²⁾	$0.7^{(3)}$	66,700	5% ⁴⁾	5,970

Table 7.2-3 Estimation of Trip Generation from Commercial Area

- Note 1): Store floor area is assumed from Master Plan & Infrastructure Feasibility Study Report Thilawa SEZ Zone B. (13/01/2016) Total store floor area is estimated as 30% of building area of commercial use (53.8ha).
 - 2): Trip generation unit is quoted from planning manual for urban transportation with large-scale development in Japan.
 - 3): This correction factor is specified in the manual as decrease ratio based on commercial area scale.
 - 4): This rate is assumed from the land use situation around SEZ.

Source: EIA Study Team

The amount of traffic volume for commercial area was assumed as 3,184 car/day. Basis for calculation is shown in Table 7.2-4.

Table 7.2-4 Traffic Volume of Commercial Area

	Zone	Transportation	Usage Rate of Transportation	Number of Customers Using Vehicle	Average Number of Passengers	Generated and Attracted Traffic Volume
			(%)	(person/day)	(person/car)	(car/day)
			7	$8 = 6 \times 7$	9	10=8/9
		Two-wheel Vehicle	33%	1,990	1	1,990
D	Commercial	Four-wheel Light Vehicle	33%	1,990	2	995
В	Area	Four-wheel Heavy Vehicle	33%	1,990	10	199
	Total	-	-	-	-	3,184

Source: EIA Study Team

Freight Transport

Traffic generation of freight transportation from the SEZ area was estimated under the following assumptions:

✓ Amount of cargo handling will be 1,600,000 TEU/year in Thilawa area port in 2025.

✓ Transportation volume between Thilawa area port and SEZ will be 1,280,000 TEU/year $(1,280,000 = 1,600,000 \times 80\%)$

✓ The remaining cargo of 20% will be transported between Thilawa area port and Yangon City directly.

 $(320,000 = 1,600,000 \times 20\%)$

✓ Transportation volume between Thilawa SEZ and Yangon City will be 256,000 TEU/year. (256,000 = 1,280,000×20%)

Basis for calculation is shown in Table 7.2-5.

Zone		0	Selling Area of Each Zone		Transportation Volume between Thilawa SEZ and Yangon City		Volume between Thilawa SEZ and Weight per TEU* Capacity of Heavy		Operating Days	Generated and Attracted Traffic Volume
		(ha)	(%)	(TEU	(TEU/year)		(t/car)	(day/year)	(car/day)	
			Area Ratio	Total ②	3=1×2	4	5	6	7=3×4/5/6	
A Industrial Area		284.0	43.4%	256,000	111,117	10	20	250	222	
B Industrial and Logistics Area		3703	56.6%	230,000	144,883	10	20	250	290	
Total		654.3	100.0%	-	256,000	-	-	-	512	

Table 7.2-5 Amount of Freight Transportation from Thilawa SEZ Area

* TEU: twenty-foot equivalent unit

Source: EIA Study Team

2) Trip Distribution


Generated and attracted traffic volume will be distributed to the access routes in the perimeter of SEZ. The distribution rates, which are referred from the EIA report of Zone A, are shown in Table 7.2-6 and the route map is shown in Figure 7.2-2

Table 7.2-6 Distribution Rate of Each Access Road to Thilawa SEZ

Transportation		Route 1	Route 2	Route 3		
Two-wheel Vehicle		Vehicle 15.05%		15.05%		
Four-wheel L	Four-wheel Light Vehicle		69.9%	15.05%		
Four-wheel	Bus	15.05%	69.9%	15.05%		
Heavy Vehicle	Freight	0.0%	0.0%	100.0%		

Note Distribution rate of above table is referring to EIA Report for Thilawa Special Economic Zone Development Project (Class A). In this EIA study, Traffic volume bound for Kyauktan Township is divided on Route 1 and Route 3.

Source: EIA Study Team



Source: EIA Study Team

Figure 7.2-2 Transport Route from/to Thilawa SEZ and Forecast Points

Traffic volumes of each route are shown in Table 7.2-7.

Table 7.2-7 Estimated Traffic Volume of Each Access Route

(Unit: car/day)

			Route 1			Route 2			Route 3	
	Zone	Two- wheel Vehicle	Four- wheel Light Vehicle	Four- wheel Heavy Vehicle	Two- wheel Vehicle	Four- wheel Light Vehicle	Four- wheel Heavy Vehicle	Two- wheel Vehicle	Four- wheel Light Vehicle	Four- wheel Heavy Vehicle
A	Industrial Area	764	50	101	3,549	233	467	764	50	323
	Industrial Area	493	33	65	2,292	151	301	493	33	
В	Logistics Area	126	8	17	584	38	77	126	8	401
	Commercial Area	120	150	30	556	696	139	120	150	
	Subtotal	739	191	112	3,432	885	517	739	191	401
	Total	1,503	241	213	6,981	1,118	984	1,503	241	724

Note: It is assumed that 60% of two-wheel vehicles are bicycle and 40% are bike.

Source: EIA Study Team

3) Traffic Volume at Forecast Points

The traffic volumes at forecast points, namely, location 1 (Route1) and location 2 (Route 3) are shown in Table 7.2-8. Present traffic volumes are mentioned in Section 6 of the Chapter 6.

Table 7.2-8 Traffic Volume at Forecast Point during Operation Phase

	Type of Vehicle	Present Traffic Volume	Rel to Thila	Volume lated awa SEZ s/day)	Total Traffic Volume (cars/day)		
		(cars/day)	Zone A	Zone B	Start of Operation of Zone A	Start of Operation of Zone B	
	Two-wheel Vehicle	9,098	3,549	3,432	12,647	16,079	
Location 1	Four-wheel Light Vehicle	2,928	233	885	3,161	4,046	
(Route2)	Four-wheel Heavy Vehicle	1,135	467	517	1,602	2,119	
	Two-wheel Vehicle	3,132	764	739	3,896	4,635	
Location 2	Four-wheel Light Vehicle	1,443	50	191	1,493	1,684	
(Route3)	Four-wheel Heavy Vehicle	1,142	323	401	1,465	1,866	

Source: EIA Study Team

4) Coefficient of Discharge

The coefficient of discharge for NO₂ and PM₁₀ were set as shown in Table 7.2-9 and Table 7.2-10.

Table 7.2-9 Coefficient of Discharge for NOx

Unit: g/km/car

Traveling Velocity (km/hr)	Two-wheeled Vehicle (Bike)	Four-wheeled Vehicle (Car)	Four-wheeled Vehicle (Fixed Route Bus)	Four-wheeled Vehicle (Pickup Bus, 5 t bus)
30	0.047	0.097	1.67	0.0785
40	-	0.077	1.35	0.0571
50	-	0.070	1.23	0.0491

Source: Thilawa Special Economic Zone Development Project (Class A) Environmental Impact Assessment Report

Table 7.2-10 Coefficient of Discharge for PM_{10}

Unit: g/km/car

Traveling Velocity (km/hr)	Two-wheeled Vehicle (Bike)	Four-wheeled Vehicle (Car)	Four-wheeled Vehicle (Fixed Route Bus)	Four-wheeled Vehicle (Pickup Bus, 5 t bus)
30	0.006971	0.006971	0.179832	0.179832
40	-	0.005183	0.143874	0.143874
50	-	0.004194	0.121167	0.121167

Source: National Institute for Land and Infrastructure management Japan, Grounds for calculation of Motor vehicle emission factors using environment impact assessment of road project etc. (Revision of FY 2010) p6-6

7.2.5 Forecast Result

(1) Construction Phase

1) Impact from Vehicle Exhaust Emission along Route 2 (Thanlyin-Thilawa Road)

During the construction phase, air pollutants such as NO_2 , SO_2 , CO, $PM_{2.5}$, and PM_{10} would be discharged from construction vehicles. Taking into account the peripheral air quality situation, NO_2 was selected as a representative parameter of this study for exhaust emission. According to the actual result of construction works in Zone A, the traffic volume of the construction vehicles was at most about 200^1 vehicles a day. It would be assumed that the generated traffic volume of construction vehicles in the project area is the same as in Zone A.

Present traffic volume of Route 2 (Thanlyin-Thilawa Road) is approximately 4,000 cars per day. If 50% of the 200 construction vehicles will use Route 2, increment of traffic volume will not be more than 5%. Impact of air pollution is expected to be limited because construction vehicles will be little as compared with the current traffic.

Note 1): This daily traffic volume was set based on the construction work in Thilawa SEZ Zone A.

2) Impact from Vehicle Exhaust Emission along Route3 (Dagon-Thilawa Road)

Present traffic volume of Route 3 (Dagon-Thilawa Road) is approximately 2,500 cars per day. If 50% of the 200 construction vehicles will use Route 3, increment of traffic volume will not be more than 8%. Impact of air pollution is expected to be limited because construction vehicles will be little as compared with the current traffic.

3) Impact from Construction Machineries

During the construction phase, the dust would be generated by the landfill activity in the project site, and air pollutants would be discharged from construction machineries at specific and temporary time. The dust generated by cutting, heaping up and transporting the earth shall be controlled and minimized by sprinkling a road and cleaning the tire. The air pollutants discharged by construction machineries shall be controlled and minimized by the contractor. Impact of air pollution is expected to be limited because dust and emission gases from construction works will be diffused within a narrow area near the construction site and construction works are temporary events. As one example, air monitoring results in Zone A during construction are still acceptable level.

Hence, it is judged that air pollution from the construction work of the Project would not cause any significant environmental impact in the surrounding area.

(2) Operational Phase

1) Impact from Vehicle Exhaust Emission at the Residence Area (Route 2 and Route 3)

Regarding the NO₂ concentration at the residence area along the main roads, the NO₂ discharge amount from vehicles and contribution rate in each phase are shown in Table 7.2-11 and Table 7.2-12.

Table 7.2-11 NO₂ Discharge Amount in Route 2 during Operation phase

	Traveling Velocity (km/hr)		Traff	ic Volume (car/day)	Discharge Amount (g/km/day)		
Tyme of Webieles				Operation	on Phase		Operation	on Phase
Type of Vehicles	Present	Operational	Present	Start of	Start of	Present	Start of	Start of
	1 i esciit	Phase	1 1 Cociii	Operation	Operation	1 Teschie	Operation	Operation
				of Zone A	of Zone B		of Zone A	of Zone B
Two-wheel Vehicle	30	30	9,098	12,647	16,079	427.6	594.4	755.7
Four-wheel Light Vehicle	30	50	2,928	3,161	4,046	284.0	221.3	283.2
Four-wheel Heavy Vehicle	30	50	1,135	1,602	2,119	1532.3	1970.5	2,606.4
Total	-	-	13,161	17,410	22,244	2243.9	2786.1	3,645.3
Contrib	100.0	124.2	162.5					

Source: EIA Study Team

Table 7.2-12 NO₂ Discharge Amount in Route 3 during Operation phase


		ng Velocity m/hr)	Traffic Volume (car/day)			Discharge Amount (g/km/da				
Type of Vehicles					Operation Phase		Operation	on Phase		
Type of venicles	Present	Operational	Present	Start of	Start of	Present	Start of	Start of		
	1 i esciit	Phase	1 1 esciit	Operation of	Operation	1 i esciit	Operation	Operation		
					of Zone B		of Zone A	of Zone B		
Two-wheel Vehicle	30	30	3,132	3,896	4,635	147.2	183.1	217.8		
Four-wheel Light Vehicle	50	50	1,443	1,493	1,684	101.0	104.5	117.9		
Four-wheel Heavy Vehicle	50	50	1,142	1,465	1,866	1404.7	1802.0	2295.2		
Total	-	-	5,717	6,854	8,185	1652.9	2089.6	2630.9		
Contr	Contribution Rate for Future Air Quality (%)									

Source: EIA Study Team

To use this rate, NO₂ concentration was estimated as shown in Figure 7.2-3 using the following steps:

- Step 1: To calculate contribution concentration at present air quality
- Step 2: To calculate contribution rate for future air quality (Table 7.2-11 and Table 7.2-12)
- Step 3: To calculate contribution concentration at future air quality
- Step 4: To estimate future NO₂ concentration

The forecasted concentration in each project phase is shown in Table 7.2-13 and satisfy the tentative target value. Besides, the utilization of tenants' commuter bus for workers will help to reduce the emission gas generated from private cars.



Source: EIA Study Team

Figure 7.2-3 Steps of NO₂ Concentration Calculation

Table 7.2-13 Forecasted Results of NO₂ Concentration

	Rou	ite 2	Route 3			
Concentration	Start of Operation of	Start of Operation of	Start of Operation of	Start of Operation of		
	Zone A	Zone B	Zone A	Zone B		
(A) Living Environment (ppm) ²	0.031					
(D) Contribution Concentration (ppm)	0.009	0.011	0.009	0.011		
(E) Estimated NO ₂ Concentration (ppm)	0.099	0.106	0.100	0.105		
Tentative Target Value (ppm)	0.108 (200μg/m³)					

Source: EIA Study Team

_

 $^{^{2}}$ Concentration of NO₂ in living environment was set based on the field survey result at paddy field, as shown in Table 6.1.6. Since the data of paddy field in dry season was obviously higher than that of road site, it was judged that dry season data was not applicable to general ambient condition. Therefore, the average of rainy season data was set as base line data in living environment.

Regarding the PM_{10} concentration at the residential area along the main roads, the PM_{10} discharge amount from vehicles and contribution rate in each phase are shown in Table 7.2-14 and Table 7.2-15.

Table 7.2-14 PM₁₀ Discharge Amount in Route 2 during Operation phase

		ng Velocity m/hr)	Traff	ic Volume (car/day)	Discharge	e Amount (g/km/day)
Type of Vehicles			Ope		Operational Phase		Operation	nal Phase
Type of venicles	Present	Operational	Present	Start of	Start of	Present	Start of	Start of
		Phase		Operation	-		Operation	
				of Zone A	of Zone B		of Zone A	of Zone B
Two-wheel Vehicle	30	30	9,098	12,647	16,079	63.4	88.2	112.1
Four-wheel Light Vehicle	30	50	2,928	3,161	4,046	20.4	13.3	17.0
Four-wheel Heavy Vehicle	30	50	1,135	1,602	2,119	204.1	194.1	256.8
Total	-	-	13,161	17,410	22,244	287.9	295.5	385.8
Contrib	Contribution Rate for Future Air Quality (%)							

Source: EIA Study Team

Table 7.2-15 PM₁₀ Discharge Amount in Route 3 during Operation phase


		ng Velocity m/hr)	Tra	ffic Volume (ca	ar/day)	Discharge	e Amount (g/km/day)		
Type of Vehicles				Operational Phase			Operation	nal Phase	
Type of Venicles	Present	Operational	Present	Start of	Start of	Present	Start of	Start of	
	1 I CSCIII	Phase	1 1 CSCIII	Operation of	Operation	1 i esciit	Operation	Operation	
				Zone A	of Zone B		of Zone A	of Zone B	
Two-wheel Vehicle	30	30	3,132	3,896	4,635	21.8	27.2	32.3	
Four-wheel Light Vehicle	50	50	1,443	1,493	1,684	6.1	6.3	7.1	
Four-wheel Heavy Vehicle	50	50	1,142	1,465	1,866	138.4	177.5	226.1	
Total	-	-	5,717	6,854	8,185	166.3	210.9	265.5	
Contr	Contribution Rate for Future Air Quality (%)								

Source: EIA Study Team

To use this rate, PM_{10} concentration was estimated as shown in Figure 7.2-4 using the following steps:

- Step 1: To calculate contribution concentration at present air quality
- Step 2: To calculate contribution rate for future air quality (Table 7.2-14 and Table 7.2-15)
- Step 3: To calculate contribution concentration at future air quality
- Step 4: To estimate future PM₁₀ concentration

The forecasted concentration in each project phase is shown in Table 7.2-16. At the operational stage of zone A, forecasted value will satisfy the tentative target value. After the beginning of operational stage of zone B, the forecasted value will be over the tentative target value. However, the present concentration is already over the tentative target value. And the forecasted concentration will be same order as present concentration. Besides, the utilization of tenants' commuter bus for workers will help to reduce the emission gas generated from private cars.



Source: EIA Study Team

Figure 7.2-4 Steps of PM₁₀ Concentration Calculation

Table 7.2-16 Forecasted Results of PM₁₀ Concentration

	Rou	ite 2	Route 3			
Concentration	Start of Operation of Zone A	Start of Operation of Zone B	Start of Operation of Zone A	Start of Operation of Zone B		
(A) Living Environment (mg/m ³) ³	0.018					
(D) Contribution Concentration (mg/m³)	0.026	0.034	0.032	0.041		
(E) Estimated NO ₂ Concentration (mg/m ³)	0.044	0.052	0.050	0.059		
Tentative Target Value (mg/m ³)	0.05					

Source: EIA Study Team

_

 $^{^{3}}$ Concentration of PM $_{10}$ in living environment was set based on the field survey result at paddy field, as shown in Table 6.1.6. Since the data of paddy field in dry season was obviously higher than that of road site, it was judged that dry season data was not applicable to general ambient condition. Therefore, the average of rainy season data was set as base line data in living environment.

2) Impact from Tenants in Industrial and Logistic Area

Air pollutants which might be discharged by the operations of tenant in the industrial and logistic area would be well controlled and managed by the tenants. Tenants associated with emission gas would not be anticipated. In case that a tenant which may cause exhaust gas pollution such as paper and heavy industries moves into the Thilawa SEZ Zone B, the tenant shall have its own arrangement to satisfy with the standard stipulated by the National Environmental Quality (Emission) Guidelines (NEQG) and IFC's general environmental and safety guidelines, under the requirement of the proposed internal regulation. Both guidelines define the small combustion facilities emissions guidelines as mentioned in section 2.3.1. And NEQG define the industry-specific guidelines which shall be applied by all projects to ensure that air emissions conform to good industry practice. The each tenant shall conduct the environmental management, mitigation measures and monitoring on air pollution for its operation activities in accordance with ECPP approved by OSSC/TSMC.

Moreover, the tenants which may cause adverse impact to air condition by installing of combustion facilities such as boilers, furnaces, engines etc. will be required to submit EIA or IEE Report with EMP including mitigation measures on air pollution to MONREC, depending on the scale. The tenant shall analyze the impact of air pollution and evaluate in the EIA or IEE report. The proposed mitigation measures, such as energy use efficiency, process modification, selection of fuels or other materials, the processing of which may result in less polluting emission, application of emission control techniques, if necessary, in the EIA or IEE report shall be conducted by each tenant.

Hence, it is judged that the air pollution caused by the Thilawa SEZ Zone B operation would not cause any significant environmental impact on the surrounding area. Besides, it is expected that the utilization of tenants' commuter bus for workers and set of speed limit for drivers help to reduce the emission gas generated from private cars, and installing of the less pollution measures/technique for combustion facilities will be adapted.

7.3 Water Quality


7.3.1 Forecast Item

The following items were examined to forecast the impact:

- Quality and quantity of wastewater discharged from the project area during the construction/closing and operation phases; and
- Environmental impact of water discharge (stormwater, domestic wastewater, and industrial wastewater) onto the receiving water bodies.

7.3.2 Forecast Area

The areas examined to forecast the impact were set in the project area and Shwe Pyauk Creek, which will receive discharge water from the project area. The location of the project area and the creak is shown in Figure 7.3-1.



Source: EIA Study Team

Figure 7.3-1 Location of Project Area and Creek

It is expected that inflow impact will not present clearly, because Yanon River flow rate⁴ is estimated over seven hundred times larger than that of Shwe Pyauk Creek crossing Thilawa SEZ including maximum wastewater from Zone A and Zone B.

_

⁴ Note; Yangon River flow rate was estimated to be about 600 m³/sec, based on the catchment area rate between Ayeyarwady River and Yangon River. Ayeyarwady river catchment area and flow rate is 415,700km² and 12,900 m³/s, and Yangon river catchment area is 18,954 km². (*Source: National Astronomical Observatory of Japan, Chronological Environmental Table 2015-2016 Encyclopedia of world river 2013*) Shwe Pyauk Creek average flow rate including maximum wastewater from ZoneA and Zone B development was estimated to be about 0.82 m³/sec, as shown in Table 7.3-2.

In addition baseline data in Yangon River would be not stable and change depending on time or location, because Yangon River is mixed by tidal influence and its basin has a lot of pollutant source such as industry, agriculture, residence and transportation of tanker.

In consideration of situation above, Shwe Pyauk Creek was set as the forecast area and survey point, in order to identify and evaluate the impact on water body due to the implementation of the Project.

7.3.3 Forecast Period

As for the construction/closing phases, the period examined to forecast the impact was set during the implementation of the construction/closing work for the Project.

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the project area start their operation.

7.3.4 Forecast Method

(1) Construction/Closing Phases

The impact of wastewater discharge during the construction/closing phases was assessed by evaluating the possibility of generation of muddy water and sewage water due to construction/demolition work and the application of suitable mitigation measures during the period.

(2) Operation Phase

The quality and quantity of industrial wastewater discharged from the industrial area during the operation phase was estimated based on:

- i) estimated water supply capacity for the industrial area
- ii) estimated quality of treated effluent from the industrial area

The environmental impact of the industrial wastewater on the Shwe Pyauk Creek was predicted by using a complete mixing model, as shown in the following formula:

$$C = \frac{C_1 \times Q_1 + C_2 \times Q_2}{Q_1 + Q_2}$$

where, C (mg/L): Concentration of pollutant in the creek after complete mixing with wastewater

C₁ (mg/L): Concentration of pollutant in the creek at the forecast point before mixing

C₂ (mg/L): Concentration of pollutant in the wastewater before mixing

Q₁ (m³/s): Flow rate of the creek at the forecast point before mixing

Q₂ (m³/s): Flow rate of wastewater discharge before mixing

The impact of stormwater and domestic wastewater discharged from the industrial area would be judged based on qualitative determination and evaluation of the proposed design of the Project.

7.3.5 Forecast Result

(1) Construction/Closing Phase

During the construction/closing phases, muddy water would be formed during the rainy season (May to October) from the exposed soil surface and discharged to receiving water bodies. The project proponent would request contractors to optimize the work schedule in order to minimize the generation of bare land, excavation, filling, and founding embankment as much as possible. Excavation work would be arranged appropriately as much as possible to be implemented and

completed in the dry season (November to April). If necessary, settling ponds would be set up to collect generated muddy water and to settle down particulate matter before discharged to the environment.

Considering domestic wastewater generated from lodging facilities provided for construction/demolition work, would be installed at the construction/demolition site by contractors for collecting and storing wastewater from toilets. The sludge in the septic tanks would be regularly collected to attain the highest treatment efficiency.

Hence, it can be judged that wastewater resulting from the construction/demolition work in the project area would not cause any significant impact on the surrounding area and downstream water bodies.

(2) Operation Phase

There are three types of wastewater generated from the industrial area during the operation phase which can have potential environmental impacts, namely: a) stormwater, b) domestic wastewater, and c) industrial wastewater.

1) Stormwater

Stormwater runoff from paved surfaces, roof of buildings, and facilities in the industrial areas would be collected by drains, then discharged to internal canals, and finally discharged to Shwe Pyauk Creek that further flows into the Yangon River. Stormwater runoff collected from different areas may contain different types and concentration of contaminants, which would be highly dependent on the implementation of control and mitigation measures to minimize spillage and leakage of fine materials, fuel, and waste onto the surface. Tenants, during their daily operation, would be requested to implement sufficient measures and controls to minimize spillage of materials during transfer and handling. The storage of materials, fuel, and waste would be examined regularly to detect any spillage and leakage. In addition, the project proponent will regularly monitor the quality of stormwater to ensure that its quality will comply with the tentative target value.

2) Domestic Wastewater

Domestic wastewater is generated from general domestic activities such as washing and toilet flushing inside the factories of the industrial area. Tenants would be requested to install the pre-wastewater treatment plant before discharging to the drains and centralized wastewater treatment system. The project proponent will monitor the quality of drainage water at the outlets toward Shwe Pyauk Creek to ensure that their quality will comply with the tentative target value.

3) Industrial Wastewater

a) Water Supply Capacity

As mentioned above, the project area would have an area of 262 ha. Water supply capacity for the industrial area was estimated based on the water supply plan at 80 m³/ha/day. Accordingly, maximum water supply capacity for the industrial area would be about 21,000 m³/day.

b) Wastewater Amount

Wastewater amount was estimated based on the water supply volume. Wastewater yield ratio to water supply was assumed as 80%. Therefore, maximum wastewater amount generated from the industrial area would be about $17,000 \text{ m}^3/\text{day}$.

c) Quality of Effluent

Wastewater generated from tenants would undergo preliminary treatment by tenants before discharged to a central wastewater treatment plant operated by the project proponent. The tentative target value of effluent water quality discharged to the surrounding water bodies is set by the project proponent,

which is pursuant to the industrial wastewater effluent guideline of the Ministry of Industry (MOI) and MOECAF as mentioned in Chapter 2.

d) Impact on Downstream River Basin

The environmental impact of industrial wastewater discharged onto the receiving creek was predicted by using a complete mixing model with assumptions on flow rate and concentration of pollutants in the creek.

Based on the field survey, the width and sectional area of Shwe Pyauk Creek were confirmed. The flow rate of the creek during the dry and rainy seasons was estimated by using Manning's equation and hypothetical values for its conditions, as presented in Table 7.3-1

Season	Sectional Area (m²)	Wetted Perimeter (m)	Slope	Manning Roughness Coefficient*	Flow Velocity (m/s)	Flow Rate (m ³ /s)
Rainy	4.9	7	0.000125	0.06	0.15	0.74
Dry	2.1	5.5	0.000125	0.06	0.10	0.21
Average	3.5	6.25	0.000125	0.06	0.13	0.47

Table 7.3-1 Assumed Conditions of Shwe Pyauk Creek

Note:*: This coefficient is applied for minor streams on plains with weeds and winding

Source: EIA Study Team

 BOD_5 was selected as the representative indicators for evaluating the impact on the environment since this parameters are the most basic parameters of concern for the environment as well as the main pollutants discharged from the industrial area.

The water quality of Shwe Pyauk Creek was considered the cumulative impacts of other development projects in Thilawa SEZ, i.e. development project of Zone A and development project of Zone B that includes the development of the Project and the development of the logistic, residence and commercial area. Inflow situation is as shown in Figure 7.3-2.

The results estimated using the complete mixing model is presented in Table 7.3-2.




Figure 7.3-2 Forecast Inflow Model into Shwe Pyauk Creek

No.		Iı	nflow Condition	on	Existing Creek Condition			t Result Mixing)	Tentative	
		Area		Q (m3/day)	BOD (mg/l)	Q m3/sec	BOD (mg/l)	Q m3/sec	BOD (mg/l)	Target Value
1	ZoneA	Industrial	Industrial	7,000(1)	20					
2	ZoneB	Industrial	Industrial	17,000	20					
3		Logistic2B	Industrial	5,239(3)	20	0.47	4.0(2)	0.82	10.5	15
4	Logistic 3		Industrial	13(3)	20					
5		R&C3	Domestic	852(3)	30					

Table 7.3-2 Results of Water Quality Forecast

Note: (1): The value is estimated based on the actual operating data of water discharge value provided from TSMC (as of May 2016)

(2): The values is average of EIA report for Thilawa SEZ Class A Development Project (September 2013) and field survey in Chapter 6

(3): Thilawa Zone B Master Plan & Infrastructure Feasibility Study Report (logistic, residence and commercial area)

Source: EIA Study Team

As shown in Table 7.3-2, the estimated results obviously show that although the quality of creek would be changed by receiving industrial wastewater from the industrial area, its water quality would still comply with the tentative target value for protection of aquatic life. Therefore, the impacts from wastewater to the surrounding environment would be less.

On the other hand, the concentration of heavy metals and toxic substance of treated wastewater from tenants is not known concretely, at the present moment. The tenants will submit the future water demand plan to the project proponent, and the project proponent would prepare the adequate wastewater treatment measures adjust to the tenant's activities. Basically, it is expected that concentration of wastewater is diluted by mixing with stormwater through the retention pond and creek flow. In case that large amount discharge which includes heavy metals and toxic substance is expected and especially low flow season, the project proponent would review the internal target value and set strict standard for pre-treatment, if necessary.

Additionally discharge/ambient water quality and water volume will be regularly monitored by tenants and project proponent to protect discharging unexpected concentration.

In summary, it is judged that wastewater generated from the project area during the operation phase, including stormwater, domestic wastewater, and industrial wastewater, would not cause any significant impact on the surrounding and downstream area.

7.4 Waste

7.4.1 Forecast Item

The following items were examined to forecast the impact:

- Waste generated from construction work during the construction phase and from the demolition works during the closing phase; and
- Waste generated from commercial activities during the operation phase.

7.4.2 Forecast Area

The area examined to forecast the impact was set in and around the project area.

7.4.3 Forecast Period

As for the construction/closing phases, the period examined to forecast the impact was set during the implementation of the construction/closing work for the Project.

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the project area start their operation.

7.4.4 Forecast Method

(1) Waste during Construction Phase and Closing Phase

The forecast of impact of waste generated during the construction phase and closing phase was conducted as follows:

- To evaluate management of solid waste generated from the construction work for the development of infrastructure facilities of the Project as well as construction work of facilities of tenants.
- To evaluate management of solid waste generated from the demolition works for the closing the Project as well as closing tenants.

(2) Waste during Operation Phase

The forecast of impact of waste generated during the operation phase was conducted as follows:

- To evaluate capacity of treatment and disposal of industrial waste and business-related waste generated in Zone A, and logistic and commercial areas of Zone B in addition to the Project area as assessment of cumulative impact by estimating the quantity of industrial waste and business-related waste based on the projection by tenants in Zone A which submitted Environmental Conservation and Prevention Plan (ECPP) to TSMC.

7.4.5 Forecast Result

(1) Waste in Construction and Closing Phases

1) Construction Phase

Before land reclamation work, households are required to relocate, and their living structures will be demolished after compensation and assistance by the government. The waste generated by the demolition work such as logged trees, scrap steel and scrap wood by removal structure will be utilized as recyclable materials as much as possible. The rest of the waste will be treated by outsourcing to the private waste treatment firm in Thilawa SEZ which has functions of recycling, intermediate treatment, and the controlled landfill site or other proper waste treatment facilities outside of Thilawa SEZ.

After demolition work, according to the land reclamation plan, all the residual soil generated by cutting work will be used for filling work in the Project site or the other construction sites to be embanked in Thilawa SEZ, and there is no plan to dispose residual soil outside of Thilawa SEZ.

During construction work for infrastructure facilities of the Project after land reclamation, pieces of the construction materials such as used wood form, scrap metal, scrap wood, reinforcing bars, and plastics, and general waste from the construction office and rest space will be generated. The pieces of the construction materials will be utilized as recyclable materials as much as possible. The rest of pieces of the construction materials after recycling and the general waste will be also treated by outsourcing to the private waste treatment firm in Thilawa SEZ or other proper waste treatment facilities outside of Thilawa SEZ. As for construction work for tenant, methodology of waste management is same as the Project.

Therefore, the impact of waste generated in the construction phase is expected to be limited and well managed.

2) Closing Phase

During the closing phase, earthwork would not be implemented and residual soil would not be generated. Regarding the waste generated by the demolition work of the infrastructure facilities of the Project and facilities of tenant, methodology of waste management is same as the construction phase.

Therefore, the impact of waste generated in the closing phase is expected to be limited and well managed.

(2) Waste in Operation Phase

As described in Chapter 3, industrial waste generated from the industrial area will be re-used or recycled as much as possible by collecting the waste separately. This sorting out process is handled by each tenant and project proponent respectively. The waste which cannot be re-used or recycled may be managed by the waste treatment firm in Zone A or through public service such as by the Pollution Control and Cleansing Department of the Yangon City Development Committee (YCDC).

For evaluating the impact of waste in the operation phase, it is necessary to consider the cumulative impact of the waste generated from the Project in combination with the waste generated in Zone A, and logistic and commercial areas of Zone B. Thus, capacity of treatment and disposal of industrial waste and business-related waste generated from the Project and the above related Projects was confirmed.

1) Treatment and disposal of industrial waste and business-related waste to prevent environmental impact to surrounding area

Solid waste treatment and management facilities operated by a Japanese waste management company (Golden Dowa Eco-System Myanmar Co., Ltd.) are located in Thilawa SEZ Zone A. According to "Final EIA Report for the Project on Construction of Solid Waste Management Facilities in the Thilawa Zone A (DOWA Eco-System and Golden Dowa Eco-System Myanmar Co., Ltd., June 2015)", the waste treatment and management facilities has intermediate treatment facilities (sorting, stabilization, fuel conversion, and incineration to be installed), final disposal facility (controlled landfill to meet US-EPA requirement), and wastewater treatment facility, laboratory analysis facility, and so on to treat hazardous and non-hazardous wastes as described in Chapter 4.

After transportation of wastes, all wastes will be inspected for its general characteristics including burnability, hazardous properties, and infectiveness in order to decide the treatment method in advance, and then it will be separated into hazardous and non-hazardous wastes. Afterwards, each waste will be treated by its appropriate method respectively. The process flow is shown in Figure 7.4-1.

In order to manage the collection, treatment and control of all wastes, and to minimize the pollution from the collected wastes to the surrounding environment, the following process will be carried out. Before receiving waste, at first each generator will provide a representative waste sample to be disposed, and the operator of solid waste management facilities will then check the waste sample the generator wants to dispose of and conduct sample analysis. At the same time, the operator will also decide how to treat the waste. The first batch of waste from the generator will be checked carefully whether the waste characteristics are the same as in the sample analysis. After that, waste will be checked, as a kind of manifest examination, through fingerprint testing before its receipt and unloading. The treated waste and wastewater will also be analyzed to check whether or not the treatment processes are functioning properly. As for environmental monitoring, treated wastewater discharged to the water body and gas emitted from the incinerator will go through analyzing devices to check their conformity with the target environmental levels.

With respect to hazardous waste management, The Special Economic Zone Rules (2015) regulates the type of business not to be allowed to locate in Thilawa SEZ, and Section 35 of (3) provides the detail description including the type of business which produces hazardous and polluted materials as shown in Table 7.4-1. Moreover, the project proponent will make screening tenants in terms of the type of wastes to be generated before the entry in cooperation with TSMC and will not accept the entry if the tenants will generate hazardous wastes which are infectious wastes, asbestos, dioxin and PCB etc.

Table 7.4-1 Types of Business Not Allowed to locate in Thilawa SEZ

The Special Economic Zones Rules (2015), Section 35, (3)


- (a) Production/processing of munitions including arms, weapons, explosives for military use, etc. and services rendering for military-related purposes;
- (b) Production/processing or services hazardous to the environment and ecology. This may exclude the waste management and/or recycling industries that will render the waste management services to the industries outside Myanmar;
- (c) Production/processing of psychoactive substances and narcotic substances and import of any kind of their materials prohibited under the UN Convention Against Illicit Traffic in Narcotic Drugs and Psychotropic Substances (1988);
- (d) Import or production/processing of poisonous chemicals, agriculture pesticide/insecticide and other goods by using chemical substances, prohibited by international regulations or the World Health Organization, that affect the public health and environment;
- (e) Businesses utilizing the industrial waste imported from abroad;
- (f) Production/processing of prohibited substances which may destroy ozone layer;
- (g) Production/processing and sale of the good made of asbestos
- (h) Production/processing of polluted substances hazardous to the human health and environment

Source: EIA Study Team

As one of waste treatment facilities in Thilawa SEZ, the incinerator with proper emission control system will be installed by Japanese waste management company in Zone A, and hazardous wastes will become to be treated by incinerator in the future.

In case that it is confirmed wastes which cannot be treated in the treatment facilities in Thilawa SEZ or existing waste management system, the project proponent will consider the countermeasures, such as storing wastes tentatively and then exporting wastes to other countries under the frame of Basel Convention (1989) through the discussion with TSMC and related organization.

As a whole process of waste management, the project proponent will monitor the type and amount of generated wastes from each tenant periodically by the monitoring report to be submitted by each tenant in cooperation with TSMC.



Note) I, II and III shows the on-page reference which indicates that next step with the same Roman Figure is somewhere else on the drawing. Source: DOWA Eco-System Co., Ltd.

Figure 7.4-1 Process Flow of Solid Waste Management

After completion of waste disposal, final covering of the landfill by means of clay soil, impermeable layer, drainage layer, cover soil, and vegetation will be installed on the top of landfill waste as shown in Figure 7.4-2.

After installation of final covering, the Project proponent will continuously conduct the post-closure care such as the following:

Maintaining the integrity and effectiveness of the final covering, including maintenance against anticipated settlement, subsidence, and erosion of landfill caused by decomposition and consolidation of waste and other damage;

- Maintaining and operating the leachate and gas collection systems; and
- Monitoring the groundwater quality and odor.

Maintenance and monitoring will be conducted for ten years at least after installation of the final covering, and then the Project proponent will close the landfill site if no environmental impact is observed for two years.




Figure 7.4-2 Cross Section of Landfill and Structure of Final Cover

After completion of closure of the landfill, various types of eco-friendly facilities will be developed such as a park and/or a mega solar park. Figure 7.4-3 shows examples of eco-friendly facilities and its usage.



Park (Portland, USA)
Source: DOWA Eco-System Co., Ltd.

Mega Solar Park (Akita, Japan)

Figure 7.4-3 Examples of Eco-friendly Facilities after Completion of Closure of Landfill

On the above information, it is confirmed that the solid waste management facilities with enough capacity of treatment and disposal for industrial waste and business-related waste including hazardous waste is existed in Thilawa SEZ at least.

2) Capacity of final disposal site

Table 7.4-2 shows estimated maximum generation amount of industrial and business related waste in Zone A and Zone B in Thilawa based on tenant of Zone A which submitted Environmental Conservation Prevention Plan (ECPP) to TSMC and EIA report in Japan.

Table 7.4-2 Estimation of Maximum Generated Amount of Industrial Waste and Business Related Waste

Area		Sellable/ Total Building Area	Unit	Maximum Amount of Waste (ton/year)
	Industrial Area (262ha)	201 ha	135 t/ha/yr*1	28,296
Zone B	Logistic Area (267ha)	214 ha	2.1 t/ha/yr*2	449
	Commercial Area (24ha)	86 ha	124 t/ha/yr*2	10,664
Zone A	Industrial Area (370ha)	251 ha	135 t/ha/yr*1	33,912
Total of 2	Zone A and B in Thilawa SEZ			73,321

Note: *1: Tenants in Zone A which submitted Environmental Conservation Prevention Plan (ECPP)

*2: EIA reports for Construction of Shopping Malls in Japan

Source: TSMC and EIA Reports in Japan

In order to evaluate impact of generated solid waste in terms of receiving capacity, it was confirmed whether the controlled landfill site in Thilawa SEZ has enough capacity of receiving waste for their operation period (60 years) or not. The estimated cumulative amount of industrial waste and business related waste to be generated and disposed in Zone A and Zone B in Thilawa SEZ is shown in Table 7.4-3.

Table 7.4-3 Estimation of Yearly and Cumulative Generated Amount of Industrial Waste and Business Related Waste in Zone A and Zone B in Thilawa SEZ

	Amount of Solid Waste [ton/year]						Cumulative Amount of	Cumulative Amount of
Yea	ır	Zone B Industrial	Zone B Logistic	Zone B Commercial	Zone A Industrial	Total	Waste Generation [ton/year]*1	Final Disposal [ton/year]
2016	1	0	0	0	2,700	2,700	2,700	478
2017	2	0	0	0	5,400	5,400	8,100	1,434
2018	3	2,700	0	0	8,100	10,800	18,900	3,345
2019	4	5,400	42	2,480	10,800	18,722	37,622	6,659
2020	5	8,100	84	4,960	13,500	26,644	64,266	11,375
2021	6	10,800	126	7,440	16,200	34,566	98,832	17,493
2022	7	13,500	168	9,920	18,900	42,488	141,320	25,014
2023	8	16,200	210	10,664	21,600	48,674	189,994	33,629
2024	9	18,900	252	10,664	24,300	54,116	244,110	43,207
2025	10	21,600	294	10,664	27,000	59,558	303,668	53,749
2026	11	24,300	336	10,664	29,700	65,000	368,668	65,254
2027	12	27,000	378	10,664	32,400	70,442	439,110	77,722
2028	13	28,296	420	10,664	33,912	73,292	512,402	90,695
2029	14	28,296	449	10,664	33,912	73,321	585,723	103,673
2030	15	28,296	449	10,664	33,912	73,321	659,043	116,651
2040	25	28,296	449	10,664	33,912	73,321	1,392,249	246,428
2050	35	28,296	449	10,664	33,912	73,321	2,125,454	376,205
2060	45	28,296	449	10,664	33,912	73,321	2,858,660	505,983
2070	55	28,296	449	10,664	33,912	73,321	3,591,866	635,760
2075	60	28,296	449	10,664	33,912	73,321	3,958,468	700,649

Note: *1: Ratio between amount of waste to final disposal site and total waste generation is 17.7 % in accordance with Final EIA Report for the Project on Construction of Solid Waste Management Facilities in the Thilawa Zone A.

Source: EIA Study Team

The yearly cumulative amount of industrial waste and business related waste in Zone A and Zone B in Thilawa SEZ is shown in Figure 7.4-4 and the cumulative amount of the waste at 60 years after operation is estimated as 0.7 million ton. According to DOWA Eco-System and Golden Dowa Eco-System Myanmar Co., Ltd., the receiving capacity of the controlled landfill sites of the solid waste treatment and management facilities in Thilawa SEZ is estimated as 1.0 million ton at least. Thus the capacity of receiving capacity of industrial waste and business related waste in Zone A and Zone B in Thilawa SEZ is judged enough.

On the bases of the above examination, the impact of waste generated in the operation phase is expected to be limited and well managed.




Figure 7.4-4 Yearly Cumulative Amount of Industrial Waste and Business Related Waste in Zone A and Zone B in Thilawa SEZ

(3) Illegal dumped waste generation

Currently, it is confirmed that large amount of wastes such as domestic and construction etc. are illegally dumped in the surrounding area of Zone A. Considering the situation of Zone A, the illegal dumping of wastes is expected to occur during all phases due to the implementation of the Project (Zone B) without any countermeasures. Generally speaking, illegal dumping patrol, installation of fine and penalty to each construction constructor and each tenant and providing public waste collection system by government are effective actions to prevent issues on illegal dumping of wastes. It implies that these issues might be beyond responsibilities by the project proponent. In order to promote them to dispose wastes appropriately, what the project proponent can do is only to call attention to each construction contractor and each tenant periodically and to carry out monitoring of waste management by construction contractors and tenants. In case of that illegal dumping is the matter happened outside of the project area, the project proponent will consider the preventive measures and countermeasures in cooperation with TSMC and related organizations.

7.5 Soil Contamination

7.5.1 Forecast Item

The following items were examined to forecast the impact:

- Possibility of soil contamination as a result of the activities of the Project the construction, operation, and closing phases.

7.5.2 Forecast Area

The areas examined to forecast the impact were set in the project area.

7.5.3 Forecast Period

As for the construction phase, the period examined to forecast the impact was set during the implementation of the construction work for the Project.

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the project area start their operation.

As for the closing phase, the period examined to forecast the impact was set during the implementation of the closing work in the project area after all tenants stop their operation.

7.5.4 Forecast Method

The forecast of the impact of soil contamination was conducted as follows:

- During the construction phase, the possibility of soil contamination and distribution of contaminated soil as a result of the construction work in the project area was evaluated in consideration of the field survey result and the proposed construction plan of the project area.
- During the operation phase, the possibility of soil contamination in the project area by solid waste, hazardous waste (if any), and wastewater was evaluated in consideration of the proposed design and operation manner of the central wastewater treatment plant and commitment of tenant industries to install necessary pre-treatment facilities (e.g., neutralization, oil separation) as well as to handle generated waste properly.
- In the closing phase, the possibility of soil contamination and distribution of contaminated soil as a result of the demolition work in the project area was evaluated in consideration of the possibility of soil contamination during the operation phase.

7.5.5 Forecast Result

During the construction phase, all excavated soil would be backfilled into the Thilawa SEZ Zone B area as embankment soil. Excavated soil would not cause any soil contamination inside the project area and the surrounding area because soil quality of the industrial area as well as the entire area of Thilawa Zone B was observed to comply with the relevant environmental standards, as described in Section 6 of the Chapter 6. In addition, construction activities in an industrial zone and domestic activities during the construction phase would not be expected to cause any pollution to the soil environment.

During the operation phase, industrial wastewater discharged by the tenants would be collected and treated properly in the central wastewater treatment plant. Domestic wastewater would be treated by septic tanks at each tenant, while the pollution from stormwater runoff would be controlled and minimized as much as possible. With reference to the process of usage, producing, storing, disposing

and handling of oil, chemical, dangerous or hazardous materials in the project area, the tenants must strictly comply with applicable laws, regulations at its sole responsibility and expense. The tenants shall treat the materials safety on the covered area to prevent infiltration of the materials to ground, and eliminate or dispose of all dangerous or hazardous materials and waste including, but not limited to, industrial waste to prevent from distributing to the soil environment.

Accordingly, the possibility for soil contamination caused by improper treatment of wastewater and spilling of the oil, chemical, dangerous or hazardous materials in the process of operation would be eliminated. Sludge formed from industrial wastewater and domestic wastewater treatment would be treated properly as aforementioned. Hazardous waste (if any), industrial waste, and domestic waste would be well controlled and managed by each tenant. Outside storage of solid waste shall be allowed with the project proponent's prior approval only when it is stored in solid waste receptacles or trash containers which must be large enough to facilitate storage and collection and which must be installed within the land of tenant, to prevent from distributing to the soil environment.

Therefore, soil contamination caused by sludge, hazardous waste, industrial waste, and domestic waste would be minimized during the operation phase.

During the closing phase, demolition work of the industrial zone and domestic activities during the period would not be expected to cause any pollution to the soil environment. As aforementioned, soil contamination would not be expected to occur during the operation phase due to proper management and control, implying that there would be no contaminated soil at the start of the demolition work. As a result, the possibility that the contaminated soil from the industrial area is distributed to the surrounding area would not be anticipated.

In summary, it can be judged that soil contamination as a result of activities from the project during the construction, operation, and closing phases would not cause any significant environmental impact.

7.6 Noise and Vibration

7.6.1 Forecast Item

The following items were examined to forecast the impact:

- Noise and vibration along the main roads increased due to construction vehicles of the Project.
- Noise and vibration generated by construction work of the Project.
- Noise and vibration along main roads increased during operation phase of the industrial, logistic, and residence and commercial areas.
- Noise and vibration increased due to the tenants during the operation phase.

7.6.2 Forecast Area

The area examined to forecast the impact was set in and around Thilawa SEZ Zone B.

The forecast points for main roads nearby Thilawa SEZ Zone B were set as shown in Figure 7.2-1. The forecast points are along Thanlyin-Thilawa Road and Dagon-Thilawa Road.

7.6.3 Forecast Period

As for the construction phase, the period examined to forecast the impact was set during the implementation of the construction work for the Project.

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the industrial and logistic area start their operation.

7.6.4 Forecast Method

The impact forecast for noise and vibration was conducted as follows:

- To estimate the noise and vibration level increased by construction work during the construction phase by using formula prepared by the Institute of Noise Control Engineering of Japan (noise) and formula prepared by the Public Works Research Institute of Japan (vibration);
- To estimate the noise and vibration level increased by the tenant industries during the operation phase by using formula prepared by the Institute of Noise Control Engineering of Japan (noise) and formula prepared by Public Works Research Institute of Japan (vibration); and
- To estimate the noise and vibration level increased by vehicle traffic generated from Thilawa SEZ Zone B during the operation phase by utilizing ASJ RTN-Model 2013 (noise) and formula prepared by Public Works Research Institute of Japan (vibration).

The methodology of the impact forecast was described as follows.

(1) Method for Construction Noise Forecast during the Construction Phase

In order to forecast the noise level from the construction activities, the following formula formulated by the Institute of Noise Control Engineering of Japan was adopted:

$$L_C = L_{Source} - 20\log_{10}\left(\frac{r}{r_0}\right)$$

 L_C : *Noise level at evaluation point [dB]* L_{Source} : Noise level at reference point [dB]

Distance from source to reference point [m] Distance from source to evaluation point [m]

(2)Method for Construction Vibration Forecast during the Construction Phase

In order to forecast the vibration level from the construction activities, the following formula formulated by the Public Works Research Institute of Japan was adopted:

$$L_{V} = L_{V,reference} - 15 \log_{10} \left(\frac{r}{r_{0}}\right) - 8.68\alpha (r - r_{0})$$

Vibration level at evaluation point [dB] Lv:

 $L_{V,reference}$: Vibration level at reference point [dB]

Distance from source to reference point [m]

Distance from source to evaluation point [m]

 α : Internal reduction coefficient in ground (Normal: 0.01, Hard Rock: 0.001)

(3)Method for Noise Forecast from Tenant Industry during the Operation Phase

In order to forecast the noise level from the tenant industry during the operation phase, the following formula was applied:

$$L_{OP} = L_{Source} - 20\log_{10}\left(\frac{r}{r_0}\right) - TL$$

 L_{OP} : Noise level at evaluation point [dB] L_{Source} : Noise level at reference point [dB]

ro: Distance from source to reference point [m] Distance from source to evaluation point [m]

r:

TL: Effect of soundproof wall and window [dB], set as 30 [dB] this time

(4) Method for Vibration Forecast from Tenant Industry during the Operation Phase

Method for vibration forecast from tenant industry during the operation phase is the same as that during the construction phase.

Method for Noise Forecast from Traffic during the Operation Phase (5)

In order to forecast the noise level from traffic during the operation phase, ASJ RTN Model 2013 was applied along the main road as follows:

1) A-weighted Sound Level

A-weighted sound level (L_{PAi}) is calculated as follows:

$$L_{PAi} = L_{WA} - 8 - 20 \log_{10} r + \Delta L_d + \Delta L_g$$

where, L_{pAi} : A-weighted sound level propagated by sound source (l) (dB)

A-weighted sound power level by vehicle traffic (dB) L_{WA} :

Heavy vehicle : $L_{WA} = 88.8 + 10log_{10}V$ Light vehicle : $L_{WA} = 82.3 + 10log_{10}V$ Bike : $L_{WA} = 85.2 + 10log_{10}V$

V: Average traveling velocity (km/hr)

r: Distance from sound source (i) to forecast point (m)

 ΔL_d : Compensation value by diffraction effect (dB)

 ΔL_g : Compensation value by ground surface effect (dB)

As the road structures forecasted were flat and no equipment which cause diffraction were installed, $\Delta L_d = 0$ was applied in the calculation. Also, as the road condition would be solid concrete and/or asphalt, $\Delta L_g = 0$ was applied in the calculation.

2) A-weighted Equivalent Sound Level

A-weighted equivalent continuous sound pressure level is calculated as follows:

$$\begin{split} L_{AE} &= 10 \log_{10} \left(\frac{1}{T_0} \sum_{i=1}^{n} 10^{L_{PAi}/10} \Box \Delta t_i \right) \\ L_{Aeqj} &= 10 \log_{10} \left(10^{L_{AE}/10} \times \frac{N}{3600} \right) = L_{AE} + 10 \log_{10} N - 35.6 \end{split}$$

where, L_{AE} : Sound exposure level (dB)

L_{Aeqi} : A-weighted equivalent sound level by vehicle type and traffic lane (dB)

n : Number of set sound source (-)

 L_{PAi} : Sound level of sound source (i) (dB)

 Δt_i : Passing time of sound source interval (i)(sec) (= $\Delta d_i/V$)

 Δd_i : Length of sound source interval (i) (m)

V : Average traveling velocity (m/sec)

N : traffic volume (vehicle/hr)

 T_0 : Standard time (sec) (=1)

3) Synthesis Equation

The calculated equivalent sound level by vehicle type and traffic lane is synthesized as follows:

$$L_{Aeq} = 10\log_{10}\left(10^{L_{Aeq1}/10} + 10^{L_{Aeq2}/10} + \dots + 10^{L_{Aeqm}/10}\right)$$

where, L_{Aea} : Synthesized A-weighted equivalent sound level at forecast point (dB)

(6) Method for Vibration Forecast from Traffic during the Operation Phase

In order to forecast the vibration level from traffic during the operation phase, the following formula formulated by the Public Works Research Institute of Japan was adopted:

$$\begin{split} L_{10} &= {L_{10}}^* - \alpha_1 \\ L_{10}^* &= a \log_{10} (\log_{10} Q^*) + b \log_{10} V + c \log_{10} M + d + \alpha_{\sigma} + \alpha_{\sigma f} + \alpha_s \end{split}$$

where, L_{10} : vibration level at evaluation point (dB)

L₁₀*: vibration level at reference point (dB)

Q*: equivalent traffic volume during 500 sec per lane (vehicle/500 sec/lane)

$$Q^* = \frac{500}{3,600} \times \frac{1}{M} \times (Q_1 + KQ_2)$$

Q₁: traffic volume of light vehicle (vehicles/hr)

Q₂: traffic volume of heavy vehicle (vehicles/hr)

K: conversion factor of heavy vehicle to light vehicle, set as 13 this time

V: average traveling velocity (m/sec)

M: number of lanes on a road

 α_{σ} : correction value of the roughness of the pavement

 $\alpha_{\sigma} = 8.2 \log_{10} \sigma$ (in case of asphalt pavement)

 σ : standard deviation of pavement roughness, set as 5 mm this time

 α _f: correction value of specific frequency of the ground

$$\alpha_{f}$$
=-9.2log₁₀(f)-7.3 (in case of f < 8 Hz)

f: specific frequency of the ground, estimated by empirical equation this time $f=8.4N^{1/3}$

N: N value, this time set as 1

 α s: correction value of structure of the road, this time set as 0

 α_1 : correction value of distance decay from reference point to evaluation point

$$\alpha = \beta \log(r/5+1)/\log 2$$

r: distance from reference point to evaluation point

 β : 0.068 L_{10}^* -2.0 (in case of plane road on cohesive soil ground)

a, b, c, d: constant value, this time set as 47, 12, 3.5, 27.3, respectively (plane road)

7.6.5 Forecast Condition

(1) Construction Noise Forecast during Construction Phase

Table 7.6-1 shows the condition for construction noise forecast. Among the construction works, excavation for groundwork was adopted as the main construction work and one of the noisiest works of Zone B development. The ratio of time with noisy work to operating time is assumed as 70%.

Table 7.6-1 Condition for Construction Noise Forecast

Kind of Construction	Heavy Equipment	Noise Level at Reference Point [dB]	Distance from Source to Reference Point [m]	Number of Equipment [Unit]	Forecast Point
Excavation	Bulldozer	80	10	3	- Phalan Monastery (approximately 30 m from the boundary of the industrial area as the nearest case)
for groundwork	Excavator	74	10	3	Houses (approximately 15 m from the boundary of the industrial area as the nearest case)

Source: Construction Noise Prediction Model 'ASJ CN-Model 2007', The Acoustical Society of Japan, 2008

(2) Construction Vibration Forecast during Construction Phase

Table 7.6-2 shows the condition for construction vibration forecast. Among the construction works, compacting for groundwork was adopted as the main construction work and one of the highest vibration works of Zone B development.

Table 7.6-2 Condition for Construction Vibration Forecast

Kind of Construction	Heavy Equipment	Noise Level at Reference Point [dB]	Distance from Source to Reference Point [m]	Number of Equipment [Unit]	Forecast Point
	Bulldozer				- Phalan Monastery (approximately 30 m from the boundary of the industrial area as
Compacting for groundwork	Excavator	63	5	1	the nearest case)Houses (approximately 15 m from the boundary of the industrial area as the
	Compaction roller				nearest case)

Source: Environment Impact Assessment Technique for Road Project, National Institute for Land and Infrastructure Management and Public Works Research Institute, Japan, FY2012

(3) Noise Forecast from Tenant Industry during Operation Phase

Table 7.6-3 shows the condition for noise forecast from tenant industry during the operation phase. As of March 2016, there is no clear information about what kind of industries will move into the Thilawa SEZ Zone B but it is assumed that almost the same type of industries as in Zone A will move into Zone B. According to the list of approved investors from the website of Thilawa Special Economic Zone, a large-scale industrial pressing machine would be installed, which is one of the highest noise-generating equipment during the operation phase.

Table 7.6-3 Condition for Noise Forecast from Tenant Industry during Operation Phase

Heavy Equipment	Noise Level at Reference Point [dB]	Distance from Source to Reference Point [m]	No. of Equipment	Forecast Point
Large-scale Pressing Machine	105	1	1	 Phalan Monastery (approximately 30 m from the boundary of the industrial area as the nearest case) Houses (approximately 15 m from the boundary of the industrial area as the nearest case)

Source: Handbook of Noise Control Engineering, Institute of Noise Control Engineering, Japan, 2001

(4) Vibration Forecast from Tenant Industry during Operation Phase

Table 7.6-4 shows the condition for vibration forecast from tenant industry during the operation phase. The adopted heavy equipment was a large-scale industrial pressing machine, which is one of the highest vibration-generating machines during the operation of the industry.

 Table 7.6-4
 Condition for Noise Forecast from Tenant Industry during Operation Phase

Heavy Equipment	Unit Vibration Level L _{v0} [dB]	Distance from Source to Reference Point [m]	No. of Equipm ent	Forecast Point
Large-scale Pressing Machine	73	1	1	 Phalan Monastery (approximately 30 m from the boundary of the industrial area as the nearest case) Houses (approximately 15 m from the boundary of the industrial area as the nearest case)

Source: Handbook of Noise Control Engineering, Institute of Noise Control Engineering, Japan, 2001

(5) Noise Forecast from Traffic during Operation Phase

1) Traffic Volume and Traveling Velocity

The traffic volume and traveling velocity at each forecast point during the forecast period were the same as mentioned in Section 2 of the Chapter 7. The traffic volumes at the forecast points during the operation phase are shown in Table 7.6-5.

Table 7.6-5 Traffic Volumes at Forecast Points during Operation Phase

Т	ype of Vehicle	Present Traffic Volume (vehicle/day)	Traffic Volume Related to Thilawa SEZ Zone A (vehicle/day)	Traffic Volume Related to Thilawa SEZ Zone B (vehicle/day)
Kyaik Khauk	Two-wheel Vehicle (Bike)	9,098	3,549 1)	3,432 1)
Pagoda (Thanlyin-	Four-wheel Light Vehicle (Car)	2,928	233	885
Thilawa Road)	Four-wheel Heavy Vehicle (Pickup/Fixed route bus)	1,135	467	517
Planned	Two-wheel Vehicle (Bike)	3,132	764	739-
residential site (Dagon-Thilawa	Four-wheel Light Vehicle (Car)	1,443	50	191
Road)	Four-wheel Heavy Vehicle (Pickup/Fixed route bus)	1,142	323	401

Note 1) It is assumed that the ratio of using bike to using bicycle is 40% to 60%. Thus, the traffic volume of bike is calculated as 40% of the congested traffic volume of two-wheel vehicles

Source: EIA Study Team

2) Road Condition

The road conditions at the forecast points during the forecast period are presented in Table 7.6-6.

Table 7.6-6 Road Conditions at Forecast Points

Forecast Point		Remark			
(Name of Road)	Pavement	Medium	Buffer Zone	Total	Kemark
Kyaik Khauk Pagoda (Thanlyin-Thilawa Road)	7.0+7.0	1.0	4.5+4.5	24.0	Expanded road
Planned residential site (Dagon-Thilawa Road)	6.85+6.85	4.6	13.85+13.85	46.0	Existing road

Source: EIA Study Team

3) Position of Sound Source and Forecast Point

The sound sources were set on the center of both upward and downward traffic lanes. Forecast points were set at the edge of the road at a height of 1.2 m.

4) Position of Vibration Source and Forecast Point

The vibration sources were set on the center of the nearest lane to the forecast point. Forecast points were set at the edge of the road.

7.6.6 Forecast Result

(1) Construction Phase

1) Forecast Result of Noise and Vibration from Construction Vehicle at Thanlyin-Thilawa Road

During the construction phase, noise would be emitted from construction vehicles. According to the actual result of construction works in Zone A, the traffic volume of the construction vehicles were at most about 200 vehicles a day. It would be assumed that the traffic volume of construction vehicles of Zone B is generated to the same extent as Zone A.

Present traffic volume of four-wheel vehicle is about 4,000 vehicles a day, so if 50% of the construction vehicles travel along the Thanlyin-Thilawa Road, traffic volume will be temporarily increased by 5% at most. Impact of noise is expected to be limited because it would be site specific and temporary. In addition, the contractor will set the speed limit for drivers during the construction/closing phase.

Hence, it is judged that the noise and vibration generated by the construction vehicles in Thilawa SEZ Zone B would not cause any significant impact.

2) Forecast Result of Noise and Vibration from Construction Vehicle at Dagon-Thilawa Road

Present traffic volume of four-wheel vehicle is about 2,500 vehicles a day, so if 50% of the construction vehicles travel along the Dagon-Thilawa Road, traffic volume will be temporarily increased by 8% at most. Impact of noise is expected to be limited because it would be site specific and temporary. In addition, the contractor will set the speed limit for drivers during the construction/closing phase.

Hence, it is judged that the noise and vibration generated by the construction vehicles in Thilawa SEZ Zone B would not cause any significant impact.

3) Forecast Result of Construction Noise

Table 7.6-7 shows the forecast results of construction noise level depending on the distance from the sound source. In the daytime, areas less than 30 m from the houses in the residence area will be prohibited to implement construction work by heavy equipment that generates noise without installation of noise prevention sheet. In the evening, areas that are less than 200 m from the houses in Phalan Monastery and in other residential area will be prohibited to implement construction work. At nighttime, areas less than 300 m from the monastery and residential area will be also prohibited to implement construction work. In addition, the contractor will install sound-proofing sheet around the construction site. These results will be reflected in the conditions of environmental consideration of the contractor.

Hence, it is judged that the noise generated from the construction work in Thilawa SEZ Zone B would not cause any significant impact.

Table 7.6-7 Forecast Results of Construction Noise

Distance	Forecaste		tive Target Value of Noi Monastery and Reside	Note	
from the Source of	d Noise Level	Daytime (Leq) (7 am-7 pm)	Evening time (Leq) (7 pm-10 pm)	Nighttime (Leq) (10 pm-7 am)	(NG: Not Good)
Noise	Level	75 dB	60 dB	55 dB	(1/3/1/3/ 3332)
10 m	84 dB	NG	NG	NG	
15 m	81 dB	NG	NG	NG	Houses (approximately 15 m from the boundary of the industrial area as the nearest case)
20 m	78 dB	NG	NG	NG	
30 m	75 dB	OK	NG	NG	Phalan Monastery (approximately 30 m from the boundary of the industrial area as the nearest case)
40 m	72 dB	OK	NG	NG	
50 m	70 dB	OK	NG	NG	
100 m	64 dB	OK	NG	NG	
150 m	61 dB	OK	NG	NG	
200 m	58 dB	OK	OK	NG	
300 m	55dB	OK	OK	OK	

Source: EIA Study Team

4) Forecast Result of Construction Vibration

Table 7.6-8 shows the forecast results of construction vibration level depending on the distance from the vibration source. The vibration levels at all distances are forecasted to be less than the target vibration level for construction. However, prohibited areas will be set the same as the prohibited areas of noise for safety.

Hence, it is judged that the vibration generated from the construction work in Thilawa SEZ Zone B would not cause any significant impact.

Table 7.6-8 Forecast Results of Construction Vibration

Distance from the	Forecaste		tive Target Value of Vib Monastery and Residen		
Source of Vibration	d Noise Level	Daytime (La) (7am-7pm)	Evening time (La) (7 pm-10 pm)	Nighttime (La) (10 pm-7 am)	Note
10 m	58 dB	65 dB OK	65 dB OK	60 dB OK	
10 m	38 UB	UK	UK	UK	77 () 1.15
15m	55 dB	OK	OK	OK	Houses (approximately 15 m from the boundary of the industrial area as the nearest case)
20 m	53 dB	OK	OK	OK	
30 m	49 dB	OK	OK	OK	Phalan Monastery (approximately 30 m from the boundary of the industrial area as the nearest case)
40 m	46 dB	OK	OK	OK	
50 m	44 dB	OK	OK	OK	
100 m	35 dB	OK	OK	OK	
150 m	28 dB	OK	OK	OK	
200 m	<25 dB	OK	OK	OK	

Source: EIA Study Team

(2) Operation Phase

1) Forecast Result of Noise from Tenant Industry during Operation Phase

Table 7.6-9 shows the forecast results of noise level depending on the distance from tenant industry during the operation phase. As for houses in the residential area, areas less than 20 m from the houses will be prohibited to use equipment which generate noise without any measures such as installation of soundproof wall because operation hour might be 24 hours. These results will be reflected in the proposed internal regulation.

This forecast result presents only one sample of the high noise-generating equipment. In case that more than expected large-scale machinery will be installed, the tenants shall analyze and evaluate the impact of noise. Noise emitting from any source within the land of tenant shall be effectively controlled by its own arrangement, if necessary, such as sound—absorbing materials, installing the facility in the house, having the enough buffer zone between the source and any property line or other suitable means so as to comply with the tentative target value. In addition, the arrangement of the land allocation for each tenant and the installation of buffer zone with less noise impacts to the surrounding sensitive receivers (monastery, residence etc.) shall be considered by the project proponent, as possible. Hence, it is judged that the noise generated from tenant industry during the operation phase would not cause any significant impact.

Table 7.6-9 Forecast Results of Noise from Tenant Industry during Operation Phase

Distance	E	Tentative Target Valu	ue of Noise for the Mona		
from the	Forecast Noise	Daytime (Leq) (7 am-7 pm)	Evening time (Leq) (7 pm-10 pm)	Nighttime (Leq) (10 pm-7 am)	Note
Source of Noise	Level	60 dB	55 dB	50 dB	(NG: Not Good)
10 m	55 dB	OK	OK	NG	Need to install soundproof wall
15 m	51 dB	OK	OK	NG	Houses (approximately 15 m from the boundary of the industrial area as the nearest case)
20 m	49 dB	OK	OK	OK	
30 m	45 dB	OK	OK	OK	Phalan Monastery (approximately 30 m from the boundary of the industrial area as the nearest case)
40 m	43 dB	OK	OK	OK	
50 m	41 dB	OK	OK	OK	
100 m	35 dB	OK	OK	OK	
150 m	31 dB	OK	OK	OK	
200 m	29 dB	OK	OK	OK	

Source: EIA Study Team

2) Forecast Result of Vibration from Tenant Industry during Operation Phase

Table 7.6-10 shows the forecast results of vibration level depending on the distance from tenant industry during the operation phase. The vibration levels at all distances are forecasted to be less than the target vibration level for operation.

This forecast result presents only one sample of the high vibration-generating equipment. In case that more than expected large-scale machinery is installed, the tenants shall analyze and evaluate the impact of vibration. Vibration emitting from any source within the land of tenant shall be effectively controlled by its own arrangement, if necessary, such as installing vibration control devices for equipment, design of the structure to disconnect between the sources and ground or other suitable means so as to comply with the tentative target value. In addition, the arrangement of the land allocation for each tenant and the installation of buffer zone with less vibration impacts to the surrounding sensitive receivers (monastery, residence etc.) shall be considered by the project proponent, as possible

Table 7.6-10 Forecast Results of Vibration from Tenant Industrial during Operation Phase

Distance	Forecast	Tentative Target Value of Vibration for the Monastery and Residence			
from the Source of	Vibration Level	Daytime (La) (7 am-7 pm)	Evening time (L a) (7 pm-10 pm)	Nighttime (L a) (10 pm-7 am)	Note
Vibration	Level	65 dB	60 dB	60 dB	
10 m	57 dB	OK	OK	OK	
15 m	54 dB	OK	OK	OK	Houses (approximately 15 m from the boundary of the industrial area as the nearest case)
20 m	52 dB	OK	OK	OK	
30 m	48 dB	OK	OK	OK	Phalan Monastery (approximately 30 m from the boundary of the industrial area as the nearest case)
40 m	46 dB	OK	OK	OK	
50 m	43 dB	OK	OK	OK	
100 m	34 dB	OK	OK	OK	
150 m	27 dB	OK	OK	OK	
200 m	<25 dB	OK	OK	OK	

Source: EIA Study Team

3) Forecast Results of Noise from Traffic during Operation Phase

The A-weighted equivalent sound levels estimated at each forecast point are presented in Table 7.6-11. All the forecasted sound levels under the "with Project" case would satisfy the tentative target value.

Table 7.6-11 Traffic Sound Level (Leq) for With and Without Project Case along the Road

		W	ithout Project			
Forecast Point	Time Period	Present Condition	After Development of Thilawa SEZ Zone A	With Project	Tentative Target Value ²⁾	
Kyaik Khauk Pagoda	Day	71 dB	72 dB	73 dB	75 dB	
(Thanlyin-Thilawa Road)	Night	60 dB	62 dB	63 dB	70 dB	
Planned residential site ¹⁾	Day	65 dB	66 dB	67 dB	75 dB	
(Dagon-Thilawa Road)	Night	59 dB	60 dB	61 dB	70 dB	

Note 1) As the road is already developed, forecast result is calibrated based on the field survey data.

2) Applied "proximity to major arterial roads".

Source: EIA Study Team

4) Forecast Results of Vibration from Traffic during Operation Phase

The vibration levels estimated at each forecast point are presented in Table 7.6-12. All the forecasted vibration levels under the "with Project" case would satisfy the tentative target value.

Table 7.6-12 Traffic Vibration Level (L_{10}) for With and Without Project Case along the Road

		Wi	ithout Project			
Forecast Point	Time Period	Present Condition	After Development of Thilawa SEZ Zone A	With Project	Tentative Target Value	
Kyaik Khauk Pagoda	Day	46 dB	48 dB	49 dB	65 dB	
(Thanlyin-Thilawa Road)	Night	39 dB	40 dB	41 dB	60 dB	
Planned residential site ¹⁾	Day	36 dB	37 dB	39 dB	65 dB	
(Dagon-Thilawa Road)	Night	28 dB	30 dB	32 dB	60 dB	

Note 1) As the road is already developed, forecast result is calibrated based on the field survey data.

2) Applied "Residential Area".

Source: EIA Study Team

In addition, the noise and vibration which might be generated from the operation of the tenant industries in Thilawa SEZ Zone B would be well controlled and managed by the tenants. Moreover, impacts of noise and vibration are expected to be limited because the distance between source (tenants) and receptors is more than enough.

Hence, it is judged that the noise and vibration generated from Thilawa SEZ Zone B operation would not cause any significant environmental impact on the surrounding area.

7.7 Offensive Odor

7.7.1 Forecast Item

The following item was examined to forecast the impact:

- Offensive odor from the development of the project area during the operation phases.

7.7.2 Forecast Area

The area examined to forecast the impact was set in and around the project area.

7.7.3 Forecast Period

The period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the project area start their operation.

7.7.4 Forecast Method

The impact forecast for offensive odor was conducted as follows:

- To examine the impact on the surrounding area of the project area of offensive odor generated from the Project.

7.7.5 Forecast Result

(1) Operation Phase

Waste and wastewater is main generation source of offensive odor in the project area. They would be well controlled and managed by having tenants commit to install pre-treatment facilities for neutralization, oil separation, and removal of toxic and heavy metals. The tenants shall have its own arrangement, if necessary, such as installing odor pollution control devices if its plant operation produce foul odor. With reference to usage, producing of disposing and handling of dangerous or hazardous materials in the project area, the tenants must, at its sole responsibility and expense, shall treat safety manage, eliminate or dispose of all dangerous or hazardous materials and waste including, but not limited to, industrial waste to prevent from distributing to the offensive odor. Stack emissions of odor generally can be controlled using waste reduction, waste minimization and cleaner production principles or conventional emission control equipment.

Hence, it is judged that the offensive odor generated from the project would not cause any significant environmental impact on the surrounding area.

7.8 Bottom Sediment

7.8.1 Forecast Item

The following item was examined to forecast the impact:

- Possibility for contamination of bottom sediment due to the activities in the project during the operation phase.

7.8.2 Forecast Area

The areas examined to forecast the impact were set in the project area and Shwe Pyauk Creek, which will receive wastewater from the project area.

7.8.3 Forecast Period

The period examined to forecast the impact was set during the operation phase after all the tenants in the project area start their operation.

7.8.4 Forecast Method

The impact forecast for bottom sediment was conducted as follows:

- The impact on the bottom sediment in the creek of receiving wastewater discharge from the project area was evaluated by considering the result of the impact forecast for water pollution.

7.8.5 Forecast Result

The potential for contamination of bottom sediment in Shwe Pyauk Creek and the Yangon River mainly comes from polluted stormwater, domestic wastewater, and industrial wastewater discharged from the project site. The dissolved pollutants in stormwater and wastewater which are not treated properly can be absorbed by the existing bottom sediment, while undissolved pollutant matters or suspended particulates containing pollutants settle down to become part of the bottom sediment. The contamination of bottom sediment, therefore, is greatly dependent on the contamination of the creek as a result of receiving contaminated stormwater, domestic wastewater, and industrial wastewater.

As aforementioned, domestic wastewater would be treated in septic tanks and tenants would perform necessary mitigation measures to minimize contamination of stormwater runoff. As a result, it would be expected that water and wastewater collected by drains and discharged into the creek would be well controlled and managed. Meanwhile, industrial wastewater generated from the factories inside the industrial zone would be collected and treated in the central wastewater treatment plant and its effluent would comply with the designated standard. As a whole, water quality of the creek receiving stormwater and wastewater from the industrial area would comply with the required standard. Hence, it is expected that the bottom sediment in the creek would not be contaminated by wastewater discharge during the operation phase of the industrial zone.

On the other hand, the concentration of heavy metals and toxic substance of treated wastewater from tenants is not known concretely, at the present moment. The tenants will submit the future water demand plan to the project proponent, and the project proponent would prepare the adequate wastewater treatment measures adjust to the tenant's activities. Basically, it is expected that concentration of wastewater is diluted by mixing with stormwater through the retention pond and creek flow. In case that large amount discharge which includes heavy metals and toxic substance is expected and especially low flow season, the project proponent would review the internal target value and set strict standard for pre-treatment, if necessary. Additionally discharge/ambient water quality and

water volume will be regularly monitored by tenants and project proponent to protect pollution of the bottom sediment.

Hence, it is judged that stormwater and wastewater generated from the project area would not cause any significant environmental impact on the bottom sediment of Shwe Pyauk Creek and the Yangon River.

7.9 Flora/ Fauna and Biodiversity

7.9.1 Forecast Item

The following items were examined to forecast the impact:

- Change of vegetation due to the construction work in the project area;
- Loss of important species and/or their habitats caused by the project development.
- Impact on biodiversity and ecosystem by the project development.

7.9.2 Forecast Area

The area examined to forecast the impact was set in and around the project area.

7.9.3 Forecast Period

As for the construction phase, the period examined to forecast the impact was set during the implementation of the construction work for the Project.

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the industrial area start their operation.

As for the closing phase, the period examined to forecast the impact was set during the implementation of the closing work in the project area after all tenants stop their operation.

7.9.4 Forecast Method

The impact forecast for flora, fauna, and biodiversity was conducted as follows:

- The current status of vegetation in the project area was examined and then the impact on vegetation was evaluated by referring to the proposed land reclamation plan for the project development;
- The loss of important species and/or their habitats was determined by overlaying the project area on the habitats of important species; and
- The impact on biodiversity and ecosystem in the project area was evaluated in consideration of biodiversity and ecosystem of the larger region.

7.9.5 Forecast Result

(1) Alteration of Vegetation

The current vegetation in the project area, as described in Chapter 6, is mainly composed of grass and cultivated land. A part of the project area is covered by shrub land and plantation. The vegetation of the area is low-rich natural environmental vegetation and the same types of vegetation are distributed in the surrounding area of the project site. By the construction work of Zone B development, the vegetation in the project area would disappear and replace with industrial land.

Change of land use around the Thillawa SEZ before and after development of Zone B project is shown in Table 7.9-1. "Before development of Zone B" means the current condition with the development Zone A. "After development of Zone B" means the future condition with the development of industrial area, logistic area and residential & commercial area. Habitat area was calculated by GIS software. Agriculture land, grass land, and shrub area are decreased from "before" to "after", approximately

9.5 %, 5.7%, and 0.3%, respectively. Vegetation area will be cleared approximately 15.5% (682 ha) as total of in around Tillawa SEZ.

For the public space of Zone B, MJTD has responsibility to keep well-kept condition and greening. As described in Chapter 3, green space will be established for about 20.2 ha, approximately 7.7% of the project area, along the main road, sub road and retention pond in the project area. The design of the greening will follow the design of Zone A industrial area, which set about 21.7 ha of green area. In addition, tenants in Zone A industrial area set the greening area in each plot and it covers over 15 % on average in own land.

Hence, it is judged that the change of vegetation due to the project development would not cause significant impact on the environment.

Table 7.9-1 Change of Land Use Before/After Development of Zone B

No	No. Land use		Before Development		After Development		Difference (After)-(Before)	
No.	Lanu use	Area (Ha)	Percent	Area (Ha)	Percent	Area (Ha)	Percent	
1	Build up area	57	1.3%	57	1.3%	0		
2	Settlement	175	4.0%	172	3.9%	-3	-0.1%	
3	Myanmar Marine University	34	0.8%	34	0.8%	0		
4	4 Industry & Commercial Facilities		9.7%	426	9.7%	0		
5	5 SEZ Zone A		9.0%	395	9.0%	0		
6	SEZ Zone B (Industrial Area)	-	-	262	6.0%			
7	SEZ Zone B (Logistic Area)	-	-	267	6.1%			
8	SEZ Zone B (Residence & Commercial)	-	-	169	3.8%			
9	Reservoir/Lake	84	1.9%	84	1.9%	0		
10	Plantation	24	0.5%	11	0.3%	-13	-0.2%	
11	Shrub	71	1.6%	56	1.3%	-15	-0.3%	
12	Agriculture Land	1,780	40.5%	1,362	31.0%	-418	-9.5%	
13	13 Grass Land		30.8%	1,106	25.1%	-249	-5.7%	
Total		4,400	100.0%	4,400	100%			

Note; Before development: the current condition with the development Zone A.

After development : the future condition with the development of industrial area, logistic area and residential & commercial area. Source: EIA Study Team

(2) Loss of Important Species and Their Habitats

The summary of flora and fauna survey showed that 158 flora species, 71 butterflies, 4 dragonflies, 67 birds, 7 mammals, 13 reptiles and amphibians, and 22 fish species were observed or recorded through interview with the local people in the project site and the surrounding area. Most species were classified as Not Evaluated (NE), Data Deficient (DD), and Least Concern (LC) under the IUCN Red List of Threatened Species (2015-4 Version 3.1). There were 1 threatened species (1 reptile) and 5 near threatened species (2 birds and 3 fishes) recorded in the area. However, the loss of important species due to the project development would be evaluated carefully with the consideration of their habitats and specific living behavior.

According to the local people interviewed information, King Cobra (*Ophiophagus hannah*), which is classified as Vulnerable species by IUCN Red List of 2015-4 Ver 3.1, has been ever found. The latest information is around 2008, and there is no information in the project site in recent years. The presence of this species in the project site was not confirmed by direct observation during the field survey. Generally, this species is found primarily in pristine forests. On the other hand, vegetation of Zone B development area is developed area by human being such as paddy field or low – rich environmental vegetation. Based on the habitat and observed information above, the impact on this

species due to the project development would be undetermined and uncertain. It is noted that habitats of the reptilian species were also confirmed in the surrounding area, and it is expected that the implementation of zone B development will not direct impact on the important reptile. The boundary of the project site shall be marked clearly to prevent the contractor from clearing the vegetation outside of the project site.

Considering near threatened fish species, their habitats would remain unchanged as they can keep living in the existing creeks and lakes. The creeks would be conserved as much as possible in terms of drainage area, pathway, direction, and water quality. The water quality of the creeks would be adequately protected for conservation of aquatic life, as described previously in the section on water quality. Hence, fish species, in general, and near threatened fish species would be conserved in the project area.

Meanwhile, habitats for bird species would be changed due to the project development. However, near threatened bird species, Asian Golden Weaver (*Ploceus hypoxanthus*) and Oriental Darter (*Anhinga melanogaster*), are relatively common and observed in a wide area in Myanmar, though classified as NT by IUCN list. Asian Golden Weaver is observed as resident except in northern and eastern part of Myanmar. Oriental Darter is found near the lake or river (e.g. at the site of Innya Lake Yangon). These bird species can easily move to other places, because they can find similar habitats such as near water, grassland, marshes, etc. in nearby areas. Therefore, loss of near threatened bird species would be avoided.

As a whole, the loss of six threatened and near threatened species due to the project development would be minimized and limited and therefore would not cause significant impact on the environment and their existence in nature. In summary, it is judged that the project would not cause significant impact on important species and their habitats.

(3) Impact on Biodiversity and Ecosystem

Through the field survey, it was observed that biodiversity in the project area was not rich because of the fact that the area has been inhabited and cultivated by local people for a long time. In addition, the area which is located near Yangon City has recently been urbanized and strongly industrialized with industrial areas and deep terminals. The project area is not a special area in terms of biodiversity and ecosystem, compared with nearby areas in the same region. Similar ecosystem and equivalent level of biodiversity would be found in nearby areas. Besides, the loss of some important species would not occur during the project development, as discussed above. Though clearing the vegetation due to the implementation of the project, greening of the public space along the main road, sub road and retention pond in the project area of Zone A and Zone B will help to mitigate the change of biodiversity and ecosystem.

Therefore, the development of the project would not cause any significant impact on biodiversity and ecosystem of the region.

7.10 Hydrology

7.10.1 Forecast Item

The following items were examined to forecast the impact:

- Surface water flow direction;
- Water drainage volume from the project area; and
- Water consumption and its impact to the creek flow.

7.10.2 Forecast Area

The area examined to forecast the impact was set in and around the project area.

7.10.3 Forecast Period

As for the construction phase, the period examined to forecast the impact was set during the implementation of the construction work for the Project.

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the industrial area start their operation.

As for the closing phase, the period examined to forecast the impact was set during the implementation of the closing work in the project area after all tenants stop their operation.

7.10.4 Forecast Method

The impact forecast for hydrology was conducted as follows:

- During the construction phase, the impact of the construction work in the project area on surface water flow, water drainage volume, and water consumption was examined in consideration of the result of the hydrology survey and the proposed construction plan of the project site.
- During the operation phase, the impact of the operation of the industrial zone on surface water flow, water drainage volume, and water consumption was determined by referring to the proposed design plan of the industrial zone.
- During the closing phase, the impact of the closing of the project area on surface water flows, water drainage volume, and water consumption was estimated by considering the scenario of the previous phases and the field survey result.

7.10.5 Forecast Result

(1) Construction Phase

a) Surface Water Flow

It was confirmed that the path and the direction of Shwe Pyauk Creek would be kept intact during all phases of the Project. According to the land reclamation plan and the stormwater drainage plan, the project area would be excavated and embanked to attain a level platform with E.L. 5.5 - 7.0 m and general slope would be 0.2% in the direction of the drainage system with its canals and then toward Shwe Pyauk Creek. The excavation and embankment work would be designed to minimize the excavation volume and embankment volume as much as possible. In general, the difference in

elevation between adjacent points might change but their order would be almost kept unchanged. As a result, surface water flow would not change significantly and would basically keep its current water flow. According to the hydrology survey result (see Chapter 6), the current surface water mainly flows from the highest elevation points in the middle of the area toward Shwe Pyauk Creek and toward the surrounding boundary. During and at the end of the construction phase, surface water runoff would flow mainly from the middle area toward the drains and canals, and then discharge to Shwe Pyauk Creek. In short, the surface water flow would not be significantly altered during the construction phase.

b) Water Drainage Volume

Currently, as pointed out from the result of the hydrology survey, most stormwater runoff from the project area would be discharged to Shwe Pyauk Creek. During the construction phase, all stormwater runoff from the project area would be collected by drains, canals, and finally discharged to Shwe Pyauk Creek. Excess flow rate of stormwater from drainage canals would be equalized by retention ponds so that water drainage volume discharged to the creek would be distributed evenly. Therefore, it is expected that changes in water current and water flow rate of the creek due to the Project would be minimized. In summary, although the Project would result in a significant change in the water drainage volume discharged to the creek, the impact on water current and flow rate of the creek would be limited by the installation of retention ponds and retention canals.

c) Water Consumption and Its Impact on the Creek Flow

Water consumed for the construction work and related activities during the construction phase would include water for washing vehicles and equipment, sprinkling water, and domestic water. The source of water during construction is groundwater. The amount of water consumption is limited and short term. It can be concluded that water uptake from the groundwater during the construction phase would be very limited and would not cause any significant impact on Shwe Pyauk Creek.

(2) Operation Phase

a) Surface Water Flow

During the operation phase, surface water flow would be the same as the flow at the end of the construction phase because the drainage system, platform, and structures on the surface during this phase would undergo no change since they would have been completed in the previous phase. Stormwater in each plot would be collected toward drains, canals, and finally discharged to Shwe Pyauk Creek. In case a flood were to occur, additional earth drain line will be installed around the boundary of the project area in order to prevent from flooding based on the experience of Zone A industrial area. Hence, as discussed in the above section, it can be judged that the impact on surface water flow would be considered to be less during the operation phase.

b) Water Discharge Volume

During the operation phase, after all tenants in the project area start their operation, the land cover of the project area would be the same as the situation at the end of construction phase. Stormwater runoff collected during the operation phase would be equal to that at the end of the construction phase. However, in addition to stormwater runoff, Shwe Pyauk Creek would receive treated industrial wastewater and domestic wastewater from the project area. Therefore, total water discharge volume to Shwe Pyauk Creek, including stormwater runoff, industrial wastewater, and domestic wastewater would be significantly increased, compared with the present status. However, excess flow rate of water discharge from the industrial zone to the creek would be equalized by retention ponds and retention canals. As a result, it is expected that changes in water current and water flow rate of the creek due to the Project would be minimized and limited. In short, the impact of water discharge from the project area on water current and flow rate of the creek would be limited by the installation of retention ponds.

c) Water Consumption and Its Impact on Creek Flow

Water used in the industrial area of Thilawa SEZ Zone B will be supplied by water purification plants which explore water resource from designated reservoirs in the region. Water exploration from creeks and groundwater in the project area would not be carried out. Therefore, the impact on hydrology of water consumption of tenants is negligible.

In summary, it is judged that the impact of the operation of the industrial zone on hydrology in terms of surface water flow, water drainage volume, and water consumption would not cause significant environmental impact on the surrounding area and downstream water bodies.

(3) Closing Phase

a) Surface water flow

During the closing phase, all tenants would stop their operation and then demolition work would be implemented. Factories, buildings, and facilities would be demolished. However, topography of the project area would not be changed significantly. Therefore, based on the judgment on surface water flow during the construction and operation phases above, it is expected that surface water flow basically would not be altered by the demolition work.

b) Water Drainage Volume

Demolition of structures, buildings, and facilities on the land surface would return the surface of the project area to the state before the Project commences. Water drainage volume collected from the project area would be equal to the current volume. Therefore, water drainage volume from the project area to Shwe Pyauk Creek during the closing phase would be the same as in the current situation.

c) Water Consumption and Its Impact on Creek Flow

Water consumed for demolition work and related activities during the closing phase would be similar to that during the construction phase, which includes water for washing vehicles and equipment, sprinkling water, and domestic water. Therefore, as discussed and evaluated in the above section, it can be concluded that water uptake from the groundwater during the closing phase would be very limited and would not cause any significant impact on Shwe Pyauk Creek.

In summary, it is judged that the impact of demolition work of the project area to hydrology in terms of surface water flow, water drainage volume, and water consumption would not cause significant environmental impact.

7.11 Soil Erosion

7.11.1 Forecast Item

The following items were examined to forecast the impact:

- Soil erosion of the bank of the project area during the construction and closing phases; and
- Soil erosion of the existing canal's riverbed due to the heavy water stream of water discharge from the project area during the operation phase.

7.11.2 Forecast Area

The areas examined to forecast the impact were set in the project area and Shwe Pyauk Creek, which will receive water discharged from the project area.

7.11.3 Forecast Period

As for the construction/closing phase, the period examined to forecast the impact was set during the implementation of the construction/closing work for the Project.

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the project area start their operation.

7.11.4 Forecast Method


The impact forecast for soil erosion was conducted as follows:

- During the construction/closing phases, the possibility of soil contamination due to the construction/demolition work in the industrial area of Thilawa SEZ Zone B was evaluated in consideration of the result of field survey and the proposed construction plan of the industrial area; and
- During the operation phase, the possibility of soil erosion due to stormwater and wastewater discharged from the industrial area of Thilawa SEZ Zone B was evaluated in consideration of the proposed design.

7.11.5 Forecast Result

During the construction/closing phases, soil erosion of bare area/bank would occur due to heavy rainwater. To keep the stability of the foundation bank and to prevent muddy water flow downstream during the rainy season (May to October), the project proponent would request contractors to prepare temporary drainage and sandbags bank. After completion of the landfill, planting trees, vegetation, and sodding in the bare area shall be implemented as soon as possible.

During the operation phase, the stormwater and wastewater from the project site will be controlled by the designed retention pond and retention canals. Storm water and waste water will be collected at retention pond finally. There is a sluice gate which pointed out by red frame, and it connects to the drainage that has been paved with concrete. In the case of overflowing from retention pond is happen, the energy dissipater will work and the discharging water current will be decrease. After sluice gate, the drainage water current to be minimized in the contact point with the bare land. Therefore, there is no significant negative impact on soil erosion. The plan of flood spillway from retention pond is shown in Figure 7.11-1. Additionally, the existing environmental conditions along the canal will not be changed. Therefore, it can be concluded that soil erosion in the creek during the operation phase would be very limited and would not cause any significant impact on Shwe Pyauk Creek.



Source: Project Proponent

Figure 7.11-1 Plan of Flood Spillway from Retention Pond


In summary, it is judged that the impact on soil erosion would not cause significant environmental impact.

7.12 Framework of Resettlement Works for The 2000ha Development Area of Thilawa SEZ

Some of the impacts on social environment are predicted and evaluated by considering results of baseline survey as well as the Framework for Resettlement Works for the 2,000ha Development Area (Resettlement Framework for 2,000 ha) prepared by TSMC on February 2016. Resettlement Framework for 2,000 ha is available to download through the website of Thilawa SEZ Management Committee⁵. The following impacts are evaluated based on Resettlement Framework for 2,000 ha.

- (1) Involuntary Resettlement
- (2) Living and Livelihood
- (3) Vulnerable Group
- (4) Local Conflict of Interest
- (5) Misdistribution of Benefit and Damage
- (6) Water Usage

In principle, Resettlement Framework for 2,000 ha had been prepared with the purpose of establishing a common assistance policy to PAHs/ PAPs of the entire 2,000ha including the development area of the Project. It is considered based on not only the laws/regulations in Myanmar but also JICA Guidelines for Environmental and Social Considerations (April 2010) which doesn't confirms any significant deviation from the World Bank Safeguard Policy "Operational Policy 4.12" on involuntary resettlement as the international standard. It provides various kinds of supports in kind or with cash in order to minimize the impact on physical and economic displacement before the actual relocation. Furthermore, after the actual relocation, harmonization between relocated PAHs/PAPs and host community will be also assisted to establish as a part of the supporting activities. For the detailed contents, it is described in the followings.



^{*} Special arrangement is provided for applicable PAHs/PAPs.

Source: Thilawa SEZ Management Committee, Framework of Resettlement Works for the 2,000 ha Development Area of Thilawa Special Economic Zone (SEZ), February 2016

Figure 7.12-1 Overall Framework of Assistance Package

Figure 7.12-1 shows the overall framework of assistance package for resettlement work. It provides the assistances for PAHs/ PAPs by a combination of: i) assistance for loss of assets, income sources/livelihood and resettlement, ii) assistance for vulnerable groups, and iii) special arrangement (arrangement of resettlement site and income restoration program (IRP)) in order to restore their livelihood to at least the pre-displacement level. The contents of respective assistance are summarized in Table 7.12-1 to Table 7.12-3.

٠

⁵ http://www.myanmarthilawa.gov.mm/resettlement-plan

Table 7.12-1 Summary of Contents of Assistance by Myanmar Government

	Category	Assistance			
1	Loss of Assets				
1.1	Fixed Assets (Except Land, To be compensated by TSMC)				
1)	Land* (paddy, garden)	Cash compensation at full replacement cost			
,	4 3,5	(To be compensated by Yangon Region Government)			
2)-1	House at own garden area	Cash compensation at full replacement cost			
2)-2	House at other areas (pasture land,	In-kind assistance at the resettlement site or cash assistance			
,	others' land, etc.)xxx				
3)	Hut	Cash assistance two (2) times of the current market price			
,	(De (Defined below)				
4)	Other Structures	Cash assistance two (2) times of the current market price (for 2)-1)			
,	(Kitchen or Toilet)	or in kind assistance at the resettlement site (for 2)-2)			
5)	Standing crops/trees	To be assisted as a part of loss of income sources			
1.2	Movable Assets (To be compensated				
1)	Large size livestock	Cash assistance per animal			
,	(cow and buffalo only)				
2)	Agriculture machinery or other	Cash assistance in the current market price if they are not able to be			
,	assets	used after relocation/resettlement			
2	Loss of Income Sources (regardless	of main or secondary income)			
2.1	Land-Based Income (To be compens				
1)	Paddy farmer	Cash assistance for three (3) years of yield amount in total in the			
,	,	current market price			
2)	Vegetable/Fruit Tree	Cash assistance for three (3) years of yield amount in total in the			
,	farmer	current market price			
3)	Livestock farmer	Cash assistance for three (3) years of income from cow for milking			
,	(cow and buffalo for milk)				
4)	Fish famer	Cash assistance for three (3) year of income from aquaculture			
2.2	Non Land-Based Income (To be compensated by TSMC)				
1)	Contracted worker, daily worker,	Cash assistance for non-working period for moving			
,	self-employed person (e.g.				
	carpenter, taxi-driver) whose				
	working place are remained after				
	relocation/resettlement				
2)	Owner of business running inside	Cash assistance equivalent to three (3) years of income from running			
	2,000 ha	business			
3	For Relocation (To be compensated in	by TSMC)			
3.1	Moving allowance	Cash assistance for moving cost			
3.2	Commuting assistance	Cash assistance for commuting cost as per number of workers and			
	_	students			
3.3	Cooperation allowance	Cash assistance for cooperation of moving in time			
4	Vulnerable Groups (To be compensated by TSMC)				
		Cash assistance equivalent to one big bag of rice (equivalent to 50kg			
		of rice) to following households:			
	the poor household, woman headed household, household w				
		disabled or elderly person			
5	Special Arrangement (for applicable	e PAHs/PAPs) (To be provided by TSMC)			
5.1	Arrangement of resettlement site	In kind assistance as plot at resettlement site with necessary			
		infrastructure			
5.2					
	case of the land where administrative procedures of land acquisition were not conducted in 1997				

*Note: In case of the land where administrative procedures of land acquisition were not conducted in 1997
Source: Prepared by the EIA Study Team based on Thilawa SEZ Management Committee, Framework of Resettlement Works for the 2,000 ha Development Area of Thilawa Special Economic Zone (SEZ), February 2016

Table 7.12-2 Summary of Assistance for Vulnerable Households by TSMC

Content of Assistance	Category	Number/Definition of Applicable Person	
Cash assistance	Households headed by woman	No. of unemployed persons*	
equivalent to one big bag of rice (equivalent to 50	Households headed by elderly	Total two persons: elderly person and one support person in the household	
kg of rice) per applicable	Households headed by disabled person, or including a disabled person	Total two persons: disabled person and one support person in the household	
Person	Households below the poverty line	No. of unemployed persons in the household	

Note: Unemployed person is defined as a person who is under workable age but not employed.

Source: Prepared by the EIA Study Team based on Thilawa SEZ Management Committee, Framework of Resettlement Works for the 2,000 ha Development Area of Thilawa Special Economic Zone (SEZ), February 2016

Table 7.12-3 Summary of IRP Components by TSMC

Component	Contents	Detailed Main Activities		
Support for Restoration of	(1) Support for income earning opportunity	 i) Series of technical support for improvement of work skills ii) Facilitation for job matching in and around the Thilawa SEZ area iii) Assistance for starting business 		
Economic Condition	(2) Support for account management	Support to open bank account Support to learn knowledge on increase of saving and reduce of debt		
2. Support for community development of		 i) Support to create a sense of cooperation among people ii) Support for coordination with host communities iii) Support for establishment of internal rules and system 		
Environmental and Social Living Conditions	(2) Support for awareness raising	Support for enlightenment on appropriate environmental and hygienic management Support for training for sustainable resettlement site management		
3. Monitoring and Follow-up		 i) Monitoring of economic restoration ii) Monitoring of environmental and social living conditions of the resettlement site iii) Further measures if necessary 		

Source: Prepared by the EIA Study Team based on Thilawa SEZ Management Committee, Framework of Resettlement Works for the 2,000 ha Development Area of Thilawa Special Economic Zone (SEZ), February 2016

7.13 Involuntary Resettlement

7.13.1 Forecast Item

The following items were examined to forecast the impact:

- Impact of land acquisition and involuntary resettlement due to the implementation of the Project.
- Impact on livelihood of relocated households after their resettlement.

7.13.2 Forecast Area

The area examined to forecast the impact was set in and around the project area.

7.13.3 Forecast Period

As for the pre-construction phase, the period examined to forecast the impact was set before the implementation of the construction work for the Project.

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the industrial area start their operation.

7.13.4 Forecast Method

The impact forecast for involuntary resettlement was conducted as follows:

- To quantitatively examine the scale of involuntary resettlement caused by the Project by analyzing the results of the detailed measurement survey (DMS) for the Framework of Resettlement Works for the 2,000 ha Development Area of Thilawa Special Economic Zone (Resettlement Framework for 2,000 ha).
- To confirm the contents of the assistance package for the project-affected households (PAHs) which are determined in the Resettlement Framework for 2,000 ha

7.13.5 Forecast Result

(1) Pre-construction Phase

According to Resettlement Framework for 2,000 ha, there are 1,088 households in total to be affected by the entire 2,000 ha development of Thilawa SEZ except Zone A. Among the total affected households, 161 households would be affected by the Project physically and economically, and 141 households would be required to displace from their current living area due to the land acquisition as shown in the Table 7.13-1.

Table 7.13-1 Number of Affected Households⁶

No. of affected households	No. of households required relocation		
161	141		

Source: EIA Study Team

⁶ Basically the affected households are identified based on the location of their living structure / farmland and the boundary of the project area. In case of the households which own living structure inside the project area, the location of that structure is applied for the identification of the affected household. In case of the households which own only farmland and do not own living structure inside of the project area, the location of farmland is applied for the identification of the affected household. In Table 7.13-1, "No. of households required relocation" means the households who have living structure inside the project area.

In order to minimize the impact, TSMC will support PAHs with the assistance package based on the Resettlement Framework for 2000 ha, which consists of: i) assistance for loss of assets, income sources/livelihood and relocation, ii) assistance for vulnerable groups, and iii) special arrangement (arrangement of resettlement site and income restoration program). The contents of the assistance package are summarized in Table 7.12-1 and, the implementation structure for resettlement work is described in Figure 2.6-2 in p.2-20.

The resettlement site will be arranged for the applicable PAHs; however, it was confirmed that some households currently utilizes or possess in the proposed relocation site. Some are living inside the proposed relocation site, and some are living outside but leasing their land to their relative or friends. Therefore, these households are required to relocate/resettle in other area in order to develop the relocation site. For such households, TSMC will organize adequate consultation to provide sufficient information and appropriate compensation/ assistance in a timely manner.

(2) Operation Phase

After the resettlement, some PAHs are forecasted to lose their income sources because it might be difficult for them to commute to their working place from their new living place, and also might be difficult for them to cultivate their farmlands continuously due to the displacement. In order to restore and stabilize the livelihood of displaced PAHs to the pre-displacement level at least after their resettlement, TSMC will provide an Income Restoration Program (IRP) based on the Resettlement Framework for 2,000 ha as shown in Table 7.12-3. The implementation structure is described in Figure 2.6-2 in p.2-20. As mentioned above, the negative impacts of involuntary resettlement due to the Project are inevitable. However, appropriate measures for the resettlement based on the Resettlement Framework for 2,000 ha would mitigate the impact.

Hence, it is judged that the impact of involuntary resettlement due to the Project would be minimized.

7.14 Living and Livelihood

7.14.1 Forecast Item

The following items were examined to forecast the impact:

- Impact of the Project on living and livelihood of PAHs by land reclamation
- Impact of the Project on living and livelihood of local community by construction work and the operation, the closing of the Project

7.14.2 Forecast Area

The area examined to forecast the impact was set in and around the project area.

7.14.3 Forecast Period

Throughout all phases from pre-construction phase to closing phase, the period examined to forecast the impact was set from the start of the pre-construction work for the Project until after closing all facilities and area in the Project.

7.14.4 Forecast Method

The impact forecast for living and livelihood was conducted as follows:

- To quantitatively examine the livelihood of PAHs by analyzing the results of DMS for Resettlement Framework for 2,000 ha.
- To qualitatively examine the impact of the Project on living and livelihood by referring to the proposed operation plan for the Project

7.14.5 Forecast Result

(1) Impact on living and livelihood of PAHs by land reclamation

The impact on living and livelihood of PAHs is expected during the pre-construction phase because PAHs would lose their income sources after the resettlement due to the changes in their life. The main income sources of PAHs are non land-based income sources such as odd/ wage worker (approximately 60%) and, it is followed by land-based income such as farming monsoon paddy/ vegetable (approximately 40%). It is expected that land-based income source would be affected more than non land-based income source since the paddy fields will not be able to be cultivated after their resettlement. Even for PAHs who has non land-based income source, it might be difficult to continue their livelihood due to the life change caused by the relocation.

In order to minimize the impact, the assistance for the loss of income source, which is not only for land-based (e.g., paddy farmer/vegetable farmer) but also for non land-based (e.g., odd job worker/wage worker, self-employed), will be provided based on the Resettlement Framework for 2,000 ha under the responsibility of TSMC. PAHs will be compensated for the loss of their income source before the resettlement. In addition, IRP for PAHs will be planned using the participatory approach in order to restore and stabilize the livelihood of the displaced PAHs to at least the pre-displacement level. It will be implemented continuously during the construction phase. PAHs whose income source will be directly affected by the Project, assistance for finding job opportunity and facilitation for job-matching in and around Thilawa SEZ would be provided under the IRP in order to restore their livelihood. The summary of the IRP components is shown in Table 7.12-3.

Furthermore, the project proponent will provide job opportunity and community support program as the one of CSR activities by targeting not only PAH but also the surrounding communities in and around Thilawa SEZ in order to mitigate the impact on the living and livelihood together with TSMC. A community fund has been established by collecting community relation fees from the tenants to secure sustainable implementation of CSR activities, and several community support programs have been already implemented such as vocational training to local people, job seminar and knowledge sharing to students in terms of the opportunity for capacity development. Moreover, the project proponent is planning to implement new community support programs and other CSR programs based on the requests from the surrounding communities in the variety fields such as student support program, improvement of public health in the communities, improvement of community infrastructure and improvement of community safety etc.

(2) Impact on living and livelihood of the surrounding community

In construction and operation phase, the unexpected impact on living and livelihood of the surrounding community would be arisen due to the construction work and the operation more or less. Considering the above situation, the project proponent will provide job opportunity and community support program in order to improve the situation on the living and livelihood. As mentioned above (1), the project proponent is planning to implement several community support programs as the one of CSR activities by targeting not only PAH but also the surrounding communities in and around Thilawa SEZ. Therefore, the situation on living and livelihood of the surrounding community would be improved by effort of the project proponent in and around Thilawa SEZ.

During the closing phase, it is expected that some people would lose their income source belonging to the Project due to the termination on the operation of tenants. According to the Employment and Skill Development Law (2013) in Myanmar, it is stipulated that resigning and termination of service and termination of agreement shall be included in contract agreement. Based on this law, the employment contract is prepared between employer and employee under the supervision of OSSC labor section in order to secure the worker's labor rights. In case the termination service will not be preceded fairly, workers are able to claim directly to OSSC and request authorized labor officers to settle and resolve the situation. In addition, the employment service will be provided with the cooperation and facilitation of Dept. of Labor under Ministry of Labor, Immigration and Population and relevant departments in townships for their alternative livelihood. Therefore, the impact on workers due to the termination of tenants would be well controlled and mitigated.

(3) Impact on the improvement of local economy

During the construction and closing phase, job opportunities are expected to increase for the construction and demolished work, e.g., construction worker, selling of fuel for the project vehicle, and food for the workers in the surrounding community due to the influx of construction labors.

During the operation phase, job opportunities are continuously expected to increase because the tenants will start their operation, and fuel for the Project and food for the worker will be supplied from the surrounding community.

Hence, it is judged that the Project would minimize significant negative impact on living and livelihood in the surrounding area.

7.15 Vulnerable People

7.15.1 Forecast Item

The following item was examined to forecast the impact:

- Impact of the Project on vulnerable groups of PAHs by land reclamation
- Impact of the Project on vulnerable groups of the surrounding community by construction work and the operation

7.15.2 Forecast Area

The area examined to forecast the impact was set in and around the project area.

7.15.3 Forecast Period

As for the pre-construction phase, the period examined to forecast the impact was set before the implementation of the construction work for the Project.

As for the construction phase, the period examined to forecast the impact was set during the implementation of the construction work for the Project.

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the project area start their operation.

7.15.4 Forecast Method

The impact forecast for vulnerable people was conducted as follows:

- To quantitatively examine the scale of PAHs that is defined as vulnerable group by analyzing the results of DMS for Resettlement Framework for 2,000 ha.
- To examine the impact of the Project on vulnerable people among PAHs and the surrounding community qualitatively by referring to proposed operation plan for the Project.

7.15.5 Forecast Result

(1) Impact of the Project on vulnerable groups of PAHs by land reclamation

Since there is no official definition of vulnerable groups in Myanmar, Resettlement Framework for 2,000 ha defines a vulnerable household as: i) a household headed by a woman, ii) disabled person or elderly, and iii) a household including a member of disabled person or a household below the poverty line⁷ by referring to the international practices of WB and ADB.

According to the result of DMS for Resettlement Framework 2,000 ha, a total of 36 households are confirmed as vulnerable groups to be affected by the Project. The PAHs defined as vulnerable groups are summarized with categories follows:

-

⁷ Integrated Household Living Conditions and Survey in Myanmar (2009-2010) was conducted by UNDP, UNICEF, SIDA and the Ministry of National Panning and Economic Development, and survey result was publicized as Poverty Profile in June 2011. Poverty line as of 2010 was defined as 376,151 kyats per adult equivalent per year in the Poverty Profile, and this amount is referred to as the poverty line in many reports. This framework also regards 376,151 kyats per adult equivalent per year as the poverty line.

Table 7.15-1 Number of Vulnerable Households to be Affected by the Project

Category	No. of Households
Households headed by woman	20
Households headed by elderly	16
Households headed by disabled person	2
Households below the poverty line	3
Households including a disabled person	1
Total	36

Note: Total number is different of sum of each category, because some HH fell into multiple categories.

Source: EIA Study Team

In pre-construction and during the construction phase, the impact on the economic situation of vulnerable group is expected. In general, they tend to be affected easily and seriously compared with that of the non-vulnerable households. In order to mitigate the impact on vulnerable group, special attention will be given to them by providing additional assistance based on the Resettlement Framework for 2,000 ha under the responsibility of TSMC. According to the assistance package in the Resettlement Framework for 2,000 ha, household defined as vulnerable group will be given the assistance differently depending on the category. This assistance will be provided in advance of the resettlement together with the other assistance package. The content of the other assistance is described in Table 7.12-2 in Section 7.12.

During the operation phase, more impact on the economic situation of vulnerable group is expected than that of the non-vulnerable group because they would spend longer period to restore their living at pre-displacement level. Therefore, TSMC would assist them, as part of the activities under IRP, such as giving priority for finding job opportunity and facilitation for job-matching in and around Thilawa SEZ. Internal/external monitoring will be also conducted by TSMC to follow the socio-economic situation of PAHs including vulnerable group.

Furthermore, the project proponent will provide special support targeting vulnerable people based on their request as necessary in order to improve the situation on their living and livelihood together with TSMC. Moreover, the project proponent is currently planning to implement new community support programs and other CSR programs based on the requests from communities including vulnerable people in the variety fields such as student support program, improvement of public health in the communities, improvement of community infrastructure and improvement of community safety etc.

(2) Impact of the Project on vulnerable groups of the surrounding community

During the construction and operation phase, unexpected impact on living and livelihood of the surrounding community would be arisen due to the construction work and the operation more or less. Considering the above situation, the project proponent will provide job opportunity and community support program in order to improve the situation on their living and livelihood,. As mentioned above (1), the project proponent is planning to implement several community support programs as the one of CSR activities by targeting not only PAH but also the local communities including vulnerable people in and around Thilawa SEZ. Therefore, the situation on living and livelihood of local community would be improved by effort of the project proponent in and around Thilawa SEZ.

(3) Impact on the improvement of local economy

During the construction and closing phase, job opportunities are expected to increase for the construction and demolished work, e.g., construction worker, selling of fuel for the project vehicle, and food for the workers in the surrounding community due to the influx of construction labors.

During the operation phase, job opportunities are continuously expected to increase because the tenants will start their operation, and fuel for the Project and food for the worker will be supplied from the surrounding community.

Hence, it is judged that the Project would minimize significant negative impact on vulnerable people in the surrounding area.

7.16 Local Conflict of Interest

7.16.1 Forecast Item

The following item was examined to forecast the impact:

- Impact on local conflict of interest caused by the Project between the following:
 - 1) Relocated PAHs and the host community in the proposed relocation site;
 - 2) PAHs of Zone A and PAHs of the Project; and
 - 3) Construction workers and local people.

The conflict which may be caused by job opportunities is predicted and evaluated in Section 7.17 Misdistribution of Benefit and Damage.

7.16.2 Forecast Area

The area examined to forecast the impact was set in and around the project area.

7.16.3 Forecast Period

As for the pre-construction phase, the period examined to forecast the impact was set after the start of planning and designing of the Project.

As for the construction phase, the period examined to forecast the impact was set during the implementation of the construction work for the Project.

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the project area start their operation.

7.16.4 Forecast Method

The impact forecast for local conflict of interest was conducted as follows:

- To examine the impact of the Project on local conflict of interest by referring to the proposed plan for the Project.

7.16.5 Forecast Result

(1) Impact on Local Conflict of Interest between Relocated PAHs and Host Community in the Proposed Relocation Site

According to the result of DMS for the Resettlement Framework for 2,000 ha, 141 PAHs will be required to relocate from the project area to other area because of the Project. In the proposed relocation site, the population will be suddenly increased during the short period due to the relocation of PAHs who choose to relocate in the proposed relocation site in the community. The local people in the host community will face more or less changes and inconvenience in various aspects of their life, for example, the increase of users for the existing social infrastructure/ service such as school and village health care center, public well, etc. Therefore, it should be considered and planned the expansion of capacity and the improvement of specification in advance. In this case, TSMC will consider planning the arrangement of necessary public facilities according to the expected demand of future users.

On the other hand, the assistance targeted for the relocated PAHs by TSMC may cause a sense of unfairness for the local people in the host community because the project-affected peoples (PAPs) of

the resettlement site will be preferentially hired as construction workers for the resettlement site development as part of IRP. Therefore, it will bring negative feeling for non-PAPs in the surrounding area that PAPs will take advantage of the development of the proposed relocation site. Moreover, there is a possibility for conflict to arise since their living styles and conditions may be different or it might be difficult to understand the existing social rules and system.

In order to avoid the serious conflict, TSMC will provide support for social integration with host communities and support for establishment of the harmonization by IRP based on the Resettlement Framework for 2,000 ha.

(2) Impact on Local Conflict of Interest between PAHs of Zone A and PAHs of the Project

Complaints are expected to arise regarding the difference in the rate of compensation between PAHs of Zone A and PAHs of the Project. However, TSMC will consider the amount of compensation for the PAHs of the Project by taking into consideration the price inflation based on the current economic situation. Through such explanation, conflict between PAHs of Zone A and PAHs of the Project is expected to be avoided.

(3) Impact on Local Conflict of Interest between Construction Workers and Local People

The conflict between construction workers and local people might be anticipated due to workers that migrate from other area and stay temporary in the surrounding area of the project area. In case of the development of Zone A, migrated workers stay in the adjacent of their working place and they disposes garbage near their living place without paying any attentions to the local community. Apart from disposed wastes, it is expected to rise complain on the worker's behavior such as bad driving rules and bad behaviors after working hours in the community. Therefore, contractor should provide environmental and safety instruction to workers to avoid the serious conflict with local people as a mitigation measure. The instruction should include the components for public health, safety, and other issues.

As mentioned above, there is a possibility to occur minor negative impacts of local conflict of interest during the pre-construction, construction, and operation phases depending on the situation. However, the implementation of respective appropriate measures would control and mitigate the impact for each conflict.

Hence, it is judged that the Project would minimize the impact on local conflict of interest in the surrounding area.

7.17 Misdistribution of Benefit and Damage

7.17.1 Forecast Item

The following item was examined to forecast the impact:

- Impact of the assistance to be provided by TSMC in the Project.
- Impact on the living environment in the local community.

7.17.2 Forecast Area

The area examined to forecast the impact was set in and around the project area.

7.17.3 Forecast Period

As for the pre-construction phase, the period examined to forecast the impact was set after the start of planning and designing of the Project.

As for the construction phase, the period examined to forecast the impact was set during the implementation of the construction work for the Project.

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the project area start their operation.

7.17.4 Forecast Method

The impact forecast on misdistribution of benefit was conducted as follows:

To examine the impact of the assistance to be provided by TSMC on the misdistribution of benefit and damage by reviewing the Resettlement Framework for 2,000 ha.

7.17.5 Forecast Result

(1) Impact of the assistance to be provided by TSMC

Generally, the misdistribution of benefit and damage would be anticipated when certain people are unfairly benefitted by the Project and it might be a potential factor to cause local conflict of interest.

Under the Project, the assistance for PAHs such as the assistance for the loss of assets and income source is basically designed to restore their livelihood to at least the pre-displacement level by mitigating the negative impact of the involuntary resettlement due to the change caused by the Project. Therefore, there is no misdistribution of benefit between PAHs and non-PAHs by the Project as a result of the assistance to be provided by TSMC.

(2) Impact on the living environment in the local community

The impact on the living environment of some people who are directly or indirectly affected by the construction work or by the operation of each tenant is expected. If complaint or clamor about the Project occurs from local people, they can communicate with the community relation department of the project proponent to solve the raised issues through discussion among stakeholders. This department is located in Thilawa area so that everybody can access the department easily. According to the community relationship officer of the project proponent, complaints regarding construction work have not been received so far regarding Zone A project.

In addition, the project proponent has been implemented several community support programs as the one of CSR activities by targeting not only PAH but also the local communities in and around Thilawa

SEZ so far. A community fund has been established by collecting community relation fees from the tenants to secure sustainable implementation of CSR activities. Moreover, the project proponent is planning to implement new community support programs based on the requests from communities in the variety fields such as student support program, improvement of public health in the communities, improvement of community infrastructure and improvement of community safety etc.

Therefore, these activities would help to establish harmonization with local communities and to balance the social, environmental and economic impacts of the Project by playing positive role as neighbor in Thilawa SEZ. As a result, misdistribution of benefit and damage would be minimized by the effort of the project proponent.

Hence, it is judged that the Project would not cause the significant impact and minimize the impact on misdistribution of benefit and damage in the surrounding area even if it happens.

7.18 Children's Rights

7.18.1 Forecast Item

The following item was examined to forecast the impact:

- Impact on educational opportunity on school children in PAHs of the Project
- Impact on educational opportunity of school children in local community
- Impact of the Project on increase of child labor

7.18.2 Forecast Area

The area examined to forecast the impact was set in and around the project area.

7.18.3 Forecast Period

As for the pre-construction phase, the period examined to forecast the impact was set after the start of planning and designing of the Project.

As for the construction phase, the period examined to forecast the impact was set during the implementation of the construction work for the Project.

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the project area start their operation.

As for the closing phase, the period examined to forecast the impact was set during the implementation of the closing work in the project area.

7.18.4 Forecast Method

The impact forecast for children's right is conducted as follows:

- To examine the population of children in PAHs under the Project by analyzing the results of DMS for the Resettlement Framework for 2,000 ha; and
- To review legal documents on child labor in Myanmar and international project/program on this subject.

7.18.5 Forecast Result

(1) Impact on Educational Opportunity of School Children among Relocated PAHs

There are 116 school children in total among the relocated PAHs, and these children's educational opportunity will be temporarily disrupted due to the relocation. Currently, majority of the children of PAHs in the project area go to school in and around Thilawa SEZ area. For primary school (B.E.P.S) students, they mostly go to schools in the nearest villages such as located inside the Excluded Area and along the outer boundary of Thilawa SEZ. For middle/ high school students (B.E.M.S/ B.E.H.S), they mostly go to schools in the urban wards of Kyauktan Township such as along Thanlyin-Kyauktan Road. In case that they relocate in the proposed relocation site in Myan Thar Yar ward, it is expected even those children can continue to go to their school but they have to spend more time/money for the commuting. Since relocation is necessary for some households, TSMC will provide cash assistance for commuting to school and will consider measure to minimize the impact as part of the IRP activities based on the dialogue with PAHs.

(2) Impact on Educational Opportunity of School Children of local community

Currently, the project proponent has implemented "Thilawa SEZ neighboring students Support Program" as one of the community support programs targeting not only for children of PAH but also for surrounding communities as described in Chapter 2. This program has contributed to provide more educational opportunity to children in the surrounding area of Thilawa SEZ and it is estimated that around 1,000 students are benefited from these activities in the local community so far. The detailed activities are shown in Table 2.7-4 of Chapter 2. In addition, the project proponent will implement this kind of educational program continuously based on needs and requests from the community. Based on above, the educational opportunity is expected to improve by the effort of the project proponent in the local community.

Table 7.18-1 Current Activities of Students Support Program by the Project Proponent

Activities

- Free English language class in the surrounding community
- School stationeries donation to the students
- Scholarship for 11 outstanding students for 6 academic year
- Supported excursion trip to the students
- Job Seminar and knowledge sharing program at Thanlyin Technological University to be persued as an Engineering career > about 600 students
- Health education and nutrition program at Myaing Tharyar school

Source: Prepared by EIA Study Team based on the information from the project proponent

(3) Impact on the increase of Child Labor

According to the Shops and Establishments Act 1951, it provides that children below 13 years old are not permitted to work in any shop, commercial establishment or establishment for public entertainment. It further mentions that no person employed by those shops or establishments shall be permitted to work for more than 8 hours in any day or more than 48 hours in a week. The Factories Act of 1951 prohibits children below 13 years old from working in factories while those 13 years old and above are allowed to work but are required by law to procure a Certificate of Fitness to gain employment⁸. In addition, children between 13-15 years old are not allowed to work in any factory for more than 4 hours a day and between 6 p.m. to 6 a.m. Those 16-17 years old are allowed to work up to 44 hours weekly. (ILO, 2015⁹) As mentioned above, as long as the Project and tenants keep laws in Myanmar, illegal child labor will be prevented in employment of labors. Moreover, recommendations by international organizations such as ILO should be referred the Project and tenants for the Thilawa SEZ as international industrial area.

In addition, the labor section of OSSC will supervise tenants not to employ children as labors illegally at the time workers of each tenant are registered and issued working registration in Thilawa SEZ from OSSC. Therefore, it is expected child labor would be controlled well to prevent employing by the function of the labor section, OSSC.

Hence, it is judged that the Project would not cause any significant negative impact on children's right in the surrounding area.

⁸ Amendments to these laws increasing the minimum age to 14 have been submitted to the Parliament.

⁹ Myanmar: Child labour knowledge, attitudes and practices (KAP) study in Yangon, Ayeyarwady Region and Mon State / International Labour Office, International Programme on the Elimination of Child Labour (IPEC) / Fundamental Principles and Rights at Work Branch (FUNDAMENTALS) - Geneva: ILO, 2015

7.19 Existing Social Infrastructure and Service

7.19.1 Forecast Item

The following item was examined to forecast the impact:

- Impact on the accessibility to social infrastructure and services for relocated PAHs of the Project and for local people in the local community of the project area.

7.19.2 Forecast Area

The area examined to forecast the impact was set in and around the project area.

7.19.3 Forecast Period

As for the construction phase, the period examined to forecast the impact was set during the implementation of the construction work for the Project.

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the project area start their operation.

7.19.4 Forecast Method

The impact forecast for existing social infrastructure and services was conducted as follows:

- To examine the impact of the Project on existing social infrastructure and services by referring to the proposed construction plan for the Project.

7.19.5 Forecast Result

(1) Impact to Relocated PAHs of the Project

For relocated PAHs, the impact of the Project on the accessibility to social infrastructure is unavoidable because they will not be able to/ will be difficult to access the social infrastructure such as schools and hospitals which they usually access before their relocation. On the other hand, the resettlement site will be arranged with basic social infrastructure as a part of the assistance by TSMC for those PAHs. Therefore, it is expected to provide another opportunity for the relocated PAHs to continuously access alternative social infrastructure even after their relocation.

(2) Impact to Local People in the local Community of the project area

For local people living in and around the project area, the accessibility of social infrastructure is expected to change more or less because of the construction work and the operation work.

During the construction phase, access road will be constructed as the main entrance for coming and going construction vehicles. On the other hand, it is confirmed based on the existing regional information that social infrastructures such as schools and hospitals are located in the populated area outside of Thilawa SEZ. Therefore, even though the traffic congestion might occur near the access road due to the temporal increasing on the construction vehicles, it will not be seriously affected to the accessibility to schools and hospitals. However, the contractors/the project proponent should control the traffic volume of construction vehicles to avoid the traffic congestion as much as possible.

During the operation phase, the impact on social infrastructure and service is expected to some extent in terms of local community scale. Accessibility to social infrastructure and service such as school, hospital and shops would be affected by the presence of tenants in the project area because most of the tenants in the project area would ban to access their plots after starting operation. Considering the

above situation, it is planned to construct the community road by the project proponent. The community road should have alternative function of the existing road in order to keep the accessibility in the local community. Location of the existing road is described in Figure 7.19-1.



Figure 7.19-1 Existing Community Road near the Project Area

In terms of the entire regional scale, positive impact is assumed because the basic infrastructures such as existing road and power supply will be improved combined with the development of the Project. As of May 2016, there are several infrastructure development projects ongoing around Thilawa SEZ supported by JICA. One of them is the official development assistance (ODA) loan project in which the Thilawa Port facilities and power related facilities, composing of 50 MW power plant, substation, 33 kV distribution line, 230 kV transmission line, and gas pipeline are to be developed. In addition, the improvement of the access road from Yangon City to Thilawa SEZ has also been planned in Phase II. Based on above, the improvement of the infrastructure in and around Thilawa SEZ area would bring smooth transportation and stable power supply to the surrounding community.

Hence, it is judged that the Project would not cause any significant impact on the social infrastructure and services in the surrounding area.

7.20 Water Usage

7.20.1 Forecast Item

The following item was examined to forecast the impact:

- Impact of the Project on water usage for daily life and on local water resources in and around the project area.

7.20.2 Forecast Area

The area examined to forecast the impact was set in and around the project area.

7.20.3 Forecast Period

As for the construction phase, the period examined to forecast the impact was set during the implementation of the construction work for the Project.

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the project area start their operation.

7.20.4 Forecast Method

The impact forecast on water usage and water rights is conducted as follows:

- To examine the impact on water usage for daily life and on local water resources in and around the project area by referring to the proposed construction plan and water supply plan for the Project.

7.20.5 Forecast Result

(1) During Construction Phase

Based on site reconnaissance, it was confirmed that there are one pond (shown as "Pond No.1"), which is approximately 0.5 acres, and one water pump (shown as "Water Pump") inside the project area. Pond No.1 is mainly used for domestic water by villagers in the surrounding area, and the Water Pump is owned and used by a private company. Based on the situation above, it is expected that these lake and water pump will not be able to use continuously due to the construction work and basically it should be compensated appropriately. In case of individual property, they will be basically compensated through the process of land acquisition in accordance with Land Acquisition Act (1894) by Yangon Regional Government (YRG) or TSMC based on the discussion with local people. It will be compensated through the clarification of ownership and usage condition. In case of common property, it will be compensated under the compensation policy of YRG or TSMC to villages or communities. In addition, the project proponent will arrange alternative pond near the lake based on the request from the local community as necessary.

The impact on the water usage due to the deterioration of water quality during construction is expected. As shown in Figure 7.20-1, another one lake and two public wells (shown as "Lake No.1, Well No.1 & 2") are located adjacent to the project area that are used for domestic and drinking water by the local villagers in Aye Myer Thida (Phalan). However, the impact on water usage for daily life of the local people is expected to be little because the discharge of muddy water from the bare land of the construction site will be temporary and treated by the settling ponds or simple turbid water treatment. In addition, wastewater from the construction camp will be properly treated by septic tanks. Therefore, the deterioration of water quality due to the construction works is expected to be limited.

Regarding the water for construction work, adequate amount of water to be used for the construction work would be secured from the outside or groundwater inside the project area by the project proponent/contractor. Existing local water resources such as Thilawa Dam or Zamani Dam would not be used for the construction work for the Project. In addition, the volume of water used for the construction work is expected to be limited such as for washing construction machines or sprinkling water to construction site. Discharging muddy water from bare land of construction site will just be temporary and wastewater from a construction camp, and will be properly treated by the septic tanks. Therefore, the impact of water usage for the construction work on the local water resource is expected to be negligible.



Source: EIA Study Team

Figure 7.20-1 Situation of water Usage in and around the Project Area

(2) Operation Phase

Based on the water supply plan for the Project, water from Zamani Reservoir is planned to be transmitted to the water purification plant (WPP) (Q=6,000 m³/day) established in Zone A through the pipe by the pump. The treated water from WPP is distributed to each tenant. Meanwhile, one Japanese ODA loan project is ongoing in which the public water supply pipe from Lagumbine Reservoir to Thilawa SEZ would be established Proposed unit volume of water supply (daily maximum water flow) is 80 m³/ha/day by 2018. Therefore, Zamani Reservoir and Lagumbine Reservoir will be used in parallel after 2019. The amount of water consumption will be controlled without causing impact on the local water usage. Considering the progress of the above project, the water supply plan for Zone B is prepared in two stages as shown in Table 7.20-1.

Table 7.20-1 Water Supply Plan in the Project Area

Timing	Water Supply Plan
Before around 2019	Distribute water to each tenant from water purification plant
(Before the water supply pipe has been installed)	(WPP) in Zone A by pumping from Zamami Reservoir
After around 2019	Distribute water to each tenant from water purification plant
(After the water supply pipe has been installed)	(WPP) in Zone A by pumping from Zamami Reservoir
	Connect to the public water supply pipe from Lagunbyin
	Reservoir and distribute water to each tenant

Source: EIA Study Team

According to the drainage plan of the industrial area, drainage water from the industrial area will run through the drainage ditch and retention pond and will be discharged to Shwe Pyauk Creek that connects to the Yangon River. Regarding the water usage for irrigation for paddy fields, the deterioration of water quality in the wells and lake adjacent to the industrial area is anticipated due to the discharged water from tenants during the operation phase. However, the water discharge from tenants will be treated at the treatment plant to comply with the industrial wastewater effluent guideline value stipulated by MOI and MOECAF and the proposed internal regulation. Therefore, the impact on water usage along Shwe Pyauk Creek for the daily life of the local people is expected to be limited in the project area.

On the other hand, the concentration of heavy metals and toxic substance of treated wastewater from tenants is not known concretely, at the present moment. The tenants will submit the future water demand plan to the project proponent, and the project proponent would prepare the adequate wastewater treatment measures adjust to the tenant's activities. Basically, it is expected that concentration of wastewater is diluted by mixing with stormwater through the retention pond and creek flow. In case that large amount discharge which includes heavy metals and toxic substance is expected and especially low flow season, the project proponent would review the internal target value and set strict standard for pre-treatment, if necessary.

Hence, it is judged that the impact on water usage and water rights caused by the Project during the construction and operation phases would not cause any significant social impact in the surrounding area.

7.21 Cultural Heritage/ Asset

7.21.1 Forecast Item

The following item was examined to forecast the impact:

- Existence and alteration of common assets in the project area.

7.21.2 Forecast Area

The area examined to forecast the impact was set in and around the project area.

7.21.3 Forecast Period

As for the construction phase, the period examined to forecast the impact was set during the implementation of the construction work for the Project.

7.21.4 Forecast Method

The impact forecast for cultural heritage is conducted as follows:

- To overlap the existence of common assets and the project-affected area whether alternation of common assets would occur because of the Project.

7.21.5 Forecast Result

Common assets are located in and around the project area as shown in Table 7.21-1. There is one cemetery located inside the project area which is called as Phalan Cemetery locally. It has approximately 3.2 ha (8 acres) and is mainly used by villagers in Aye Myar Thidar Village under the ownership of the village. It is expected that villagers will not be able to use this cemetery because the area for this cemetery is required the clearance before the commencement of construction work. In this case, adequate dialogue should be conducted between villagers and TSMC in order to discuss the necessity of relocation, arrangement of alternative place, and the actual relocation method for the cemetery.

Meanwhile, there are two Hindu temples and three monasteries located outside but adjacent of the project area. Two Hindu temples are both located inside Thilawa SEZ, and one monastery is located inside Thilawa SEZ and the other two are located in excluded area. These assets are all used by villagers in Aye Myar Thidar and Shwe Pyi Thar Yar, or the surrounding area under the ownership of the respective village. These are not required to be relocated by the Project, however, it will be required to be relocated at the time of further development of the industrial area. In that stage, TSMC should be made the adequate dialogue with villagers in order to discuss the necessity of relocation, arrangement of alternatives and the actual relocation method for these assets. In order to avoid the impact on dust, noise and vibration caused by the traffic of construction work and construction vehicle, adequate space for the assets will be secured to keep enough distance from the construction site.

Table 7.21-1 Common Assets Located in the Surrounding Area of the Industrial Area

No	Type of Asset (name)	Address of Asset	Total No. of Applied Households	Location
1		Aye Myar Thidar, Kyauktan	Whole village	Inside the industrial area
2		Aye Myar Thidar, Kyauktan	20	Outside the industrial area (inside Thilawa SEZ)
3	-	Shwe Pyi Thar Yar , Kyauktan	100	Outside the industrial area (inside Thilawa SEZ)

No	Type of Asset (name)	Address of Asset	Total No. of Applied Households	Location
4	1	Aye Myar Thidar, Kyauktan	200	Outside the industrial area (Excluded area)
5	1	Aye Myar Thidar, Kyauktan	Whole village	Outside the industrial area (inside Thilawa SEZ)
6	1	Ah Lun Soke village Thanlyin	ND	Outside the industrial area (Excluded area)

Note: Total No. of Applied Households is based on the interview results.

Source: EIA Study Team

As mentioned above, the negative impacts on common assets are inevitable. To minimize the impact, affected common assets should be relocated to the appropriate location based on the dialogue between TSMC and the local people.

In summary, the relocation work will be implemented in a careful manner based on local people's opinion by TSMC. Therefore, it is judged that the impact of the existence and alteration of common assets is expected to be minimized through the alternative plan for securing the function of common assets in the community.

7.22 Landscape

7.22.1 Forecast Item

The following items were examined to forecast the impact:

- Existence and alteration of landscape resources in the project area
- Landscape design within the SEZ

7.22.2 Forecast Area

The area examined to forecast the impact was set in and around the project area.

7.22.3 Forecast Period

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the project area start their operation.

7.22.4 Forecast Method

The impact forecast for landscape was conducted as follows:

- To examine the existence of landscape resources and whether alteration of landscape resources would occur as a result of the construction work of the Project

7.22.5 Forecast Result

(1) Impact of Existence and Alteration of Landscape Resources

According to the existing statistic data for land use in Thanlyin and Kyauktan townships, the main land use is agricultural land which is followed by water area and settlement area. Especially, Thanlyin Township has more human settlement area since the population is almost double of the one in Kyauktan Township. Focusing on the inside of Thiawa SEZ area, it was confirmed that agricultural land and grass land dominates the type of land use from the result of field survey conducted by the EIA Study Team. Landscape of Thilawa SEZ is composed of ordinary human living area and agri-purpose land such as paddy fields.

Since the late of 2013, the landscape as mentioned above has been already changed time by time because of the construction work for Thilawa SEZ Zone A. Approximately 400 ha of agricultural land has been already cleared and altered as the industrial zone among the entire area of Thilawa SEZ, and then several tenants already moved into and partly started their operation so far. Moreover, 262 ha of agricultural land will be cleared and altered to industrial area as the part of Zone B development.

Therefore, the existing landscape is in the process of semi-urbanization due to Zone A development and it will push the semi-urbanization more and more due to the Project.

(2) Impact of Landscape Design within the SEZ

As described above, semi-urbanization of landscape in and around Thilawa SEZ is inevitable due to the Project. However, since the development will be implemented under the appropriate policy and regulation in order to secure the environmental friendliness for users and residents, it will keep harmonization with the surrounding area.

For the public space of Zone B, the project proponent has responsibility to keep well-kept condition and greening. As described in Chapter 3, green space will be established for about 20.2 ha,

approximately 7.7% of the project area, along the main road, sub road and retention pond in the project area. The design of the greening will follow the design of Zone A industrial area, which set about 21.7 ha of green area. In addition, according to the internal regulation for the development of Thilawa SEZ, it mentions that the owner of the tenant industry shall be responsible for landscaping the plot and maintaining the same in a well-kept condition including, but not limited to, trimming, watering, and fertilization. Moreover, it is also mentioned that the landscape of each plot shall be harmonized with the public space of Thilawa SEZ. According to TSMC, tenants in Zone A industrial area set the greening area in each plot that covers averagely more than 15 % of each plot area so far. Tenants in the project area are also supposed to set such greening area for landscaping.

Therefore, as long as the tenants follow the internal regulation and the project proponent will make effort to maintain the public area, the landscape of the project area is expected to be well-maintained semi-urbanized area including some green area which enables to secure the environmental friendliness for users and residents around the Project.

Hence, it is judged that the impact of landscape in and around the project area would be controlled well by the Project.

7.23 Risks for Infectious Disease such as AIDS/HIV

7.23.1 Forecast Item

The following item was examined to forecast the impact:

- Impact on the risks for infectious diseases which might occur during the construction /operation / closing phase of the Project.

7.23.2 Forecast Area

The area examined to forecast the impact was set in and around the project area.

7.23.3 Forecast Period

As for the construction phase, the period examined to forecast the impact was set during the implementation of the construction work for the Project.

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the project area start their operation.

As for the closing phase, the period examined to forecast the impact was set during the implementation of the closing work in the project area.

7.23.4 Forecast Method

The impact forecast for the risk for infectious diseases was conducted as follows:

- To examine the risks for infectious diseases such as AIDS/HIV by considering the construction work plan operation/ closing work plan for the Project.

7.23.5 Forecast Result

According to the statistical data of Thanlyin and Kyauktan townships (Table 4.3-18, p.4-26 to p.4-28), the major diseases are common diseases (epidemic-prone) such as Diarrhea, and only relatively small number of people has suffered from communicable diseases such as Tuberculosis, Malaria and AIDS/HIV. For disease which can be prevented by immunization such as Diphtheria and Measles, the immunization rates are high both in Thanlyin and Kyauktan townships. It is assumed that the immunization program, which is for Diphtheria and Polio and Hepatitis, and Measles etc., is well known among the public and worked well for its prevention.

However, the risk of infectious disease is expected to increase due to the influx of labors from outside for the implementation of the Project during all stages. According to the monitoring result of Zone A, no incident for infectious disease during the construction phase is reported so far. However since communicable and vector-borne disease such as AIDS/HIV and dengue is considered as one of the most concerned matter to be controlled, the appropriate mitigation measure and countermeasure, monitoring should be taken by the construction contractor and each tenant in the respective stage. Especially, the mitigation measure stipulated in international guidelines such as EHS Guidelines by IFC as shown in Table 7.23-1 should be taken.

 Table 7.23-1
 Expected Mitigation Measures for Communicable and Vector-Borne Disease

Items	Expected Mitigation Measures
Activities in	- To provide surveillance for worker's health
construction/ closing	- Prevention of illness among workers by undertaking health awareness and education initiatives
work site, each	and by conducting immunization programs for workers
Tenants	- To provide treatment through standard case management in on-site
	- Promoting use of repellents, clothing, netting, and other barriers to prevent insect bites
	- Educating project personnel and area residents on risks, prevention, and available treatment
	- Elimination of unusable impounded water
Activities in and	- To provide treatment through community health care facilities as necessary
around the local	- Promoting collaboration with local authorities to enhance access of worker's families and the
community	community to public health services and promote immunization as necessary
	- Prevention of larval and adult propagation through sanitary improvements and elimination of
	breeding habitats close to human settlements as necessary

Source: EIA Study Team

For planning to implement immunization programs for workers and worker's families, it is recommended to collaborate with Public Health Department of Thanlyin and Kyauktan townships since public immunization program already exists and is widely known and used among local people. Likewise, it is also recommended to cooperate with related department especially Public Health Department for setting up reporting system in case of incidents in the site.

In addition to the mitigation measure implemented by the construction contractor and each tenant, the project proponent will implement CSR activities regarding health care for local community taking consideration into the public comment during PCM at draft EIA stage. The detail will be planned by community relation department of the project proponent based on the request and demand from local community. TSMC will also support to establish health care program by coordinating with township health department as necessary.

Therefore, it is expected that the impact on the risks for infectious disease will be managed and controlled well. Hence, it is judged that the Project would manage and control the social impact on infectious diseases well and moreover, contribute to the health care for the local community.

7.24 Occupational Health and Safety

7.24.1 Forecast Item

The following item was examined to forecast the impact:

- Impact on occupational health and safety which might occur during the construction/ operation/ closing work of the Project.
- Impact on labor right during the construction/ operation/ closing work of the Project

The impact on infectious disease is predicted and evaluated in Section 7.23 Risks for Infectious Disease such as AIDS/HIV.

7.24.2 Forecast Area

The area examined to forecast the impact was set in and around the project area.

7.24.3 Forecast Period

As for the construction phase, the period examined to forecast the impact was set during the implementation of the construction work for the Project.

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the project area start their operation.

As for the closing phase, the period examined to forecast the impact was set during the implementation of the closing work in the project area.

7.24.4 Forecast Method

The impact forecast for occupational health and safety was conducted as follows:

 To examine the impact on occupational health and safety caused during the construction/ operation/ closing phases by considering the construction/ operation/ closing work plan for the Project.

7.24.5 Forecast Result

- (1) Impact on occupational health and safety
- (1) Construction/ Closing Phases

According to the Environmental Monitoring Report for Thilawa SEZ Zone A development, which was prepared by the project proponent, accidents and incidents related to occupational and community health and the environment are regularly monitored and reported. From March 2014 to June 2015¹⁰, there were neither accidents nor incidents. However, there would be a possibility to occur accidents and incident during construction and closure works for the implementation of the Project. In order to prevent accidents and incidents, the project proponent regulates to install security and maintain safety prevention measures and devices suitable for use in each plot for construction in the internal regulation. Therefore, the working condition during the construction and closure should be managed by construction contractor based on the international guidelines such as EHS Guidelines by IFC as shown in Table 7.24-1. Especially when it is hot, countermeasures toward intense heat should be well

7-86

¹⁰ Monitoring result is available on website of the project proponent: http://mjtd.com.mm/jp/environmental-monitoring

conducted, by the construction contractor, while the project proponent will continuously give announcement to the construction contractor for the prevention of heat stroke.

In addition, the accommodation for workers will be arranged according to the project proponent of logistic, residential and commercial area in order to provide dwelling place for them.

Table 7.24-1 Expected Mitigation Measures for Occupational Health and Safety (During Construction/ Closing Phase)

Expected Mitigation Measures				
Common				
	uate health care facilities and first aid within construction sites			
	- To provide OHS training program and information of basic hazard awareness, site specific hazards, safe work practices, and			
emergency proce				
	S orientation training such as to all new employees the basic site rules of work at on the site and of personal			
protection and pro				
Occupational He	ealth			
- To provide adec	uate lavatory facilities for the number of people expected to work in the facility			
- To provide adec	uate supplies and easy access of drinking water with a sanitary means			
	porary shelters to protect against heat stroke during working activities or for use as rest areas as needed			
- To promote the	use of repellents, clothing, netting, and other barriers to prevent insect bites and snake bite			
Occupational Sa				
Over-exertion	- Training of workers in lifting and materials handling techniques in construction and decommissioning			
	projects, including the placement of weight limits above which mechanical assists or two-person lifts are			
	necessary			
	- Planning work site layout to minimize the need for manual transfer of heavy loads			
	- Selecting tools and designing work stations that reduce force requirements and holding times, and which			
	promote improved postures, including, where applicable, user			
	adjustable work stations			
	- Implementing administrative controls into work processes, such as job rotations and rest or stretch			
Slips and Falls	breaks - Implementing good house-keeping practices, such as the sorting and placing loose construction materials			
Stips and Falls	or demolition debris in established areas away from foot paths			
	- Cleaning up excessive waste debris and liquid spills regularly			
	- Locating electrical cords and ropes in common areas and marked corridors			
	- Use of slip retardant footwear			
Work in	- Training and use of temporary fall prevention devices, such as rails or other barriers able to support a			
Heights	weight of 200 pounds, when working at heights equal or greater than two			
8	meters or at any height if the risk includes falling into operating machinery, into water or other liquid, into			
	hazardous substances, or through an opening in a work surface			
	- Training and use of personal fall arrest systems, such as full body harnesses and energy absorbing			
	lanyards able to support 5000 pounds (also described in this section in Working at - Heights above), as			
	well as fall rescue procedures to deal with workers whose fall has been successfully arrested. The tie in			
	point of the fall arresting system should also be able to support 5000 pounds			
	- Use of control zones and safety monitoring systems to warn workers of their proximity to fall hazard			
	zones, as well as securing, marking, and labeling covers for openings in floors, roofs, or walking surfaces			
Struck By	- Using a designated and restricted waste drop or discharge zones, and/or a chute for safe movement of			
Objects	wastes from upper to lower levels			
	- Conducting sawing, cutting, grinding, sanding, chipping or chiseling with proper guards and anchoring			
	as applicable Maintaining along traffic ways to avoid thiving of beauty againment avon losse sorrer			
	- Maintaining clear traffic ways to avoid driving of heavy equipment over loose scrap			
	- Use of temporary fall protection measures in scaffolds and out edges of elevated work surfaces, such as hand rails and toe boards to prevent materials from being dislodged			
	- Evacuating work areas during blasting operations, and using blast mats or other means of deflection to			
	minimize fly rock or ejection of demolition debris if work is conducted in proximity to people or			
	structures			
	- Wearing appropriate PPE, such as safety glasses with side shields, face shields, hard hats, and safety			
	shoes			
Moving	- Planning and segregating the location of vehicle traffic, machine operation, and walking areas, and			
Machinery	controlling vehicle traffic through the use of one-way traffic routes,			
	establishment of speed limits, and on-site trained flag-people wearing high-visibility vests or outer			
	clothing covering to direct traffic			
	- Ensuring the visibility of personnel through their use of high visibility vests when working in or walking			
	through heavy equipment operating areas, and training of workers to verify			
	eye contact with equipment operators before approaching the operating vehicle			

Expected Mitigation Measures		
	- Ensuring moving equipment is outfitted with audible back-up alarms	
	- Using inspected and well-maintained lifting devices that are appropriate for the load, such as cranes, and	
	securing loads when lifting them to higher job-site elevations.	
Dust	- Dust suppression techniques should be implemented, such as applying water or non-toxic chemicals to	
	minimize dust from vehicle movements	
	- PPE, such as dusk masks, should be used where dust levels are excessive	
Confined	- Controlling site-specific factors which may contribute to excavation slope instability including, for	
Spaces and	example, the use of excavation dewatering, side-walls support, and slope	
Excavations	gradient adjustments that eliminate or minimize the risk of collapse, entrapment, or drowning	
	- Providing safe means of access and egress from excavations, such as graded slopes, graded access route,	
	or stairs and ladders	
	- Avoiding the operation of combustion equipment for prolonged periods inside excavations areas where	
	other workers are required to enter unless the area is actively ventilated	
Industrial	- To train and license industrial vehicle operators in the safe operation of specialized vehicles such as	
Vehicle Driving	forklifts, including safe loading/unloading, load limits	
and Site Traffic	- To establish rights-of-way, site speed limits, vehicle inspection requirements, operating rules and	
	procedures, and control of traffic patterns or direction	
Personal	- To identify and provide appropriate PPE that offers adequate protection to the worker, co-workers, and	
Protective	occasional visitors	
Equipment	- Proper maintenance of PPE and the instruction of proper use	

Source: EIA Study Team

(2) Operation Phase

At the time each tenant start their operation, accidents or incidents are expected to occur more or less during the operation phase. As same as construction phase, the project proponent regulates to install security and maintain safety prevention measures and devices suitable for use in each plot for operation as well in the internal regulation in order to prevent accidents and incidents. Based on the rules, the respective tenants should prepare and implement appropriate mitigation measure under the respective impact assessment based on the international guidelines such as EHS Guidelines by IFC with their own budget. Especially during the rainy season, countermeasures toward intense heat should be well prepared by each tenant, while the project proponent will continuously give announcement to the construction contractor for the prevention of heat stroke. In addition, the accommodation for workers will be arranged according to the project proponent of logistic, residential and commercial area in order to provide dwelling place for them.

Since the type of business is different in each tenant, the mitigation measure should be prepared for the respective occupational risk based on the operation plan and working condition of each tenant. Expected mitigation measure which recommends to be implemented by the project proponent or each tenant is shown in Table 7.24-2.

Table 7.24-2 Expected Mitigation Measures for Occupational Health and Safety (Operation Phase)

Expected Mitigation Measures			
Common			
- To provide adequate h	ealth care facilities and first aid within construction sites		
- To provide OHS traini	ng program and information of basic hazard awareness, site specific hazards, safe work practices, and		
emergency procedure			
- To provide OHS orien	ttation training such as to all new employees the basic site rules of work at on the site and of personal		
protection and preventir	ng injury		
Occupational Health			
- To provide adequate la	avatory facilities for the number of people expected to work in the facility		
- To provide adequate s	- To provide adequate supplies and easy access of drinking water with a sanitary means		
	- To provide temporary shelters to protect against heat stroke during working activities or for use as rest areas as needed		
- To arrange for provisi	- To arrange for provision of clean eating areas where workers are not exposed to the hazardous or noxious substances where		
there is potential for exp	posure to substances poisonous by ingestion of food as necessary		
- To promote the use of	repellents, clothing, netting, and other barriers to prevent insect bites and snake bite		
Occupational Safety			
Fire Precautions To i	nstall adequate number of equipping facilities with fire detectors, alarm systems and fire-fighting		
equi	pment and to maintain in good working order and be readily accessible.		

Expected Mitigation Measures		
Lighting	To arrange workplaces which receive natural light and are supplemented with sufficient artificial	
	illumination to promote workers' safety and health, and enable safe equipment operation to the degree	
	feasible.	
	To install emergency lighting of adequate intensity	
Safe Access	To install passageways for pedestrians and vehicles within and outside buildings for easy, safe, and	
	appropriate access	
	To install unobstructed, unrestricted, and ready access for equipment and installations requiring servicing,	
	inspection, and/or cleaning	
	To be in place measures to prevent unauthorized access to dangerous areas	
Work	To maintain the temperature at a level appropriate for the purpose of the facility in work, rest room and	
Environment	other welfare facilities during service hours	
Temperature		
Area Signage	To mark hazardous areas and installations and materials, safety measures appropriately in accordance	
	with international standards	
Labelling of	To label all vessels that may contain substances that are hazardous as a result of chemical or toxicological	
Equipment	properties, or temperature or pressure as to the contents and hazard, or appropriately colour coded.	
Communicate	To post copies of the hazard coding system appropriate place such as outside the facility at emergency	
Hazard Codes	entrance doors and fire emergency connection systems	
	To share information regarding the types of hazardous materials stored, handled or used at the facility	
	proactively with emergency services and security personnel	
Electrical	To mark all energized electrical devices and lines with warning signs	
	To lock out and tag out devices during service or maintenance	
Industrial	To train and license industrial vehicle operators in the safe operation of specialized vehicles such as	
Vehicle Driving	forklifts, including safe loading/unloading, load limits	
and Site Traffic	To establish rights-of-way, site speed limits, vehicle inspection requirements, operating rules and	
	procedures, and control of traffic patterns or direction	
Personal	- To identify and provide appropriate PPE that offers adequate protection to the worker, co-workers, and	
Protective	occasional visitors	
Equipment	- Proper maintenance of PPE and the instruction of proper use	

Source: EIA Study Team

(2) Impact on Labor Rights

According to Myanmar Special Economic Zone Law (2014), it is stipulated that TSMC "shall coordinate in determining the rights and duties of the employer and employee or terms and conditions relating to employment contained in the employment agreements for enjoying the rights in accordance with the existing labour laws including minimum wages, salary, leave, holiday, overtime charges, compensation for dismissal from work and workmen's compensation" in clause 70 (b). In Myanmar, the several labor related laws are stipulated labor rights as described in Section 2.1.2. Basic framework such as working hours, working days, payment of wage etc. and occupational safety and health in worksite is stipulated in the Factory Act (1951), the Shops and Establishment Act (1951), the Payment of Wages Act (1936). In addition, the Labour Organization Law (2011) and the Labour Dispute Settlement Law (2012) stipulate labor rights for labor organization and dispute settlement. Also, in case any injury or death happens due to any accidents or diseases arising during and in consequence of their employment, compensation shall be made in accordance with the Worker's Compensation Act (1923). On the basis with these laws, the employment contract shall be prepared between employer and employee under the supervision of OSSC labor section in order to secure the worker's labor rights.

Moreover, Myanmar Special Economic Zone Law stipulates that TSMC "shall inspect and supervise so as not to diminish or lose the rights and entitlements of the employees, technicians and staffs" in clause 70 (c) and "shall negotiate and mediate the disputes arising between the employer and the employee, the technician or the staff in the Special Economic Zone" in clause 76 (a). In accordance with these stipulations, currently, workers are able to claim directly to OSSC and request authorized labor officers to settle and resolve any disputes or conflicts between employee and employer during their contract period. Labor officers directly communicate and discuss with employee as necessary in order to solve problems, and this process works as a kind of grievance redress system. Therefore, it is expected that labor rights for workers of the Project will be secured well under the related labor laws.

Regarding dwelling place for workers, the accommodation only for single workers is currently being constructed near the project area. Furthermore the accommodation for the family of workers will be

newly planned considering the demand from workers and worker's family.

Hence, it is judged that the Project would control and minimize negative impacts on occupational health and safety.

7.25 Community Health and Safety

7.25.1 Forecast Item

The following item was examined to forecast the impact:

- Impact on public safety and security due to construction work and the operation, the closing work of the Project

The impact on infectious disease is predicted and evaluated in Section 7.23 Risks for Infectious Disease such as AIDS/HIV.

7.25.2 Forecast Area

The area examined to forecast the impact was set in and around the project area.

7.25.3 Forecast Period

As for the construction phase, the period examined to forecast the impact was set during the implementation of the construction work for the Project.

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the project area start their operation.

As for the closing phase, the period examined to forecast the impact was set during the implementation of the closing work in the project area.

7.25.4 Forecast Method

The impact forecast for community health and safety was conducted as follows:

- To examine the impact on public safety and security during the construction/ operation/ closing phases by considering the construction/ operation/ closing work plan for the Project.

7.25.5 Forecast Result

Regarding the impact on public safety, the risk of third party accidents is expected to increase due to the increase of vehicle traffic during all phases and the operation of heavy machineries during the construction/closing phases. The third party accident might be increased with local people especially children and student commuting to school near the project area. Increase of vehicle traffic will be caused not only by the project but also by the surrounding development project, i.e. development project of Zone A and development project of the logistic, residence and commercial areas of Zone B. As described in Section 7.2.4, traffic volume to be generated from the operation of the Project and the above mentioned two projects is estimated about 28,500 cars/day around the Thilawa SEZ after all three projects start their operation.

Regarding the impact on public security, the deterioration of public order such as crime is expected because of the influx of labors and people who are eager to have opportunies to gain profit by dealing business such as small restaurant or tea shop etc. Therefore, occurrence of incidents and disputes among local people and migrated workers may occur more or less. The living environment of local people is expected to be disturbed and lose their comfort by migrated workers in case they stay in and around the local community and they dispose garbage around their living place without paying any attentions to the local community.

In order to minimize such risks and the deterioration and disturbance in the local community, mitigation measures should be planned and implemented based on the international guidelines such as

the EHS Guidelines by IFC by the construction contractors during the construction and closing phase and by each tenant during the operation phase. The expected mitigation measure is summarized as shown in Table 7.25-1.

Table 7.25-1 Expected Mitigation Measures for Public Safety and Security

Factors	Expected Mitigation Measures
Common	- Establish the plan of site safety and security measures to communities and its implementation
	- Education and instruction to the project personnel and construction workers on risks, prevention, and
	available treatment
General Site	- Restricting access to the site, through a combination of institutional and administrative controls, with
Hazards	a focus on high risk structures or areas depending on site-specific situations,
	including fencing, signage, and communication of risks to the local community
	- Removing hazardous conditions on construction sites that cannot be controlled affectively with site
	access restrictions, such as covering openings to small confined spaces, ensuring means of escape for
	larger openings such as trenches or excavations, or locked storage of hazardous materials
Traffic Safety	Adoption of best transport safety practices across all aspects of project operations with the goal of
	preventing traffic accidents and minimizing injuries suffered by project personnel and the public.
	Measures should include:
	- Emphasizing safety aspects among drivers
	- Set of speed limit for drivers
	- Improving driving skills and requiring licensing of drivers
	- Adopting limits for trip duration and arranging driver rosters to avoid overtiredness
	- Avoiding dangerous routes and times of day to reduce the risk of accidents
Living	- Dispute settlement among stakeholders in case incidences occur
Environment	- Arrangement of worker's accommodation as necessary
and Others	

Source: EIA Study Team

In addition, the project proponent will install speed bump with the sign board on the road so as to let the speed of vehicle slow down. Moreover, TSMC and the project proponent should provide coordination with local people and handling complaints to solve as necessary. In addition to these mitigation measures, the project proponent will implement CSR activities regarding community safety as a part of the community support programs. The detail will be planned by community relation department of the project proponent based on actual request and demand from local community.

Hence, it is judged that the Project would control and minimize negative impacts on public safety and security in the surrounding area.

7.26 Usage of Chemicals

7.26.1 Forecast Item

The following item was examined to forecast the impact:

- Risk on usage of chemicals which might increase during the operation phase of the Project.

7.26.2 Forecast Area

The area examined to forecast the impact was set in and around the project area.

7.26.3 Forecast Period

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the industrial area start their operation.

7.26.4 Forecast Method

The impact forecast for usage of chemicals was conducted as follows:

- To examine the risk on usage of chemicals during the operation phase by considering the management activities to be carried out by the tenants.

7.26.5 Forecast Result

At present, the types of activities of tenants moving into the project area could not be clearly expected. Although the project proponent is not supposed to accept tenants whose operation is related to heavy chemical industries, some tenants would use chemicals to be managed under specific condition. Such tenants should have a chemical management plan which shall regulate their storage and usage condition. Under the plan, each tenant would secure specific storage site for chemicals, record the amount of chemicals used, provide the required training for safe usage, and prepare emergency response plans in case of emergency. In addition, the tenants as well as the project proponent should communicate chemicals to workers through labeling and making according to national and internationally recognized requirements and standards including Material Safety Data Sheet (MSDS) as stipulated in the EHS Guidelines by IFC. According to the guidance of the TSMC, tenants will be required to conduct the self-inspection biannually and to record the type/quantity of the chemicals and hazardous substance with the status of these management.

Under the Prevention of Hazard from Chemical and Related Substances Law (2013), the tenant dealing with vapor and oily liquid materials and solid having active chemical reaction should have the registered certifications for dealing with such chemicals, and conduct required actions stipulated under the abovementioned law, i.e.: (a) classify the danger level according to the properties of the chemicals, (b) reveal the danger warning sign, (c) attend the training for maintaining personal protective equipment and using them systematically to prevent accident, and (d) carry out the stipulations under the law in connection with the transporting, storing, using, and disposing of the chemicals. In case that each tenant operates the chemical management plan properly, the risk of usage of chemicals can be reduced to an acceptable level.

With reference to usage, producing, storing, disposing and handling of dangerous and hazardous materials, it is stipulated in the proposed internal regulation that the tenants must strictly comply with applicable laws, regulations, notice and any requirements from the project proponent.

Therefore, the risk of usage of chemicals is expected to be limited through the implementation of proper chemical management plans by the tenants.

7.27 Flood Risk

7.27.1 Forecast Item

The following item was examined to forecast the impact:

- Flood risk which might occur during the construction/operation/closing phases of the Project.

7.27.2 Forecast Area

The area examined to forecast the impact was set in and around the project area.

7.27.3 Forecast Period

As for the construction phase, the period examined to forecast the impact was set during the implementation of the construction work for the Project.

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the industrial area start their operation.

As for the closing phase, the period examined to forecast the impact was set during the implementation of the closing work in the project area.

7.27.4 Forecast Method

The impact forecast for flood risk was conducted as follows:

- To examine the impact on flood risk during the construction/operation/closing phases by considering the project plan.

7.27.5 Forecast Result

The elevation under the land reclamation plan of the Project is planned to be EL+5.5-7.0 m in consideration of EL+5.5 m, which is higher than the flood analysis water level (100 years return rainfall) of EL+4.9 m. In addition, appropriate drainage system will be installed so as to prevent inundation in the project area. Moreover, in terms of disaster management system, plan for emergency preparedness and response should be prepared including the contents below based on international guidelines such as the EHS Guidelines by IFC as much as possible by each tenant and the project proponent. Based on this plan, necessary equipment should be introduced in the proper mean.

Table 7.27-1 Expected Contents for Emergency Preparedness and Response Plan

- · Administration (policy, purpose, distribution, definitions, etc.)
- · Organization of emergency areas (command centers, medical stations, etc.)
- · Roles and responsibilities
- · Communication systems
- $\cdot\;$ Emergency response procedures and Emergency resources
- · Training and updating
- · Checklists (role and action list and equipment checklist)
- · Business Continuity and Contingency

Source: EIA Study Team

Hence, it is judged that flood risk is expected to be minimized by setting the abovementioned elevation level and appropriate drainage system in the proposed project plan.

7.28 Risk of Fire

7.28.1 Forecast Item

The following items were examined to forecast the impact:

- Risk of fire which might increase due to the construction/closing work of the Project.
- Risk of fire which might increase due to the operation of the Project.

7.28.2 Forecast Area

The area examined to forecast the impact was set in and around the project area.

7.28.3 Forecast Period

As for the construction phase, the period examined to forecast the impact was set during the implementation of the construction work for the Project.

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the industrial area start their operation.

As for the closing phase, the period examined to forecast the impact was set during the implementation of the closing work in the project area.

7.28.4 Forecast Method

The impact forecast for fire risk was conducted as follows:

- To examine the increase of risk of fire during the construction/closing phase by considering the construction/closing work-plan for the Project.
- To examine the increase of risk of fire during the operation phase by considering the Internal Regulations of Zone A prepared by MJTD that will also be prepared for the industrial area of Zone B.

7.28.5 Forecast Result

(1) Construction Phase

Risk of fire would increase due to the construction works and laborer's camp. However, it would be limited because the TSMC will regulate and apply the "building construction and fire safety" in the project area. According to this rule, investors shall apply for a Fire Safety Certificate to the Construction Section through the front office of the One Stop Service Center (OSSC) before construction. The application includes the following drawings: 1) architectural drawings (layout plan, finishing schedule, floor plans, elevations and sections), 2) means of egress (fire escape plan), 3) emergency lighting and exit signs, 4) fire alarm and detection system, 5) emergency generator, 6) fire hydrant (hose reel), 7) fire extinguisher, 8) sprinkler (if necessary), 9) dry riser/ breeching inlet (if necessary), 10) lightning arrester, 11) hazardous material safety plan, and 12) other items required by the Construction Section of OSSC. Investors should receive the certificate during the pre-construction phase.

In addition, internal regulation will be prepared for the industrial area of Zone B similar to the Internal Regulation of Zone A that obligates the installation and maintenance of security and safety measures and devices suitable for use during construction.

(2) Operation Phase

Risk of fire would increase due to the economic activities of the tenants and population growth in and around the project area. To minimize the impact, the abovementioned TSMC rule and the internal regulation for the industrial area of Zone B will be applied and obligate tenants to install appropriate security and safety system for their operations. The tenants shall install and maintain an effective fire alarm system and firefighting system for each building in the plot, and implement emergency drill with reference to the rule and regulation.

(3) Closing Phase

Risk of fire would be generated during the closing work such as demolition of facilities and removal of tenants in the industrial area. However, mitigation measures that will be applied during the construction phase will also be applied during the closing phase to minimize the impact.

As mentioned above, risk of fire is expected. However, appropriate mitigation measures will minimize the impact. Hence, it is judged that the Project would not cause any significant negative impact related to the risk of fire.

7.29 Earthquake

7.29.1 Forecast Item

The following item was examined to forecast the impact:

- Earthquake damage which might be extended during the construction/operation/closing phases of the Project.

7.29.2 Forecast Area

The area examined to forecast the impact was set in the project area.

7.29.3 Forecast Period

As for the construction phase, the period examined to forecast the impact was set during the implementation of the construction work for the Project.

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the industrial area start their operation.

As for the closing phase, the period examined to forecast the impact was set during the implementation of the closing work in the project area.

7.29.4 Forecast Method

The impact forecast for earthquake damage was conducted as follows:

- To examine the earthquake damage extended by the Project during the construction/closing phases by considering the construction/closing work-plans for the Project.
- To examine the earthquake damage extended by the Project during the operation phase by considering the environmental management by each tenant of the industrial area.

7.29.5 Forecast Result

(1) Construction and Closing Phases

Yangon has experienced several huge earthquakes in the past as mentioned in Chapter 4 and there is a possibility that earthquake will occur in and around Thilawa SEZ. If earthquake occurs during the construction/closing phases, the damage would be extended to some extent such as collapse of stage planks or buildings and injury by falling object. To minimize the damage by earthquake, working condition and disaster prevention activities should be managed by the contractor based on OHS training stipulated in international guidelines such as the EHS Guidelines of the IFC.

(2) Operation Phase

If earthquake occurs during the operation phase, the damage would be extended in the project area including buildings/factories of each tenant and infrastructure such as road, water treatment plant, sewage treatment plant, retention pond which is constructed by project proponent. To minimize the damage, the project proponent and tenants should design and construct their structures properly to meet the required standards such as earthquake resistance standards. As of March 2016, there are no enforced earthquake resistance standards in Myanmar. However, the Provisional Myanmar National Building Code 2012 was issued by the Ministry of Construction in Myanmar which sets the building design requirements including strength design. OSSC of TSMC has inspected the tenant's building

design with reference to this Code 2012 as described in the TSMC's Standard Operational Procedure (SOP) for building construction and fire safety.

Since the earthquake impact on this infrastructure development is not expected sever negative damage, special mitigations, required standard and code have not been set for development for road and retention pond and canal. However, to ensure safety in occupational environment for the staff, water treatment plant and sewage treatment plant in Zone B industrial area will be constructed to meet the required the Uniform Building Code. And emergency response plan for earthquake should be established by each tenant, and emergency drill should be implemented by the tenants to minimize the negative impact of earthquake.

Hence, it is judged that the earthquake damage during the construction/operation/closing works of the Project is expected to be limited because of the disaster prevention activities and application of earthquake resistance standards by the tenants.

7.30 Global Warming

7.30.1 Forecast Item

The following items were examined to forecast the impact:

- Greenhouse gas (GHG) emission increase due to the construction work of the Project.
- GHG emission increase because of the Project during the operation/closing phases.

7.30.2 Forecast Area

The area examined to forecast the impact was set in and around the project area.

7.30.3 Forecast Period

As for the construction phase, the period examined to forecast the impact was set during the implementation of the construction work for the Project.

As for the operation phase, the period examined to forecast the impact was set after the start of the operation of all phases when all the tenants in the industrial area start their operation.

As for the closing phase, the period examined to forecast the impact was set during the implementation of the closing work in the project area.

7.30.4 Forecast Method

The impact forecast for global warming was conducted as follows:

- To examine GHG emission during the construction/closing phases by considering the construction/closing work-plans for the Project.
- To examine GHG emission from tenants in the project area and vehicle traffic during the operation phase by considering the Internal Regulations of Zone A prepared by MJTD that will also be prepared for the industrial area of Zone B.

7.30.5 Forecast Result

(1) Construction Phase

GHG will be discharged from construction machineries and vehicles to some extent during the construction phase. To minimize GHG emission during the construction phase, mitigation measures shall be taken by the contractor, such as management of operation time of construction machineries, avoidance of excessive loading operation, and education of construction workers/drivers about the idling stop practice for construction machineries and vehicles.

(2) Operation Phase

GHG will be emitted by vehicles related to the Project and from the operation of tenants. In order to reduce GHG emission, usage of solar power to the street lamp and usage of LED in the project area is planned. In addition, energy-saving equipment and fuels that emit less GHG will be recommended to be installed to all tenants for their operations as much as possible. Besides, the utilization of commuter bus for workers to reduce traffic GHG emission will be initiated by the tenants.

(3) Closing Phase

GHG will be emitted from construction machineries and vehicles to some extent due to closing work such as demolition of facilities and removal of tenants. As is the case in the construction phase, GHG emissions would be reduced by mitigation measures for controlling GHG emissions.


Hence, it is judged that GHG emission due to the construction/operation/closing works of the Project would not cause any significant impact on global warming.

CHAPTER 8: CUMULATIVE IMPACT ASSESSMENT

As described in Chapter 3, Thilawa SEZ has been developed by each zone starting from Zone A since 2014. So far, there are three projects that have been operated/planned in the Thilawa SEZ, i.e. [Project 1] the development project of Zone A, [Project 2] the development project of the industrial area of Zone B (the Project) and [Project 3] the development project of the logistic, residence and commercial areas of Zone B. When assessing the impacts of the Project, it is necessary to consider the cumulative impacts that might occur from the combined effect over a given resource of several projects that will be operated physically close to the Project in future. Table 8.1-1 summarizes two surrounding projects that should be considered its impacts for assessing cumulative impacts. Figure 8.1-1 shows the location of two surrounding projects and the Project.

Table 8.1-1 Brief Description of the Projects that should be assessed the cumulative impacts

	Project	Project Description
1	Development Project of Zone	Area: Approximately 400 ha
	A	Land use: industrial area (total 284 ha of selling area)
		Its construction started in Jaunary 2014, and its operatoin started in August 2015. Some
		tenants already started their operation in Zone A.
2	Development Project of the	The Project
	Industrial Area of Zone B	
3	Development Project of the	Area: Approximately 267 ha of logistic area and 169 ha of residence and commercial
	Logistic, Residence and	areas.
	Commercial Areas of Zone B	Land use: logistic area (total 186.9 ha of selling area), commercial area (total 16.1 ha
		of floor area), and residence area
		This project is now on the EIA process and the construction work will start when it is
		approved.



Source: EIA Study Team prepared on the basis of the information from the project proponent

Figure 8.1-1 Location of the Projects that should be assessed Cumulative Impacts

In the assessment of the Project, the following environmental items were identified that should be considered the cumulative impacts of the two projects in Thilawa SEZ as mentioned above.

- (1) Air Quality,
- (2) Water Quality
- (3) Waste
- (4) Noise and Vibration
- (5) Flora/Fauna and Ecosystem
- (6) Community Health and Safety

Table 8.1-2 summarizes the basic concept of cumulative impact assessment of each items.

 Table 8.1-2
 Environmental Items of Cumulative Impact Assessment

	Environmental Item	Basic Concept of Cumulative Impact Assessment	Results of Assessment
(1)	Air Quality	When all three projects start their operation and all the tenants in the	Described in
		industrial, logistic and commercial areas of three projects start their	Section 7.2.
		operation, traffic volume will be increased cumulatively in and around	
		the Thilawa SEZ. Therefore, impact on air quality generated from these	
		traffic increased by operation of all three projects should be assessed. In	
		this assessment, NO ₂ and PM ₁₀ concentration was selected to be	
		estimated due to vehicle traffic increased by the three projects.	
(2)	Water Quality	In the project plan, drainage water from the project area will run	Described in
		through the drainage ditch and retention pond, and will be discharged to	Section 7.3.
		Shwe Pyauk Creek, which Zone A and a part of logistic, residence and	
		commercial area of Zone B will also discharge the drainage water.	
		Therefore cumulative impact should be assessed on water quality of	
		Shwe Pyauk Creek when all of three project start their operation.	
(3)	Waste	When all three projects start their operation and the number of tenants	Described in
		that start its operation is going to increase, amount of industrial and	Section 7.4.
		business related waste generated from the three projects will	
		proportionately be increased.	
		Therefore it is needed to evaluate impact of generated industrial and	
		business related waste in terms of receiving capacity of the final	
		disposal site located in Zone A.	
(4)	Noise and	When all three projects start their operation and all the tenants in the	Described in
	Vibration	industrial, logistic and commercial areas of three projects start their	Section 7.6.
		operation, traffic volume will be increased cumulatively in and around	
		the Thilawa SEZ.	
		Therefore, impact of noise and vibration increased by vehicle traffic	
(5)	E1 /E 1	generated from operation of all three projects should be estimated.	D " 1"
(5)	Flora/Fauna and	Change of land use and reduction of the habitat of species in the	Described in
	Ecosystem	Thilawa SEZ will impact on ecosystem. Since land reclamation of Zone	Section 7.9.
		A had already conducted when this assessment started, cumulative	
		impacts on ecosystem will be assessed by considering the change of	
		each land area including grass land, shrub, and reservoirs caused by the	
(6)	C : II 14	development of whole Zone B.	D '1 1'
(6)	Community Health	Community safety might be influenced by the increase of traffic volume	Described in
	and Safety	in and around the Thilawa SEZ caused by the operation of all three	Section 7.25.
		projects.	

CHAPTER 9: ENVIRONMENTAL AND SOCIAL CONSIDERATIONS IN TERMINATION AND AFTER TERMINATION

The "closing" hereby means demolition of facilities and structures within the project site. Whereas, "termination" and "after termination" mean complete stop of the Project (and returning the project site to pre-project condition) after the closing. The project proponent does not expect to close and terminate the operation of the industrial area of Zone B at least another 50 years. On the other hand, in case closing and termination of tenants in the industrial area of Zone B will occur in the future, the project proponent and each tenant will take necessary environmental mitigation measures in the termination phase as shown in Table 9.1-1. The project proponent will confirm their performance of environmental mitigation measures especially soil remediation, treatment of chemical and hazardous substances after termination of tenants, and report it to TSMC as shown in Table 9.1-2.

Table 9.1-1 Mitigation and Consideration Measures in the Termination Phase

Category	Item	Mitigation and Consideration Measures	Responsibility
Pollution	Waste, Soil contamination, Chemical	 Implementation of soil contamination survey including laboratory analysis. Treatment or removal of contaminated soil if contamination is found in the project site. Preparation of report to certify completion of treatment or removal of contaminated soil and its submission to the project proponent. 	Project Proponent/ Tenant

Source: EIA Study Team

Table 9.1-2 Mitigation and Consideration Measures after the Termination Phase

Category	Item	Mitigation and Consideration Measures	Responsibility
Pollution	Waste,	- Confirmation of the termination of tenants and performance	Project
	Soil contamination, Chemical	of treatment or removal of soil contamination. - Report of the results of confirmation of termination of tenants and the performance of treatment or removal of soil	Proponent/ Tenant
		contamination to TSMC.	

CHAPTER 10: ENVIRONMENTAL MITIGATION, MANAGEMENT AND MONITORING PLAN

10.1 Environmental Mitigation and Management Plan

As for the environmental items evaluated as A or B in accordance with the result of the impact assessment described in Chapter 7, the proposed Environmental Management Plans (EMPs) including mitigation measures to reduce and minimize the negative impacts for each phase of the Project: pre-construction phase, construction/closing phase, and operation phase, are prepared as shown in Table 10.1-1 to Table 10.1-3.

In implementation of the resettlement, the Thilawa SEZ Management Committee (TSMC) coordinated by two committees, namely: Relocation Implementation Committee (RIC) and Income Restoration Program Implementation Committee (IRPIC), will be responsible for the actual relocation and resettlement works in Thilawa SEZ, including income restoration program.

A consolidated summary list of environmental, social and health commitments that will be implemented in the Project in order to manage and mitigate potential impacts associated with the project development is provided in Annex10-1.

 Table 10.1-1
 Environmental Mitigation and Management Plan (Pre-construction Phase)

Category	Item	Expected Environmental and Social Impacts	Proposed Environmental Mitigation Measures and Environmental Management	Implementing Organization	Responsible Organization	Item of Expenditure
Pollution	Noise and Vibration	- Noise and vibration from tenants	 Arrangement of the land allocation for each tenant and the installation of buffer zone with less noise and vibration impacts to the surrounding sensitive receivers (monastery, residence etc.), as possible. 	Project Proponent	Project Proponent	-Layout planning cost
Social Environment	Involuntary Resettlement	- Loss or change of livelihood of relocated PAHs - Social impact to households that currently occupying the proposed relocation site	 Provision of land compensation (if applicable) Provision of assistance package based on Resettlement Framework for 2000 ha Preliminary discussion and provision of compensation and assistance for the households in the proposed relocation site as necessary 	TSMC	TSMC	Cost for land compensation, Cost for assistance package determined by Resettlement Framework for 2000 ha
	Living and Livelihood	 Impact of loss of livelihood opportunity, especially land-based livelihood such as paddy field and/or vegetable field 	 Provision of assistance on loss of income source and full implementation of IRP based on Resettlement Framework for 2000ha 	TSMC	TSMC	Cost for assistance package
	Vulnerable Group	- Loss or change of livelihood	Provision of special assistance in addition to the assistance on loss of assets and income source based on Resettlement Framework for 2000 ha	TSMC	TSMC	
	Local Conflict of Interests	Shortage of capacity on the existing infrastructure and service around the proposed relocation site	 Arrangement of adequate infrastructure and service based on the actual demand 	TSMC	TSMC	Installation cost
	Children's right	Impact on expenditure and time for commuting	- Commuting assistance for school for children of relocated PAHs	TSMC	TSMC	Cost for assistance package
	Existing Infrastructures and Services	- Suspension of existing road due to the construction work	- Construction of alternative community road	Project Proponent	Project Proponent	Cost for constructing road
		- Impact on accessibility of existing infrastructure and service to relocated PAHs	- Arrangement of alternative option for infrastructure and service after relocation	TSMC	TSMC	Installation cost
	Water Usage	- Suspension of using pond located inside the project area	- Arrangement of alternative pond near the project area	Project Proponent	Project Proponent	Cost for constructing pond
	Cultural Heritage/ Asset	 Possibility on the relocation of cemetery Indirect impact on other common asset 	- Adequate dialogue with local community in order to discuss necessity of relocation and the detail process for cemetery	TSMC	TSMC	Cost for the relocation of cemetary (if required to relocate) or cost for securing the space for the affected common asset

 Table 10.1-2
 Environmental Mitigation and Management Plan (Construction/Closing Phase)

Category	Item	Expected Environmental and Social Impacts	Proposed Environmental Mitigation Measures and Environmental Management	Implementing Organization	Responsible Organization	Item of expenditure
Pollution	Air Quality	- Impact of air pollution, dust/emission gases by construction work	 Sprinkle water around the project site and roads. Avoidance of intensive operation of construction machineries 	Contractor	Project Proponent	- Water and car running cost for sprinkling water
	Water Quality	Discharging muddy water from bare land Wastewater from construction camps	 Installation of settling ponds or simple turbid water treatment Installation of septic tank Preparation of the discharge water treatment plan 	Contractor	Project Proponent	- Equipment Installation Cost
	Waste	- Construction waste by cut earthwork	Reuse the residual soil generated in cutting work for filling work in the site Preparation and implementation of the waste management program	Contractor	Project Proponent	-Included in construction cost
	Noise and Vibration	Impacts of noise and vibration by construction machineries and vehicles	 Installation of sound-proofing sheet, Avoidance of construction at nighttime, Advanced notice for construction work time near the monastery and residential area Avoidance of intensive operation of construction machineries Speed limit for drivers 	Contractor	Project Proponent	- Facility installation cost- Education cost-Miscellaneous expenses
Natural Environment	Flora, Fauna, and Biodiversity	- Clearance of existing vegetation	- Clear marking of boundary of the project site to prevent the contractor from clearing the vegetation outside of the project site	Contractor	Project Proponent	-Miscellaneous expenses
	Hydrology	Impact on hydrology due to water consumption used in the construction work	 Limited and short term usage of groundwater Preparation of tentative retention pond 	Contractor	Project Proponent	- Construction cost for tentative retention pond
	Soil Erosion	- Soil erosion of the bank	- Provision of temporary drainage and/or sandbag to minimize soil erosion due to rainy water	Contractor	Project Proponent	-Miscellaneous expenses
Social Environment	Living and livelihood/	- Impact on the living and livelihood by construction	- Implementation of IRP for PAHs based on Resettlement Framework for 2000ha	TSMC	TSMC	-Assistance Package
	Vulnerable Group	works	 Advanced notice for construction work time Avoidance of intensive operation of construction vehicle 	Contractor	Project Proponent	-Miscellaneous expenses
	Local Conflict of Interests	- Conflict between construction workers and local people	- Education and training to give instruction to workers to avoid the conflict with local people	Contractor	Project Proponent	- Education cost
	Misdistribution of Benefit and Damage	- Impact on living environment in local community	- Communication with local community though community relation department	Project Proponent	Project Proponent	-Operation cost
	Children's right	- Impact on illegal child labor	- Compliance with the relevant regulations	Contractor	Project Proponent	-Miscellaneous expenses
	Existing Infrastructures and Services	Accessibility to social infrastructure for local community	- Control of traffic volume	Contractor	Project Proponent	-Miscellaneous expenses

Category	Item	Expected Environmental and Social Impacts	Proposed Environmental Mitigation Measures and Environmental Management	Implementing Organization	Responsible Organization	Item of expenditure
	Water Usage	Impact on the daily water use of local people by well or pond near project site	 Installation of settling ponds or simple turbid water treatment Installation of septic tank Preparation of the discharge water treatment plan 	Contractor	Project Proponent	-Assistance Package
	Cultural Heritage/ Asset	- Impact of dust, noise and vibration, traffic caused by construction work	- Securing adequate space for the assets to keep enough distance from construction site	Contractor	Project Proponent	-Miscellaneous expenses
Health and Safety	Risks for infectious diseases such as AIDS/HIV	- Increasing risks for infectious diseases due to the influx of workers	Conducting mitigation measures stipulated in the international guidelines such as EHS Guidelines of IFC such as; To provide surveillance for worker's health Prevention of illness among workers by undertaking health awareness and education initiatives and by conducting immunization programs for workers To provide treatment through standard case management in on-site and community health care facilities as necessary Educating project personnel and area residents on risks, prevention, and available treatment Promoting collaboration with local authorities to enhance access of worker's families and the community to public health services and promote immunization as necessary Promoting use of repellents, clothing, netting, and other barriers to prevent insect bites Prevention of larval and adult propagation through sanitary improvements and elimination of breeding habitats close to human settlements Elimination of unusable impounded water	Contractor	Project Proponent	- Education cost
Health and Safety	Occupational Health and Safety	- Accidents during construction work/closing work	Conducting mitigation measures stipulated in the international guidelines such as EHS Guidelines of IFC such as; [Common] - To provide adequate health care facilities and first aid within construction sites - To provide OHS training program and information of basic site rules of work, basic hazard awareness, site specific hazards, safe work practices, and emergency procedure [Occupational Health] - To provide adequate lavatory facilities for the number of people expected to work in the facility - To provide adequate supplies and easy access of drinking water with a sanitary means - To provide temporary shelters to protect against heat stroke	Contractor	Project Proponent	- Education cost - Water and car running cost for sprinkling water

Item	Expected Environmental and Social Impacts	Proposed Environmental Mitigation Measures and Environmental Management	Implementing Organization	Responsible Organization	Item of expenditure
Community Health and Safety	- Third party accidents with residents near the construction site - Accidents with local people by the traffic of construction vehicles - Disputes among local people and migrated workers	during working activities or for use as rest areas as needed To promote the use of repellents, clothing, netting, and other barriers to prevent insect bites and snake bite [Occupation Safety] Adequate preventive measures from negative factors such as over-exertion, slips and falls, work in heights, struck by objects, moving machinery, dust, confined spaces and excavations, and other site hazards To train and license industrial vehicle operators in the safe operation of specialized vehicles To establish driving and traffic rules To identify and provide appropriate PPE that offers adequate protection to the worker, co-workers, and occasional visitors Proper maintenance of PPE and the instruction of proper use Conducting mitigation measures stipulated in the international guidelines such as EHS Guidelines of IFC such as; [Common & Other] Establish the plan of site safety and security measures to communities and its implementation Education and instruction to the project personnel and construction workers on risks, prevention, and available treatment Dispute settlement among stakeholders in case incidences occur Arrangement of worker's accommodation as necessary Securing the existing water source [General Site Hazard] Restricting access to the site with a focus on high risk structures or areas depending on site-specific situations including fencing, signage, and communication of risks to the local community Removing hazardous conditions on construction sites such as covering openings to small confined spaces, ensuring means of escape for larger openings such as trenches or excavations, or locked storage of hazardous materials [Traffic Safety]		Project Proponent	- Education cost - Water and car running cost for sprinkling water
	Community Health and	Community Health and Safety - Third party accidents with residents near the construction site - Accidents with local people by the traffic of construction vehicles - Disputes among local people	Community Health and Safety	during working activities or for use as rest areas as needed - To promote the use of repellents, clothing, netting, and other barriers to prevent insect bites and snake bite Occupation Safety - Adequate preventive measures from negative factors such as over-exertion, slips and falls, work in heights, struck by objects, moving machinery, dust, confined spaces and excavations, and other site hazards - To train and license industrial vehicle operators in the safe operation of specialized vehicles - To identify and provide appropriate PPE that offers adequate protection to the worker, co-workers, and occasional visitors - Proper maintenance of PPE and the instruction of proper use Community	Community Health and Safety - Third party accidents with residents near the construction site Accidents with local people and migrated workers Disputes among local apeople and migrated workers Disputes among local apeople and migrated workers Securing the existing water source [General Site Hazard] Restricting access to the site with a focus on high risk structures or areas depending on site-specific situations including fencing, signage, and communication of risks to the local community Removing hazardous conditions or construction site Securing signage, and communication of risks to the local community Removing hazardous conditions on construction site Securing signage, and communication of risks to the local community Removing hazardous conditions on construction site Securing signage, and communities and its mightenentation Securing signage, and communities and its mightenentation Securing signage, and communication of risks to the local community Removing hazardous conditions on construction site such as covering openings to small confined spaces, ensuring means of escape for larger openings such as trenches or excavations, or locked storage of hazardous materials

Category	Item	Expected Environmental and Social Impacts	Proposed Environmental Mitigation Measures and Environmental Management	Implementing Organization	Responsible Organization	Item of expenditure
			to avoid overtiredness - Avoiding dangerous routes and times of day to reduce the risk of accidents			
Emergency	Flood Risk	- Increase of the impact of flood in and around the projects site	- Preparation of the disaster prevention equipment and management manual	Contractor	Project Proponent	- Education cost - Equipment purchase cost
	Risk of Fire	- Impact on the community around the project site by increasing of risk of fire	- Compliance with the TSMC's regulation for building construction and fire safety	Contractor	Project Proponent	- Education cost - Equipment purchase cost
	Earthquake	Increasing of the damage of the earthquake in and around the projects site	- Preparation of the disaster prevention equipment and management manual	Contractor	Project Proponent	-Education cost -Equipment purchase cost
Others	Global Warming	- Emission of greenhouse gases (GHGs) construction machineries and vehicles	- Control of GHGs emission in the construction work	Contractor	Project Proponent	-Miscellaneous expenses

 Table 10.1-3
 Environmental Mitigation and Management Plan (Operation Phase)

Category	Item	Expected Environmental and Social Impacts	Proposed Environmental Mitigation Measures and Environmental Management	Implementing Organization	Responsible Organization	Item of expenditure
Pollution	Air Quality	- Impact of air pollution caused by the tenants	 Provision of commuter bus Speed limit for drivers in the project area 	Tenants including Project Proponent		- Bus Operation cost
			 Preparation of feasible mitigation measures, such as, energy use efficiency, process modification, selection of fuels or other materials, the processing of which may result in less polluting emission, application of emission control techniques, if necessary 	Tenants	Tenants	- Installation cost
	Water Quality	- Effluent water from tenants and offices	- Operation and maintenance of pre-wastewater treatment	Tenants	Tenants	Installation costO&M cost
			 Operation and maintenance of centralized wastewater treatment system In case that large amount discharge which includes heavy metals and toxic substance is expected and especially low flow season, the project proponent would review the internal target value and set strict standard for pre-treatment, if necessary. 	Project Proponent	Project Proponent	- Installation cost of water treatment system - O&M cost

Category	Item	Expected Environmental and Social Impacts	Proposed Environmental Mitigation Measures and Environmental Management	Implementing Organization	Responsible Organization	Item of expenditure
	Waste	Impact of waste generated from factories and offices.	- Management of non-hazardous waste from tenants and utility area of themselves	Tenants	Tenants	- Disposal cost
			- Management of hazardous waste by tenants	Tenants	Tenants	Treatment costDisposal cost
	Soil Contamination	- Soil contamination is caused by the tenants and offices	 With reference to the process of usage, producing, storing, disposing and handling of oil, chemical, dangerous or hazardous materials in the project area, the tenants shall treat the materials safety on the covered area to prevent infiltration of the materials to ground, eliminate or dispose of all dangerous or hazardous materials and waste Solid waste receptacles or trash containers which must be large enough to facilitate storage and collection and which must be installed within the land of tenant. 	Tenants	Tenants	- Treatment cost
	Noise and Vibration	- Noise and vibration from tenants	 Preparation of the sound barrier, sound—absorbing materials, installing the facility in the house, having the enough buffer zone as necessary Installing vibration control devices for equipment, design of the structure to disconnect between the sources and ground as necessary 	Tenants	Tenants	-Installation cost
	Offensive Odor	- Odor caused by the tenants.	- With reference to usage, producing of disposing and handling of dangerous or hazardous materials in the project area, the tenants must, at its sole responsibility and expense, shall treat safety manage, eliminate or dispose of all dangerous or hazardous materials and waste - Waste reduction, waste minimization and cleaner production principles or conventional emission control equipment, as necessary	Tenants	Tenants	- Treatment cost
	Bottom Sediment	- Impact on bottom sediment by discharge water	 Operation and maintenance of the centralized wastewater treatment system In case that large amount discharge which includes heavy metals and toxic substance is expected and especially low flow season, the project proponent would review the internal target value and set strict standard for pre-treatment, if necessary. 	Project Proponent	Project Proponent	- Installation cost - O&M cost
Natural Environment	Flora, Fauna, and Biodiversity	- Impact of changing the vegetation	- Planting trees, vegetation, sodding of public spaces such as road, retention ponds, and other open space of each tenant	Tenants and Project Proponent	Tenants and Project Proponent	- Installation cost - Maintenance cost
	Hydrological	- Impact on hydrology due to the change in land use.	- Management of retention ponds	Project Proponent	Project Proponent	Installation costO&M cost
			- Install of additional earth drain line around the boundary of	Project Proponent	Project Proponent	Installation costO&M cost

Category	Item	Expected Environmental and Social Impacts	Proposed Environmental Mitigation Measures and Environmental Management	Implementing Organization	Responsible Organization	Item of expenditure
			the project area if a flood were to occur.			
	Soil Erosion	- Impact on existing canal by discharge water	- Management of retention pond	Project Proponent	Project Proponent	Installation costO&M cost
Social Environment	Living and Livelihood/ Vulnerable Group	- Impact on the living and livelihood for PAHs	- Implementation of IRP for PAHs based on Resettlement Framework for 2000ha	TSMC	TSMC	-Assistance Package
	Misdistribution of Benefit and Damage	- Impact on living environment in local community	- Communication with local community though community relation department	Project Proponent	Project Proponent	-Operation cost
	Children's right	- Impact on illegal child labor	- Compliance with the relevant regulations	Tenants and Project Proponent	Tenants and Project Proponent	-Miscellaneous expenses
	Water Usage	Impact on the daily water use of local people by well of lake near project site	 Management of drainage ditch and retention ponds inside of the Zone B industrial area In case that large amount discharge which includes heavy metals and toxic substance is expected and especially low flow season, the project proponent would review the internal target value and set strict standard for pre-treatment, if necessary. 	Project Proponent	Project Proponent	- Installation cost - O&M cost
	Cultural Heritage/ Asset	- Impact of dust, noise and vibration, traffic caused by	Securing adequate space for the assets to keep enough distance from construction site	Project Proponent	Project Proponent	-Miscellaneous expenses
	Landscape	- Alternation of the landscape	Following the rule of landscape in accordance with proposed industrial internal regulation	Tenants including Project Proponent	Tenants including Project Proponent	- Design and construction cost
Health and Safety	Risks for Infectious Diseases such as AIDS/HIV	Increasing risks for infectious diseases due to the influx of workers	Conducting mitigation measures stipulated in the international guidelines such as EHS Guidelines of IFC such as; To provide surveillance for worker's health Prevention of illness among workers by undertaking health awareness and education initiatives and by conducting immunization programs for workers To provide treatment through standard case management in on-site and community health care facilities as necessary Educating project personnel and area residents on risks, prevention, and available treatment Promoting collaboration with local authorities to enhance access of worker's families and the community to public health services and promote immunization as necessary	Tenants including Project Proponent	Tenants including Project Proponent	-Education cost

Category	Item	Expected Environmental and Social Impacts	Proposed Environmental Mitigation Measures and Environmental Management	Implementing Organization	Responsible Organization	Item of expenditure
	Occupational	- Accidents and incidents during	- Promoting use of repellents, clothing, netting, and other barriers to prevent insect bites - Prevention of larval and adult propagation through sanitary improvements and elimination of breeding habitats close to human settlements - Elimination of unusable impounded water Conducting mitigation measures training stipulated in the	Tenants	Tenants	- Education cost
	Health and Safety	the operation of each tenant	 international guidelines such as EHS Guidelines of IFC such as; [Common] To provide adequate health care facilities and first aid within construction sites To provide OHS training program and information of basic site rules of work, basic hazard awareness, site specific hazards, safe work practices, and emergency procedure [Occupational Health] To provide adequate lavatory facilities for the number of people expected to work in the facility To provide adequate supplies and easy access of drinking water with a sanitary means To provide temporary shelters to protect against heat stroke during working activities or for use as rest areas as needed To arrange for provision of clean eating areas where workers are not exposed to the hazardous or noxious substances where there is potential for exposure to substances poisonous by ingestion of food as necessary To promote the use of repellents, clothing, netting, and other barriers to prevent insect bites and snake bite [Occupational Safety] Adequate preventive measures from negative factors such as fire precautions, lighting, safe access, work environment temperature, area signage, labelling of equipment, communicate Hazard codes, electrical To establish rights-of-way, site speed limits, vehicle inspection requirements, operating rules and procedures, and control of traffic patterns or direction To identify and provide appropriate PPE that offers adequate protection to the worker, co-workers, and occasional visitors Proper maintenance of PPE and the instruction of proper use 			- Cost for installation of safety facilities

Category	Item	Expected Environmental and Social Impacts	Proposed Environmental Mitigation Measures and Environmental Management	Implementing Organization	Responsible Organization	Item of expenditure
	Community Health and Safety	 Third party accidents with residents near the construction site Accidents with local people by the traffic of construction vehicles Disputes among local people and migrated workers 	Conducting mitigation measures stipulated in the international guidelines such as EHS Guidelines of IFC such as; [Common] - Establish the plan of site safety and security measures to communities and its implementation - Education and instruction to the project personnel and construction workers on risks, prevention, and available treatment [General Site Hazard] - Restricting access to the site with a focus on high risk structures or areas depending on site-specific situations including fencing, signage, and communication of risks to the local community - Removing hazardous conditions on construction sites such as covering openings to small confined spaces, ensuring means of escape for larger openings such as trenches or excavations, or locked storage of hazardous materials [Traffic Safety] - Emphasizing safety aspects among drivers - Improving driving skills and requiring licensing of drivers - Adopting limits for trip duration and arranging driver rosters to avoid overtiredness - Avoiding dangerous routes and times of day to reduce the risk of accidents [Other] - Dispute settlement among stakeholders in case incidences occur - Arrangement of worker's accommodation as necessary	Tenants	Tenants	- Education cost - Cost for installation of safety facilities
			- Installation of speed bump with the sign board on the road as necessary	Project Proponent	Project Proponent	Installation costO&M cost
Emergency	Usage of Chemical	- Risk of chemical material	 Formulation of chemical management plan as necessary Training of safety usage and preparation of the emergency response plans Implementation of the proper storage and record of usage. Applying for the acquisition of the license with management plan in accordance with the relevant law, and compliance with the law. Provision of protective equipment and clothes to workers as necessary. 	Tenants	Tenants	-Education cost - Equipment purchase cost

Category	Item	Expected Environmental and Social Impacts	Proposed Environmental Mitigation Measures and Environmental Management	Implementing Organization	Responsible Organization	Item of expenditure
	Flood Risk	Increasing of the impact of flood in and around the projects site	Preparation of the disaster prevention equipment and management manual	Tenants including Project Proponent	Tenants including Project Proponent	-Education cost - Equipment purchase cost
	Risk of Fire	- Impact on the community around the project site by increasing of risk of fire	Installation of the fire hydrants along the road Implementation of emergency drill	Tenants including Project Proponent	Tenants including Project Proponent	-Education cost - Equipment purchase cost
	Earthquake	- Increasing of the damage of the earthquake in and around the projects site	 Compliance with the TSMC's Standard Operational Procedure for (SOP) for building construction Preparation of the disaster prevention plan such as emergency contact list 	Tenants including Project Proponent	Tenants including Project Proponent	-Education cost - Equipment purchase cost
Others	Global Warming	- Impact in the increase of GHGs by vehicle traffic operation of tenants in the operation phase.	- Control of GHGs emission by energy use efficiency, process modification, selection of fuels or other materials, the processing of which may result in less emission, application of emission control techniques, if possible - Provision of commuter bus	Tenants	Tenants	- Installation cost - O&M cost - Bus operation cost

10.2 Environmental Monitoring Plan

The environmental monitoring plan including monitoring items, location, frequency, and responsible organization at the pre-construction phase, construction phase, and operation phase are shown in Table 10.2-1 to Table 10.2-3. Responsible organizations shall review the monitoring plan in accordance with the progress of the Project and status of the situation before monitoring, if necessary, and implement monitoring activities and preparation of monitoring report on its results. The project proponent will submit the monitoring report at three stages to TSMC. The proposed monitoring form is shown in Annex 10-2.

Table 10.2-1 Monitoring Plan (Pre-construction Phase)

Category	Item	Location	Frequency	Responsible Organizations
Common	 Checking and revising the Environmental Mitigation (as shown in Table 10.1-1, 10.1-2, and 10.1-3) and Management Plan by reviewing the final detailed design of the Project Checking the Environmental Monitoring Plan during Construction prepared by Contractor 	Project Site	Once	Contractor
Social Environment - Involuntary Resettlement, - Living and Livelihood - Vulnerable Group,	- Monitoring of the implementation status of Resettlement works such as provision of assistance package for project affected persons, and common assets	Project Site and Relocation Site	Once	TSMC
- Vulnerable Group, - Cultural Heritage/ Asset	- Monitoring of the implementation status for CSR activities such as community support program	Around Project Site	Once /year	TSMC
Existing social infra- structures and services	- Securing of community accessibility	Around Project Site	Once	Contractor

Table 10.2-2 Monitoring Plan (Construction Phase)

Category	Item	Location	Frequency	Responsible Organizations
Common	- Monitoring of mitigation measures (as shown in Table 10.1-2)	Each location	Once/month	Contractor
Air Quality	- NO ₂ , SO ₂ , CO, PM _{2.5} , PM ₁₀	Construction site (1 point)*	1 week/3 months	Contractor
Water Quality	- Water temperature, pH, SS, DO, BOD ₅ , COD, coliforms, oil and grease, chromium	- Outflow of construction site to the creek (at least 3 sampling points/mixing point: i) discharge water, ii) upstream water, and iii) downstream water) ** - Well near the construction site (1 point)	Once/2 months	Contractor
Waste	- Amount and kind of solid waste	Construction site	Once/3 months	Contractor
Noise and Vibration	Noise and vibration levelTraffic count	Preservation area such as residence around the proposed construction site (at least 1 point	Once (24 hours)/3 months	Contractor
		Preservation site such as residence along the route for on-site vehicles (1point for noise and vibration and 2 points for traffic count)	Once (24 hours)/3 months	Contractor
Hydrology	Groundwater level Ground elevation level Consumption of groundwater amount	Well near the construction site	Once/ months	Contractor

Category	Item	Location	Frequency	Responsible Organizations
Living and Livelihood/ Vulnerable Group/ Misdistribution of Benefit and Damage/ Children's Right	- The implementation status for CSR activities such as community support program	Around Project Site	Once /year	Project Proponent
Risks for Infectious Disease such as AIDS/HIV	- Awareness of infectious diseases	Construction site	Once/month	Contractor
Occupational Health and Safety	- Record of accidents and infectious diseases	Construction site	Once/month	Contractor
Community Health and Safety	- Record of accidents and infectious diseases related to the community	Around construction site	Once/month	Contractor
	- The implementation status for CSR activities such as community support program	Around Project Site	Once /year	Project Proponent

Note: *Air quality monitoring site in the construction area should be selected in consideration of keeping the same location during construction phase.

** Water quality monitoring location should be selected at least three points for one discharge point to confirm the impact of the

Table 10.2-3 Monitoring Plan (Operation Phase)

Survey Item	Item	Location	Frequency	Responsible Organizations
Common	- Monitoring of mitigation measures (as shown in Table 10.1-3)	Project site	Quarterly (3 years after operation) Yearly (after 3 years operation)	Project Proponent
Air Quality	- NO ₂ , SO ₂ , CO, PM _{2.5} , PM ₁₀	Representative point inside the project area	1 week each in the dry and rainy seasons (first 3 years after starting of the operation stage)	Project Proponent
Water Quality	- Water temperature, water flow rate, pH, SS, DO, BOD ₅ , COD, color and odor, Total Nitrogen, Total Phosphorus, Sulphide, HCN, Oil, Grease, Formaldehyde, Phenols, Free chlorine, Zinc, Chromium, Arsenic, Copper, Mercury, Cadmium, Barium, Selenium, Lead, and Nickel	- Outflow of retention pond to the creek (at least 3 sampling points/mixing point: discharge water, upstream water, and downstream water)	Every month: Water temperature, pH, SS, DO, BOD ₅ , COD, color and odor, Every 3 month :all parameters	Project Proponent
Waste	 Amount of non-hazardous waste management Amount of hazardous waste management 	Each tenant	Twice/year (submission of the environmental report by the tenants)	Tenants
Soil Contamination	- Status of control of solid and liquid waste which causes soil contamination	Each tenant	Twice/year (submission of the environmental report by the tenants)	Tenants
Noise and Vibration	Noise level at the monastery and residences Traffic count	Tenants including Project Proponent	One time each in the dry and rainy seasons (first 3 years after starting the operation stage)	Tenants including Project Proponent

effluent water from the project site to the existing canal.

Survey Item	Item	Location	Frequency	Responsible Organizations
Offensive Odor	- Status offensive odor control by the tenants	Each tenant	Twice/year (submission of the environmental report by tenants)	Tenants
Bottom Sediment	- Water quality monitoring (as indicator of the pollution of the bottom sediment)	Same as the water quality monitoring	- Additional analysis on the bottom sediment of creek, in case of finding continuous high concentration	Project Proponent
Hydrological Situation	- Checking the function of retention pond at heavy rain.	Retention pond	When the heavy rain	Project Proponent
Living and Livelihood/ Vulnerable Group/ Misdistribution of Benefit and Damage/ Children's Right	- The implementation status for CSR activities such as community support program	Around Project Site	Once /year	Project Proponent
Risks for Infectious Disease such as AIDS/HIV	- Status of measures against infectious diseases	Each tenant	Twice/year (Submission of the environmental report by the tenants)	Tenants including Project Proponent
Occupational Health and Safety	- Record of accidents and infectious diseases	Work site and office	Twice/year (Submission of the environmental report by the tenants)	Tenants including Project Proponent
Community Health and Safety	- Record of accidents and infectious diseases related to the community	Around the project site	Twice/year (Submission of the environmental report by the tenants)	Project Proponent
	- The implementation status for CSR activities such as community support program	Around Project Site	Once /year	Project Proponent
Usage of Chemicals	- Record of the type and quantity of chemicals and implementation status of control measures through self-inspection	Each tenant (that uses chemicals)	biannually	Tenants

10.3 Budget for the Environmental Management and Monitoring

This section describes the budget plans for the environmental management and environmental monitoring by the project proponent.

On the other hand, the tenants will take necessary environmental mitigation measures and its expenses for the environmental management not only at the construction and operation phases but also at the closing, termination, and after termination phases in accordance with their EIA/IEE studies. However, the budget plan for environmental management of each work cannot be estimated at this stage because there is no certain information on industrial sectors of tenants.

10.3.1 Budget Plan for Environmental Management

Most of the mitigation measures such as construction of retention ponds, centralized wastewater treatment plant, and plans and trainings are already included in the project cost. The main costs for mitigation measures are shown in Table 10.3-1. The detailed costs for each mitigation measure are to be calculated at the detailed design stage.

Table 10.3-1 Cost for Main Mitigation Measures (as of May 2016)

		Budget		
No.	Item	Before/During Construction Phase	Operation Phase	
1	Retention ponds	USD 70,000	USD 3,000/year	
2	Residential road for the purpose of community accessibility improvement	USD 50,000	USD 2,500/year	
3	Greening area	USD 130,000	USD 7,000/year	
4	Others (sprinkle water, waste disposal, training and education)	Included in the project cost	-	

Note: Budget is estimated as of May, 2016

Source: EIA Study Team

10.3.2 Budget Plan for Environmental Monitoring

In terms of the budget for environmental monitoring before/during construction and operation phases, main monitoring cost is a cost for field measurements such as air quality, water, and quality noise. Annual costs for field measurements in the construction phase by contractor and in the operation phase by the project proponent are estimated, respectively, as shown in Table 10.3-2.

In addition, another main cost is the one for community support programs as a part of CSR activities as mentioned in Section 2.7.3 of Chapter 2. The budget of community support programs is collected monthly with certain amount as community relation fees from each tenant of the industrial zone. All of the money is allocated to implementation of community support programs and other CSR programs which are planned based on the request and actual demand from the communities.

Table 10.3-2 Estimated Annual Costs for Monitoring in the Construction and Operation Phases

Phase	Monitoring Items	Implementing Organization	Expected Cost	Remarks
Construction Phase	Air Quality, Water Quality, Noise and Vibration, Ground Water Level	Contractor	USD 15,000/year	Only the cost for field measurements is included
Operation Phase	Air Quality, Water Quality, Noise and Vibration, Ground Water Level	Project proponent	USD 10,000/year	Not included is the cost used by tenants. Only the cost for field measurements is included

Note: 1) Budget is estimated as of May, 2016

2) In case that the cost for monitoring in construction and operation phase will be exceeded the budget, the extra expense will be secured by the project proponent.

10.4 Implementation Schedule

The implementation schedule as of May 2016 of the pre-construction, construction, and operation phases of Thilawa SEZ Development Project (Industrial Area of Zone B) is as follows:

1) Pre-construction period: from 2015 to get approval of EIA and land lease agreement

2) Construction period : 17 months (After get approval of EIA and land lease agreement)

3) Operation period : 75 years (Maximum)

10.5 Institutional Arrangement

The organizational structure for the operation and management of environmental monitoring is shown in Figure 10.5-1. Each tenant will implement EMP and EMoP for each business and submit the environmental monitoring report to OSSC of TSMC and the project proponent based on its IEE/EIA. The project proponent will submit the monitoring report based on the results of implementation of EMP and EMoP for the Thilawa SEZ Zone B industrial area development.

As for environmental management, two officers from Environmental Conservation Department of MONREC have been dispatched to the environment section in OSSC. As the regular tasks, the officers review application documents related to environment from investors, conduct environmental inspection during construction phase, before commencement of operation, and during operation.

The project proponent will be in charge of the overall operation of the Thilawa SEZ Zone B industrial area. Firstly, the project proponent will formulate the internal regulations for the industrial area of Zone B, like the Internal Regulations for Zone A formulated in January 2015 that stipulates several obligations such as effluent standards of wastewater and air, noise standard, and regulation of protective controls to the tenants.

Main tasks for environmental and social consideration in the project proponent are managed by Environment, safety and health section and/or Community relation division, as show in Table 10.5-1.

On the other hand, some tenants which may cause adverse environmental impacts may be required to conduct IEE or EIA. TSMC judges necessity of IEE or EIA based on the draft ECPP prepared by applicants. The each tenant above shall conduct the environmental management, mitigation measures and monitoring for its operation activities by own expense in accordance with ECPP approved by OSSC/TSMC.




Figure 10.5-1 Proposed Organizational Structure for Environmental Management of the Project during the Operation Phase

Table 10.5-1 Main Tasks for Environmental and Social Consideration in MJTD

Division/ Section	Main Tasks
Environment, safety	1) Assisting tenants in the environmental assessment of factory development as follows:
and health section	- Providing information on environmental regulations and local consultants; and
	- Facilitating communication with TSMC for environmental and social issues.
	2) Monitoring the Thilawa SEZ Zone B industrial area operations according to EMP and EMoP, and;
	3) Submitting environmental monitoring reports to TSMC.
Community relation	1) Grievance Adjustment
division	- Handling complains/ claims/ requests from community and its response as necessary
	- Coordinating between tenant and community for grievance adjustment
	2) Planning and implementation of CSR activities
	3) Consultation with tenant related to community relation
	4) Job matching and assistance

CHAPTER 11: PUBLIC CONSULTATION AND PUBLIC DISCLOSURE

11.1 Approach and Objectives of PCM and PD for EIA

11.1.1 Approach of PCM and PD for EIA

Public consultation meeting (PCM) and public disclosure (PD) offer an opportunity for people to participate in the decision making process for project design, development, and implementation of the Project. It provides a platform for project-affected persons and different stakeholders to express their views on possible impacts of the proposed intervention on environmental and social parameters.

PCM and PD for EIA are planned at two different stages (EIA scoping stage and draft EIA report stage) in order to collect opinions and feedback of the public and to disseminate information on the Project and EIA Study.

(1) EIA Scoping Stage

The first stage of the PCM and PD for EIA is conducted at the time of environmental scoping in the initial stage of the EIA study. Information on the Project and scope of the EIA study is disseminated to the public and then comments and opinions are collected to incorporate into the EIA study.

(2) Draft EIA Report Stage

The second stage of the PCM and PD for EIA is conducted at the time of preparations of draft EIA report. Information about findings of draft environmental and social impact assessment study and proposed mitigation measures are disseminated to the general public that are directly or indirectly affected by the Project. In addition, their feedback and opinions are obtained which are reflected in the EIA report together with their comments and request on the environmental and social mitigation measures, environmental management plan (EMP) and environmental monitoring plan (EMOP).

11.1.2 Objectives of PCM and PD for EIA

The primary objective of the PCM and PD is to incorporate the opinion and suggestions of the public and all other stakeholders at the project planning stage to ensure wider acceptability of the Project. The key objectives are as follows:

- 1) To provide information on the economic, environmental, and social benefits as well as potential negative impacts from the Project;
- 2) To ensure that the potential PAPs, stakeholders, and local communities are engaged in a meaningful dialogue and are well informed prior to the decision of the project proponent as to the nature and extent of social and environmental impacts attributable to the proposed project with respect to planning;
- 3) To ensure that the concerns of, and issues raised by the PAPs, stakeholders, and local communities are incorporated and adequately addressed in the EIA study;
- 4) To engage in a participative exercise with PAPs, stakeholders, and local communities and obtain expertise and local, traditional wisdom and knowledge from them in order to plan the mitigation measures; and
- 5) To facilitate periodic opportunities to the principal stakeholders to offer their inputs on all key components of the Project.

11.1.3 Stakeholder Engagement Plan

In order to ensure effective engagement and open, frequent and honest dialogue with local communities and other key stakeholders, a stakeholder engagement plan is designed throughout the life of the Project. This plan is to be developed and implemented in order to identify stakeholder and their issues of concern, establishes the methods for consultation, and provides a specific action plan for stakeholder engagement throughout the life of the Project.

Table 11.1-1 Stakeholder Engagement Plan

Key stakeholders			
Project Proponent:	Myanmar Japan Thilawa Development Limited (MJTD)		
Related organizations/	Thilawa SEZ Management Committee (TSMC)		
Local government:	General Administration Department (GAD), Yangon Southern District		
o o	GAD, Thanlyin and Kyauktan townships		
	Municipal Department, Thanlyin and Kyauktan townships		
	Municipal Department, Thanlyin and Kyauktan townships		
	Housing Department, Ministry of Construction, Thanlyin Township		
	Rural Development Department, Thanlyin and Kyauktan townships		
	Department of Health, , Thanlyin and Kyauktan townships		
Local people:	Under Thanlyin Township;		
	Villagers in Hpa Yar Kone/ Let Yet San/ Ah Lun Soke Village Tract		
	Under Kyauktan Township;		
	Villagers in Aye Mya Thi Dar/ Shwe Pyi Thar Yar/ Thi Tar Myaing/ Shwe Pyauk Ward or		
	Village Tract		
Private business:	Private companies/ factories including tenants in Zone A and self-employed business in and		
	around Thilawa SEZ area		
Non Governmental	Community Based Organizations that do activities Thilawa SEZ area		
Organizations:			
Engagement methods			
EIA phase:	- Organizing consultation meetings inviting key stakeholders above at draft scoping report and		
	draft EIA report		
Pre construction/	- Regular communication with local community through Community Relation Department at		
Construction phase/	MJTD office		
Regular operation	- Meeting with the representative of village* around Thilawa SEZ area on the quarterly basis		
Phase:	at least (* village tract officer, 100 household head, other represented persons etc.)		
	- Participatory meeting with villagers		
	- Interview survey with villagers		
	- Communication with local community in cooperation with Front Office of TSMC		
Information disclosure			
EIA phase:	- Disclosures of draft scoping report and draft EIA report		
Pre construction/	- Information sharing at Community Relation Department at MJTD office		
Construction phase/	- Responding inquiries at Community Relation Department at MJTD office		
Regular operation	- Communication with local community in cooperation with Front Office of TSMC		
Phase:	• •		
Grievance mechanism pro	ocess and complaints register		
All phase:	Receiving complains and opinions from the public on regular basis at MJTD office through		
	the engagement method;		
	- Meeting with the representative of village		
	- Participatory meeting with villagers		
Source: EIA Study Team			

Source: EIA Study Team

11.2 Scoping Stage

11.2.1 Public Consultation Meeting at the Scoping Stage

(1) Implementation of PCM at the Scoping Stage

For the public consultation meetings, four meetings were planned on two different days, namely: one meeting in the morning and another in the afternoon per day, which were organized for one weekday and one-day weekend in order to ensure the participation of the stakeholders in the public sector as

well as the local residents who are not available during the weekdays. The venue was selected in terms of easy accessibility from villages in and around Thilawa SEZ and the meeting room capacity of the building. Local transportation, arrangement of a shuttle bus, was offered from the major residential areas in the project area to the meeting venue, and the actual provision was decided based on the requests/decision from each village tract office.

The project proponent prepared the invitation letter together with the notice of the meeting in Myanmar language and announced to the invitees, who are villagers in Thilawa SEZ and relevant governmental organizations, non-governmental organizations (NGOs), community-based organizations (CBOs), and anyone who are interested.

Basically, information on the meeting was announced to the invitees one week in advance before the meeting by sending invitation letters to the respective invitees.

Especially for the villagers, the information on the meeting was announced based on the administrative procedure and local practice. Firstly, the invitation letter was sent to the township offices in order to ask them to provide instructions to each village-tract office under their jurisdiction. And then it was sent from the township offices to each village-tract office one week in advance. The notice of the meeting was displayed together with the invitation letter on the public notice board of townships and village-tract level. Afterwards, the information on the meeting under the village level was requested to be disseminated by 100 household head leaders of the respective villages in accordance with local practice. The 100 household head leaders were informed about the meeting in a convenient way and timing such as verbal announcement or displaying the notice somewhere. Moreover, the dissemination of the information on the meeting below the village level was followed up and reminded over phone.

The invitation letter with the notice and list of invitees as attachments are enclosed in Annex 11-1.

The presentation and handouts were prepared and explained in Myanmar language. The opinions from the participants were received in the question and answer session. Additionally, feedback forms were provided to the participants so that those who are hesitant to speak out in public could share their views and comments. Special arrangement for the vulnerable group was given; assistant staff were available to fill out the form in case the participant needs help in writing/reading. Furthermore, female assistants were also available for the female participants who need any help. The presentation material and handouts both in Myanmar and English language, and a sample of the feedback form are shown in Annex 11-2.





Source: EIA Study Team



Notice Displayed in 100 Household Head Leader's House in Lat Yat San Village under Hpa Yar Kone Village Tract

Figure 11.2-1 Pictures of Notice Displayed (PCM at the Scoping Stage)

(2) Summarized Outcomes of PCMs at the Scoping Stage

Three PCMs were organized on 19 and 22 December 2015 at the Convention Hall of the Housing Department in Thanlyin Township. Originally, it was planned to be held in four meetings; however, the afternoon session on 19 December 2015 was canceled on that day in consultation with the participants and TSMC due to the small number of participants (i.e., three participants).

On 19 December 2015, 347 people attended the morning session, while on 22 December 2015, 35 people attended the morning session and 48 people attended the afternoon session. In total, approximately 30% of the participants are women. The list of attendees is shown in Annex 11-3.

In the consultation meeting, after the explanation on the project outline planned in Zone B, which includes the industrial area, residential and commercial areas, and the logistic area, the expected key environmental and social benefits as well as potential negative impacts were explained during the construction and in the operation stage. In addition, survey items of the baseline EIA study and future schedule for the EIA were presented to the participants. At the end, a question and answer session was organized in all the meetings. As a whole, eight questions were raised from the participants and discussed with the project proponent and coordinating organization. The summary of the meetings is provided in Table 11.2-2 and Table 11.2-3. The meeting records in Myanmar language are included in Annex 11-4.

Moreover, feedback forms were distributed to the participants in order to receive comments and opinions from them. A total of 18 comment forms were received. The major comments and opinions written in the collected feedback forms were summarized in each session.

Table 11.2-1 Summary of Public Consultation Meeting for EIA at the Scoping Stage

	(1) Saturday, 19 December 2015			
Time and	1st session: 9:30 AM to 10:45 AM			
Date	(2) Tuesday, 22 December 2015			
	2nd session: 9:30 AM to 10:45 AM, 3rd session: 3:00 PM to 4:15 PM			
Venue	Convention Hall, Department of Human Settlement and Housing Development, Thilawa SEZ Management Committee Office (Temporary), Thanlyin Township near Thilawa SEZ			
	- Director, Environmental Conservation Department in Yangon Division, MOECAF			
	- Deputy Commissioner, General Administration Department, Yangon Southern District			
	- Officers, General Administration Dept. in Thanlyin and Kyauktan townships			
	- Officers, Housing Department, Ministry of Construction, Thanlyin Township			
	- Township officers, Municipal Dept. and Rural Development Department, Department of			
Invitees	Health in Thanlyin Township and Kyauktan Township			
	- Officers, Myanmar Port Authority, Ministry of Transportation			
	- Relevant companies/factories in Thilawa SEZ			
	- Local residents in and around Thilawa SEZ area			
	- Project proponent/developer and related government organizations (e.g., TSMC, MJTD)			
	- Other organizations and individuals who are interested in the Project			
	1st session: 347 people (men: 234, women: 113)			
Attendee	2nd session: 35 people (men: 30, women: 5)			
	3rd session: 48 people (men: 34, women: 14)			
	- Brief explanation on the past EIA-related studies			
	- Project brief in the industrial area, residential and commercial areas, and the logistic area			
Agenda	planned in Zone B area			
	- Major positive and negative findings on the draft scoping results			
	- Scope of the EIA study			
	- Further schedule of EIA			
Language Used	In local language: Myanmar language			

- (3) Summary of Comments from PCMs at the Scoping Stage
 - 1) First Session (Morning, 19 December 2015)

Table 11.2-2 Main Questions and Responses at the First Session of PCM at the Scoping Stage

No.	Questions	Answers at PCM
1	Currently, the road surrounding Thilawa SEZ area is seriously being damaged. Do you consider the impact on the road condition in this EIA study? If it is considered in this EIA study, what kind of activities will be implemented for those roads in the development of Zone B area?	The road in front of the garment factory is already maintained by MOC according to a letter regarding the road condition which was submitted on 19 November. For the Thilawa Development Road, one Japanese company is now investigating the physical ground condition of the road and then they will design and maintain it. (TSMC) Further Response: In terms of the improvement of community infrastructure, the comment will be considered as one of CSR activities.
2	In the other previous meetings, if the villagers want to send their suggestion letters, comments, or complaints, they send it to TSMC only. However, in this meeting, two addresses (MJTD and TSMC) are mentioned. If the villagers want to send their letters, which office addresses should they used?	The villagers should send suggestion letters, comments, and complaint letters to both TSMC and MJTD. (TSMC) Further Response: Not required
3	In this presentation, it mentioned the impacts on air and soil due to the disposal of wastes by those workers who came from other places. If so, is there any place or accommodation where such kind of workers can stay in Thilawa SEZ area? If there is no place for these workers, how can they stay in Thilawa SEZ area?	Some workers came from other places to work in the SEZ area but their accommodation has not been arranged yet at present. They are staying in a monastery or a part of the village area. Currently, there are two six-storied buildings being constructed. When these two buildings are finished, these workers can stay in the said buildings. After that, the impact on the environment due to the disposal of wastes by these workers will decrease. (TSMC) Further Response: Not required
4	The offices where EIA will be disclosed are very far from the villages. I would like to request for the distribution of the summary of the scoping report in Myanmar language and in English.	Noted. After confirmation whether it is okay or not, the report will be shared, if possible. (Local consultant: REM) Further Response: Considered in EIA stage
5	Will the EIA study be carried out in Zone B area (700 ha) or entire Thilawa SEZ area?	As it is already explained in the presentation, the EIA study was conducted targeting the entire 2,000 ha, although the explanation is intended for 700 ha. (TSMC) <i>Further Response: Not required</i>
6	I would like to know about the power supply plan and water resources plan of the Thilawa SEZ area. If the Thilawa SEZ uses underground water, exploitation of underground water from SEZ can indirectly affect other villages' cultivation in the long term. The electricity is also not sufficient in our country that is why the monk would like to know the power supply source of the SEZ area.	For the source of power supply, the electricity will be provided to Thilawa SEZ area from Yangon through the substation in Thanlyin. Moreover, 50 MW of Gas Turbine Station will be also constructed to get sufficient power. For water resource, exploitation of underground water is not allowed in Thilawa SEZ area. It is currently provided by Zarma Ni Dam under the permission of providing 60,000 m³/day. After 2018, the Lagunbyin Dam will be the source of water of the Thilawa SEZ area. (TSMC) <i>Further Response: Not required</i>

Note: "Further Response" describes the necessity of additional response and the taken correspondence by the project proponent to the received comments or requests, opinion during PCM as of December 2015.





Presentation

Source: EIA Study Team

Participants

Figure 11.2-2 Pictures of PCM at Scoping Stage (First Session)

2) Second Session (Morning, 22 December 2015)

Table 11.2-3 Main Questions and Responses at the Second Session of PCM at the Scoping Stage

No.	Questions	Answers at PCM
1	In Shwe Pyauk Village, 45	Well noted. I will submit your request to the chairman of Thilawa SEZ
	households will have to relocate.	Management Committee. (TSMC)
	So, I would like to request for	Further Response: Not required
	relocation between the area of	
	Aye Mya Thida Village Tract and	
	Shwe Pyi Thar Yar Village Tract.	
2	How far is the safest distance	Impacts on the environment can either be positive or negative. If it is explained in
	from the project site that will have	simple words, we can say it is safe to "live far away from the project site".
	less health effects on local	(Local consultant: REM)
	villagers?	This Project has been planned according to the international guideline and JICA
		guideline, and the environmental mitigation measure will be implemented
		properly. Therefore, you do not need to worry about health problems due to the
		Project. (TSMC)
		Further Response: Not required

Source: EIA Study Team

Note: "Further Response" describes the necessity of additional response and the taken correspondence by the project proponent to the received comments or requests, opinion during PCM as of December 2015.







Question from the Participant

Figure 11.2-3 Pictures of PCM at the Scoping Stage (Second Session)

3) Third Session (Afternoon, 22 December 2015)

No questions were raised from the participants.





Participants

Source: EIA Study Team

Figure 11.2-4 Pictures of PCM at the Scoping Stage (Third Session)

(4) Summary of Comments from Feedback Forms

There are 18 comment forms received from the participants in total at the three PCM sessions. The major comments and opinions written in the collected feedback forms and their answers are summarized in Table 11.2-4 below.

Table 11.2-4 Major Comments from Feedback Forms and Responses

	Major Comment	Comment From	Answer to the Comments
1	In the implementation of the Project, the concerned authorities should provide more consideration on the social environment such as health care, road accessibility, and education program for local people's happiness.	Villager, Male	Impact on social environment including health care, road accessibility, and education by the Project will be assessed in the draft EIA report. In addition, mitigation measures toward the potential adverse impacts will be proposed in the draft EIA report. Further Response: Considered in draft EIA report (Chapter 7 & 9)
2	The impact on natural environment should be assessed to reduce social impact such as impacts on the economy and health because social impact can be expected secondarily from the impact on natural environment.	Villager, Female	Not only the impacts on natural environment but also impacts on social environmental including indirect impacts by the Project will be assessed in the draft EIA report. Further Response: Considered in draft EIA report (Chapter 7)
3	Careful assessment with adequate time is necessary to avoid great impacts on the environment, destruction and loss, and effects on weather because of a long-term project.	Villager, Female	Environmental impact assessment will be carefully conducted in the draft EIA report. Further Response: Considered in draft EIA report (Overall)
4	Person in authority needs to implement the Project by assigning competent staff in appropriate places with precise duties.	Villager, Male	Environmental and social consultants will conduct the environmental impact assessment in cooperation with the relevant organizations. Further Response: Not Required
5	What kind of environmental mitigation measures are planned to avoid possible problems, for example, air pollution, water pollution, or contamination problems of water and latrine, and health? If those problems occur, systematic management is necessary (e.g., fire accident, shortage of electricity).	Villager, Female	Mitigation measures will be proposed toward the potential adverse impacts in the draft EIA report. In addition, environmental management plan and environmental monitoring plan proposed in the draft EIA report will be conducted during project implementation. Further Response: Considered in draft EIA report (Chapter 9)

	Major Comment	Comment From	Answer to the Comments
6	Developer side needs to consider the voice and advice from local residents to avoid any negative impacts on the environment. Therefore, they need to monitor the whole process of the Project.	Villager, Female	Comments and opinions received this time will be reflected to the draft EIA report. Environmental management plan and environmental monitoring plan proposed in the draft EIA report will be conducted during project implementation. Further Response: Considered in EIA stage and in draft EIA report (Chapter 9)
7	Planting of green trees is needed to serve as protection around the factory and resident population.	Villager, Male	Project plan will be designed in the draft EIA report in consideration of the environmental and social impacts. Further Response: Considered in EIA stage
8	Cemetery within the project area needs to be relocated.	Villager, Male	Discussion with the concerned people will be conducted to discuss how to manage the cemetery within the project area. Further Response: Not required
9	Developer of the Project needs to clean up the dust and mud left on the road.	Villager, Male	Environmental management plan at the construction stage will be proposed in the draft EIA report. Further Response: Considered in draft EIA report (Chapter 9)
10	People should receive explanation about the situation of the Project concerning the natural environment transparently on a monthly or yearly basis from the developer.	Villager, Male	Environmental monitoring will be conducted based on the EMoP during the construction stage and operation stage. The project proponent is considering having a meeting with local people periodically during project implementation to disclose the monitoring results. Further Response: Considered in draft EIA report (Chapter 9)
11	Mutual understanding can be achieved by direct discussions and explanation between the project developer and local people.	Villager, Male	Another public consultation meeting and public disclosure are planned to be conducted again for the draft EIA report. Further Response: Considered in draft EIA report (Chapter 10)
12	My house was displaced in the project area and now I have difficulty on my residency. Therefore, I would like to give an advice to implement this Project as early as possible.	Villager, Male	The project will be implemented through an appropriate process in reference to the JICA Guidelines and legal procedure in Myanmar, at the same time listening to the opinions of relevant people. According to TSMC, Resettlement Work Plan shall be formulated by TSMC. It is based on the opinions of relevant people. Further Response: Not required
13	It is good the development of Thilawa SEZ will create a lot of job opportunities among our township/community/area.	Villager, Male	 Further Response: Not required
14	Special thanks to the development of Thilawa SEZ. However, it is best to do this without causing any harmful effects on health, social affairs, and economic status among the communities.	Villager, Male	Mitigation measures will be proposed in the draft EIA report in order to minimize the potential adverse impacts of the Project. Further Response: Considered in EIA stage

Note: "Further Response" describes the necessity of additional response and the taken correspondence by the project proponent to the received comments or requests, opinion from feedback form as of December 2015. Chapter number refers to the draft EIA report.

Source: EIA Study Team

11.2.2 Public Disclosure at the Scoping Stage

(1) Implementation of Public Disclosure at the Scoping Stage

As part of public consultation, the public disclosure of the draft scoping report is organized for review and comments of the public after holding the public consultation meeting. The set of draft scoping reports, which consists of three documents, the main part is in English and the summary is both in English and in Myanmar language, is prepared and distributed to the designated places for disclosure. Comment form is provided to each place as well. The public disclosure period sets ten working days, which excludes national holidays, Saturday, and Sunday. The details, such as exact disclosure period

and comment submission method, are announced in the public consultation meetings and described in the disclosure places.

(2) Summarized Outcomes of Public Disclosure at the Scoping Stage

Originally, the public disclosure of the draft scoping report was scheduled from 23 December 2015 to 7 January 2016 in 12 disclosure places as shown in Table 11.2-5 below as it was explained in the meetings. However, the event was re-arranged from 31 December 2015 to 14 January 2016 for ten working days in order to secure enough time for reviewing the scoping report on the project proponent's side. This rearrangement of disclosure period was informed to the public by sending the announcement letter to each disclosure place. The announcement letter is enclosed in Annex 11-5.


In addition to the information mentioned on the table below, the participants were requested during the meeting to ask their neighbors to submit their views or comments regardless of whether they attended the meeting or not. Moreover, it was also notified that each disclosure place will provide assistance to fill up the comment box for those who have difficulties in writing or reading.

Table 11.2-5 Summary of Public Disclosure for EIA at the Scoping Stage

Disclosure Period	[Original] Wednesday, 23 December 2015 to Thursday, 7 January 2016		
(Ten Working Days)	[Re-arranged] Thursday, 31 December 2015 to Thursday, 14 January 2016		
	A total of 12 places		
	1) Yangon Southern District General Administration Office		
	2) Thanlyin Township General Administration Office		
	3) Kyauktan Township General Administration Office		
	4) Thilawa SEZ Management Committee Office (Temporary) near Thilawa SEZ; and		
	5) Myanmar Japan Thilawa Development Limited Office in Thilawa SEZ		
D' 1 DI	6) Seven (7) Village Tracts/Ward Office in Thanlyin and Kyauktan Township;		
Disclosure Place	- Hpa Yar Kone Village Tract Office		
	- Let Yet San Village Tract Office		
	- Ah Lun Soke Village Tract Office		
	- Aye Mya Thi Dar Ward Office		
	- Shwe Pyi Thar Yar Ward Office		
	- Thi Tar Myaing Ward Office		
	- Shwe Pyauk Village Tract Office		
Comment	Comments can be submitted with the comment form provided at the disclosure places or by		
Submission Method	e-mail either in Myanmar or English language.		
Language Used	In local language: Myanmar and English language		



Announcement Letter Displayed at Ah Lun Soke Village Tract Office



Announcement Letter Displayed at Thilawa SEZ Management Committee Office (Temporary)



Draft Scoping Report Distributed at Let Yet San Village Tract Office Source: EIA Study Team



Draft Scoping Report Distributed at Shwe Pyauk Village Tract Office

Figure 11.2-5 Pictures of the Announcement Letter and the Draft Scoping Report Distributed at the Village Tract Office

(3) Summary of Comments from Public Disclosure at the Scoping Stage

Two comments were received from the public. The comments and responses are summarized in Table 11.2-6.

Table 11.2-6 Brief Summary of Public Comments and Responses

No.	Comment	Comment from	Answer to the Comments
I-1	We would like to request the following: i) Do not affect the environment for public health. ii) Do not affect nearby villagers due to bad odor caused by the Project (air pollution).	_	i) With respect to impact on environment for public health as living environment such as air, water, noise, and odor, these impacts will be controlled and managed not to affect the surrounding area and people by implementing various mitigation measures. ii) With respect to air pollution and odor, the following measures will be taken: a) installation of emission gas control system (by a tenant associated with furnace facility); b) appropriate maintenance such as frequent removal of waste; and c) keep enough distance from odor source. The above impacts will be evaluated in the draft EIA report by the project proponent and will also be evaluated by an EIA, IEE, or ECPP (Environmental Conservation and Prevention Plan) by tenants to be
			submitted to TSMC.

No.	Comment	Comment from	Answer to the Comments
			Further Response: Considered in draft EIA report(Overall, Chapter 9)
I-2	We would like to thank for establishment of industries from foreign countries because we could get jobs from these industries.	Villager (Ah Lun Soke Village)	 Further Response: Not required
II-1	This draft scoping report was prepared for only 262 ha development and not for 700 ha of overall Zone B development. Therefore, all draft reports for 700 ha of Zone B should be disclosed at the same time.	Thilawa Local People	Since the project proponents of the industrial area and logistic, residence, and commercial area in Zone B are different, the scoping reports have been prepared by each project proponent, separately. The scoping report for logistic, residence, and commercial area has been disclosed from 18 to 29 January 2016. Further Response: Considered at EIA stage
II-2	According to Table 2.1: Infrastructure Development Plan of Industrial Area under Article 2. Project description in draft scoping report, regarding the treatment plan, it was described that wastewater from industries will be treated at the central wastewater treatment plant and each industry should install wastewater treatment system with reference to the standard and policy of Zone A. Information on inspection for permission and checking compliance status shall be included in the report. A punishment plan should be also included in the report in case that wastewater treatment system of an industry does not meet the standard.	Thilawa Local People	The project proponent has internal regulations called "Thilawa Special Economic Zone (Zone-A) Industrial Zone Internal Regulations" including wastewater treatment by tenants. In the internal regulations, tenants have to comply with the standard value for wastewater before discharging to the central wastewater treatment plant. The internal regulations will be also applied to the industrial area of Zone B. With respect to ensuring proper wastewater treatment by tenants, the project proponent will check the designs of wastewater treatment system before construction, inspect constructed wastewater treatment facilities before commencement of commercial operation, and check results of wastewater monitoring for treated wastewater and guide improvement (if issues arise) during operation stage in collaboration with Thilawa SEZ Management Committee (TSMC). Further Response: Considered in draft EIA report (Chapter 3)
II-3	The following sentence, "The Project would be closed by external factors", which was indicated in Article 3, is difficult to understand the meaning. In the closing phase, environmental and social issues may arise because of the Project. The contents of 'Closing' should be explained in more detail.	Thilawa Local People	The impacts at the closing stage will be considered in the draft EIA report in consideration of the case that the tenant in the industrial area will terminate the operation of business or in case that the industrial area will be closed after compression of the period for lease agreement. Further Response: Considered in draft EIA report(Chapter 7&8)
II-4	Under Article 3: Environmental and social issues that were evaluated that will be affected in a draft scoping report, it was described that "Based on existing situation of environmental and social condition collected by the existing materials and field observation, the contents and volume of environmental and social impacts caused by the Project will be forecasted and evaluated in the EIA process". It means that field survey was not conducted for the time being. Therefore, this draft report shall be prepared after conducting the field survey.	Thilawa Local People	The field survey has been implemented and the result will be presented in the draft EIA report. In the draft EIA report, environmental and social impacts caused by the Project will be forecasted and evaluated in consideration of the results of the field survey and collected information. Further Response: Considered in draft EIA report (Chapter 6 & 7)
II-5	Precaution plan to avoid spread of infectious diseases due to OS/CS worker in the development area should be included in the EIA report.	Thilawa Local People	In the draft scoping report, risks for infectious diseases such as AID/HIV have been evaluated in consideration of impact by influx of workers. The impact will be evaluated and the mitigation plan is proposed in the draft EIA report. Further Response: Considered in draft EIA report (Chapter 7&10)
II-6	Concerning waste, it was described that waste will be generated by construction work during construction phase, hazardous and non-hazardous waste from tenant during	Thilawa Local People	In the draft EIA report, impact of the wastes will be forecasted and evaluated with reference to the experience of Thilawa SEZ Zone A area. Based on the result of draft EIA report to be prepared, the project

No.	Comment	Comment from	Answer to the Comments
	operation stage in the industrial zone, and waste from demolition by workers during the closing phase. Thus, regarding such waste, detailed information about prevention methods, management methods, and punishment (penalty) methods should be prepared in the EIA report.		proponent will manage and monitor solid waste in accordance with EMP and EMoP. The tenants will manage solid waste in accordance with the internal regulations of Zone A Industrial area and their ECPP to be submitted to TSMC. Further Response: Considered in draft EIA report (Chapter 7 & 9)
II-7	It was shown that while workable workers in the vulnerable group will be slightly affected, the farmers will be totally affected. Therefore, this fact shall be mentioned in detail accurately.	Thilawa Local People	Project affected persons (PAPs) including farmers will be considered carefully. Further Response: Considered in draft EIA report (Chapter 7)
II-8	Regarding cultural heritage, the impression that Hindu Temple and cemeteries in the development area will be affected by the Project is clear. Moreover, evaluation of the impact in both English and Myanmar reports is not suitable and the impact shall be evaluated as grade (A) in both languages. Therefore, this fact should be included completely.	Thilawa Local People	Based on your suggestion, social impact on cultural heritage will be considered carefully in the draft EIA report. The evaluation of the impact will be based on the field survey for confirmation of the number and scale of affected cultural heritage. Further Response: Considered in draft EIA report (Chapter 7)
II-9	Involuntary resettlement under social environment, the statement "there is no residential area in the construction stage. Therefore, resettlement will not be required is inappropriate. It is advised that impact condition shall be prepared in detail completely. Currently, there are residences in the development area of Zone (B).	Thilawa Local People	Impact of involuntary resettlement will be considered and evaluated before the construction stage (BC) and operation stage (OS). Further Response: Considered in draft EIA report (Chapter 7) *In the scoping report, it was evaluated that "since there is no residential area, involuntary resettlement is not expected" at the closing stage (CS). There must be some confusion among the local people between "OS" and "CS". The EIA Study Team will clarify this issue in the draft EIA report.

Note: "Further Response" describes the necessity of additional response and the taken correspondence by the project proponent to the received comments or requests, opinion during PD as of December 2015. Chapter number refers to the draft EIA report.

Source: EIA Study Team

11.2.3 Conclusion for the EIA at the Scoping Stage

As described above, 430 participants in total joined the three-day PCMs at the scoping stage. Among them, 132 were women. There were local leaders and local NGO members, too. During the PCM session, people seemed to be interested in the Project and some were taking photographs of the explanation slides.


Regarding public comments, totally 18 comments in the three PCM sessions and two comments during the public disclosure were submitted. Among them, there were several comments concerning health and social infrastructure that might be impacted by the Project. On the other hand, there was a comment about the positive impact of new employment opportunity. These received comments were reflected in the draft EIA report, EMP, and EMoP.

11.3 Draft EIA Stage

11.3.1 Public Consultation Meeting at the Draft EIA Stage

(1) Implementation of PCM at the Draft EIA Stage

PCM at the draft EIA stage was applied same arrangement for the implementation as the scoping stage. The invitation letter with the notice and list of invitees as attachments at the draft EIA stage are enclosed in Annex 11-6.





Notice Displayed in 100 Household Head Leader's House in Alunsut Village Tract

Notice Displayed in Shwe Pyi Thar Yar Village Tract Office

Source: EIA Study Team

Figure 11.3-1 Pictures of Notice Displayed (PCM at the Draft EIA Stage)

(2) Summarized Outcomes of PCMs at the Draft EIA Stage

Three PCMs were organized on 2 and 7 April 2016 at the Convention Hall of the Housing Department in Thanlyin Township. Originally, it was planned to be held in four meetings; however, the afternoon session on 2 April 2016 was canceled on that day in consultation with the participants and TSMC due to the small number of participants (i.e., two participants).

On 2 April 2016, 110 people attended the morning session, while on 7 April 2016, 65 people attended the morning session and 2 people attended the afternoon session. In total, approximately 40% of the participants are women. Presentation materials and handout used in the PCMs are attached in Annex 11.7, and the list of attendees is attached in Annex 11-8.

In the consultation meeting, after the explanation on 1) the project outline planned in Zone B which includes the industrial area, residential and commercial areas, and the logistic area, 2) the results of baseline survey and 3) the results of impact assessment, 3) proposed mitigation measure and monitoring plan, were explained. Furthermore, results of public consultation and public disclosure, and the response to the public comments and comment from TSMC were briefly presented to the participants. At the end, a question and answer session was organized in all the meetings. As a whole, questions were raised from five persons and discussed with the project proponent and coordinating organization. The summary of the meetings is provided in Table 11.3-1 Table 11.2-3. The meeting records in Myanmar language are included in Annex 11-9.

Moreover, feedback forms were distributed to the participants in order to collect comments and opinions from them. A total of 7 comment forms were received. The major comments and opinions written in the collected feedback forms and the responses were summarized in each session.

Table 11.3-1 Summary of Public Consultation Meeting for EIA at the Draft EIA Stage

Time and Date	(1) Saturday, 2 April 2016 1st session: 10:00 AM to 11:30 AM			
Time and Date	(2) Thursday, 7 April 2016			
	2nd session: 10:00 AM to 11:30 AM, 3rd session: 1:30 PM to 3:00 PM			
Venue	Convention Hall, Department of Human Settlement and Housing Development, Thilawa SEZ			
Venue	Management Committee Office (Temporary), Thanlyin Township near Thilawa SEZ			
	- Director, Environmental Conservation Department in Yangon Division, MOECAF			
	- Deputy Commissioner, General Administration Department, Yangon Southern District			
	- Officers, General Administration Dept. in Thanlyin and Kyauktan townships			
	- Officers, Housing Department, Ministry of Construction, Thanlyin Township			
	- Township officers, Municipal Dept. and Rural Development Department, Department			
	of Health in Thanlyin Township and Kyauktan Township			
Invitees	- Officers, Myanmar Port Authority, Ministry of Transportation			
	- Relevant companies/factories in Thilawa SEZ			
	- Local residents in and around Thilawa SEZ area			
	- Project proponent/developer and related government organizations (e.g., TSMC,			
	MJTD)			
	- Other organizations and individuals who are interested in the Project			
	1st session: 110 people (men: 68, women: 42)			
Attendee	2nd session: 65 people (men: 39, women: 26)			
	3rd session: 2 people (men: 2, women: 0)			
	- Outline of the Thilawa SEZ Project (Zone B)			
	- Results of Baseline survey			
Agenda	- Results of Impact assessment results			
	- Proposed mitigation measures, environmental management and monitoring plans			
	- Institutional Arrangements			
	- Public consultation and public disclosure			
	- Conclusion and Further EIA schedule			
Language Used	In local language: Myanmar language			

(3) Summary of Comments from PCMs at the draft EIA Stage

1) First Session (Morning, 2 April 2016)

Table 11.3-2 Main Questions and Responses at the First Session of PCM at the Draft EI A Stage

No.	Questions	Answers at PCM
1	According to your report, it is forecasted that the water volume demanded for Zone B is about 17,000m³/day. Around 2019, Lagunbyin Reservoir will supply 42,000m³/day of the water to Thilawa SEZ. So could you provide the extra volume of water to religious places	We will check again the water demand of Thilawa SEZ and the usage from Lagunbyin Reservoir. (TSMC) Further Response: In terms of the improvement of community infrastructure, the comment will be considered as one of CSR activities.
2	and local people around the project area? Regarding solid wastes in the report, it is estimated to be buried 4,100 ton/year and proposed to apply land-filled system for industrial solid wastes. However, the capacity of the landfill in Thilawa SEZ may not be enough to use for long term. I would like to request to describe the long term plan to understand the local people clearly. For domestic wastes, it is just generally described to be disposed by the arrangement with Thanlyin Development Committee. Please explain your plan in more detail.	In Environmental Conservation Prevention Plan (ECPP), it is required to describe to the source of wastes and the treatment method of industrial solid wastes and domestic wastes. For industrial solid waste, we are not only depends on dumping site, some of the solid waste can be reuse and some are disposed. (OSSC) Further Response: Considered in EIA report (Chapter 3 & 7)
3	I would like to request the detail description on the impact and mitigation measures of HIV/AIDS and chemical usage, environmental management plan, closing system and the employment contract, the organization structure, responsibility, members of monitoring system in pre-construction and operation phase.	In ECPP, it is also mentioned that each tenant should provide medical checkup for worker twice per year and should prepare chemical usage plan and occupational safety plan for worker. Since his is the very first project being implemented under EIA law in Myanmar, so we are welcome to your comments and suggestion. (ECD) Further Response: Considered in EIA report(Chapter 10)

No.	Questions	Answers at PCM
4	Currently air quality causes no problem for the life of	As for air quality and water quality, the measurement is
	local people, however, how will the impact be increased	difficult to understand for local people since it is
	due to the project? It is difficult to understand the	described with technical terms. As a result, all
	measurement for local people. Please explain about it by	parameters are under the target value and satisfied the
	using simple words for better understanding.	environmental standards. (OSSC)
	For water quality, we are satisfied for the water	Further Response: No required
	treatment system to be installed. However, I would like	
	to know whether the water treatment system will be	
	actually introduced according to your proposed plan or	
	not.	
5	How will the job opportunity be created for the affected	We will consider your advice on job opportunity of the
	36 vulnerable households? The report describes for	affected vulnerable group, the relocation and restoration
	vulnerable group in closing phase as "D". Actually these	of income source for PAHs especially who have
	people should be monitored continuously even in closing	land-based income source. In addition, we will consider
	stage. In addition, it is described approximately 40% of	providing the training program for the PAHs
	PAHs have land-based income source in chapter 7. For	appropriately. (TSMC)
	these households, how do you plan to provide Income	Further Response: Considered in EIA report (Chapter
	Restoration Program in order to restore their income	7&10)
	source?	
6	Too much water is sprayed along the road in order to	Well noted. Thanks for your suggestion. (TSMC, OSSC)
	prevent the dust problem, and the road condition is bad.	Further Response: No required
	It may be caused some accident.	
Source	e: FIA Study Team	

Note: "Further Response" describes the necessity of additional response and the taken correspondence by the project proponent to the received comments or requests, opinion during PCM as of April 2016.





Presentation

Source: EIA Study Team

Participants

Figure 11.3-2 Pictures of PCM at Draft EIA Stage (First Session)

2) Second Session (Morning, 7 April 2016)

Table 11.3-3 Main Questions and Responses at the Second Session of PCM at the Draft EIA Stage

No.	Questions	Answers at PCM
1	Now we are attending this meeting so we can	This is the second day of the 2nd public consultation meeting,
	know about your presentation and the project	and the 1st meeting was held in December 2015and this time is
	description. However, a lot of people are left	2ndApril 2016. One time was organized by four secessions
	in the village. Of course we can share our	inviting government department, local people around the project
	knowledge from the meeting to them	area, project affected persons and others interest person. We
	remaining in village but we cannot share it	announced about the meeting by sending invitation letter to
	perfectly without missing. Therefore you	village leader and also asked them whether they need the ferry
	should invite house by house and disclose	bus for villagers or not for the transportation. In addition to that,
	more and more for the public consultation and	we have disclosed our two scoping report to public and requested
	disclosure.	to your suggestions and comments (In December and January).
		We will add your comments and suggestion in draft EIA report.

No.	Questions	Answers at PCM
		Our draft EIA report with feedback form was delivered at 16 places of Thanlyin and Kyauktan Township and disclosed from 24th March to 23rd April 2016. You can read and give suggestion and feedback to us. We are welcome to the suggestion and your corporation. (REM) Further Response: No required
2	There is electricity inside of the Thilawa SEZ, but no electricity along the Dagon-Thilawa road. Therefore some accidents can be occurred at night.	We are in charge of managing the infrastructure only Thilawa SEZ and are not responsible for the management of Dagon-Thilawa road. It is under responsibility of Yangon Electric Corporation. We will inform about your comment to the related department. (OSSC) Further Response: The comment is submitted to the related department. In terms of the improvement of community infrastructure, the comment will be considered as one of CSR activities.
3	Do you have any housing plan for worker?	Now we are being constructed six stories building for workers over 1000 of workers can stay there. (OSSC) Further Response: No required

Source: EIA Study Team

Note: "Further Response" describes the necessity of additional response and the taken correspondence by the project proponent to the received comments or requests, opinion during PCM as of April 2016.





Source: EIA Study Team

Figure 11.3-3 Pictures of PCM at Draft EIA Stage (Second Session)

3) Third Session (Afternoon, 7 April 2016)

No questions were raised from the participants.







Participants

Figure 11.3-4 Pictures of PCM at Draft EIA Stage (Third Session)

(4) Summary of Comments from Feedback Forms

There are seven comment forms received from the participants in total at the three PCM sessions. The major comments and opinions written in the collected feedback forms and their answers are summarized in Table 11.3-4 below.

Table 11.3-4 Major Comments from Feedback Forms and Responses

	Major Comment	Comment From	Response
1	I would like to request to implement planting program in and around Thilawa area. If this program will be implemented, it should be maintained and monitored well.	Villager, Male	For the inside of SEZ, it is planned to create green space in the project area for not only flora and fauna, landscape but also employee's and comfort. In addition, each tenant will prepare the green space inside the plot. These green spaces will be maintained well by the project proponent and each tenant. For the outside of SEZ, the planting program will be considered as the one of community support programs. Further Response: According to the comment, the project proponent will consider to plan planting program.
2	Environmental Impact Assessment Team should describe disadvantages of environment to the community definitely.	Villager, Male	The negative impact to the surrounding community identified in the project is described in the draft EIA report. Moreover, the impact is assessed and considered the mitigation measure in order to avoid serious damage. Further Response: No required
3	I would like to request to consider the issues regarding health, social and other of local people in the surrounding area of Thilawa SEZ.	Villager, Male	The project proponent will prepare for the support to local people regarding health issues. Further Response: According to the comment, the project proponent will consider to plan health care program.
4	I would like to request to implement the project by the project proponent effectively.	Villager, Male	Well noted. We are appreciated your comment. Further Response: No required
5	Agree. Good.	Villager, Male	Well noted. We are appreciated your comment. Further Response: No required
6	If Thilawa SEZ will be developed completely, the local people can get the job opportunities.	Villager, Male	Well noted. We are appreciated your comment. Further Response: No required
7	If the drainage system of the land is not proper, it can be caused some risk especially in rainy season.	Villager, Male	The project proponent is planning to implement the improvement of drainage system in and around project area. Further Response: According to the comment, the project proponent will consider the improvement of drainage system.
8	I agree to implement Thilawa SEZ project because the local people can get the job opportunities.	Villager, Male	Well noted. We are appreciated your comment. Further Response: No required
9	I would like to request to implement environmental impact assessment according to the international standards.	Villager, Male	This EIA study is implemented in accordance with the international guideline, conventions, and treaties. Further Response: No required
10	I would like to request to provide educational program to local people and to place the priority to employ the local people.	Villager, Male	Educational program such as English school has been already implemented by the project proponent. Moreover, another program will be considered for the community as a part of CSR activities. The job vacancy will be announced in villages of surrounding Thilawa SEZ. Further Response: According to the comment, the project proponent will consider to plan educational program.

	Major Comment	Comment From	Response
11	There were no lights along Dagon-Thilawa Road. So, this situation can be caused accident sometimes.	Villager, Male	The project proponent or TSMC has the responsibility on the infrastructure only inside of Thilawa SEZ, this matter is under the responsibility of Ministry of Construction (MOC). Request will be forwarded to MOC. Further Response: The comment is forwarded to MOC.
12	I would like to know whether there is any plans to protect workers from the heat or not, because the weather is too hot for the workers at present year.	Villager, Male	Basically in case of construction stage, the construction plan which includes occupational health such as the protection from the hot prepared by construction contractor. In addition, the project proponent will make announcement on paying attention to measures against intense heat to each contractor in meetings. Further Response: The project proponent will give announcement to construction contractor for the prevention of heat stroke.

Note: "Further Response" describes the necessity of additional response and the taken correspondence by the project proponent to the received comments or requests, opinion from feedback form as of April 2016.

11.3.2 Public Disclosure at the Draft EIA Stage

(1) Implementation of Public Disclosure at the Draft EIA Stage

For the implementation of PD at the draft EIA stage, the additional arrangement was made to implement at the draft EIA stage taking into account the opinion received at the scoping stage as follows:

- 1) Preparation and disclosure of the main part in Myanmar language in addition to the documents which are officially required (the main part in English, the summary in English and Myanmar language) in accordance with EIA procedure
- 2) Arrangement of PD before the day of holding PCM
- 3) Arrangement for changing PD period to 1 month from 2 weeks
- 4) Distribution of the reports to more places (added 4 disclosure places newly)

The details, such as exact disclosure period and comment submission method, are announced and posted in the respective disclosure places. The announcement letter at the draft EIA stage is enclosed in Annex 11-10.

(2) Summarized Outcomes of Public Disclosure at the draft EIA Stage

The public disclosure of the draft EIA report was arranged from 24 March 2016 to 23 April 2016. It was disclosed at 16 places as shown in Table 11.3-5.

Table 11.3-5 Summary of Public Disclosure for Draft EIA Stage

Disclosure Period	Thursday, 24 March 2016 to Saturday, 23 April 2016	
	A total of 16 places	
	Yangon Southern District General Administration Office	
	2) Thanlyin Township General Administration Office	
	3) Kyauktan Township General Administration Office	
	4) Thilawa SEZ Management Committee Office (Temporary) near Thilawa SEZ; and	
Disclosure Place	5) Myanmar Japan Thilawa Development Limited Office in Thilawa SEZ	
	6) Seven (7) Village Tracts/Ward Office in Thanlyin and Kyauktan Township;	
	- Hpa Yar Kone Village Tract Office	
	- Let Yet San Village Tract Office	
	- Ah Lun Soke Village Tract Office	
	- Aye Mya Thi Dar Ward Office	

	- Shwe Pyi Thar Yar Ward Office	
	- Thi Tar Myaing Ward Office	
	- Shwe Pyauk Village Tract Office	
	7) 100 household head's and other villager's house (4 places)	
Comment	Comments can be submitted with the comment form provided at the disclosure places or by	
Submission Method	e-mail either in Myanmar or English language.	
Language Used	In local language: Myanmar and English language	

(3) Summary of Comments from Public Disclosure at the Draft EIA Stage

One letter was received from the public. The comments and responses are summarized in Table 11.3-6. Further Response by the project proponent to the received comments above is described in Section 11.3.3.

Table 11.3-6 Brief Summary of Public Comments and Responses

	Major Comment	Answer to the Comments
1	As the EIA study team, we would like to request to	EIA procedure is described in page 2-2 of Chapter 2, and
	explain EIA procedure to local people to understand	the whole process of EIA is described with flow chart in
	easily and more clearly.	page 2-13 to 2-15 of Chapter 2 in the draft EIA report.
2	To explain the whole process of EIA for the local	Also, these were explained in PCM in Myanmar
	people more clearly.	language.
3	To send the related EIA documents before public	Even after public disclosure period was ended, comments
	consultation meeting because it was not enough	or suggestions are still able to submit and it is
	time for reviewing these documents this time.	appreciated.
4	In the draft EIA report, some technical terms are	Since the impacts are described with technical terms in
	difficult to understand for us. Therefore, it should	the draft EIA report, the contents were explained verbally
	be described with simple words for better	in Myanmar language during public consultation meeting
	understanding.	to villagers, and the full version of scoping report was
		prepared in Myanmar. If you have any further questions,
		please kindly ask to the project proponent or TSMC.
5	The above subjects 1 to 4 concerned with EIA	The disclosure period of the draft EIA report was ended,
	should be considered well so that we can give some	however; you can submit your comments and suggestions
	advices and comments effectively. In current	continuously to TSMC and the project proponent even
	situation, it is difficult to advice on the draft EIA	after the end of the public disclosure period. We are all
	report. Therefore I would like to request to extend	welcome to your advices.
	the disclosure period. Moreover, if you extend, the	_
	duration of disclosure should be arranged in timely	
	manner.	

Source: EIA Study Team.

11.3.3 Follow-up Meeting

In response to the public comment described in Table 11.3-6, the follow up meetings were organized two times in 10 and 18 May 2016 in order to have the opportunity to discuss and solve question and problem with villagers. The outline of the follow up meetings is summarized in Table 11.3-7.

Table 11.3-7 Summary of Follow-up Meetings

Item	1st Follow-up meeting	2 nd follow-up meeting
Time & Date Tuesday, 10 May 2016, 10:30 -12:30		Wednesday, 18 May 2016, 15:00 -17:00
Venue	Meeting room of MJTD	Meeting room of TSMC
No. of Attendee	Total 5 people	Total 19 people
	- Thilawa Social Development Group	- Thilawa Social Development Group
Main	- Community Relation Department, MJTD	- Environmental Section of OSSC, TSMC
Participant	- EIA Study Team	- Community Relation Department, MJTD
		- EIA Study Team
	- Expected impact of air pollution, waste water,	- Process of EIA, IEE, EMP described in EIA
Main	chemical usage, solid waste, involuntary	Procedure
Discussion	resettlement, and vulnerable group by the	- Activities on Environmental Protection in OSSC
	Project	- Methodology and result of Field Survey

Item	1st Follow-up meeting	2 nd follow-up meeting
	- Expected impact of each tenant depending on	- Arrangement of PCM and PD
	the type of business	- Treatment system of wastewater
	- Activities of environmental management in Zone A	- Issue on involuntary resettlement
	Zone A	- Example case of other industrial areas

Through the follow up meeting, a lot of questions were raised and it was answered by the project proponent and OSSC, EIA Study Team. Unclear points from villagers were mostly disappeared and better understanding among stakeholders was established. As a result the following three comments were proposed from villagers to the project proponent and TSMC for taking into consideration as much as possible and to describe in EIA report and the EIA process.





Participants (1)

Source: EIA Study Team

Participants (2)

Figure 11.3-5 Pictures of 2nd Follow-up Meeting

Table 11.3-8 Summary of Comment and Correspondence in Follow-up Meeting

No.	Comment	Correspondence
1	To consider public involvement on the environmental monitoring during construction phase and operation phase.	The plan for public involvement is described in Chapter 11 as Stakeholder Engagement Plan in Section 11.1.3.
2	To add more description and explanation in Chapter 7 for Environmental and Social Impact Assessment especially for Involuntary Resettlement.	Additional description is added regarding involuntary resettlement in Section 7.13.
3	To disclose the information of each tenant regarding EIA/ IEE requirement, the contents of EIA, the situation and condition on the approval of EIA to the public.	TSMC will consider the availability of the information disclosure regarding IEE/EIA for each tenant.

Source: EIA Study Team

Considering the comments above, the draft EIA report was revised and finalized as final EIA report.

11.3.4 Conclusion for the EIA at the Draft EIA Stage


As described above, 177 participants in total joined the three-day PCMs at the draft EIA stage. Among them, 68 were women. There were local leaders and local NGO members as well. During the PCM session, people seemed to be concentrated the explanation slides and some were discussed the contents of the slides of the draft EIA each other. As a result, five comments in the three PCMs and one comment during the public disclosure were submitted. These received comments were reflected in the EIA report, EMP, and EMoP.

11.4 Public Consultation Meeting and Public Disclosue for the RWP

A series of public consultation meetings and public disclosure for Resettlement Work Plan (RWP) is planned to be implemented by the respective RWP area based on the framework. In the framework, the 2,000 ha development area is broadly divided into Area 1 to Area 6 and moreover, some RWP areas are divided into small parts as shown in Figure 11.4-1 in terms of the smooth implementation of resettlement works and the timing of actual development.

The industrial area is composed of four RWP areas which are Area 2-1, a part of Area 2-2, and Area 4-1. The resettlement works for Area 2-1 has been already started to be implemented as the first step since Area 2-1 is currently determined as the initial development area. Afterwards, it will be followed by Area 2-2, and Area 4-1 according to the actual development schedule. The provisional schedule is Table 11.4-1.

Based on the schedule, a series of public consultation meetings and public disclosure for RWP is planned to be implemented by each RWP area which formulated in the Framework of Resettlement Works for the 2,000 ha Development Area of Thilawa Special Economic Zone (SEZ).



Source: Thilawa SEZ Management Committee, Framework of Resettlement Works for the 2,000 ha Development Area of Thilawa Special Economic Zone (SEZ) February 2016

Figure 11.4-1 Provisionally Divided Area for Resettlement Works of the 2,000 ha Development Area

Table 11.4-1 Provisional Commencing Time of Resettlement Works for the Industrial Area

RWPArea	Provisional Commencing Time
Area 2-1, Area 2-2	Beginning of 2016
Area 4-1	Beginning of 2017

Source: Thilawa SEZ Management Committee, Framework of Resettlement Works for the 2,000 ha Development Area of Thilawa Special Economic Zone (SEZ) February 2016

11.4.1 Public Consultation Meeting for the RWP

(1) Area 2-1

The two public consultation meetings for the draft RWP for Area 2-1 was held on 14 February 2016 and 27 March at Ordination Hall, Aye Myar Thida Ward (Phalan), Kyauktan Township. The summary of the consultation meeting is presented in Table 11.4-2 and Table 11.4-3. During the consultation meeting, feedback forms were distributed to the participants to receive comments and opinions from them. The major comments and opinions written in the collected feedback forms will be summarized in the draft final RWP.

Table 11.4-2 Summary of 1st Consultation Meeting for Area 2-1

Items	Contents				
1. Date and time	14:00 – 16:30, Sunday, 14 February 2016				
2. Venue	Ordination Hall, Aye Myar Thida Ward (Phalan), Kyauktan Township				
3. Invitee	PAHs for Area 2-1				
	33 33 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3				
4. Participant	Approximately 95 persons				
5.Main	1. Administrator, General administration Department, Thanlyin Township				
invitees/participants	2. Administrator, General administration Department, Kyauktan Township				
from	3. Village Administrator, Shwe Pyi Thar Yar Village Tract				
government/others	4. Village Administrator, Aye Mya Thida Ward				
	5. 100/10 household head leaders, Shwe Pyi Thar Yar Village Tract				
	6. 100/10 household head leaders, Aye Mya Thida Ward				
	7. Villagers from Shwe Pyi Thar Yar Village Tract				
	8. Villagers from Aye Mya Thida Ward				
	9. Other organizations and individuals who are interested in the Project				
6. Agenda	Background and RWP activities				
	2. Area of 100 ha Initial Development Area (Area 2-1)				
	3. Eligible households for Area 2-1,				
	4. Proposed compensation and assistance package				
	5. Planned implementation organization				
	6. Planned grievance redress mechanism				
	7. Possible relocation sites				
	8. Further steps				
	9. Q & A session				
7. Major opinions and	or opinions and 1) Inquiry regarding the place of cemetery in Area 2-1 will be affected and cows/ buffaloes of				
comments from the	pasture land will be affected.				
participants	2) Clarification the compensation issues before the project begins.				
_ ^	3) Inquiry regarding the La Na (39) was issued need to pay the tax.				
4) Inquiry regarding their comments sent to TSMC three months ago.					
8. Feedback Form	No comments and opinions were submitted in the collected feedback form.				

Source: Thilawa SEZ Management Committee, Resettlement Work Plan (RWP) for Development of Area 2-1 (100ha) of Thilawa Special Economic Zone (Draft) February, 2016





Presentation Participants

Source: Thilawa SEZ Management Committee, Resettlement Work Plan (RWP) for Development of Area 2-1 (100ha) of Thilawa Special Economic Zone (Draft) February, 2016

Figure 11.4-2 PCM on 14 February 2016

Table 11.4-3 Summary of 2nd Consultation Meeting for Area 2-1

Items	Contents		
1. Date and time	9:00AM- 10:30AM, Sunday, 27 March 2016		
2. Venue	Ordination Hall, Aye Myar Thida Ward (Phalan), Kyauktan Township		
3. Invitee	PAHs for Area 2-1		
4. Participant	30 PAHs and 41 other participants; 71 persons as a total		
5.Main	Administrator, General Administration Department, Thanlyin Township		
invitees/participants	2. Administrator, General Administration Department, Kyauktan Township		
from	3. Village Administrator, Shwe Pyi Thar Yar Village Tract		
government/others	4. Village Administrator, Aye Mya Thida Ward		
	5. 100/10 household head leader, Shwe Pyi Thar Yar Village Tract		
	6. 100 /10 household head leader, Aye Mya Thida Ward		
	7. Villagers from Shwe Pyi Thar Yar Village Tract		
	8. Villagers from Aye Mya Thida Ward		
	9. Other organizations and individuals who are interested in the project		
6. Agenda	Background and RWP activities		
	2. Summary of the past consultation meetings incl. village level meetings		
	3. Eligible households for Area 2-1		
	4. Proposed compensation and assistance package with detailed assistance allowances		
	5. Possible resettlement sites		
	6. Planned IRP activities		
	7. Planned implementation organization		
	8. Proposed grievance redress mechanism		
	9. Further steps and expected timeline for Area 2-1		
	10. Other activities for Area 2-1 in the near future		
	11. Q & A		
7. Major opinions and	1) Request for the implementation about the entire 700ha together with 100ha.		
comments from the	2) Request for the explanation of land compensation of local people from the 200ha of Thilawa		
participants	SEZ (from area 6).		
	3) Inquiry regarding the name of ownership.		
	4) Request for the relocation together with the cemetery and big tree to the place nearby.		
	5) Inquiry regarding the land compensation for farm land and garden land.		
	6) Request for the IRP planned before resettlement.		
	7) Request for the implementation of the project in accordance with 2012 farm land law.		
	8) Complain related with their farmland not to accept for the construction of living structure.		
8. Feedback Form	Fours comments and opinions were submitted in the collected feedback form.		

Source: Thilawa SEZ Management Committee





Source: Thilawa SEZ Management Committee

Participants

Figure 11.4-3 PCM on 27 March 2016

(2) Other RWP Area

The public consultation meeting for the draft RWP for other areas is planned to be implemented area by area, as shown in Table 11.4-4.

Table 11.4-4 Public Consultation Meetings for the RWP (Planned)

Methodology and Special Considerations

[Method and Number of Meetings]

- A total of three meetings at a maximum in one day during weekend based on the number of expected participants (planned)
- Local transportation will be provided from major residential area in the project area to the meeting venue

[Venue]

Convention Hall, Department of Human Settlement and Housing Development, Thilawa SEZ Management Committee Office (Temporary), Kyauktan Township near Thilawa SEZ (can be arranged to another places based on the accessibility of participants)

[Agenda]

- Contents of assistance package for loss of assets, income source, relocation, etc.
- Resettlement site
- Contents of Income Restoration Program (IRP)
- Further schedule (schedule of individual negotiation and relocation)

[Expected Participants and Invitation Method]

- Project Affected Households
- The meeting will be informed through the invitation letters or public notice posted in each village one week in advance.

[Language Used]

The presentation and handout in Myanmar language. The explanation will be provided in Myanmar language.

[Special Considerations to Socially Vulnerable Groups]

- Feedback forms will be provided to the participants to share their views and comments without presenting it to the public.

Source: EIA Study Team

11.4.2 Public Disclosure of draft RWP

(1) Area 2-1

The draft RWP for Area 2-1 were disclosed from 29 February 2016 to 8 April 2016 for forty days in nine places listed in Table 11.4-5. In addition, the draft RWP both in English and Myanmar language

was uploaded on the website of TSMC. Public comments were received with the comment form at the disclosure places or by e-mail either in Myanmar or English language.

Table 11.4-5 Draft RWP Disclosure Places

- 1. Office of Thilawa SEZ Management Committee (temp)
- 2. Office of Thilawa SEZ Management Committee, Thilawa SEZ
- 3. Office of DUHD of MOC in Yangon.
- 4. Administrative Office of Kyauktan Township
- 5. Administrative Office of Thanlyin Township
- 6. Administrative Office of Aye Mya Thida
- 7. Administrative Office of Shwe Pyi Thar Yar
- 8. One nearest 100 HH Head's place each for Aye Mya Thida and Shwe Pyi Thar Yar

Source: Thilawa SEZ Management Committee, Resettlement Work Plan (RWP) for Development of Area 2-1 (100ha) of Thilawa Special Economic Zone (Draft) February, 2016

(2) Other RWP Area

The public disclosure of the draft RWP in other areas will be organized as part of public consultation. The draft RWP will be disclosed as described in Table 11.4-6 for review and comments, and the final RWP will be available for public viewing at the Thilawa SEZ Office (planned) and on the website.

Table 11.4-6 Public Disclosure for the RWP (Planned)

Methodology and Special Considerations

[Announcement Method]

- Public disclosure will be announced in the public consultation meetings.
- Disclosure period and comment submission method will be described in the disclosure places.
- The draft RWP will be available on the official website.

[Disclosure Place]

- Convention Hall, DUHD of MOC, Thilawa SEZ Management Committee Office (Temporary), Kyauktan Township near Thilawa SEZ (planned)
- General Administration Office, Thanlyin Township
- General Administration Office ,Kyauktan Township
- Village Tract Office/Ward Office in the Thilawa SEZ Area
- Other places based on the request from the project-affected people

[Disclosure Period]

- One Month

[Comment Submission Method]

 Comments can be submitted with the comment form provided at the disclosure places or by e-mail either in Myanmar or English language.

CHAPTER 12: COMMENTS FROM TSMC

12.1 Comments on the Scoping Report

The Thilawa SEZ Management Committee (TSMC) issued an approval letter (Ref: TSEZ-EIA-003) of the Scoping Report on Environmental Impact Assessment for Development of Industrial Area of Zone B in the Thilawa Special Economic Zone on 26 February 2016 with terms and conditions. The project proponent prepared the draft EIA report which corresponds to the terms and conditions as shown in Table 12.1-1.

Table 12.1-1 Correspondence to the Terms and Conditions from TSMC (Scoping Report)

No.	Terms and Condition from TSMC	Correspondence
(i)	You shall describe the contact address, profile, and relevant experience of the organization which has been conducting the EIA study as well as information on environmental, social, and health experts as key personnel including each person's experience in the field of environmental, social, and health impacts assessment, academic credentials, and relevant certificates and accreditations.	Information of the implementation organizations of EIA was described in Chapter 1 of the draft EIA report. CVs of each expert of the EIA Study Team were attached in Annex.
(ii)	You shall describe international conventions, treaties and agreements related to your project as the project's policy and legal framework.	Major international conventions, treaties, and agreements that the Myanmar government has ratified related to the Project were described in Chapter 2 of the draft EIA report.
(iii)	You shall set project's target levels for environment taking into consideration Myanmar National Environmental Quality (Emission) Guidelines issued by Ministry of Environmental Conservation and Forestry on 29 December 2015 and conditions of surrounding area.	Taken into account the Myanmar National Environmental Quality (Emission) Guideline, the project's target levels were revised and described in Chapter 2 of the draft EIA report.
(iv)	You shall describe institutional arrangement for environmental management by your organization including organization chart, a section in charge of environment, and its role and responsibility in construction stage and operation stage at least.	Institutional arrangements for environmental management for two phases: (i) pre-construction, construction, and closing phases, and (ii) operation phase were summarized in Chapter 2 of the draft EIA report.
(v)	You shall describe detailed project information in order to assess environmental, social, and health impacts properly.	Detailed project information was presented in Chapter 3 of the draft EIA report.
(vi)	You shall include socio-economic components such as access to public services and natural resources in the ToR for the EIA Investigation in order to assess social impacts properly.	Impact on accessibility to public services and natural resources was included in the TOR for EIA investigation and assessment in Chapter 7 of the draft EIA report.
(vii)	You shall conduct scoping evaluation for impacts on soil erosion, usage of chemicals, and earthquakes, and shall conduct its impact assessment if any.	Impacts on soil erosion, usage of chemicals, and earthquakes were considered for scoping and evaluated in Chapter 7 of the draft EIA report.
(viii)	You shall conduct scoping evaluation for residual impact in the stage of after project closure and conduct its impact assessment if any.	Residual impacts in the stage after project closure were considered in Chapter 8 of the draft EIA report.
(ix)	In addition to the impact assessment for the development of industrial area of Zone B, you shall assess cumulative impact including the development of Zone A and the development of logistic area and residential and commercial area of Zone B.	Cumulative impacts of the development of Zone A were taken into consideration when impacts of the Project were assessed in Chapter 7 of the draft EIA report. Impacts which should be assessed cumulatively such as air and noise/vibration were evaluated in consideration of Zone B development including logistic, residence, and commercial area.
(x)	You shall reflect all of the above comments to the draft EIA Report.	The comments received from TSMC were considered to be reflected in the draft EIA report.

12.2 Comments on the Draft EIA Report

The Thilawa SEZ Management Committee (TSMC) issued a notification regarding the comments for the draft EIA Report on Environmental Impact Assessment for Development of Industrial Area of Zone B in the Thilawa Special Economic Zone on 17 May 2016. The project proponent prepared the final EIA report which corresponds to the terms and conditions as shown in Table 12.2-1.

Table 12.2-1 Correspondence to the Comments from TSMC (OSSC) (Draft EIA Report)

	Chapter/	Findings	Comments	Common and an ac
	Section		Comments	Correspondence
1	Common	-	Names of the Ministry and numbers of ministry which reformed in April 2016 shall be revised in the Final EIA report	In accordance with the comments, names of the ministry and numbers of ministry are modified in the final EIA report.
2	Common	A letter of endorsement by the Project Proponent is not attached in the draft EIA Report.	The project proponent shall issue a letter of endorsement and attach in the Final EIA Report.	A letter of endorsement issued by the project proponent is attached in the final EIA report.
3	Common	EIA study team has not registered to the Environmental Conservation Department (ECD) of Ministry of Natural Resources and Environmental Conservation for undertaking EIA.	EIA study team shall submit application form for registration of undertaking EIA to the ECD before submission of the Final EIA Report.	Nippon Koei Co, Ltd., that EIA Study team belongs to, submitted the application form for registration to the ECD and the ECD received it on May 11, 2016.
4	Common	Resettlement Work Plan (RWP) including Income Restoration Plan (IRP) for PAHs are prepared and will be implemented by TSMC. The project proponent is a position to wait for completion of resettlement before signing "Land Lease Agreement" and start construction. After land lease agreement, the project proponent is a position to support income restoration for PAHs indirectly through TSMC after the Land Lease Agreement.	It is recommended that finalization of the RWP and completion of the signing compensation/ assistance with PAHs shall be a condition in the approval letter of EIA to start construction work.	The project proponent will follow the comment.
5	Common	Cumulative impact assessments are implemented for only air, water, noise, and vibration. The impacts on flora/ fauna and biodiversity, and community health and safety are not described.	The cumulative impact on flora/ fauna and biodiversity, and community health and safety, and traffic (for both construction and operation stages) shall be described in the Final EIA Report.	In accordance with the comments, the cumulative impact on flora/ fauna and biodiversity due to the clearing of vegetation land are added in Section 7.9 (p.7-52– p.7-54), and the cumulative impact on public safety and security due to the increase of traffic and population among local community are added in Section 7.25 (p.7-91 – p.7-92). In addition, new chapter for the cumulative impact assessment, as Chapter 8, is added and explains environmental items, basic concept and reference section of Chapter 7 of Final EIA report.(p.8-1 and p.8-2)
6	Common	Proper environmental management mechanism by tenant and sub-zone development shall be secured.	It shall be described in the Final EIA Report that ECPP (kind of EMP), IEE or EIA for each projects/factories in Zone B shall be conducted.	In accordance with the comments, contents of ECPP, IEE or EIA that should be conducted by each projects/factories is described in Section 2.7.1. (p.2-20 – p.2-24).
7	Common	Project Commitments is not clearly mentioned in the draft EIA Report.	The Project Proponent should provide a clear list of commitments that the Project will undertake. This includes	In accordance with the comments, commitments that the Project will undertake including relevant laws, standards, and proposed mitigation

	Chapter/ Section	Findings	Comments	Correspondence
			compliance with the relevant laws and standards and all proposed mitigation measures to be undertaken. This should include the provision of adequate services for the workers on the SEZ (which may include medical services and other services). It would also include any mitigation measures to be carried out for the whole SEZ, including waste management and landscaping. CSR should be treated as a separate component. It is not to be considered as a part of the requirements of the EIA. It may be included but separate from the Project Commitments.	measures to be conducted is summarized in Annex 10-1. On the other hand, activities of CSR are described in Section 2.7.3(3) (p.2-27 — p.2-28)
8	Common	The results of PCM are not mentioned in Executive Summary.	The results of PCM shall be added to Executive Summary in the Final EIA Report.	In accordance with the comments, the results of PCM at draft EIA stage are summarized in the Executive Summary. Moreover, the further responses to the received comments are briefly described.
9	Executive Summary Table 6	Living and livelihood: Impacts and mitigation must be considered as part of EIA not as CSR.	Wording of results of impact assessment shall be reconsidered in the Final EIA Report.	In accordance with the comments, wording of results of impact assessment is revised in the Executive Summary.
10	Executive Summary Table 6	Flood risk-low impact due to EL – 5m	It shall be described in the Final EIA Report how have climate change impacts been modeled and considered over life of project including increase floods, cyclones and sea level rise.	In accordance with the comments, consideration of climate change impacts, increasing of floods, cyclone and sea level rise for setting the elevation level are added in Section 3.4. (p.3-6)
11	Executive Summary Table3-8	Impacts and mitigation measures	Does not address existence of vulnerable and near threatened species of fauna.	Considerations for existence of vulnerable and near threatened species of fauna are mentioned in the Executive Summary and Section 7.9.5. (p.7-4, p.7-52– p.7-54)
12	Chapter 2	-	Proponent's corporate environmental and social policies should be provided in detail (if available).	In accordance with the comments, it is described in Section 2.1 that the project proponent joins UN Global Compact which focuses on the areas of Human Rights, Labor, Environment and Anti-corruption. (p.2-1)
13	Chapter 2 2.1.2 Fundamental Laws and Regulations related to Environmental and Social Consideration	- It is described the fundamental laws and regulations related to the environmental and social considerations in Myanmar. But, some related laws are needed to mention in table 2.1-1 and summary of related laws Some of the laws referred in some chapters of the report are not described in table 2.1-1 and summaries of key laws, such as the Shops and establishment Act (2051) and The Factories Act (2051) Prevention of Hazard from chemicals and related substances	The following modification shall be implemented in the Final EIA Report. - To change the enacted year of Prevention of Hazard from Chemical and Related Substances Law. (not in 2003, enacted in 2013) - To describe some internal laws in table 2.1-1 and summarize some important laws such as: - Prevention of Hazard from Chemical and Related (2013) - Substances Law (2013) - Labour Dispute	In accordance with the comments, the said laws and acts were added in Section 2.2.2 (p.2-1 – p.2-7).

	Chapter/ Section	Findings	Comments	Correspondence
	Secuoli	law was enacted in 2013, not in 2003.	Settlement Law (2012) - Foreign investment law (2012) - Myanmar Citizen Investment Law - Social Security Law (2014) - Boiler Law (2015) - Export and Import Law (2012) - Electricity Law(2015) - Labour Organization Law(2011) - Workmen Compensation Act(1955) - The Prevention and Control of Communicable Diseases Law - Payment of Wages Law/Rules - Factory Act (1951) - The Explosive Act(1987) - The Explosive Substances Act(1908) - Heritage Goods Protection Law(2015) - The Conservation of Water Resources Law(2006) - The Conservation of Water Resources Rules(2013) - The Shops and Establishment Act(1951) - Leaves and Holidays Act (1951) - Minimum Wages Law and Rules (2013) - Employment and skill development law (2013)	
14	Chapter 2 2.1.2 Fundamental Laws and Regulations related to Environmental and Social Consideration	- It is described about the major international agreements and Treaties that the Myanmar has ratified related to environment and social considerations in table 2.1-2.	The following international conventions and treaties shall be added. a) Vienna Convention (1985) b) Montreal Protocol (1989)	In accordance with the comments, the said laws and acts were added in Section 2.2.2. (p.2-3)
15	Chapter 2 2.2.1 Air Quality	Target level of emission gas is not described. Some tenants have a plan to install small-medium combustion facilities such as boiler and melting furnace.	Besides target level of ambient air quality, target level of emission gas shall be set taking into consideration of National Environmental Quality (Emission) Guidelines.	In accordance with the comments, target level of emission gas as well as ambient air quality set in National Environmental Quality (Emission) Guidelines is added in Section 2.4.1. (p.2-8 – p.2-10)
16	Chapter 2 2.2.1 Air Quality	In 2.2.1, it is described that there is no ambient air quality standard in Myanmar. But, ambient air quality standards are mentioned in MEQG. In table 2.2-2, there is no MEQG value in parallel with other standards.	In table 2.2-2, MEQG value should be added in order to correlate the other standards.	In accordance with the comments, NEQG value is added in Section 2.4.1 and the tentative target value of the Project is reconsidered. (p.2-8 – p.2-10)
17	Chapter 2 2.3 Institutional	-	Remaining ministries at the OSSC, such as Central Bank, Ministry of Industry, etc shall	In accordance with the comments, members of OSSC are modified in Section 2.6.1. (p.2-18)

	Chapter/ Section	Findings	Comments	Correspondence
	Arrangement		be added.	
18	Chapter 2 2.3 Institutional Arrangement	-	Table 2.3-5 shall be included more detailed information CSR activities by the Project Proponent (list of activities with date, number of participants, etc.), describe the effective period of the CSR	In accordance with the comments, detailed information of CSR activities by the project proponent are added in Section 2.7.3(3). (p.2-27 – p.2-28)
19	Chapter 3	Project development and implementation time schedules are not described (It is required by EIA Procedures.).	activities Project development and implementation time schedules shall be described in the Final EIA Report.	In accordance with the comments, project development and implementation time schedule are added in Section 3.12. (p.3-22)
20	Chapter 3 3.4 Land reclamation	Detailed information on materials for land reclamation from outside is not clear.	For the land reclamation plan, estimates of the amount of materials (rock, gravel, and sand) from outside, source, and expected mitigation measures in sourcing, transporting, placing shall be described if available.	The excavated volume and embankment volume are planned to be balanced in the development area. Since the land reclamation plan including the amount of materials will be prepared by the construction contractor in the construction phase, the land reclamation plan is not described in the final EIA report.
21	Chapter 3 3.6 Drainage Plan	The capacities of retention pond and retention canal for prevention of flood are not found. It is difficult to assess flood risk inside of the Project Site.	The capacities of retention pond and retention canal for prevention of flood shall be described in the Final EIA Report.	In accordance with the comments, the capacities of retention pond and retention canal are added in Section 3.6. (p.3-10 – p.3-11)
22	Chapter 3 3.7.2 Water Supply Distribution System	Capacity of the existing centralized wastewater treatment system of Zone A and estimated wastewater volume from Zone A are not described. Thus it is difficult to evaluate whether the treatment system still have enough capacity of receiving wastewater from Zone B tenants in the initial phase.	The capacities of existing treatment system and estimated wastewater volume from the Zone A at the timing of starting operation of Zone B shall be described.	In accordance with the comments, The capacities of existing treatment system and estimated wastewater volume from the Zone A at the timing of starting operation of Zone B is added in Section 3.7.2. (p.3-13 – p.3-14)
23	Chapter 3 3.8.2 Wastewater Treatment Plant	Target parameters of design wastewater quality are only BOD and SS (Table 3.8-2). However some parameters after primary wastewater treatment (Table 2.2-4) such as iron, silver, total phosphorus, ammonia, and fluoride are not covered compare with the target wastewater quality discharging to water body (Table 2.2-7). It is not clear that which treatment facilities (pre-treatment by tenant or centralized wastewater treatment) will treat these parameters.	The design wastewater quality and diagram of wastewater treatment or target level of wastewater quality after primary wastewater by tenant shall be revised to archive the target wastewater quality discharging to water body. In addition, information on the location of waste water treatment plant and mention more clearly about treatment plant capacity, facilities and final discharge system shall be described.	In accordance with the comments, the target level of wastewater quality after primary wastewater treatment is modified in Section 2.4.2. (p.2-11-p.2-14)
24	Chapter 3 3.10 Solid Waste Management	It is described that the waste which cannot be reused or recycled may be managed by the waste treatment firm in Zone A or through public service such as by the Pollution Control and Cleansing Department of the Yangon City Development Committee (YCDC).	Are there any internal regulations for tenants particularly regarding the disposal of hazardous waste? If there is no instruction to tenants, it may be arisen an issue due to improper disposal ways particularly for hazardous waste.	There is a regulation for disposal of hazardous waste in the proposed internal regulation for the Industrial area. In accordance with the comments, the proposed internal regulations for tenants particularly regarding the disposal of hazardous waste is added in Section 3.10. (p.3-19 – p.3-20)
25	Chapter 3 3.10 Solid Waste	In figure 3.10-1, type of treatment will not be representing the solid waste management of project	The solid waste management of industrial area by the project proponent should be	In accordance with the comments, the solid waste management of the industrial area by the project

	Chapter/ Section	Findings	Comments	Correspondence
	Management	proponent.	mention clearly. Need to provide the detailed information on the estimate annual amount of hazardous wastes (if possible) and disposal system.	proponent is added in Figure 3.10-1. (p.3-20) The detailed information on the disposal system are described in Section 4.3.7 (3). (p.4-21 – p.4-24) However, the estimated annual amount of hazardous wastes is not described in final EIA report. Because type of tenant has not been fixed at this stage. The project proponent will monitor the amount and type of waste from each tenant in all phases. It is described in Section 10.2 (p.10-13)
26	Chapter 3 3.11 Greening Plan	The area information of greening is not described in this section. The information will be a basic indicator of mitigation measures for flora, fauna, and ecosystem.	Area information of greening in the non-sales area shall be added to Section 3.11 and monitored as a part of environmental monitoring plan.	In accordance with the comments, the area information of greening in non-sales area is added in Section 3.11. (p.3-20 – p.3-21)
27	Chapter 4	The SEZ is one of the large areas located on the bank of Yangon River. Baseline information on river water quality and biodiversity of the river.	Baseline survey for river water quality is recommended to implement in order to identify impact on water pollution before and after development of SEZ.	In accordance with the comments, Yangon River water quality data is added in Section 4.1.2. (p.4-4 – p.4-5) However, it is expected that inflow impact of Yangon River will not present clearly, because Yanon River average flow rate is estimated over seven hundred times larger than that of Shwe Pyauk Creek crossing Thilawa SEZ including maximum wastewater from Zone A and Zone B. In addition baseline data in Yangon River would be not stable and change depending on time or location, because Yangon River is mixed by tidal influence and its basin has a lot of pollutant source such as industry, agriculture, residence and transportation of tanker. In consideration of situation above, Shwe Pyauk Creek was set as the forecast area and survey point, in order to identify and evaluate the impact on water body due to the implementation of the Project.
28	Chapter 4	Public health components (Infant mortality rate, Maternal Mortality Rate, Crude Death Rate, morbidity, occurrence of diseases, Communicable diseases Incidence under DUNS, accidents and injuries, and social health determinants) are not mentioned.	Public health components shall be included in the Final EIA Report.	In accordance with the comments, current situation regarding public health components around the project area is added in Section 4.3.8. (p.4-28 – p.4-30)
29	Chapter 4 4.1.4	Existing noise assessment: The ambient noise measures taken in April 2013 show that the noise level during daytime along the road is above the criteria. The noise levels are acceptable level during nighttime. It is proposed to increase this level from 58 dB(A) to 70 dB(A) along the roadway. See Table 2.2-11 at page 2-12. No justification has been provided for this.	Results of noise monitoring shall be reconsidered to make consistency.	Noise level from traffic is different characteristic from ambient noise, and generally higher. Though the target noise level for living area (Table 2.4-7) is set in NEQG, there is no target level specified for traffic noise along the road in NEQG. Therefore, tentative target levels for traffic noise along the road are set in accordance with the Japanese traffic noise target level (Table 2.4-10), in this EIA study. In accordance with the comment,

	Chapter/ Section	Findings	Comments	Correspondence
				target values for noise are installed in Table 4.1-8, which was referred to the EIA Report for the Thilawa SEZ Class A development project (September 2013). (p.2-14 – p.2-16, p.4-6)
30	Chapter 4 4.2.6 Flora, Fauna, and Biodiversity	Information of natural conservation area such as reserved forests in the surrounding area of the Project site is not described. This information is a basic information to assess impact on flora, fauna, and ecosystem.	Information on natural conservation area such as reserved forests shall be added to Section 4.2.6. The impact on flora, fauna, and ecosystem shall be assessed based on the information if necessary.	There is no protected area including natural reserve, national park, wildlife sanctuary and bird sanctuary around Thilawa SEZ. On the other hand, there is a reserved forest (553 acer) located around Ban Bwe Gon Dam in Kyauktan Township, 3km away from Thilawa SEZ. There is no impact on this reserved forest due to the implementation of the Project. In accordance with the comments, information on reserved forest is added in Section 4.2.6. (p.4-12 – p.4-14)
31	Chapter 4 4.3.6 Livelihood	Not mention about the Livelihood of people relying on the creeks	Information on the livelihood of those persons using the creeks to access the agriculture land shall be added in the Final EIA Report.	In accordance with the comments, the information on the livelihood of those persons who are using the creeks to access the agriculture is added in Section 4.3.6. (p.4-16 – p.4-17)
32	Chapter 4 6.3 Noise	Tables 2.2-10 and 2.2-11 The noise levels set in the MEQS related to impact at receptors. The MEQS would apply unless the project can justify why any level should be chosen. The receptor should be the most sensitive point at the location closest to the source. In the case of traffic there needs to be an assessment of the number and type of vehicles and the transport routes to be taken. Noise assessments within the SEZ are likely to be high. Whilst each tenant will be required to adopt noise mitigation measures and provide hearing protection where required, this should also be a requirement of the TSMC.	The justification of the reason why tentative target noise level from traffic in the Table 2.2-11 shall be described in the Final EIA Report.	Noise level from traffic is different characteristic from ambient noise, and generally higher. Though the target noise level for living area (Table 2.4-7) is set in NEQG, there is no target level specified for traffic noise along the road in NEQG. Therefore, tentative target levels for traffic noise along the road are set in accordance with the Japanese traffic noise target level (Table 2.4-10), in this EIA study. In accordance with the comment, the justification of the reason why tentative target noise level from traffic is described in Section 2.4.3 of the Final EIA Report. (p.2-14 – p.2-16)
33	Chapter 7 7.1 Summary of Environmental and Social impact Assessment	In table 7.1-1, it is described that increasing of traffic volume might be affect the safety of children and project proponent shall design the mitigation measures for security of school children. It is also not link with 7.17.1 Forecast Item of Children's Rights. But in chapter (9), there is no mitigation measure for that and also need to link with 7.17.1.	Consistency among Section 7.1 (summary of impact assessment), Section 7.17 (Forecast Results) and Section 9.1 (Mitigation Measures) shall be ensured in the Final EIA Report.	In accordance with the comments, Section 7.1 and 10.1 are modified in order to ensure the consistency regarding Section 7.18. For the impact on the traffic safety for children due to the increase of traffic volume is considered and described in Section 7.25.(p.7-91 – p.7-92) In addition, the other section is also clarified to ensure the consistency among Section 7.1, forecast results in each section and Section 10.1 of the Final EIA Report.
34	Chapter 7 7.2 Air Quality	In the note in Page 7-8, it is understandable that NO2 is representative parameter for impact assessment on air quality from vehicle among NO2, SO2, and CO. However, it is not clear why impact on PM is not described. Some impact may be occur due to construction activities in and around Thilawa	Impact on PM from vehicle shall be assessed in the Final EIA Report	In accordance with the comments, impact on PM10 from vehicle is added in Section 7.2. (p.7-13, p.7-18 – p.7-22)

	Chapter/ Section	Findings	Comments	Correspondence
	Couldin	SEZ.		
35	Chapter 7 7.2 Air Quality	With respect to impact from tenants in Industrial and Logistic Area, some tenants in Zone A have already had a plan to install small-medium combustion facilities such as boiler and melting furnace. Impact assessment shall be implemented taking into consideration of Internal Regulations of Zone A and Appraisal of ECPP by OSSC/TSMC.	Impact assessment on emission from tenants in Industrial and Logistic Area shall be implemented taking into consideration of Internal Regulations of Zone A and Appraisal of ECPP by OSSC/TSMC.	In accordance with the comments, impact of emission from tenants in the industrial area and the logistic area is assessed taking into consideration of proposed internal regulations of Zone B and appraisal of ECPP by OSSC/TSMC in Section 7.2.5, 2). (p.7-23)
36	Chapter 7 7.3 Water Quality	Clarify the approach for the impacts on water quality. Verify that Shwe Pyauk Creek is the only tidal river and stream that will be affected by discharges from the Industrial estate. Indicate the reason that data on the actual flow in Shwe Pyauk Creek was not collected and used for the impact assessment. Indicate why the impacts on water quality in Yangon River were not considered by the EIA. Estimate the water quality impacts on Shwe Pyauk Creek assuming rainy season flow conditions and dry season flow conditions.	The reason why water quality survey and impact assessment was not taken into account of tidal affect from Yangon River shall be described in the Final EIA Report.	In accordance with the comments, the reason of selection of the forecast area of water quality is described in Section 7.3.2. (p.7-24 – p.7-25)
37	Chapter 7 7.3 Water Quality	Total wastewater from Zone A and Zone B are exceeded total water supply volume. Water demand shall be reconsidered taking into account of actual and planned information of Zone A.	Water demand shall be reconsidered taking into account of actual and planned information of Zone A.	In accordance with the comments, water demand taking into account of actual and planned information of Zone A is considered in Section 7.3.5.(p.7-28)
38	Chapter 7 7.3 Water Quality/ 7.8 Bottom Sediment/ 7.19 Water Use	Forecast of water quality is only targeting BOD. If same methodology is applied for forecasting heavy metals and toxic substance, some parameters of forecasted surface water quality will exceed the target level of ambient water quality because volume of wastewater from Industrial Area of Zone A and Zone B more than existing flow rages. On the other hands, it is not realistic that concentration of heavy metals of treated wastewater to water body will be same as its target level as long as tenants comply with target level for primary wastewater.	Measures for compliance of target level of ambient water quality shall be re-considered and described in the Final EIA Report.	The concentration of heavy metals and toxic substance of treated wastewater from tenants is not known concretely, at the present moment. The tenants will submit the future water demand plan to the project proponent, and the project proponent would prepare the adequate wastewater treatment measures adjust to the tenant's activities. Basically, it is expected that concentration of wastewater is diluted by mixing with stormwater through the retention pond and creek flow. In case that large amount discharge which includes heavy metals and toxic substance is expected and especially low flow season, the project proponent would review the internal target value and set strict standard for pre-treatment, if necessary. (p.7-28, p.7-50 – p.7-51, p.7-79)
39	Chapter 7 7.4 Solid Waste Management	It is described that the operator of SWM facilities checks the waste sample the generators want to dispose of and conduct sample analysis to evaluate whether the waste can be received and managed properly.	What are the restrictions for types of wastes which can be managed properly by the SWM Company? If the waste is not accepted by the SWM company, how such wastes will be controlled?	In accordance with the comments, the restrictions for types of waste which can be managed properly by the SWM Company are added in Section 4.3.7. (p.4-21 – p.4-25) The measure for wastes which is not accepted by SWM company is described in Section 7.4.5

	Chapter/ Section	Findings	Comments	Correspondence
		The assessment of waste is not clear as no details have been provided of the estimated number of people on site or the possible tenants. No details have been provided in the EIA (except references to the DOWA Eco-system and Table 4.3-13 at page 4-20) that there is a suitable facility for the disposal of hazardous and dangerous waste in accordance with the laws of Myanmar.	There should be a clear letter of intent that the land-fill site will accept the waste, including hazardous waste.	(2), p.7-31)
40	Chapter 7 7.4 Solid Waste Management	For hazardous waste management during construction and operation stages should be fully considered the facts that in proper recycling of hazardous wastes, hazardous wastes neither Golden Dowa Ecosystem Myanmar nor YCDC can treat (eg. PCB, infectious waste).	Treatment methodology of hazardous waste which neither Golden DOWA Ecosystem Myanmar nor YCDC can treat shall be described in the Final EIA Report.	In accordance with the comments, the detailed information of treatment methodology of hazardous waste by Golden DOWA Ecosystem Myanmar and YCDC is added in Section 4.3.7 and 7.4.5. (p.4-22, p.7-31—p.7-32)
41	Chapter 7 7.4 Solid Waste Management	For non-hazardous wastes during construction and operation stages should be considered the facts that to collect the public wastes from out of service area in Thilawa SEZ, domestic wastes from Zone A and Zone B, Construction worker's waste outside of Zone A and Zone B and other waste from surrounding area.	The countermeasures of illegal dumped waste generated in the surrounding area related to Zone A and Zone B shall be described in the Final EIA Report.	In accordance with the comments, the countermeasures of illegal dumped waste generated in the surrounding area of Zone A and Zone B is added in Section 7.4.5 (3) (p.7-35)
42	Chapter 7 7.5 Soil Contamination	Actual mitigation measures to prevent infiltration of wastewater to ground such as installation of water proof floor, enough thickness of floor, and adequate drainage to divide water use area and non-water use area are not described.	Actual mitigation measures to prevent infiltration of wastewater to ground shall be added to the Final EIA Report taking into consideration of Zone A Internal Regulations.	In accordance with the comments, actual mitigation measures to prevent infiltration of wastewater to ground taking into consideration of proposed internal regulations of Zone B are added in Section 7.5.5. (p.7-36 – p.7-37)
43	Chapter 7 7.6 Noise and Vibration	More than large-scale machinery such as grinding/ milling machines are planned to install by some tenants. In case that, control methodology of noise and vibration by the project proponent together with TSMC shall be required.	Measures for compliance of target level of noise and vibration in operation phase shall be re-considered and described in the Final EIA Report in case that more than expected large-scale machinery will be installed.	In case that more than expected large-scale machinery will be installed, the tenants shall analyze and evaluate the impact of noise and vibration. Noise and vibration emitted from any source within the land of the tenant shall be effectively controlled by its own arrangement, if necessary. In accordance with the comments, considerations above are added in Section 7.6.6. (p.7-44—p.7-48)
44	Chapter 7 7.6 Noise and Vibration	The forecast result at Section 7.6.6 needs further justification. The management option at page 7-34 to halt work 30m from impacted homes during the day and 200m from impact homes during the night requires detailed investigation to identify how many homes will be impacted. It may be better to provide a buffer zone and landscaping.	Arrangement of lot layout plan to allocate the tenant and installation of buffer zone with less noise and vibration impacts to the surrounding sensitive receivers (monastery, houses etc.) shall be considered taking into account of actual and planned information of Zone A.	In accordance with the comments, feasible mitigation measures are added in Section7.6.6. (p.7-46)
45	Chapter 7 7.7 Offensive	Actual mitigation measures to prevent offensive odor such as	Actual mitigation measures to prevent offensive odor shall	In accordance with the comments, actual mitigation measures to prevent

	Chapter/ Section	Findings	Comments	Correspondence
	Odor	installation of deodorization system, ventilation system are not described.	be added to the Final EIA Report taking into consideration of Zone A Internal Regulations.	offensive odor taking into consideration of proposed internal regulations of Zone B are added in Section 7.7.5. (p.7-49)
46	Chapter 7 7.9 Flora/ Fauna and Biodiversity	With respect to assessment of biodiversity and ecosystem, land use change, remaining area of natural area in and around the SEZ, and mitigation measures such as greening are unconsidered.	Land use change, remaining area of natural area in and around the SEZ, and mitigation measures such as greening shall be added to assessment of biodiversity and ecosystem.	In accordance with the comments, greening plan is added to the assessment of biodiversity and ecosystem in Section 7.9.5. (p.7-52 – p.7-54)
47	Chapter 7 7.10 Hydrology	With respect to assessment of surface water flow, drainage plan of boundary of the project site is not clear to prevent generation of backwater from surrounding area in rainy season.	Drainage plan of boundary of the project site to prevent generation of backwater from surrounding area shall be added in the Final EIA Report.	The drainage plan of boundary of project site will be prepared by construction contractor in during construction phase. For the reference, the drainage plan of boundary of the industrial area of Zone A is described in Section 7.10.5. The drainage plan of boundary of the Project will be prepared in the same manner of Zone A. (p.7-56)
48	Chapter 7 7.11 Soil Erosion	Mitigation measures of prevention of soil erosion caused by discharging storm water from retention pond are not clear.	Impact assessment on soil erosion shall be implemented taking into consideration of mitigation measures of prevention of soil erosion caused by discharging storm water from retention pond.	In accordance with the comments, the mitigation measure of prevention of soil erosion caused by discharging storm water from retention pond is added in Section 7.11.5. (p.7-58—p.7-59)
49	Chapter 7 Social Impact (Direct Impact to PAPs)	The Resettlement Work Plan by Myanmar Government should be provided with the EIA. It must have had extensive public consultation. In addition, given the recommendations made by the JICA Reviewers, the RAP needs to be revisited to ensure compliance with best practice and the EIA Procedure 2015.	Outline of Resettlement of Work Plan by Myanmar Government such as clarification of responsibilities for the Plan, cost for implementation of the Plan, and measures on maintaining current livelihood of PAPs shall be summarized in the Final EIA Report.	As outline of Resettlement of Work Plan, responsibilities and implementation structure is described in Section 2.6.3. (p.2-19—p.2-20) The contents of assistance packages (items of costs for the implementation) and the detail (measures on maintaining current livelihood of PAPs) are summarized in Section 7.12. (p.7-60—p.7-62)
50	Chapter 7 7.20 Cultural Heritage/ Asset	One cemetery and one temple are located in the Project Site but it is not clear that actual relocation method has not been decided. Clear provision needs to be made for an assessment of the cultural values of the assets identified in 6.7.1.	It is recommended that completion of actual implementation of relocation of cemetery and temple with agreement of PAH shall be a condition in the approval letter of EIA to start construction work.	The Project Proponent will follow the comments.
51	Chapter 7 7.21 Landscape	It is described the tenant industry shall be responsible for landscaping the plot and maintaining the same in a well-kept condition. But not limited to trimming, watering and fertilization. Tenants will have to follow the internal regulations of MJTD.	It is need to mention how much area will be maintained for landscaping and greening after the Zone A and Zone B development? The estimated area which will be maintained as landscaping and greening should calculate and mention in this section.	In accordance with the comments, the information of landscaping and greening area of Zone A and Zone B industrial area is added in Section 7.22. (p.7-82— p.7-83)
52	Chapter 7 7.22 Risks for Infection Diseases such as AIDS/HIV	It is mentioned about that the risk for infectious disease and only described the management of AIDS/HIV as an example.	Shall be mentioned other infectious disease such as Hepatitis C, Hepatitis B, and outbreak prone diseases such as Diarrhoea, food poisoning, meningitis etc. Shall be mentioned on other communicable diseases such as malaria, dengue,	In accordance with the comments, infectious disease and outbreak prone diseases and other communicable diseases other than AIDS/HIV are described additionally in Section 7.23. (p.7-84) Accordingly, the profile of health is enclosed as public health components in Section 4.3.8. (p.4-28–p.4-30) In addition, health education

	Chapter/ Section	Findings	Comments	Correspondence
			tuberculosis, sexually transmitted diseases. Shall include diseases preventable by immunization such as diphtheria, measles etc Shall set up health education program, early reporting and referral system, and immunization program for under 5 years old children from family at construction site and tenants.	and reporting system, immunization program to be recommended to establish are described in Section 7.23. (p.7-85)
53	Chapter 7 7.23 Occupational Health and Safety	Concrete activities on occupational health and safety stipulated in IFC General EHS Guidelines are not described. For any workers living on the SEZ, there is a need to undertaken an assessment based on the IFC General EHS Guidelines. This should also be the minimum standard if any tenants also provide worker accommodation. No assessment has been made on the number of workers for Zone B.	Mass casualty events and disaster should be mentioned and preparedness and response plan should be developed. Snake bite should be mentioned. Concrete activities on occupational health and safety stipulated related to the Project in IFC General EHS Guidelines and labour related laws and regulations in Myanmar shall be added. The following facts should be considered in EIA study according to the labour related laws and regulations in Myanmar: 1) labour rights 2) contract between tenants and labours which includes working hours, working days and other negotiations. 3) safety awareness and health check 4) safety health plan 5) work place diseases and accidents 6) accommodation facilities for the workers with family. A Grievance Mechanism needs to be established to assist in the resolution of disputes during construction and operation of the Zone B. This should enable disputes to be resolved quickly and easily to promote harmonious relationships between the communities and the TSMC. Once tenants are on the site they should be involved with the Dispute Resolution Committee if required.	Preparedness and response plan for mass casualty events and disaster are mentioned in Section 7.27. (p.7-94) In accordance with the comments, additional contents such as snake bite, concrete activities for OHS stipulated in IFC General EHS Guidelines and law and regulation in Myanmar related occupational health are described in Section 7.24. In addition, the facts mentioned in the left column are incorporated in Section 7.24 (p.7-86—p.7-90) as well. As a function of grievance mechanism, the process of dispute settlement in current situation is described in the paragraph of (2) Impact on Labor Right in Section 7.24.5. (p.7-89)
54	Chapter 7 7.24 Community Health and Safety	Concrete activities on community health and safety stipulated in IFC General EHS Guidelines are not described.	Safe water supply should be mentioned. Mass casualty events and disaster should be mentioned and preparedness and response plan should be developed. Concrete activities on	Preparedness and response plan for mass casualty events and disaster are mentioned in Section 7.27. (p.7-94) Safe water supply is described in Section 7.20 (p.7-77– p.7-79) as one of the contents for water usage. In accordance with the comments, concrete activities for CHS stipulated

	Chapter/ Section	Findings	Comments	Correspondence
			community health and safety stipulated related to the Project in IFC General EHS Guidelines shall be added. Security safety for community, the following facts should be considered: 1) Traffic accidents 2) Increase of crime, infectious diseases such as Hepatitis C, Hepatitis B, Diarrhoea etc. 3) Utilization of worker's accommodation	in IFC General EHS Guidelines are described in Section 7.25. (p.7-91 – p.7-92) In addition, the facts mentioned in the left column except "2) infectious diseases such as Hepatitis C, Hepatitis B, Diarrhoea etc." are incorporated in Section 7.24 as well. (p.7-86 – p.7-90) For the contents regarding infectious diseases, it is described in Section 7.23 (p.7-84 – p.7-85)
55	Chapter 7 7.25 Usage of Chemical	Actual/ planned control measures of usage of chemical in Zone A such as preparation of list of chemical and its Material Safety Data Sheet (MSDS), monitoring of amount and control measures, and implementation of self-inspection are not described.	Actual/ planned control measures of usage of chemical in Zone A such as preparation of list of chemical and its Material Safety Data Sheet (MSDS), monitoring of amount and control measures, and implementation of self-inspection shall be described in the Final EIA Report taking into consideration of Zone A Internal Regulations and SOPs of TSMC.	In accordance with the comments, several control measures of usage of chemical that can be applied to the project area taking into consideration of the proposed internal regulation of Zone B and EHS Guidelines are added in Section 7.26.(p.7-93) and 10.2 (p.10-14)
56	Chapter 7 7.26 Flood Risks	Setting elevation of flood risk is only taking into consideration of the highest level of MITT but not clear of highest date. It is not consideration of past flood and cyclone.	The elevation shall be set taking into consideration of not only the highest level of MITT but also past flood and cyclone.	In accordance with the comments, setting the elevation level taking into consideration of past flood and cyclone is added in Section 3.4. (P. 3-6) and Section 7.27 (p.7-94).
57	Chapter 7 7.28 Earthquake	With respect to forecasting impact on earthquake in operation phase, there is no description about measures on infrastructure of the Project such as canal, pond, and road.	Impact assessment on earthquake for infrastructure facilities shall be included in the Final EIA Report.	In accordance with the comments, mitigation measure for earthquake impact on infrastructure facilities in the project area is added in Section 7.29. (p. 7-97 – p.7-98)
58	Chapter 7 7.29 Global Warming	Concrete activities on minimization of GHGs emission by tenant in their operation are not clear. Identify all emissions sources and their locations. Provide estimates (tonnes per year) of GHG emissions (e.g., CO ₂ , NO ₂ , SO ₂ , CH ₄ , VOC).	Concrete activities on minimization of GHGs emission by tenant in their operation shall be added taking into consideration of actual activities in Zone A.	In accordance with the comments, some activities for minimization of GHGs emission are added, such as usage of solar power to the street lamp, usage of LED and recommendation of usage of energy-saving equipment to the tenants in Section 7.30. (p.7-99—p.7-100)
59	Chapter 9 9.1 Environmental Mitigation and Management Plan	Need to link with Chapter 2. Provide a description of the Proponent staff that will be responsible for supervision and implementation of the Environmental Management Plan. Please indicate the responsibilities of construction contractors for implementation of environmental management plans. Please clarify that independent monitoring consultants and agencies will conduct environment monitoring programs. Include the Proponent's	Environmental mitigation measures and management plan shall be revised in the Final EIA Report as much as possible taking into consideration of the finding in the left column:	As for the project proponent, environmental management system was already established during development of Zone A. The current staff will hold the additional post for Zone B. Implementing organization and responsible organization for environmental management plan are mentioned in Table 10.1-1-Table 10.1-3. (p.10-2—p.10-11) And implementation structure of the project proponent and main tasks for environmental and social considerations in the project proponent are added in Section 10.5. (p.10-16)

	Chapter/ Section	Findings	Comments	Correspondence
	-	responsibilities for monitoring and reporting under EIA Procedure Chapter IX.		Responsible organization for monitoring plan is mentioned in Table 10.1-1-Table 10.1-3.
		Monitoring. Include who will be responsible for ensuring/monitoring compliance by individual tenants.		On the other hand, each tenant will implement EMP and EMoP for each business and submit the
		Similarly, who will be aggregating the monitoring reports from individual tenants.		environmental monitoring report to OSSC of TSMC and the project proponent based on its IEE/EIA.
		The role and responsibilities of the Environmental Conservation Department (ECD) including the		Mitigation measures and monitoring plan will be conducted by own expense based on its IEE/EIA
		Yangon Region ECD needs to be described.		In accordance with the comments, the role and responsibilities of the
				Environmental Conservation Department (ECD), as a member of OSSC, is added in Section 10.5. (p.10-16)
60	Chapter 9 9.1 Environmental	Specific EMPs are not mentioned. Need to mention the following points in detail:	Environmental mitigation measures and management plan shall be revised in the	1) Based on the proposed environmental mitigation and management plans in Table 10.1-1,
	Mitigation and Management Plan	1) Verify the items in each of the environmental mitigation and management plans in Table 9.1-1,	Final EIA Report as much as possible taking into consideration of the finding in	10.1-2, 10.1-3., contractor/tenants will select adequate /feasible measures or add better measurement depending on
		9.1-2, 9.1-3.2) Each plan needs staffing requirements, cost estimation, and	the left column:.	the situation. 2) Environmental management system was already established during
		capacity development and training should be separated for mitigation and monitoring		development of Zone A. The current staff will hold the additional post for Zone B. On the other hand,
		programs. 3) plans to address full implementation of the IRP and to		environmental management staff of contractors/tenant will be proposed by contractor/tenants
		include details of the program- census of PAPs, budget estimates, time frame, institutional		3) In accordance with the comments, the detail contents of IRP are added in Section 7.12. (p.7-60– p.7-62)
		arrangements and reporting. 4) plans to address mitigation measures and monitoring		plans to address mitigation measures and monitoring for incineration, common waste water
		requirements for incineration, common waste water treatment plant, sludge disposal facilities,		treatment plant, sludge disposal facilities, hazardous wastes management site will be prepared by
		hazardous wastes management sits etc. 5) the mechanism for grievance		Private Solid waste management company in ZoneA. 5) In accordance with the comments,
		redress and community outreach efforts to deal with any complaints from nearby residents.		the mechanism for grievance redress and community outreach efforts is described as a part of stakeholder
		6) Plan for compensation for land disturbance and land acquisition should be provided attached with		engagement plan in Chapter 11. (p.11-2) 6) In accordance with the comments,
		Resettlement Plan 7) Plans for consultation, grievance redress, and disclosure		the plan for land compensation is added in 7.12 (p.7-60 – p.7-62). 7) In accordance with the comments,
		during implementation is needed to prepare. 8) plan for supervision and		plans for consultation, grievance redress, and disclosure are described as a part of stakeholder engagement
		monitoring for the compliance and EMP implementation needed		plan in Chapter 11. (p.11-2) 8) In accordance with the comments,
		to be prepared.		implementation organization structure including tenants and project proponents for environmental
				management is added in Section 10.5

	Chapter/ Section	Findings	Comments	Correspondence	
61	Chapter 9 9.1 Environmental Mitigation and Management Plan	Staffing Requirements and Terms of Reference for key positions are needed, including: 1) environmental staffing requirements for the Proponent Environmental Management Staff 2) Contractors environmental management staff 3) TOR for third party environmental consultants involved in preparation and implementation of environmental management sub plans.	Environmental mitigation measures and management plan shall be revised in the Final EIA Report as much as possible taking into consideration of the finding in the left column:	(p.10-17). 1) Environmental management system was already established during development of Zone A. The current staff will hold the additional post for Zone B. Main tasks for environmental and social considerations of the project proponent are added in Table 10.5-1(p.10-17). 2) Contractor's environmental management staff will be proposed by the contractor under requirement from the project proponent 3) TOR for third party's environmental consultants in monitoring is shown in Annex 10-2, including monitoring points, items, monitoring form and contents of monitoring reports	
62	Chapter 9 9.1 Environmental Mitigation and Management Plan (page9-1)	Mitigation measures on water use, social infrastructure are not described even there are impacts to some extent.	Mitigation measures on water use, social infrastructure shall be described in the Final EIA Report.	In accordance with the comments, the mitigation measures on water use and existing social infrastructure are added in Section 10.1. (p.10-2 – p.10-11)	
63	Chapter 9 9.1 Environmental Mitigation and Management Plan	In table 9.1-3, under Pollution, proposed mitigation measures and environmental management for air quality is only emphasize to control the emission from vehicles, not include to control the emission from various kinds of factory in Zone B.	It should be mentioned that the implementation organization including tenants and project proponents have to control the emission from factory with proper management plan.	In accordance with the comments, implementation organization structure including tenants and the project proponents for environmental management is added in Section 10.5. (p.10-16 – p.10-17)	
64	Chapter 9 9.1 Environmental Mitigation and Management Plan (page9-2 to page 9-5)	Some mitigation measures are not clear.	Mitigation measures on water use, social infrastructure shall be described specifically as much as possible in the Final EIA Report.	In accordance with the comments, the mitigation measures on water use and existing social infrastructure are added in Section 10.1. (p.10-3 – p.10-4, p.10-8)	
65	Chapter 9 9.2 Environmental Monitoring	Monitoring plans for some elements (category) which assessed in Chapter 7 are not described.	All of the elements (category) which assessed in Chapter 7 shall be included in the monitoring plan.	In accordance with the comments, all of the elements (category) which assessed in Chapter 7 are included in the monitoring plan in Section 10.2. (p.10-12 – p.10-14)	
66	Chapter 9 9.2 Environmental Monitoring	As the results of findings and comments regarding section 7.3 Water Quality, frequency of water quality monitoring at outlet of centralized wastewater may be insufficient.	Water quality monitoring at outlet of centralized wastewater is recommended from every two months to every month (basic parameter) and from every six months to every three months (toxic and heavy metals).	In accordance with the comments, water quality monitoring at outlet of centralized wastewater is revised from every two months to every month (basic parameter) and from every six months to every three months. (p.10-13)	
67	Chapter 9 9.2 Environmental Monitoring	Monitoring plan for activities on social aspect is not clear.	Results of activities on community support programs related to EIA shall be including the Environmental Monitoring Report.	In accordance with the comments, the implementation status of CSR activities such as community support program are added as monitoring item for applicable categories in Section 10.2. (p.10-12 – p.10-14)	
68	Chapter 9 9.3 Budget for the Environmental Management	Wastewater treatment will be treated by the central wastewater treatment plant in Zone A for the time being, but there is no mentioned about operation and	The operation and maintenance cost shall be added in the Final EIA Report.	It is difficult to present the operation and maintenance cost of the wastewater treatment plant at the present moment because the cost is depending on the capacity/quality of	

	Chapter/ Section	Findings	Comments	Correspondence
		maintenance cost of the plant in		the system and volume of treatment
69	Chapter 9 9.3 Budget for the Environmental Management	Zone A. A budget is needed with: 1) costs for establishment and operation of the Proponents environmental management system; 2) costs for Third Party Environmental Consultant services; 3) cost of monitoring and reporting for compliance with the ECC and EMP; 4) costs of further preparation, training, and implementation of environmental mitigation and management plans for; (i) preconstruction phase (Table 9.1.1); (ii) construction /closing phase (Table 9.1.2); and operation phase (Table 9.1.3.); 5) costs for Land Acquisition and Resettlement; 6) the costs for construction and operation of the central waste water treatment plant.	Budget plan shall be revised in the Final EIA Report as much as possible taking into consideration of the finding as shown in the left column.	water. 1) Environmental management system was already established during development of Zone A. The current staff will hold the additional post for Zone B. There is no additional cost for establishment. Cost of operation is included daily work. 2) There is no cost estimation because there is no concrete TOR for third party's Environmental Consultant services. 3) Cost of monitoring and reporting are added in Table 10.3-2 (p.10-15). 4) Mitigation measures will be designed by contractor or tenants by own expense. 5) Items of costs for land acquisition and resettlement are described in Section 7.12. (p.7-60 – p.7-62) 6) It is difficult to present the operation and maintenance cost of wastewater treatment plant at the present moment because the cost is depending on the capacity/quality of the system and volume of treatment water.
70	Chapter 10	Public consultation meeting: Chapter 10 provides a listing and summary of the issues and concerns raised by the communities and the public. Many responses the questions, implied that the issues would be addressed in the EIA Report	For each issue, explain how the Project and/or the Proponent are addressing the issue. Need to consider and mention the solutions to solve the request from the public at PCM. The public consultation process shall be continued periodically. Key elements are required to ensure that the public consultation achieves a minimum acceptable level: 1) A stakeholder engagement plan shall be developed to ensure engagement with PAP, PAH and civil society. 2) The PAP and PAH need to be consulted on the mitigation measures for noise and traffic safety. 3) The PAP and PAH need to be consulted on the RAP and should provide comments and feedback for consideration 4) There should be consultation in particular on the air quality and waste issues to ensure that this can be addressed. 5) The community of Township (using Cemetery) need to be consulted and	In accordance with the comments, the further responses to the public comments and requests by the project/the project proponent are described in Chapter 11. (p.11-1–p.11-20; Table 11.2-2, 11.2-4, 11.2-6, 11.3-2 to 11.3-4, 11.3-6, 11.3-8) In addition, stakeholder engagement plan, which includes the process of public consultation in case that any environmental and social, health issue occurs among local community, is described in Chapter 11 considering the comments in the left column. (p.11-1–p.11-20)

EIA Report for Thilawa Special Economic Zone Development Project (Industrial Area of Zone B)

Chapter/ Section	Findings	Comments	Correspondence
		approval received to	
		relocate the ceremony. This	
		must be done in accordance	
		with any conditions	
		required by that	
		community.	

CHAPTER 13: CONCLUSIONS

As to the results of the EIA study for the Industrial area of Thilawa SEZ project, the following items are found:

- 1) In terms of living environment, most of the impacts are controlled and limited in and around the project area. The key negative impacts such as emission of gas and dust, deterioration of water quality, generation of noise and vibration are expected. However, implementation of appropriate mitigation and management plan, such as to spray water to bare areas for dust prevention and to avoid the incentive operation of the construction machinery for prevention of emission gas, noise and vibration during construction phase, and to provide the commuter bus by tenants and to comply with the tentative target value of effluent water flowing out of the wastewater treatment plant by tenants including the project proponent during operation phase, will minimize these impacts.
- 2) In terms of natural environment, the key negative impact is the clearance of existing vegetation during construction phase, though there is no sensitive ecological protection area. However, implementation of appropriate mitigation measures, such as planting trees, vegetation and sodding of public spaces as soon as possible and keeping the environmental conditions along the existing canal will minimize the impact on the ecosystem.
- 3) In terms of social environment, land acquisition and some scale of involuntary resettlement are expected. Impact on livelihood of the project-affected persons (PAPs) including vulnerable people and children is also expected during the pre-construction, construction and operation phase. Toward this issue, the resettlement framework of the Thilawa Special Economic Zone (SEZ) (2,000 ha) was prepared that includes compensation and assistance package and income restoration program for the PAPs and will be conducted by Thilawa SEZ Management Committee (TSMC), that will mitigate the impacts of the Project on social environment.
 - On the other hand, some positive impacts of the Project such as increase in job opportunity and improvement of social infrastructure are also expected.
- 4) In terms of health and safety, some impacts on occupational/community health and safety and increase in number of accidents are expected. However, implementation of appropriate mitigation and management plan, such as to manage working conditions during the construction work and to provide security and maintain safety prevention measures during construction/operation phase will minimize these impacts.
- 5) In consideration of the result of the EIA study for the Project, the Environmental Management Plans (EMPs) including adequate mitigation measures to reduce the negative impacts and Environmental Monitoring Plan (EMoP) are proposed for each phase of the Project: pre-construction phase, construction/closing phase, and operation phase.

It was confirmed that the environmental, social and health impacts of the Project were assessed and the Environmental Management Plan was formulated properly. In the process of EIA, opportunity of public involvement was ensured and comments from the public, TSMC and MONREC were reflected into the final EIA Report. Thus the EIA was completed in accordance with the requirements of the EIA Procedure properly in case that project proponent will follow EMP accordingly.



Annex 1-1

Curriculum Vitae of the Key Experts of the EIA Study Team

Annex 2-1

Comparison between the JICA Guidelines and the Relevant Regulations in Myanmar

Annex 2-1 Comparison between the JICA Guidelines and the Relevant Regulations in Myanmar

Table 2-1-1 Comparison between the JICA Guidelines and EIA Procedure in Myanmar

Contents	Requirements and Key Points in the JICA Guidelines	Requirements in EIA Procedure in Myanmar	Consistency/Differences between JICA Guideline and EIA Procedure in Myanmar
Information Disclosure in the official language or/and in a language widely used in the country	EIA reports must be written in the official language or in a language widely used in the country in which the project is to be implemented. When explaining projects to local residents, written materials must be provided in a language and form understandable to them. The documents that would be used in the meetings with local stakeholders will be prepared in an official or widely used language and in a form understandable by local people.	IEE report, scoping report and EIA report shall be prepared either in the Myanmar language or in the English language with an accompanying accurate summary in the Myanmar language. (Chapter IV 35, Chapter V 51, 62)	Since the relevant reports are required to be written in the Myanmar language (summary or the entire text), EIA Procedure in Myanmar is consistent with the JICA Guidelines. On the other hand, there is no written rule about the language to be used in the public consultation meetings. In the Project, Myanmar language was used for a series of public consultation meeting and the documents used in the meeting.
Scope of impact to be assessed	The impacts to be assessed with regard to environmental and social considerations include impacts on human health and safety, as well as on the natural environment, that are transmitted through air, water, soil, waste, accidents, water usage, climate change, ecosystems, fauna and flora, including trans-boundary or global scale impacts. These also include social impacts, including migration of population and involuntary resettlement, local economy, existing social infrastructures and services, vulnerable social groups such as poor and indigenous peoples and equality of benefits and losses. In addition to the direct and immediate impacts of projects, their derivative, secondary, and cumulative impacts as well as the impacts of projects that are indivisible from the project are also to be examined and assessed to a reasonable extent.	The EIA investigation shall consider all biological, physical, social, economic, health, cultural and visual components of the study area during all project phases including pre-construction, construction, operation, decommissioning, closure and post-closure and shall identify and assess all adverse impacts, risks, cumulative impacts and residual impacts. (Chapter V 56)	EIA Procedure in Myanmar is consistent with the JICA Guidelines.
Examination of Alternatives	Multiple alternatives must be examined in order to avoid or minimize adverse impacts and to choose better project options in terms of environmental and social considerations.	In the procedure of EIA investigation, consideration of the selected alternatives and comparison and selection of the preferred alternatives shall be done. (Chapter V 58)	EIA Procedure in Myanmar is consistent with the JICA Guidelines.
Environmental Management Plan, Environmental Monitoring Plan	Appropriate follow-up plans and systems, such as monitoring plans and environmental management plans, must be prepared; the costs of implementing such plans and systems, and the financial methods to fund such costs, must be determined.	Management and monitoring sub-plans by project phase (pre-construction, construction, operation, decommissioning, closure and post-closure) shall be prepared in the EIA Report. The project Proponent shall submit monitoring reports o the Ministry not less frequently than every six months as provided in a	EIA Procedure in Myanmar is consistent with the JICA Guidelines.

Contents	Requirements and Key Points in the JICA Guidelines	Requirements in EIA Procedure in Myanmar	Consistency/Differences between JICA Guideline and EIA Procedure in Myanmar
		schedule in the environmental monitoring plan. (Chapter V 63, Chapter IX)	

Source: EIA Study Team

Table 2-1-2 Comparison between the JICA Guidelines and Relevant Laws in Myanmar regarding Land Acquisition and Involuntary Resettlement

No.	JICA Guidelines/ World Bank Safeguards Policies	Law in Myanmar	Gap Between Laws in Myanmar and JICA Guidelines	Measures to Filling Gap
1.	Involuntary resettlement and loss of means of livelihood are to be avoided when feasible by exploring all viable alternatives. (JICA Guidelines: JICA GL)	Not applicable	There is no regulation which mentions or requests to avoid or minimize involuntary resettlement and loss of livelihood means.	The project examines alternatives to avoid or minimize resettlement impact
2.	When population displacement is unavoidable, effective measures to minimize impact and to compensate for losses should be taken. (JICA GL)	Compensation or indemnity is provided for farmland acquisition for the interest of the State or public. (Farmland Law (2012) Art. 26, Farmland Rules (2012) Art. 64)	There is no difference.	-
3.	People who must be resettled involuntarily and people whose means of livelihood will be hindered or lost must be sufficiently compensated and supported, so that they can improve or at least restore their standard of living, income opportunities and production levels to pre-project levels. (JICA GL)	Damages to standing crops/trees, lands, movable/immovable properties, relocation cost, economic activities are requested to compensate. (Land Acquisition Act (1894) Art. 23, Farmland Rules (2012) Art. 67)	There is no stipulation of improving or at least restoring living standard, income opportunities and production levels to pre-project levels in the Myanmar legal framework.	Assistance for improving or restoring livelihood at least to pre-project level is provided.
4.	Compensation must be based on the full replacement cost as much as possible. (JICA GL)	Land: Market-value compensation (Land Acquisition Act (1894) Art.9, 23 (1) and 23(2)) Crops: Compensation at three times of the value calculated based on the average production of crops in the current market price of that area is provided. (Farmland Rules (2012) Art. 67)	Land: Partial gap since the act lacks standard methodology in determining compensation, though it requires considering the market value. Additionally, there would be a gap between the market value and full replacement cost. Crops: There is no significant difference.	Land: Needs to be compensated at replacement cost which generally consists of the market value and other transaction costs.
5.	Compensation and other kinds of assistance must be provided prior	When compensation is not paid on or before	There is no clear indication about timing	Assistance is planned to be provided by dividing

No.	JICA Guidelines/ World Bank Safeguards Policies	Law in Myanmar	Gap Between Laws in Myanmar and JICA Guidelines	Measures to Filling Gap
	to displacement. (JICA GL)	land acquisition, compensation amount awarded with interest rate must be paid.	of compensation payment in the Myanmar legal framework.	in a few times (not providing all amount in one time before displacement) in order to manage provided assistance amount properly.
6.	For projects that entail large-scale involuntary resettlement, resettlement action plans must be prepared and made available to the public. (JICA GL)	Not applicable	There is no regulation which mentions or requests to avoid or minimize involuntary resettlement and loss of livelihood means.	Resettlement Work Plan (RWP) is prepared in consultation with PAPs and will be disclosed to the public.
7.	In preparing a resettlement action plan, consultations must be held with the affected people and their communities based on sufficient information made available to them in advance. (JICA GL)	Not applicable	There is no regulation requesting to organize consultations with PAPs.	Consultations with PAPs have been organized in timely manner.
8.	When consultations are held, explanations must be given in a form, manner, and language that are understandable to the affected people. (JICA GL)	Not applicable	There is no regulation requesting to organize consultations with PAPs.	Consultations with PAPs have been organized using understandable explanation methods.
9.	Appropriate participation of affected people must be promoted in planning, implementation, and monitoring of resettlement action plans. (JICA GL)	Not applicable	There is no regulation requesting participation of PAPs into planning, implementation and monitoring of resettlement action plans.	Participation of PAPs is secured by organizing consultations in timely manner.
10.	Appropriate and accessible grievance mechanisms must be established for the affected people and their communities. (JICA GL)	1) Notice of compensation amount to PAPs directly: appeal to the court within 6 weeks from the date of compensation award 2) Notice of compensation amount to representatives of PAPs: i) within 6 weeks of receipt of compensation notice, or ii) within 6 months from the from the date of compensation award, whichever period shall be first expire (Land Acquisition Act (1894) Art. 18)	The procedure of grievance in the Myanmar context is direct settlement at the court, which is not necessarily easy or accessible to PAPs.	The grievance redress mechanism is established by utilizing the existing administration system to be convenient for PAPs.
11.	Affected people are to be identified and recorded as early as possible in order to establish their eligibility through an initial	A notification of land acquisition or public purposes is published in the Gazette, which is	There is no specific description of identifying affected people as early as	Census was initially conducted at the preliminary delineated boundary in April 2013,

No.	JICA Guidelines/ World Bank Safeguards Policies	Law in Myanmar	Gap Between Laws in Myanmar and JICA Guidelines	Measures to Filling Gap
	baseline survey (including population census that serves as an eligibility cut-off date, asset inventory, and socioeconomic survey), preferably at the project identification stage, to prevent a subsequent influx of encroachers of others who wish to take advance of such benefits. (WB OP4.12 Para.6)	also published at the convenient place in the concerned municipality. (Land Acquisition Act (1894) Article 4)	possible in the national law.	and supplemental survey was conducted to the final boundary in May 2014 to September 2015 for identifying number of affected households as well as their socio-economic condition.
12.	Eligibility of benefits includes, the PAPs who have formal legal rights to land (including customary and traditional land rights recognized under law), the PAPs who don't have formal legal rights to land at the time of census but have a claim to such land or assets and the PAPs who have no recognizable legal right to the land they are occupying.(WB OP4.12 Para.15)	Occupiers/stakeholders of lands to be acquired are explained about acquisition and claims to compensations. (Land Acquisition Act (1894) Article 9)	Detail procedures as well as eligibility criteria are not clearly defined. Also there is no specific indication about displaced persons without titles.	The project establishes eligibility for assistance to all households whose income sources or assets are confirmed as affected due to project implementation.
13.	Preference should be given to land-based resettlement strategies for displaced persons whose livelihoods are land-based. (WB OP4.12 Para.11)	Not Applicable	There is no regulation stipulating to give land-based resettlement strategies.	Appropriate measures are provided to PAPs based on consultation with them.
14.	Provide support for the transition period (between displacement and livelihood restoration). (WB OP4.12 Para.6)	Not Applicable	There is no regulation stipulating to provide support for the transition period.	Sufficient support for the transition period is provided.
15.	Particular attention must be paid to the needs of the vulnerable groups among those displaced, especially those below the poverty line, landless, elderly, women and children, ethnic minorities etc. (WB OP4.12 Para.8)	Not Applicable	There is no regulation stipulating to provide particular attention to the vulnerable groups.	Additional support for the vulnerable groups is provided.
16.	For projects that entail land acquisition or involuntary resettlement of fewer than 200 people, abbreviated resettlement plan is to be prepared. (WB OP4.12 Para.25)	Not Applicable	There is no regulation stipulating to prepare resettlement plan.	The project requests more than 200 people of displacement, and prepares RWP accordingly.

Source: Thilawa SEZ Management Committee, Framework of Resettlement Works for the 2000ha Development Area of Thilawa Special Economic Zone (SEZ) February 2016

Annex 6-1

Laboratory Analysis Record

Annex 6-1 Laboratory Analysis Record

Surface Water Quality Survey – Rainy Season-



ANALYSIS REPORT

ORIGINAL

Job Rof: 6218/2015 Date : 20.10.2015 Page 1 of 1

Sample Described as :

SURFACE WATER (8,10.15) FIA STUDY FOR PHASE II.

AREA DEVELOPMENT IN THILAWA SEZ

Client Name Sample Received Date ... RESCURCE & ENVIRONMENT MYANIMAR

Sample Brought By

0.10.2015 Client

Sample Reference

SW = I (THLAWA)

Analysed Date

9.10.2015

Lab Code No.

170/16

No	Test Parameter	Method	Loc	Result	Unit
4	Qi & Gresse	Based on Standard methods for the examination of water & waste water APHA AWWA & WEF 22nd ed. 2012 : 5520 8	0.2	1.2	mgd
2	Manganese	Dased on Standard morhods for the examination of water & waste water APHA ,AVWA & WEF, 22nd ed., 2012; 31118 (Direct Air- Acetylene Frame method)	0.1	≈0,1	mg/l

"End of Report"

SGS (Myanmar) Limited

(No No VI)

20 Fermini Limital Agriculumi Schloss 1978, Sthost Huna ey Complex Windon Steet Levin abov Sey, Yergini Wyamsell 1 459/12/1952; 211527, 211533, 211517 4 499/12/1946, 9 (2)49/12/1969 er ogt in yertin af Bigs com

Member of SSS CompGSS SVI



ORIGINAL

Job Ref: 6216/2015 Date + 25.10.2015 Page 1 of 1

Sample Described as :

SURFACE WATER (6.10.16) EIA STUDY FOR PHASE II

AREA DEVELOPMENT IN THILAWA SEZ

Clent Name

RESOURCE & ENVIRONMENT MYANIMAR

Sample Received Date :

8 10 2015

Sample Brought By

Client

Sample Reference

SW-2 (THILAWA)

Analysed Date

9,10,2016

Lab Code No.

171715

No	Test Parameter	Method	Lod	Result	Unit
ŧ	Cil & Crease	Based on Standard methods for the examination of water & waste water APHA, AWWA & WEF 22nd ed, 2012 : 5520 B	0.2	3.4	mgA
2	Manganese	Based on Standard methods for the examination of water & wasts water AFRA, AV/WA & WEF,22rd ed, 2012 ; 31 118 (Direct Air- Acetylane Flame method)	0.1	<0.1	Ngm

End of Report

SGS (Myanmar) Limited

(Nu Nu YI) Manager

JGT (Mycowell Linear)
Agreetics: Service: 79/80, 68/80 Ferrating Complex, Worder Street, Language Visco Microsoft L. (1931)77/1562, 77/517, 21938, 27/501 | 1-954)77/516-9, 27/507 | a bg: opening Copy time.

University Designations





Job Ref: 6216/2015 Date : 20,10,2016 Page 1 of 1

Sample Described as : SURFACE WATER (\$.10.15) EIA STUDY FOR PHASE II.

AREA DEVELOPMENT IN THILAWA SEZ RESOURCE & ENVIRONMENT MYANNAR

Client Name : RESOURC Sample Received Date : 8,70 2010 Sample Brought By Client

Sample Reference EW - 3 (THE AVVA)

Analysed Date : 9.10.2016 List Code No. : 172/15

No	Test Parameter	Method	Lod	Result	Unit
V.	Ol & Greate	Based on Standard methods for the examination of water & waste water APHA ,AAWA & WEE .22nd ed, 2012 ; 5520 B	0.2	02	mg/
2	Manganesa	Based on Standard methods for the exemination of water & waste water APHA AWWA & WEF 22nd ed, 2012; 31118 (Ciredt Ar-Apetylene Flame method)	0.1	49.1	mail

End of Report

SGS (Myanmar) Limited

(Nu Nu Yi) Manager

The migration is about by the Company sorter to Control Complians of Service administration of English programme and Company of Company of Service Ser

The Company's one properties is to be Class and the Assessment of Company of the Sea of the company of the sea of the sea of the company of t

REPORTED FIRST, TO REPORT TO COMMITTED WARREL OF COMPAY THAT DEPORTS INTO COMPANY OF THE PERFORMANCE OF COMPANY OF THE PERFORMANCE OF THE PERFORMA

Salar High

Agricultural Services 76/60, fiships Hausen borostor, Warden Stret Hamming Tree Yangot, Majamin T #86/1/191662 [1908], 201608, 271641 T #86/1/81/549, 271648 in agricultural diagrams.

Burnishers sought (II)



ORIGINAL

Job Ref; 6218/2015 Unite : 20,10,2015 Page 1 of 1

Sample Described as :

SURFACE WATER (6.10.15) EIA STUDY FOR PHASE II

AREA DEVELOPMENT IN THILAWA SEZ RESOURCE & ENVIRONMENT MYANNAFI

Client Name Sample Received Date :

8.10.2016

Sample Brought By

Chent

Sample Reference

SW-4 (THILAWA)

Analysed Date

Lab Code No.

9,10,2015

173/15

No	Test Parameter	Method	Lod	Result	Unit
1	Ol & Grease	Based on Standard methods for the examination of water 5 waste water APHA, AMWA 5 WEF ,22nd ed, 2012; 5520 B	0.2	40.2	mpl
2	Manganese	Based on Standard methods for the examination of water & waste water APHA AVAVA & WEE, 22nd ed. 2012; 31118 (Orect Air-Applytene Flame method)	0,1	<0.1	mal

End of Reportressessessesses

SGS (Myaningr) Limited

(Nu Nu YI) Manager

Wey took of the Geometria strategy for incomplete present religion to Company to large or the first of incommunities and with the control of the community of the first of the community of the c

ACACHTED STORM, IS ARTY IN TO SUSPENDED SAMPLE OF COUNTY OF A SAMPLE TO ARTY IN FOR INCIDENT TO ACAL THE TO ACAC THE TOTAL OF THE TOTAL

Agractical Sevens 79/00, Byses Houng Complex Verder Steet, Lornadon Top, Yangor, Myunta 4 +96(1701)562, 2(1537, 2(1538, 2(1557, 1 +96(12))1545, 2(1))45 a pp. ryyunin Sags com

Monthly of 925 firms 625 SAI



ANALYSIS REPORT

Job Ref: 6215/2015 Date : 20.10.2015 Page 7 of 1

Sample Described as : SURFACE WATER (6.10.15) EIA STUDY FOR PHASE II

AREA DEVELOPMENT IN THILAWA SEZ

Client Name RESOURCE & ENVIRONMENT MYANMAR Sample Received Date : 8.10.2015

Sample Brought By : Client

Sample Reference : SW - 5 (THILAWA)

Analysed Date 9.10.2016 Lab Gode No. 174/15

No	Test Parameter	Method	Lod	Result	Unit
j	Oli & Grease	Based on Standard multipoits for the examination of water & waste water APHA AVWA & WEF 22nd ed, 2012; 5520 B	0.2	8	mgil
2	Manganese	Based on Standard methods for the event/nation of water & weete wells APHA ANYVA & IVEF,22nd ed, 2012; 31118 (Direct Air-Acetylene Flams method)	0.1	×0.1	mgd

End of Report Ministration

aged

SOS (Myermar) Limited

(Nu Nu Yi) Manager

The former is about by the Continue of the Continue of General Property of the Continue of the

The Concess are reported in the contest of the cont

SERVITOR BETTER TO DEPORT THE BENEFIT BY AND THE REPORT IN THE CONTROL OF THE PROPERTY AT THE A SERVICE THE WINDOW, AND TO SERVICE AND THE WINDOW, AND THE PROPERTY AND THE PROP

Semilime!

Aprilatival Severa (1986) Below Harring Complex Warren Steel, Lorentzer (op., longer, Mystere) 1 (48)(1971) 82 (1983), (1984),

Married SECONSTRUCTION

Surface Water Quality Survey - Dry Season-

: 2016-00182 / 001 (Page 1 of 1)

issued date. March 3, 2016

CLIENT CONTACT ADDRESS

RESOURCE AND ENVIRONMENT MYANMAR CO., LTD. Ms. Tos Tos Harry 8702 Della Pieza, Sirwegondaing Rd., Bahan, Yangari, Myanmie

Tel +959-73013448 Fax +951-552901

E-msli teetouhlainggeo@gmail.com

Analysis Report

EIA Study for Phase II Area Development in Thilawa SEZ

SAMPLE DESIGNATED AS : Surface Water Quality SAMPLING LOCATION Telawa, Myanmar

SAMPLING DATE February 2, 2016

SAMPLING BY Chent

B Constitution of	Contract Con	100		Results		
Parameters Dator	Units	LOG	SW-I	SW-2	SW-3	
Dato	Pt.Qu	1.	41	6.	2	
Odor	-	-	filetary).	Natural	Natural	
Phores.	mg/r	0.001	<0.001	46.001	=0.001	
Pustologyte	regs	0.01	<0.01	10.01	10.01	
Free Chance (Ct.)	mgi	0,01	5,63	U.03	0.00	
Austriic (As)	mg/l	0.002	<0.002	<0.000	<0.002	
Sarian Chai	mor	0.4	+0.1	40.1	10.7	
Total Chromium (Cr)	Ng/	0.02	<0.02	< 0.02	~0.02	
Cintrium (Od)	mo/	0.0020	<0.0000	<0.0020	< 0.0020	
Lead (Pb)	mpi	0.040	+0.010	<0.010	40.010	
SYCKEL(NI)	mp1	D.010	<0.040	<0.010	40.010	
Mercury (Hg)	rigil	0.0005	<0.0000	40.0005	<0.0000	
Selonium (Se)	mg/f	0.01	<0.01	≠0.01	<0,01	
Total Conform Bacteria	MPNITIONA	-	1.100	490	130	
Name-Nanguri (NO ₂ N)	1993	0.02	1.59	-010	0.58	
Flueride (F)	ng/l	0.06	0,63	0.49	0.66	
Gyaniak (CN)	1987	B 004	0.009	40.004	×0.004	
Ammonia-Nitrogen (NH-N)	mp/	0.02	0.248	0.230	0.282	
Namgen-Nitrite (as N)	197	0.02	<0.02	0.17	<0.02	
Sulfide (S)	Tgre	p.ot	-0.01	*D.D1	+0.01	
Tintal Chronine.	mg/	0.91	0.05	0.07	0.30	

Remarks: -

Analysis Mathods followed the Sciencest Methods for the Exemplan of Water and Westernator entirement by American Public Health Association (APHA), American Water Works Association (AWWA) and Water Environment Fisteration (WEF) except .

• Oddy Missert SQ 8388-1867.

• Formalishings followed Water and Waterswaller Analysis endorsed by Environmental Engineering.

Association of Thatland (EEAT)

• Mercury (Right blowed U.S. EPA method 348.1, LOG = Limit of Quarritation

(Sinpam Inswitasian)

Environmental Monitoring Manager

Thupson Yomma

Technical Managur

TY/ClienWC/CI

SGS (THAILAND) LIMITED

114665

Transport and analysis of



ANALYSIS REPORT

Job Ref: 0626/2016 Date: 25.02.2016 Page 1 of 2

Client Nama

RESOURCE AND ENVIRONMENT MYANMAR CO., LTD.

B-702 Delta Plaza, Shwegondaing Rd, Bahan Township,

Yangon, Myanmar

Project Name

EIA Study for Phase II Area Development in Thilawa SEZ

Sample Brought By Sample Location Sample Received Date

Client Thilawa 11.02.2016

Analysed Date

11.02.2016

Distribe broth	24/16/2				
Results (mg/l)	Methods	SW-1 (2.2.2016)	SW-2 (2.2.2016)	SW-3 (2.2.2016)	Detection Limit
Lab Code		015/16	016/16	017/16	- 100
Commodity Name		Surface Water	Surface Water	Surface	
Total Suspended Solid	Based on Standard methods for the examination of water & weste water APHA . AWWA & WEF, 22nd ed, 2012; 2540 D		488.67	235.5	20
Oil & Grease	Based on Standard methods for the examination of water 8 waste water APHA AWWA 8 WEF ,22nd ed, 2012; 5520 B	<5	6.1	< 5	5
Total Nitrogen (organic)	Based on Standard methods for the examination of water & waste water APHA , AWWA & WEF 22nd ed, 2012; 4500-New C	1.4	1.12	ধা	1
Total Hardness(asCaCO ₃) AOAC 18 Ed (2005) Rev 4, 2011 (method no973.52)		1275	668.84	1410	5
Total Phosphorus	Laboratory Manual For the Physico- Chemical Analysis of Soil, Waser and Plant; Phototmetric (Ascorbic) Method	0.023	0.047	0.045	0.01



community. This believes to be became in process density and process density in process of any goods and supply make to provide by the Cherticr by a third party acting at the Cherticr by acting at the Chertic

503 (Avenue 1 Traille) Agricultural Services 79/80, Salars Housing Complex, Warden Street, Lamnadaw Top, Yangon, Myaniner 1 +95(1)211562, 211502, 211508, 211507, 1 +95(1)211569, 217049 a. pgs.myaninan@ags.com

Meaning of 905 House 518 51)



Job Ref: 0626/2016 Date: 25.02.2016 Page 2 of 2

		r=====	· ndin	4.01	e e
	and the second				
Results (mg/l)	Methods	SW-1 (2.2.2016)	SW-2 (2.2.2016)	SW-3 (2.2.2016)	Detection Limit
Lab Code	- 4	1315/16	016/16	017/18	- 3
Commodity Name		Surface Water	Surface Water	Surface Water	-
BOD	In-house method based on Standard methods for the examination of water & waste water, APHA , AWWA & WEF,22nd ed, 2012 ;5210 D (Respirometric) and manual of BOD System Ox direct (Lovbond)	3	a	9	2
In-house method based on Standard methods for the examination of water & waste water APHA . AWWA & WEF, 22nd ed, 2012; 5220 D(Closed Reflux ,Colorimetric) and manual of Photometer-system MD 100 and RD 125 Reactor(Lovibond)		1380	810	1280	10
fron	Based on Standard methods for the examination of water & waste water APHA AWWA & WEF.22nd ed, 2012; 31118 (Direct Air- Acetylane Flame method)	6.920	8,243	1.401	0.1
Copper	Based on Standard methods for the		<0.1	<0.1	0,1
Zinc	Based on Standard methods for the examination of water & waste water APHA AWWA & WEF,22nd ed, 2012 : 31118 (Direct Air- Apotylene Flame method)	<0,1	<0.1	<0.1	0.1
Manganese	Based on Standard methods for the examination of water & waste water APHA AVWA & WEF 22nd ed, 2012 ; 31118 (Direct Air- Acctylene Flame method)	0.144	0.178	<0.1	0,1

eci Air- Acetylene Flame meinog/

SGS (Myarmar) Limited

(Nu Nu YI) Manager

Will No. The sample of the first parameters where Endings' paids and percent stay of a previously see Claim or by a tree gaint attained for the first parameters of any processor of the parameters of the sample of

(FES Myannon) Finished Agricultural Services 79/90, Bahasi Minesing Complex, Warden Street, Lanhadaw Tep, Yangan, Myannot 1 +95(1)(2) 1552, 217537, 217538, 217547, of +95(1)(2) 1562, 217647 of sgr. sayerman@agr.com

Monutor of SSS Group(SSS SA)



ANALYSIS REPORT

Job Ref: 6810/2015 Date : 23.12.2015 Page 1 of 1

Client Name

RESOURCE AND ENVIRONMENT MYANMAR CO., LTD.

B-702 Delta Plaza, Stwegondaing Rd. Bahan Township.

Yangon, Myanmar

Project Name

EIA Study for Phase II Area Development in Thilawa SEZ

Sample Brought By Sample Location Sample Received Date Analysed Date

Thilarea 16.12.2016 17.12.2015

Client

	-	1000	Results	(mg/l)
Stations	Commodity Name	Lab Code	Manganese	Oil & Grease
Method	51	-	Based on Standard methods for the examination of water & waste water APHA ,AWWA & WEF,22nd ed, 2012; 31118 (Direct Air-Acetylene Flame method)	Based on Standard methods for the examination of water 8 waste water APNA ,AWWA 6 WEF ,22nd ed, 2012 ; 5520 8
SW-1	Surface Water	260/15	1.373	<0.2
9W-2	Surface Water	261/15	0.558	5.2
SW-3	Surface Water	262/15	40.1	0.9
SW-≤	Surface Water	263/15	0.481	5,4
SW-5	Surface Water	264/15	1,099	1.0
	Datection Limit		0.1	02

End Of Report

5GS (Myanmag) Limited

(Nu Nu Yi)

Withhird, The empirical or which the feedings specified people of planting is seen and the provided by the Client or by a fixed perty strong sit to Clients. The Findings constitutes the service is sentent in provided by the Client or by a fixed perty strong sit to Clients. The Findings constitutes the sentent is represented this document is meand by the Company upons in Company, isotated by the Company. Society of Lecture, you consider the sentent of the findings of sections of the Company is the Findings of the Company is the Clients of the Clients of the Company is the Clients of th

Apruata of Services, 70/00, Balton Housing Conspice, Worston Street, Landackov (pt., Vangas, Myummar 4 (05)10211562, 211607, 211507, 211507, 4 (05)1(2)1549, 217509 e ego pyromat Cope com

Manager of Wife Sprooffeld Salt

Ground Water Quality Survey - Rainy Season-



: 2015-01367 / 001 (Page 1 of 1) Issued date : November 4, 2015

CLIENT : RESOURCE AND ENVIRONMENT MYANMAR CO., LTD.

CONTACT ADDRESS

Ms. Too Toe Hising 8702 Delta Plaza, Shwegondaing Rd., Bahan, Yangan, Myanmer Tel. +939-73013448 Fax. +951-552901

E-mail: toetochlainggeo@gmail.com

Analysis Report

PROJECT NAME : EIA Study for Phase II Area Development in Thilawa SEZ.

SAMPLE DESIGNATED AS : Groundwater Quality SAMPLING DATE : October 8, 2015

SAMPLING LOCATION : Thilawa, Yango, Myanmar SAMPLING BY : Client

Parameters	Unite	LOG -	Res	ruits
, es enteres	- City	100	GW-1	GW-2
Oder	F. J. C. T.		None	None
Color	Pt.Co	.t	<1	<1
Biochemical Oxygen Demand (BOD.)	mg/l	2	<2	<2
Chemical Oxygen Demend (COD).	mpl	10	<10	- 11
Ammonium-Ntrogen (NHeN)	mg/l	100	0.13	0.24
Nitrito-Nitrogen (ND)-N)	mg/l	0.02	0.76	<0.02
Nitrate-Nitrogen (NO ₃ -N)	mg/l	0.02	16.07	14.96
Cyanida (CN)	mg/l	10	<10	*16
Arsenic (As)	ingel .	0.001	<0.001	<0.001
Cadmum (Gd)	mg4	0.001	<0.001	<0.001
Chromium Hexavalera (Cr ^(*))	mg#	0.02	<0.02	< 0.02
Fluendo (F)	mg/l	0.05	0.56	0.25
Lead (Fb)	mgs	0.006	<0.006	<0.006
Moroury (Hg)	mgh	0,0005	<0.0005	<0.0005
Mickel (Ni)	mgfl	0.002	<0.002	<0.032
Total Cottorm Bacteria	MPN*100mL		>23	>23

Analysis Methods followed the Standard Methods for the Examination of Water and Wastewater endursed by American Public Health Association (APHA), American Water Works Association (AWWA) and Water Environment Federation (WEF) except Mercury (Hg) followed U.S. EPA method 245.1. Ammonium Narogon (NH₂-N) is from calculation and the field data (pH and Temperature) for the calculation

was measured by client. LOQ = Limit of Quantitation

Environmental Monitoring Manager

Technical Manager

TY/Client/PPT/C

WARMING: The semple in owner the immigrate code in the other than in a time body school at the Charles street in the America consisting to seem in the last of the Sample in the Sample The National Human and I or provided by the Charmon by the nample representativeness of and goods and shickly double from which the sample(a) is are said to be exhibited

SGS (THAILAND) DINTED

The same apply and the second second

ne for it in my (which makes the Copyr) when the form the most of the control of

£ 105440

(1775 fin World, 1879 at | Engineermental Sancias 100 Margington Road Chargininae Yeniswo Bargkok (0120) 1 +85 (007 67 8 18 13 1 +65 (0)2 678 (05 22 www.sgs.com

Memberal mestile about



ORIGINAL

Job Ref: 6216/2015 Date : 20.10,2015 Page 1 of 1

Sample Described as :

GROUND WATER (5.10.15) EIA STUDY FOR PHASE II

AREA DEVELOPMENT IN THILAWA SEZ

Client Name

RESOURCE & ENVIRONMENT MYANMAR

Sample Received Date :

8,10,2015 Client

Sample Brought By Sample Reference

GW - 1 (THILAWA)

Analysed Date

9.10.2015

Lab Code No.

17515

No	Test Parameter	Mothod	Lod	Result	Unit
1	Total Suspended Solid	Based on Standard methods for the examination of water & waste water APHA ,AWWA & WEF.22nd ed, 2012; 2540 D	30	97	mg/
2	Oil & Grease	Based on Standard methods for the examination of water & waste water APHA ,AWWA & WEF 22nd ed, 2012 ; 5520 B	0.2	<0.2	mg/
3.	Total Nitrogen (organic)	Based on Standard methods for the examination of water & waste water APHA ,AWWA & WEF,22nd ed; 2012; 4500-Nos C	0,6	<0.6	mgf
4.	Laboratory Manual For the Physico-Chemical		0.01	0.03	mg/
5.	Total Hardness (asCeCo ₂)	AOAC 18 Ed (2006) Rev 4, 2011(method no973 52)	2	972.4	mg/
6	Based on Standard methods for the examination of water & wasts water APHA AWWA & WEF, 22nd ed, 2012; 31118 (Direct Air- Acetylens Flame method)		0.1	<0.1	mg/
7	Соррег	Based on Standard methods for the examination of water & waste water APHA ,AWWA & WEF 22nd ed, 2012 ; 311 18 (Direct Air- Acetylane Flame method)	0.1	<0.1	mg/
8	Zinc Based on Standard methods for the examination of water & waste water APHA ,AWWA & WEF,22nd ed. 2012; 31118 (Direct Air- Acetylan Flame method)		0.1	<0.1	mg/
9	Manganese	Based on Standard methods for the examination of water & waste water APHA ,AWWA & WEF,22nd ed, 2012; 31118 (Direct Air- Apetylene Flame method)	0.1	5.7	mg/

SGS (Myanmar) Limited

Princepartner is leaded by the Chimosop under 16 General Condition of Setting accounting a) into Avenue approximate lists, described in the Chimosophic Armster in the Condition of the Chimosophic and Armster in the Chimosophic and Chimoso (Nu Nu YI)

Manager

Yes, the Congress of the submert of the Congress of t

MEANING RESULTS REPORT OF COMMITTED SAMPLE (SO ONLY THIS REPORT ENAMED NOT BE RESPONDED RESIDES IN YOUR, NOT RESULT IN ADDRESS, AND COUNTY CARRIES OF CONTROL AND CONTROL OF COUNTY CARRIES OF C

Agricultural Services 78/80 Balosi Housing Complex, Worden Ster., Lanceston Ten, Yeogon, Myenmar 1 495(1)(11:662, 21:53), 71:538, 71:547, 1 495(17)(15/8, 27)(48, 9.00)

Annexes of SES Energists SS



ORIGINAL

Job Ref: 6216/2015 Date: 20.10.2015 Page 1 of 1

Sample Described as :

GROUND WATER (6.10.15) EIA STUDY FOR PHASE II

AREA DEVELOPMENT IN THILAWA SEZ

Client Name

RESOURCE & ENVIRONMENT MYANMAR.

Sample Received Date Sample Brought By

8.10.2015 Client

Sample Reference

GW-2 (THILAWA)

Analysed Date

9,10,2015

Leb Code No. 176/15

No	Test Parameter	Method	Lod	Result	Unit
t.	Total Suspended Solid			119	mg/l
2	Oil & Grease	Based on Standard methods for the examination of water & waste water APHA ,AWWA & WEF ,22nd ed, 2012 ; 5520 B	0.2	<0.2	mg/l
3.	Total Nitrogen (organic)	Pased on Standard methods for the examination of water & waste water APHA ,AWWA & WEF,22nd ed, 2012; 4500-Nan C	0.6	<0.6	mg/l
4.	Phosphorus	Laboratory Manual For the Physico-Chemical Analysis of Soil, Water and Plant : Phototmetric (Ascorbic) Method	0.01	0.39	mg/l
5.	Total Hardness (asCaCo ₂)	AOAC 18 Ed (2005) Rev 4, 2011(method no973,52)	2	350.4	mg/r
В	kon	Based on Standard methods for the examination		0.186	mg/l
7	Copper	Based on Standard methods for the examination		<0.1	mg/l
H	Zinc	Besed on Standard methods for the examination of water & waste water APHA AWWA & WEF.22nd ed, 2012; 3111B (Direct Air- Agetylene Flame method)	0,1	<0.1	mg/l
0	Manganese	Based on Standard methods for the examination of water & waste water APHA_AVVVA & WEF,22nd ed, 2012; 31118 (Direct Ar-Acetylene Flame method)	0,1	0.226	mg/l

End of Report*

SOS (Myenmas) Limited

This constructs instead by the Company within the General Conditions of Service accessible of this Service and conditions lifty. Assertion is instructed to the Condition and conditions are accessed from No. 171). Manages

With notice of the document is advised that informating contained his notice of the Congress of the time of the information only and behind the initial and cold and the Congress of the rings of the time of the information from exercising all their rights and ophysically under the united by a time in given and ophysically under the united of the rights of the Congress of the Congr

REPORTED PLOURING HERE TO COMMITTED CHARMED (b) DISC THIS REPORT SHALL, WIT HE REPORT CHARMED EXCEPT ON FIRE. WITHOUT THIS WISTIAN APPRICALL OF CONFERENCE OF THE PROPERTY OF

565 Myonoul House

Agricultural Saryces 79/80, Bahosi Holosing Complex, Wardan Stres Landrative Sey, Yangru, Mysturan 1 499/1/201562, 211537, 211538, 211547, f 495/11/201549, 217042, a sgs. hyanmar@sgs.com

Ground Water Quality Survey - Dry Season-



ORIGINAL

ANALYSIS REPORT

Job Ref: 0626/2016 Date: 25.02.2016 Page 1 of 2

Client Name

RESOURCE AND ENVIRONMENT MYANMAR CO., LTD

B-702 Delta Plaza, Shwegondaing Rd. Bahan Township

Yangon, Myanmar

Project Name

EIA Study for Phase II Area Development in Thilawa SEZ

Sample Brought By : Client
Sample Location : Thilawa
Sample Received Date : 11.02.2016
Analysed Date : 11.02.2016

Results (mg/l)	2000		Particular.		
	Methods	SW-1 (2.2.2016)	SW-2 (2.2.2016)	SW-3 (2.2.2016)	Detection
Lab Code	The state of the s	015/16	016/15	017/15	3.0
Commodity Name		Surface Water	Surface Water	Surface	-
Total Suspended Solid	Based on Standard methods for the examination of water & waste water APHA , AWWA & WEF,22nd ed, 2012; 2540 D		488.67	235.5	20
Oll & Grease	Based on Standard methods for the examination of water & waste water APHA AWWA & WEF 22nd ed, 2012; 5520 B	<5	8,1	<5	5
Total Nitrogen (organic)	Based on Standard methods for the examination of water & waste water APHA , AWWA & WEF 22nd ed, 2012; 4500-Neg C	1.4	1.12	41	-1
Total Hardness(asCaCO ₃)	Total		668,84	1410	5
Total Phosphorus Leboratory Manual For the Physico- Chemical Analysis of Soil, Water and Plan Phototmetric (Ascorbic) Method		0.023	0.047	0.045	0.01



WARNING: The sequency is which the Endings seconded notes (are "Proteign") would end proposed and array relate in the employs. The Congress second array is a related to the end of the congress of the end of the congress of the end of the congress of the end of the e

SEE (Marrier) United

Agricultural Services 79/80, Bahasi Housing Complex, Waidon Street, Lammacow Top, Yangor, Myanimar 1 +95(1):211562, 211537, 211538, 211547, 1 +95(1):211598, 217(4):9 is sps.myaninan@ags.com

Marker of 983 (mag 988.57)





Job Ref: 0626/2016 Date : 25.02.2016 Page 2 of 2

		Page 2 of 2					
375 776	5.573	In the same	Stations				
Results (mg/l)	Methods	SW-1 (2.2.2016)	SW-2 (2.2.2016)	SW-3 (2,2,2016)	Detection Limit		
Lab Code	3	015/15	016/16	017/16	- 4		
Commodity Name		Surface Water	Surface Water	Surface Water	a		
BCD	In-house method based on Standard methods for the examination of water & waste water, APHA , AWWA & WEF,22nd ed, 2012 :5210 D (Respiremetric) and manual of BOD System Ox direct (Lovibond)	3	đ	9	2		
COD	In-house method based on Standard methods for the examination of water &		ato	1280	10		
Iron	Based on Standard methods for the examination of water & waste water APHA ,AWWA & WEF 22nd ed, 2012 ; 3111B (Direct Air- Acetylene Flame method)	5 920	8.243	1,401	0.1		
Copper	Based on Standard methods for the examination of water & waste water AFHA AWWA & WEF 22nd ed. 2012 ; 3111B (Direct Air- Acatylene Flame method)	<0.1	<0.1	<0.1	0.1		
Zinc	Based on Standard methods for the examination of water & waste water APHA AWWA & WEF, 22nd ed, 2012; 31118 (Direct Air- Acctylene Flame method)	⊲0.1	<0.1	<0.1	0.1		
Manganase	Based on Standard methods for the examination of water & wasts water APHA AWWA & WEF 22nd ed, 2012 , 3111B (Direct Air- Acetylene Flame method)	0.144	0.178	<0.1	0.1		

SGS (Myanmar) Limited

(Nu Nu Yi) Manager

WARRENG. The complete is which the findings perceive homeous the "Endoge", retain as all processes of the complete of the comp

S6- Minimum Dimited Agricultural Services 76/80, Refers Boysing Complex, Warden Street, Laurendew Top, Yangsu, Myanesar J. +96(8)21/562, 211562, 211562, 211567, 4 +95(1)211565, 217649, e.agr. myanesidzegi, cam

Microscraf SGS Group (GDS SA)

Soil Quality Survey (Geology Department of Yangon Univ.)

APPLIED GEOLOGY DEPARTMNENT, GEOCHEMISTRY LABORATORY

Sample Type — Soil Method — Atom - Atomic Absorption Spectrophotometer

Digestion - Aqua-regia

Project – EIA Study for Phase II Area Development in Thilawa SEZ. Resource and Environment Myanmar Co.,Ltd. Sampling Date – 14-12-2015

Unit - mg/kg

Sample No	Mercury (Hg)	Arsenic (As)	Lead (Pb)	Cadmium (Cd)	(Cu)	Zinc (Zn)	Chromium (Cr)	Iron (Fe)	Manganese (Mn)
50-1	ND	ND	85	0.007	.60	75	12	5210	10
50-2	ND	ND	100	0.006	65	70	- 10	5400	- 8
SO-3	ND	ND	87	0.006	68	80	8	4900	12
SO-4	ND	ND	90)	0.005	72	78	- 11	4750	9

Associate Professor Applied Geology Department

Annex 6-2

Flora and Fauna List of Thilawa SEZ Zone B Area

Annex 6-2 Flora and Fauna List of Thilawa SEZ Zone B Area

Table 6-2-1 Recorded Flora of Thilawa SEZ Zone B Area

No.	Scientific Name	Local Name	Family	Habitat	Distribution	IUCN (2015-4 ver.3.1)
1	Abelmoschus esculentus	Yonbade	Malvaceae	Shrub	Cultivated	NE
2	Acacia auriculiformis	Malaysia-padauk	Mimosaceae	Small Tree	Cultivated	LC
3	Acacia concinna	Kinmon	Mimosaceae	Shrub	Cultivated	NE
4	Acacia concinna	Kinmun-gyin	Mimosaceae	Shrub	Cultivated	NE
5	Acacia inopinata	Sha-hta-naung	Mimosaceae	Tree	Mandalay, Shan	NE
6	Acacia pennata	Suyit	Mimosaceae	Climber/ Climber	Reported from Myanmar	LC
7	Acanthus ilicifolius	Khaya	Acanthaceae	Shurb	Ayeyarwady, Rakhine, Taninthayi, Yangon	LC
8	Achyranthes aspera	Kyet-mauk-sue-pyan	Amaranthaceae	Herb	Magway, Yangon	NE
9	Albizia falcata	Thinbaw-magyi	Mimosaceae	Tree	Cultivated	NE
10	Albizia lebbek	Kokko	Mimosaceae	Tree	Reported from Myanmar	NE
11	Albizia procera	Sit	Mimosaceae	Tree	Reported from Myanmar	NE
12	Althaea rosea	Pan-chinbaung	Malvaceae	Shrub	Cultivated	NE
13	Alysicarpus vaginalis	Than-ma-naing-kyau k-ma-naing	Fabaceae	Shrub	Bago, Mandalay, Mon, Sagaing, Shan, Yangon	NE
14	Amaranthus bitoides	Hin-nu-new	Amaranthaceae	Herb	Cultivated	NE
15	Amaranthus caudatus	Kyet-mauk	Amaranthaceae	Herb	Cultivated	NE
16	Amaranthus spinosus	Hin-nu-new-subauk	Amaranthaceae	Herb	Cultivated	NE
17	Anacardium occidentale	Thiho	Anacardiaceae	Tree	Cultivated	NE
18	Annona squamosa	Awza	Annonaceae	Small Tree	Cultivated	NE
19	Areca catechu	Kunthi-pin	Arecaceae	Small Tree	Cultivated	NE
20	Artocarpus heterophyllus	Peinne	Moraceae	Tree	Cultivated	NE
21	Azadirachta indica	Tama	Meliaceae	Tree	Wide	NE
22	Bambusa bambos	Kyakat-wa	Poaceae	Bamboo	Reported from Myanmar	NE
23	Bambusa burmanica	Waya	Poaceae	Bamboo	Bago, Kachin, Magway, Mandalay, Mon, Sagaing, Shan, Taninthayi	NE
24	Bambusa wamin	Wamin	Poaceae	Bamboo	Cultivated	NE
25	Bauhinia acuminata	Swe-daw	Caesalpinaceae	Small Tree	Wide	LC
26	Benincasa hispida	Kyauk-pha-yon	Cucurbitaceae	Cl/Cr	Cultivated	NE
27	Bombax ceiba	Let-pan	Bombacaceae	Tree	Wide	NE
28	Borassus flabellifer L.	Htan	Areaceae	Tree	Bago, Mandalay, Sagaing, Taninthayi	NE
29	Butea frondosa	Kyi-ah	Fabaceae	Tree	Reported from Myanmar	NE
30	Butea frondosa	Pauk	Fabaceae	Tree	Reported from Myanmar	NE
31	Canna indica	Budatharana	Cannaceae	Herb	Cultivated	NE
32	Capparis spinosa	Kywe-hna-kaung-gy eik	Capparaceae	Small Tree	-	NE

No.	Scientific Name	Local Name	Family	Habitat	Distribution	IUCN (2015-4 ver.3.1)
33	Capparis spinosa	Kywel-na-khaung	Capparaceae	Shrub	Mandalay	NE
34	Capsicum annuum	Ngayote	Solanaceae	Shrub	Cultivated	NE
35	Caraya arborea	Bambwe	Lecythidaceae	Tree	Wide	NE
36	Cassia fistula	Ngu	Caesalpinaceae	Tree	Wide	NE
37	Cassia occidentalis	Dangwe	Caesalpinaceae	Shrub	Wide	NE
38	Ceiba pentandra	Moh-pin	Bombacaceae	Tree	Cultivated	NE
39	Cerbera manghas	Zalat	Apocynaceae	Small tree	Ayeyarwady, Bago, Rakhine, Taninthayi, Yangon	NE
40	Chionanthus macrocarpus	Taw-sabe	Oleaceae	Shrub	Kachin, Mon, Taninthayi, Yangon	NE
41	Chromolaena odorata	Bezat	Asteraceae	Shrub	Wide	NE
42	Chukrasia velutina	Yinma	Meliaceae	Tree	Wide	NE
43	Citrus medica	Shauk	Rutaceae	Shrub/	Cultivated	NE
44	Clausena excavata	Taw pyindawthein	Rutaceae	Grass	Bago, Kachin, Mandalay, Shan, Tanintharyi, Yangon	LC
45	Clerodendrum villosum	Ka-on	Verbenaceae	Herb	Wide	NE
46	Clitoria mariana	Taw-peik-san	Fabaceae	Climber/ Creeper	Kachin, Magway, Mandalay, Yangon	NE
47	Cnestis ramflora	Gwe-dauk	Connaraceae	Shrub	Ayeyarway, Mon, Taninthayi, Yangon	NE
48	Cocos nucifera L.	Ohn	Arecaceae	Tree	Cultivated	NE
49	Codiaeum variegatum	Ywet-hla	Euphorbiaceae	Shrub	Cultivated	NE
50	Colocasia esculenta	Pein	Araceae	Herb	Cultivated	LC
51	Commelina diffusa	Myat kyut	Commelinaceae	Herb	Bago, Kachin, Mandalay, Shan, Yangon	LC
52	Costus speciosus	Phalan taung hmwe	Costaceae	Herb	Yangon, Sagaing, Mandalay, Bago, Shan, Kachin	NE
53	Croton oblongifolius	Thetyin-gyi	Euphorbiaceae	Shrub	Wide	NE
54	Cynodon dactylon	Myesa-myet	Poaceae	Shrub, Climber	Wide	NE
55	Delonix rigia	Sein-ban	Caesalpinaceae	Tree	Cultivated	NE
56	Dendrocalamus brandisii	Wabo	Poaceae	Bamboo	Bago, Chin, Kachin, Mandalay, Shan, Yangon, Yangon	NE
57	Dendrocalamus strictus	Hmyin-wa	Poaceae	Bamboo	Bago, Kachin, Kayin, Mon,	NE
58	Desmodium triflorum	Pe yaing	Fabaceae	Herb	Wide	LC
59	Dichanthium caricosum	Myet-kha	Poaceae	Grass	Bago, Magway, Mandalay, Yangon	NE
60	Dichanthium caricosum	Ta-myet-si	Poaceae	Grass	Bago, Magway, Mandalay, Yangon	NE
61	Dioscorea wallichii	Ka-dat	Dioscoreaceae	Climber/ Creeper	Rakhine, Yangon	LC
62	Dregea volubilis	Gwe-dauk-nwe	Asclepiadaceae	Cl/Cr	Wide	NE
63	Dypsis lutescens	Kyein-htan	Arecaceae	Tree	Bago, Rakhine, Yangon	NE
64	Eclipta alba	Kyeik-hman	Asteraceae	Herb	Reported from Myanmar	DD
65	Eleusine indica	Sin-ngo-myet	Poaceae	Grass	Bago, Kachin, Mandalay, Shan, Tanintharyi, Yangon	LC
66	Enhydra fluctuans	Kana-hpaw	Asteraceae	Herb	Yangon, Mandalay, Taninthayi	NE
67	Eryngium foetidum	Shan-nan-nan	Apiaceae	Herb	Chin, Mandalay	NE

No.	Scientific Name	Local Name	Family	Habitat	Distribution	IUCN (2015-4 ver.3.1)
68	Erythrina arborescens	Kathis	Fabaceae	Tree	Kachin, Sagaing	NE
69	Eucalyptus camaldulensis	Eucalypt	Myrtaceae	Tree	Cultivated	NE
70	Eucalyptus torelliana	Pyi-lon-chantha	Myrtaceae	Tree	Cultivated	NE
71	Eugenia bracteolata	Tha-bye	Myrtaceae	Tree	Rakhine, Taninthayi	NE
72	Euphorbia milii	Kiss-me-quick	Euphorbiaceae	Shrub	Cultivated	DD
73	Euphorbia neriifolia	Ta-zaung	Euphorbiaceae	Small tree	Cultivated	NE
74	Ficus glomerata	Ye-thapan	Moraceae	Tree	Bago, Kachin, Mandalay, Yangon	NE
75	Ficus religiosa	Bawdi-nyaung	Moraceae	Tree	Cultivated	NE
76	Ficus rumphii	Nyaung	Moraceae	Tree	Bago, Yangon, Rakhine	NE
77	Flueggea leucopyrus	Chinya-phyu	Euphorbiaceae	Shrub	Kachin, Sagaing, Shan	NE
78	Fuirena ciliaris	-	Cyperaceae	Grass	-	LC
79	Garcinia cowa	Taung-thale	Hypericaceae	Tree	Wide	NE
80	Gardenia jasminoides	Zizawa	Rubiaceae	Shrub	Cultivated	NE
81	Gardenia sessiliflora	Magyi-bauk	Rubiaceae	Small Tree	Wide	NE
82	Gigantochloa wanet	Wa-net	Poaceae	Bamboo	Kachin, Sagaing	NE
83	Glochdion fagifolium	Htamasok gyi	Euphorbiaceae	Small Tree	Bago, Tanintharyi	NE
84	Glochidion glaucifolium	Htamasok	Euphorbiaceae	Herb	Yangon, Sagaing, Mandalay, Bago, Shan, Kachin	NE
85	Gnaphalium indium	Byaing-che	Asteraceae	Herb	Magway, Yangon	NE
86	Gossypium arboreum	Wah	Malvaceae	Shrub	Cultivated	NE
87	Hedychium gracile	Pade-gaw	Zingiberaceae	Herb	Mandalay	NE
88	Hibiscus cannabinus	Chin-baung	Malvaceae	Shrub	Cultivated	NE
89	Hibiscus panduriformis	Taw-yone-pa-di	Malvaceae	Shrub	Yangon	NE
90	Hygrophila phlomoides Nee	Migyaung-kunbat	Acanthaceae	Herb	Bago, Mandalay, Taninthayi, Yangon	NE
91	Hyptis suaveolens	Kala pin sein	Lamiaceae	Herb	Mandalay, Rakhine, Taninthayi, Yangon	NE
92	Ipomoea aquatica	Kazun-ywet	Convolvulaceae	Climber / Creeper	Wide	LC
93	Ixora coccinea	Pon-na-yeik	Rubiaceae	Shrub	Cultivated	NE
94	Jasminum arborescens	Sabe	Oleaceae	Shrub/	Magway, Mandalay, Yangon	NE
95	Justica decussata	Nat-pan	Acanthaceae	Shrub	Wide	NE
96	Kalanchoe pinnata	Ywet-kya-pin-pauk	Crassulaceae	Herb	Wide	NE
97	Lagenaria siceraria	Bu	Cucurbitaceae	Climber/ Creeper	Cultivated	NE
98	Lagerstroemia speciosa	Pyinma	Lythraceae	Tree	Reported from Myanmar	NE
99	Lannea coromandelica	Nabe	Anacardiaceae	Tree	Bago, Kayin, Mandalay, Rakhine, Shan, Taninthayi	NE
100	Lawsonia alba	Dan	Lythraceae	Shrub	Cultivated	NE
101	Leucaena leucocephala	Baw-sa-gaing	Mimosaceae	Tree	Mandalay,Sagaing,Yangon	NE
102	Leucas aspera	Taw-pin-sein	Lamiaceae	Shrub	Bago, Mandalay, Shan, Yangon	NE

No.	Scientific Name	Local Name	Family	Habitat	Distribution	IUCN (2015-4 ver.3.1)
103	Luffa acutangula	Kha-we	Cucurbitaceae	Climber/C reeper	Reported from Myanmar	NE
104	Luffa acutangula	Kha-we-yaing	Cucurbitaceae	Climber/C reeper	Reported from Myanmar	NE
105	Malvastrum coromandelianum	Taw-pilaw	Malvaceae	Herb	Kachin, Sagaing	NE
106	Mangifera indica	Tha-yet	Anacardiaceae	Tree	Wide	DD
107	Markhamia stipulata	Ma-hlwa	Bignoniaceae	Tree	Wide	NE
108	Melia azedarach	Pan-tama	Meliaceae	Small Tree	Cultivated	NE
109	Microcos paniculata	Mya-yar	Tiliaceae	Small Tree	Ayeyarwady, Bago, Yangon, Mandalay,Mon, Taninthayi	NE
110	Millettia pendula	Thinwin	Febaceae	Tree	Bago, Magway, Mandalay, Taninthayi, Yangon	NE
111	Mimosa pudica	Hti-ka-yone	Mimosaceae	Herb	Wide	LC
112	Mimosa rubicaulis	Biat-hti-ka-yone	Mimosaceae	Herb	Yangon	NE
113	Mitragyna parvifolia	Htein	Rubiaceae	Shrub/	Cultivated	NE
114	Momordica charantia	Kyet-hin-khar	Cucurbitaceae	Cl/Cr	Cultivated	NE
115	Morinda angustifolia	Yeyo	Rubiaceae	Small Tree	Wide	NE
116	Moringa oleifera	Dan-da-lun	Moringaceae	Tree	Cultivated	NE
117	Mucuna pruriens	Khwela-ya	Fabaceae	Climber	Bago, Chin, Kayin, Mandalay, Sagaing, Shan, Yangon	NE
118	Musa sapientum	Nget-pyaw	Musaceae	Herb	Cultivated	NE
119	Oreocnide frutescens	Myauk u	Urticaceae	Small Tree	Kachin, Mandalay, Shan, Unknown	NE
120	Oreocnide frutescens	Obok	Urticaceae	Small Tree	Kachin, Mandalay, Shan, Unknown	NE
121	Oroxylum indicum	Kyaung-sha	Bignoniceae	Tree	Wide	NE
122	Oxytenanthera albociliata	Wa-gauk	Poaceae	Bamboo	Reported from Myanmar	NE
123	Peltophorum pterocarpum	Thinbaw-mezali	Caesalpinaceae	Tree	Cultivated	NE
124	Phragmites vallatoria	Kyu	Poaceae	Grass	Reported from Myanmar	NE
125	Physalis minima	Bauk-pin	Solanaceae	Herb	Bago, Taninthayi, Yangon	NE
126	Piper betle	Betle	Piperaceae	Climber/ Creeper	Cultivated	NE
127	Polyalthia simiarum	Thabut	Annonaceae	Tree	Mandalay, Taninthayi, Yangon	NE
128	Psidium guajava	Malaka	Myrtaceae	Small Tree	Cultivated	NE
129	Pterocarpus macrocarpus	Padauk	Fabaceae	Tree	Bago, Mandalay, Sagaing, Shan, Taninthayi	NE
130	Pueraria sp	Taw-pe	Febaceae	Climber,C reeper	Bago, Mon	NE
131	Raphanus sativus	Monla-u	Brassicaceae	Herb	Cultivated	NE
132	Ricinus communis	Kyet-su	Euphorbiaceae	Small tree	Cultivated	NE
133	Saccharum sinense	Kyan	Poaceae	Grass	Yangon	NE
134	Sandoricum koetijabe	Thitto	Meliaceae	Tree	Ayeyarwady, Kayin, Mon, Taninthayi, Yangon	NE
135	Scoparia dulcis	Darna-thu-kha	Scorphulariaceae	Herb	Bago,Chin,Mandalay,Taninthayi,Ya ngon	NE
136	Senna siamea	Mazali	Caesalpinaceae	Tree	Reported from Myanmar	NE
137	Sesbania bispinosa	Nyan	Fabaceae	Shrub	Rakhine, Sagaing	LC

No.	Scientific Name	Local Name	Family	Habitat	Distribution	IUCN (2015-4 ver.3.1)
138	Sesbania grandiflora	Pauk pan phyu	Fabaceae	Small Tree	Cultivated	NE
139	Sida acuta	Wet-chay-pan	Malvaceae	Herb	Reported from Myanmar	NE
140	Solanum indicum L.	Khayan-kazaw	Solanaceae	Shrub	Bago, Mandalay, Shan, Yangon	NE
141	Solanum melongena	Khayan	Solanaceae	Shrub	Cultivated	NE
142	Sphaeranthus indicus	Mwe-sok	Asteraceae	Herb	Bago, Chin, Sagaing, Taninthayi, Yangon	LC
143	Spondias malayana	Gwe	Anacardiaceae	Tree	Reported from Myanmar	NE
144	Stemona tuberosa	Simi-tauk	Stemonaceae	Herb	Bago	NE
145	Streblus asper	Okhne	Moraceae	Small Tree	Bago, Sagaing, Tanintharyi, Unknown,	NE
146	Syzygium aromaticum	Lay-hnyin	Myrtaceae	Small Tree	Cultivated	NE
147	Syzygium fruticosum	Taw-thabye	Myrtaceae	Tree	Bago, Mon, Taninthayi	NE
148	Tabernaemontana divaricata	Taw-zalat	Apocynaceae	Shrub/	Cultivated	NE
149	Tamarindus indica	Magyi	Caesalpinaceae	Tree	Cultivated	NE
150	Tectona grandis	Kyun	Verbenaceae	Tree	Wide	NE
151	Terminalia catappa	Banda	Combretaceae	Tree	Cultivated	NE
152	Themeda triandra	Myauk-mi	Poaceae	Grass	Bago, Magway, Yangon	NE
153	Thyrsostachys siamensis	Htiyo-wa	Poaceae	Bamboo	Cultivated	NE
154	Urena lobata	Katsene	Malvaceae	Shrub	Bago, Chin, Mandalay, Taninthayi, Yangon	NE
155	Urena lobata	Wetchi-pane	Malvaceae	Shrub	Bago, Cnin, Mandalay, Taninthayi,	NE
156	Vigna catjang	Pedaung-she	Fabaceae	Climber/C reeper	Cultivated	NE
157	Ziziphus jujuba	Zee	Rhamnaceae	Tree	Cultivated	LC
158	Ziziphus oenoplia	Supauk-pin	Rhamnaceae	Shrub,	Wide	NE

Note: NE: Not Evaluated; DD: Data Deficient; LC: Least Concern; (IUCN category)

Source of Name : A checklist of the trees, shrubs, herbs and climber of Myanmar. W. John Kress, Robert A. DeFilipps, Ellen Farr and Daw Yin Kyi. Washington, DC: Smithsonian Institution. Contributions from the United States National Herbarium, Vol. 45. 2003. 590pp. ISSN 0097 1618.

Source of Data : EIA Study Team

Table 6-2-2 Recorded Butterfly Species of Thilawa SEZ Zone B Area

						Survey	period
No.	Scientific Name	Common name	Family	Habitat	IUCN (2015-4 ver.3.1)	Dry season December 2015	Rainy season October 2015
1	Anthene lycaenina	Pointed Ciliate Blue	Lycaenidae	bush	NE		
2	Appias lalage	Spot Puffin	Pieridae	tail	NE	√	
3	Appias libythea	Striped Albatross	Pieridae	bush	NE	√	
4	Appias lyncida	Chocolate Albatross	Pieridae	bush	NE	√	
5	Appias nero	Orange Albatross	Pieridae	trail	NE	√	
6	Ariadne ariadne	Angled Castor	Nymphalidae	shrub	NE	√	
7	Arnetta alkinsoni	Black-tufted Bob	Hesperiidae	trail	NE	√	

					HIGN	Survey	
No.	Scientific Name	Common name	Family	Habitat	IUCN (2015-4 ver.3.1)	Dry season December 2015	Rainy season October 2015
8	Athyma perius	Common Sergeant	Nymphalidae	trail	NE	√	$\sqrt{}$
9	Basarona sahadeva	Green Duke	Nymphalidae	trail	NE	V	
10	Castalius rosiman	common Pierrot	Lycaenidae	shrub, bush, trail	NE	√	$\sqrt{}$
11	Catopsilia florella	African Migrant	Pieridae	trail	NE	√	
12	Catopsilia pomona	Common Emigrant	Pieridae	on the trail	NE		\checkmark
13	Catopsilia puranthe	Mottled Emigrant	Pieridae	trail	NE	√	
14	Celastrina argiolus	Holy Blue	Lycaenidae	bush	NE		
15	Celastrina rona		Lycaenidae	on the trail	NE		√
16	Cepora nerissa	Common Gull	Pieridae	trail	NE	√	
17	Cethosia biblis	Red Lacewing	Nymphalidae	trail	NE	√	
18	Cethosia cyane	Leopard Lacewing	Nymphalidae	bush	NE	V	
19	Cethosia penthesilea	Orange Lacewing	Nymphalidae	on the shrub	NE		√
20	Chilasa clytia	Common Mime	Papilionidae	trail	NE	V	
21	Danaus affinis	Malay Tiger	Nymphalidae	bush	NE	V	
22	Danaus Chrysippus	Plain Tiger	Nymphalidae	bush	NE	V	$\sqrt{}$
23	Danaus genutia	Common Tiger	Nymphalidae	bush	NE	V	$\sqrt{}$
24	Danaus limniace		Danaidae		NE	V	
25	Delias agostina	Yellow Jezebel	Pieridae	trail	NE	V	
26	Delias decombi	Redspot Jezebel	Pieridae	on the trail	NE	V	
27	Delias descombi		Pieridae		NE		$\sqrt{}$
28	Delias eucharis	Common Jezebel	Pieridae	trail	NE	V	
29	Delias hyparete	Painted Jezebel	Pieridae	shrub	NE	V	
30	Delias hyparete		Pieridae		NE	V	
31	Dercas lycorias	Plain Sulphur	Pieridae	bush	NE	V	
32	Euploea dicletianus		Danaidae		NE		√
33	Euploea sylvester	Double-branded Crow	Nymphalidae	on the shrub	NE		V
34	Eurema ada		Pieridae	trail	NE	√	
35	Eurema andersoni	One-spot Grass Yellow	Pieridae	trail	LC	√	
36	Eurema blanda	Three-Spot Grass Yellow	Pieridae	trail	NE	V	V
37	Eurema brigitta	Small Grass Yellow	Pieridae	trail	LC	V	
38	Eurema hecabe	Large Grass Yellow	Pieridae		NE		$\sqrt{}$
39	Eurema laeta	Spotless Grass Yellow	Pieridae	trail	NE	√	$\sqrt{}$
40	Eurema sari	Chocolate Grass Yellow	Pieridae	shrub	NE	√	$\sqrt{}$
41	Eurema simulatrix	Changeable Grass Yellow	Pieridae	bush	NE	√	
42	Eurema simulatrix	Changeable Grass Yellow	Pieridae	bush	NE	√	√

						Survey	
No.	Scientific Name	Common name	Family	Habitat	IUCN (2015-4 ver.3.1)	Dry season December 2015	Rainy season October 2015
43	Euthalia phemius	White-edged Blue Baron	Nymphalidae	trail	NE	√	
44	Gandaca harina	Tree Yellow	Pieridae	trail	NE	√	
45	Graphium doson	Common Jay	Papilionidae	bush	NE	√	
46	Graphium sarpedon	Common Bluebottle	Papilionidae	bush	NE		√
47	Halpe ormese		Hesperiidae	trail	NE	√	
48	Hypolimnas bolina	Great Eggfly	Nymphalidae	on the trail	NE	√	√
49	Ixias pyrene	Yellow Orange Tip	Pieridae	Shrub	NE	√	√
50	Junonia almana	Peacock Pansy	Nymphalidae	on the shrub	LC	√	\checkmark
51	Junonia atlities	Gray Pansy	Nymphalidae	bush	NE	√	\checkmark
52	Junonia lemonias		Nymphalidae		NE		
53	Junonia lemonias	Lemon Pansy	Nymphalidae	bush	NE	√	
54	Leptosia nina	Psyche	Pieridae	trail	NE	√	
55	Megisba malaya	Malayan	Lycaenidae	on the tree	NE		$\sqrt{}$
56	Mycalesis perseus	Dingy Bushbrown	Nymphalidae		NE		$\sqrt{}$
57	Nacaduba beroe	Opaque Six-line Blue	Lycaenidae	shrub	NE	√	
58	Neptis hylas	Common Sailer	Nymphalidae	on the trail	NE		\checkmark
59	Neptis jumbah	Chestnut-Streaked Sailer	Nymphalidae	bush	NE	√	
60	Neptis soma	Sullied Sailer	Nymphalidae	bush	NE	√	
61	Papilio demoleus	Common Lime	Papilionidae	bush	NE	√	$\sqrt{}$
62	Papilio iswara	Great Helen	Papilionidae	bush	NE	√	
63	Papilio mahadeva	Burmese Raven	Papilionidae	on the trail	NE		\checkmark
64	Papilio memnon	Great Mormon	Papilionidae	trail	NE	√	√
65	Papilio polytes	Common Mormon	Papilionidae	on the tree	NE		$\sqrt{}$
66	Parantica agleoides	Dark Glassy Tiger	Nymphalidae	bush	NE	√	
67	Parnara ganga	Continental Swift	Hesperiidae		NE		$\sqrt{}$
68	Pseudogalis wedah	Tabby	Nymphalidae	bush	NE	√	
69	Tirumala limniace	Blue Tiger	Danaidae		NE		\checkmark
70	Zizula hylax	Gaika Blue	Lycaenidae	trail	NE	√	\checkmark
71	Zizzeeria maha	Pale Grass Blue	Hesperiidae		NE		

Note: NE: Not Evaluated; DD: Data Deficient; LC: Least Concern;

Source of Name: Buttetrflies of Myanmar', Version 2003 (Stephen Kinyon)

Source of Data : EIA Study Team

Table 6-2-3 Recorded Dragonfly Species of Thilawa SEZ Zone B Area

						Survey	period
No.	Scientific name	Common name	Family	Habitat	IUCN (2015-4 ver. 3.1)	Dry season December 2015	Rainy season October 2015
1	Brachydiplax sobrina	Sombre Lieutenant	Libellulidae	near paddy field	LC		\checkmark
2	Ictinogomphus rapax		Libellulidae	near paddy field	LC		\checkmark
3	Neurothemis tullia	Pied Paddy Skimmer	Libellulidae	trail	LC		√
4	Urothemis signata	Greater Crimson Glider	Libellulidae	near the paddy field	LC		√

Note: LC: Least Concern; Source of Name : IUCN

Source of Data: EIA Study Team

Table 6-2-4 Bird Species Recorded in Thilawa SEZ Zone B Area

				IUCN	Survey period		
No.	Scientific Name	Common Name	Family	(2015-4 ver.3.1)	Dry season December 2015	Rainy season October 2015	
1	Accipiter badius	Shikra	Accipitridae	LC	V		
2	Acridotheres fuscus	Jungle Myna	Sturnidae	LC	V	√	
3	Acridotheres tristis	Common Myna	Sturnidae	LC	V	√	
4	Actitis hypoleucos	Common Sandpiper	Scolopacidae	LC		√	
5	Aegithina tiphia	Common Iora	Aegithinidae	LC		√	
6	Anhinga melanogaster	Oriental Darter	Anhingidae	NT		√	
7	Anthus hodgsoni	Olive-backed Pipit	Motacillidae	LC	√	√	
8	Anthus rufulus	Paddyfield Pipit	Motacillidae	LC	√	√	
9	Apus affinis	House Swift	Apodidae	LC		√	
10	Ardea purpurea	Purple Heron	Ardeidae	LC	V	√	
11	Ardea alba	Great Egret	Ardeidae	LC	V	√	
12	Ardea cinerea	Grey Heron	Ardeidae	LC	√	√	
13	Ardeola bacchus	Chinese Pond Heron	Ardeidae	LC	√	√	
14	Bubulcus coromandus	Cattle Egret	Ardeidae	LC	√	√	
15	Cacomantis merulinus	Plaintive Cuckoo	Cuculidae	LC		√	
16	Charadrius dubius	Little- ringed Plover	Charadriidae	LC		√	
17	Chlidonias leucopterus	White-winged Tern	Sternidae	LC		√	
18	Chroicocephalus ridibundus	Black-headed Gull	Laridae	LC		√	
19	Circus macrourus	Pied Harrier	Accipitridae	LC		√	
20	Columba livia	Rock Pigeon	Columbidae	LC	√	√	
21	Copsychus malabaricus	White -rumped Shama	Muscicupidae	LC	√		
22	Copsychus saularis	Oriental Magpie Robin	Muscicapidae	LC	√		
23	Coracias benghalensis	Indian Roller	Coraciidae	LC	$\sqrt{}$	$\sqrt{}$	
24	Corvus splendens	House Crow	Corvidae	LC	$\sqrt{}$		
25	Corvus splendens	House Crow	Corvidae	LC	$\sqrt{}$		
26	Crypsirina temia	Racket–tailed Treepie	Corvidae	LC			
27	Cypsiurus balasiensis	Asiam Palm Swift	Apodidae	LC	√	V	
28	Dendrocygna javanica	Lesser Whistling Duck	Anatidae	LC	√	√	
29	Dicrurus macrocercus	Black Drongo	Dicruridae	LC	√	V	
30	Egretta garzetta	Little Egret	Ardeidae	LC	√		
31	Gallinago gallinago	Common Snipe	Scolopacidae	LC	√		
32	Gracupica contra	Asian Pied Starling	Sturnidae	LC	√	√	
33	Halcyon smyrnensis	White-throated Kingfisher	Alcedinidae	LC	√		

				HICN	Survey period		
No.	Scientific Name	Common Name	Family	IUCN (2015-4 ver.3.1)	Dry season December 2015	Rainy season October 2015	
34	Hirundo rustica	Barn Swallow	Hirundinidae	LC	V	√	
35	Jynx torquilla	Eurasian Wryneck	Picidae	LC			
36	Lanius cristatus	Brown Shrike	Laniidae	LC	√	√	
37	Lonchura punctulata	Scaly-breasted Munia	Estrididae	LC	√	√	
38	Megalaima haemacephala	Coppersmith Barbet	Megalaimidae	LC	√		
39	Merops orientalis	Little Green Bee-eater	Meropidae	LC	\checkmark	√	
40	Mesophoyx intermedia	Intermediate Egret	Ardeidae	LC	$\sqrt{}$	$\sqrt{}$	
41	Metopidius indicus	Bronze-winged Jacana	Jacanidae	LC	√		
42	Milvus lineatus	Black-eared Kite	Accipitridae	NE	$\sqrt{}$	√	
43	Milvus migrans	Black Kite	Accipitridae	LC	√	√	
44	Motacilla alba	White Wagtail	Montacillidae	LC	√		
45	Nettapus coromandelianus	Cotton Pygmy Goose	Anatidae	LC	√		
46	Oriolus chinensis	Black-naped Oriole	Oriolidae	LC	\checkmark		
47	Orthotomus atrogularis	Dark-necked Tailorbird	Sylviidae	LC	√		
48	Passer domesticus	House Sparrow	Passeridae	LC	$\sqrt{}$	√	
49	Passer montanus	Eurasian Tree Sparrow	Passeridae	LC	$\sqrt{}$	\checkmark	
50	Phalacrocorax niger	Little Cormorant	Phalacrocoracidae	LC	$\sqrt{}$	√	
51	Ploceus hypoxanthus	Asian Golden Weaver	Ploceidae	NT		√	
52	Ploceus philippinus	Baya weaver	Ploceidae	LC	$\sqrt{}$		
53	Pluvialis fulva	Pacific Golden Plover	Charadriidae	LC		√	
54	Prinia hodgsonii	Grey-breasted Prinia	Cisticolidae	LC	V	V	
55	Prinia inornata	Plain Prinia	Cisticolidae	LC	√	√	
56	Pycnonotus blanfordi	Streak-eared Bulbul	Pycnonotidae	LC	√	√	
57	Pycnonotus cafer	Red-vented Bulbul	Pycnonotidae	LC	V	√	
58	Pycnonotus jocosus	Red-whiskered Bulbul	Pycnonotidae	LC	√	√	
59	Saxicola caprata	Pied Bushchat	Muscicapidae	LC	V	√	
60	Saxicola maurus	Eastern Stonechat	Muscicapidae	LC	V		
61	Streptopelia chinensis	Spotted Dove	Columbidae	LC	$\sqrt{}$		
62	Streptopelia tranquebarica	Red-collared Dove	Columbidae	LC	\checkmark		
63	Timalia pileata	Chestnut-capped Babbler	Timalidae	LC	√		
64	Tringa ochropus	Green Sandpiper	Scolopacidae	LC	√		
65	Turdoides gularis	White-throated Babbler	Leiothrichidae	LC	√	√	
66	Vanellus cinereus	Grey-headed Lapwing	Charadriidae	LC	√	√	
67	Vanellus indicus	Red-wattled Lapwing	Charadriidae	LC	√	√	

Note: Not Evaluated; LC: Least Concern;
Source of Name: CRAIG ROBSON, A Field Guide to the Birds of South-east Asia (2011).
Source of Data: EIA Study Team

Table 6-2-5 Recorded Mammal Species of Thilawa SEZ Zone B Area

						Survey	period
No.	Scientific Name	Common Name	Family	IUCN (2015-4 ver.3.1)	Remark	Dry season December 2015	Rainy season October 2015
1	Bandicota indica	Greater bandicoot Rat	Muridae	LC	Interviewed		\checkmark
2	Echinosorex gymnurus	Moonrat	Erinaceidae	LC	Interviewed	\checkmark	\checkmark
3	Herpestes javanicus	Small Asian Mongoose	Herpestidae	LC	Interviewed	\checkmark	$\sqrt{}$
4	Herpestes urva	Crab-eating Mongoose	Herpestidae	LC	Interviewed	\checkmark	$\sqrt{}$
5	Lepus peguensis	Burmese Hare	Leporidae	LC	Interviewed	\checkmark	$\sqrt{}$
6	Paradoxurus hermaphroditus	Common Palm Civet	Viverridae	LC	Interviewed		√
7	Viverricula indica	Small Indian Civet	Viverridae	LC	Interviewed	√	V

Note: LC: Least Concern; Source of Name :IUCN Source of Data : EIA Study Team

Table 6-2-6 Recorded Reptile and Amphibian Species of Thilawa SEZ Zone B Area

						Survey	period
No.	Scientific Name	Common name	Family	IUCN (2015-4 ver.3.1)	Remark	Dry season December 2015	Rainy season October 2015
1	Bufo bufo	Common Toad	Bufonidae	LC	Observed	V	\checkmark
2	Hylarana erythraea	Common Green Frog	Ranidae	LC	Observed	V	\checkmark
3	Kaloula pulchra	Painted Bullfrog	Microhylidae	LC	Observed	V	\checkmark
4	Rana leptolossa	Flying Frog	Rhacophoridae	NE	Observed	V	
5	Amphiesma stolatum	Buff-striped Keelback	Colubridae	NE	Observed	V	
6	Bungarus fasciatus	Banded Krait	Elapidae	LC	Interviewed	V	
7	Bungarus fasciatus	Yellow-banded Krait	Elapidae	NE	Observed		\checkmark
8	Calotes emma	Crested forest lizard	Agamidae	NE	Observed	V	
9	Calotes versicolor	Oriental garden lizard	Agamidae	NE	Observed	√	√
10	Daboia russelii	Russell's Viper	Viperidae	NE	Interviewed		\checkmark
11	Ophiophagus hannah	King Cobra	Elapidae	VU	Interviewed		√
12	Ptyas mucosa	Indian Rat Snake	Colubridae	NE	Observed	√	
13	Xenochrophis piscator	Checkered Keelback	Colubridae	NE	Interviewed		√

Note: NE: Not Evaluated; LC: Least Concern; VU: Vulnerable;

Source of Name :IUCN Source: EIA Study Team

Table 6-2-7 Fish Species Recorded in Thilawa SEZ Zone B Area

	Scientific Name	Common Name	Family	IUCN (2015-4 ver.3.1)	Remark	Survey period	
No.						Dry season December 2015	Rainy season October 2015
1	Anabas testudineus	Climbing perch	Anabantidae	DD	Observed	\checkmark	
2	Channa harcourtbutleri	Asiatic Snaked head	Channidae	NE	Interviewed	√	
3	Channa marulius	Giant Snake head	Channidae	LC	Interviewed	√	
4	Channa punctata	Spotted Snake head	Channidae	LC	Interviewed	√	
5	Channa striata	Snakehead Murrel	Channidae	LC	Interviewed		\checkmark
6	Cirrhinus mrigala	Mrigal	Cyprinidae	LC	Interviewed	√	\checkmark
7	Clarias batrachus	Magur	Clariidae	LC	Interviewed	√	\checkmark
8	Fenneropenaeus indicus	Indian Prawn	Penaeidae	NE	Interviewed	√	V
9	Gecarcinidae natalis	Christmas Island red crab	Gecarcoidae	NE	Interviewed	√	\checkmark
10	Lates calcarifer	Asian seabass	Latidae	NE	Interviewed	√	
11	Monopterus albus	Rice swampeel	Synbranchidae	LC	Interviewed	√	
12	Mystus cavasius	Gangetic mystus	Bagridae	LC	Interviewed	V	V
13	Notopterus notopterus	Grey feather back	Notopteridae	LC	Interviewed		√
14	Ompok bimaculatus	Indian butter fish	Siluridae	NT	Interviewed	√	
15	Oreochromis mossambicus	Mozambique Tilapia	Cichlidae	LC	Interviewed		√
16	Osteobrama feae	Burmese osteobrama	Cyprinidae	LC	Interviewed	\checkmark	
17	Parambassis ranga	Indian Glassy fish	Ambassidae	LC	Interviewed	\checkmark	
18	Puntius chola	Chola barb	Cyprinidae	LC	Interviewed	√	
19	Puntius chola	Chola barb	Cyprinidae	LC	Interviewed		√
20	Salmophasia sardinella	Sardinella Razobelly	Cyprinidae	NE	Interviewed	√	
21	Scylla serrata	Mud crab	Portunidae	NT	Interviewed	√	√
22	Wallago attu	Boal (in Bengali)	Siluridae	NT	Interviewed		√

Note: NE: Not Evaluated; LC: Least Concern; VU: Vulnerable;

Source of Name :IUCN Source: EIA Study Team

Annex 6-3

Vulnerable and Near Threatened Species Recorded during the Survey of the Project

Annex 6-3 Vulnerable and Near Threatened Species Recorded during the Survey of the Project

Scientific Name: Anhinga melanogaster		Common Name: Oriental Dart	IUCN Red List: er NT		
Population	The popul	lation is estimated to nun	aber at least 22,000 mature individuals, ividuals in total. (source: IUCN Website)		
Geographic Range	Vietnam, O In Myann	Cambodia, Malaysia, Singap nar, previously a widespre	Bangladesh, Myanmar, Thailand, Laos, bore, Brunei, Indonesia, Timor-Leste. ad resident, now scarce to locally fairly ewhere. (source: IUCN Website)		
	Distribution	on Map (source: IUCN Web	site)		
Habitat Local Information/ The situation at the time of	It inhabits shallow inland wetlands including lakes, rivers, swamps reservoirs. (Not a migrate) (source: IUCN Website) It inhabits lakes, Marshes, Large rivers; up to 1200m, swims open water; Some submerges, (Resident) (source: A Field Guide to the Birds of South-East Asia C ROBSON), These species mostly occurs are Indawgyi Wetland Wildlife Sanc Kachin North Myanmar and Ayeyarwaddy River, Myitkyina Section Kachin, Myanmar, (Source; SST Tourism, Myanmar Birds Photo Gallery). At the site of Lake, Yangon. (Source, this found by bird watching). And then other reference are of Myanmar' (Kyaw myo lwin and Daw khin Ma Ma Twin 2003). Oriental Darter is found in colony, flying on the site. It makes the nest near river or lake in Yangon but in the forest, it use to live more near lake than				
the discovery during field survey	similar in	cie of Anhingidae and residappearances. Feed on fishes			
Photos	ARKIVE WWW.BRKIVE.OPI	a Someor Shah / www.sameorshah.com			

Scientific Name:		Common Name:	IUCN Red I	List:
Ploceus hypoxanth		Asian Golden We		
Population	habitat rec 10,000-19, 000-30,000	s is thought to have a modera quirements and population of 999 mature individuals, proba) individuals. (source: IUCN)	declines. It is placed in ably equating to total populesite)	the band for ulation of c.15,
Geographic Range		n Myanmar (scarce to locally serim), Thailand, Laos, Vietrosite)		
	Distributio	n Map (source: IUCN Websit		
Habitat	the lowlar	marshes, grassland, reeds ands where large flocks somource: IUCN Website)		
	A Field Gu reference ar and These	Marshes, grass, reeds, rice paddies, tide to the Birds of South-East re 'Birds of Myanmar' (Kyaw marspecies mostly are found Moamar (July 2016) Photographer by	Asia CRAIG ROBSON), yo lwin and Daw khin Ma yungyi Wetland Wildlife S	And then other Ma Twin 2003), anctuary, Bago
Local Information/ The situation at the time of the discovery during field survey	their nests and bambo	den Weaver is found out of tare found in the tree mostly. oo. Many species are exploited a resident except northern and	Feed mainly on seeds in ged for cage bird trade. In	grassland, crop,
	Taken at Th (1/10/2016	ilawa SEZ by EIA Study Team	Taken at Thilawa SEZ by 1 (1/10/2016)	EIA Study Team

Scientific Name: Ophiophagus hann	ah	Common Name: King Cobra	IUCN Red List: VU
Population		nar, only three or four have been recorded. Wogan pers. comm. 2011). (source: IUC	
Geographic Range	southern Indonesia	stributed in South and Southeast Asia, f. China, southward to the Philippines (weast as far as Sulawesi and Bali, as well k and Sabah, and Brunei, on the island of	where it is widespread) and as the Malaysian territories
	Distribution	on Map (source: IUCN Website)	
Habitat	can also bareas with	tes is found in a variety of habitats, primare found in degraded forest, mangrove swaremants of woodland. It has also been ted land. Females build nests of dead leathatch, which takes 70 days at 28 ² C. (source	wamps and even agricultural found swimming in rivers in aves and stay with the eggs
	deciduous observed in at an elevat than others	es inhabitant primary forests, including sen and tropical dipterocarp forests and mang more open area such as alluvial grassland, fit tion of 2181m all. Diurnal and terrestrial, with and juveniles more arboreal than adults. (south-east Asia INDRANEIL DAS. (2010).	rove swamps, and sometimes rom sea level to montane forest some population more arboreal
Local Information/ The situation at the time of the discovery during field survey	around 20 rarely to d	g to the interview survey of local people 08. It was rainy season. It is a kind of hibe observe. King cobra are able to hunt thro at night. Leading more herpectologist to Habitat are mostly observed in bambs.	ernate animal that's why it is bughout the day but difficult o classify them as a diurnal
Photos	Source: IU	CN	

Scientific Name:		Common Name: IUCN Red List:	
Ompok bimaculatus		Indian butter-fish	NT
Population	This specie Website)	es is relatively abundant throughout its	distribution. (source: IUCN
Geographic Range	However,	stributed in Pakistan, India, Sri Lanka, given the uncertainties surrounding the at its range is more geographically circum	identity of this species, it is
	Distributio	n Map (source: IUCN Website)	
Habitat		ains and sub montane regions, and is fou arce: IUCN Website)	nd in rivers, lakes, tanks and
	silt bottom and to the	t of this species is freshwater river slug in search for food. They are migrating to floodplain during the flood season (so ist of fishes of Burma. (Union of Burma)	o the smaller streams, canals ource: Tint Hlaing, 1967. A
Local Information/ The situation at the time of the discovery during field survey	insect and	maculatus used to feed on crustaceans, algae in the river. The fish do their annuring the monsoon before returning to the the year.	nual upstream journey to lay
Photos	Photo: AM Im	teazzáman 7 8 9 10 11 12 13 14 15 16 osite of www.bdfish.org	

Scientific Name:		Common Name:	IUCN Red List:
Oreochromis mossam		Mozambique Tilapia	NT
Population	Common Website)	and widespread through south ea	astern Africa. (source: IUCN
Geographic Range	Bay. Occur Transvaal i range to in the lower temperate	nbezi, Lower Shire and coastal plair rs southwards to the Bushmans Rive in the Limpopo system (Skelton 2001 land regions and to the south west a Orange and rivers of Namibia. Intercalities throughout the world. (sour map (source: IUCN Website)	r in the eastern Cape and in the l). Widely dispersed beyond this nd west coastal rivers including troduced to tropical and warm
Habitat	in its rang tolerates it diatoms, and Breeds in season. Me mouthbrood Prone to st. The prefer of salt. Ho salty ocean water bodi 1967. A cl. Science.)	all but fast-flowing waters; thrives in e it is most common in blind estua brackish and marine environments and detritus, large individuals also take summer, females raising multiple broales construct a saucer-shaped nest ds the eggs, larvae and small fry. Junting under adverse or crowded confreshwater, such as lakes and streams wever, they can also survive in brack a water mix. In the Myanmar, Tilapia es such as man-made lake, canals, assified list of fishes of Burma. (Ur	aries and coastal lakes where it its. Feeds on algae, especially it insects and other invertebrates. Feeds every 3 to 4 weeks during a on sandy bottoms: the female aveniles shoal in shallow water. In ditions (Skelton 2001). It is, which have low concentration it is water, where freshwater and has been found in the variety of rice field (source: Tint Hlaing, nion of Burma). Journal of Life
Local Information/ The situation at the time of the discovery during field survey	coastal lak	abicus is found in habitat ranging for and well vegetated area. They consults are group-living and can toler thavior of tilapia is primarily on macfry.	an also thrive in sea water. O rate a variety of habitats. The
Photos	Source: Wel	osite of www.fishbase.org.	

Annex 10-1

List of Commitment

Annex 10-1 List of Commitment

A consolidated summary list of environmental, social and health commitments that will be implemented in the Project in order to manage and mitigate potential impacts associated with the project development is provided below in Table 10-1.

Table 10-1 Project Key Commitments

	N	No.	EIA	Supervise/Responsible (◎) Implementing (●) Examining (▲) (if any) Organizations			
Field	No.	Commitment	Reference	Project Proponent	Contractor	Tenant	TSMC
General	1-1	The Project will follow the UN Global Compact.	Section 2.1	•			
	1-2	The relevant Myanmar laws, rules and regulations as follows will be complied with. - The National Environment Policy (1994) - The Environmental Conservation Law (2012) and the Environmental Conservation Rules (2014) - The EIA Procedure (2015) - Notice to Ensure the Responsible Investment in the Thilawa SEZ (Notice No.04/2015) - the National Environmental Quality (Emission) Guidelines (2015)	Section 2.2.2	•	•	•	•
	1-3	The Project will basically follow the General EHS Guidelines (IFC) (2007).		•	•	•	
	1-4	The Project will comply with the JICA Guidelines for Environmental and Social Considerations (April 2010).	Section 2.8	•	•	•	•
	1-5	The internal regulation for the industrial area of Zone B will be formulated by the project proponent in order to operate the whole industrial area properly, and also manage and supervise the tenants entered in the industrial area of Zone B. Several obligations for tenants stipulated on it will be complied with.	Section 2.3	•	•	•	
	1-6	The Project will comply with all of the target values which set in EIA report.	Section 2.3	•	•	•	•
Air Quality	2-1	The Project set the target value of ambient air quality in accordance with the National Environmental Quality (Emission) Guidelines (NEQG) (1.1 Air Emissions).	Section 2.3.1	0	•	•	
	2-2	The tenants will have its own arrangement to satisfy with the standard stipulated by the regulation in the republic of the union of Myanmar ((NEQG at this moment) and IFC's General EHS Guidelines in accordance with the proposed internal regulation.	Section 2.3.1	0		•	
	2-3	The contractor will sprinkle water around the project site and roads, and avoid intensive operation of construction machineries during the construction/closing phase.	Section 7.2.5, 10.1	0	•		
	2-4	The project proponent/tenants will provide the commuter bus during the operation phase.	Section 7.2.5, 10.1	•		•	
	2-5	The project proponent/tenants will set the speed limit for drivers in the project area during the operation phase.	Section 7.2.5, 10.1	⊚●		•	
	2-6	The tenants will consider mitigation measures such as energy use efficiency, process modification, and selection of fuels in order for less impact on air quality.	Section 7.2.5			•	
	2-7	Monitoring of air quality will be conducted in accordance with the EMoP during the construction phase.	Section 10.2	0	•	0	A
	2-8	Monitoring of air quality will be conducted in accordance with the EMoP during the operation phase.	Section 10.2	•		•	A
Water Quality	3-1	The Project set the target value of ambient water quality by adopting the strictest one among the standards of	Section 2.3.2	0	•	•	

			EIA	Supervise/Responsible (◎) Implementing (●) Examining (▲) (if any) Organizations			
Field	No.	Commitment	Reference	Project Proponent	Contractor	Tenant	TSMC
		Indonesia, Thailand, Vietnam and Japan.					
	3-2	The Project set the target value of effluent water quality for discharging to water body by adopting the stricter one either the industrial wastewater effluent guideline value determined by the Ministry of Industry or wastewater value set in NEGQ (1.2 Wastewater).	Section 2.3.2	©	•	•	
	3-3	The constructer will install the settling ponds or simple turbid water treatment and the septic tank during the construction/closing phase.	Section 7.3.5, 10.1	0	•		
	3-4	The constructer will prepare the discharge water treatment plan during the construction/closing phase.	Section 7.3.5, 10.1	0	•		
	3-3	In case that large amount discharge which includes heavy metals and toxic substance is expected and especially low flow season, the project proponent would review the internal target value and set strict standard for pre-treatment, if necessary.	Section 7.3.5, 10.1	0		•	
	3-6	The project proponent will operate and maintain the centralized wastewater treatment system during the operation phase.	Section 7.3.5, 10.1	•			
	3-7	The tenants will operate and maintain the pre-wastewater treatment	Section 7.3.5, 10.1			•	
	3-8	Monitoring of water quality will be conducted in accordance with the EMoP during the construction phase.	Section 10.2	0	•	0	A
	3-9	Monitoring of water quality will be conducted in accordance with the EMoP during the operation phase.	Section 10.2	O		$\odot lacktriangle$	•
Waste	4-1	The tenant will have its own arrangement with a company duly authorized by the project proponent for removal and disposal to sanitary landfill or their disposal systems in accordance with the proposed internal regulation.	Section 7.4.5, 10.1			© •	
	4-2	The contractor will reuse the residual soil generated in cutting work for filling work in the site during the construction/closing phase.	Section 7.4.5, 10.1	0	•		
	4-3	The contractor will prepare and implement waste management program during the construction/closing phase.	Section 7.4.5, 10.1	0	•		
	4-4	The tenants will manage non-hazardous waste from tenants and utility area of themselves, and also manage hazardous waste by tenants during the operation phase.	Section 7.4.5, 10.1			•	
	4-5	Amount and kind of solid waste will be monitored in accordance with the EMoP during the construction phase.	Section 10.2	0	•		
	4-6	Amount of non-hazardous/hazardous waste will be monitored in accordance with the EMoP during the operation phase.	Section 10.2	0		⊚●	•
Soil Contamination	5-1	The tenants will control solid and liquid waste which causes soil contamination during the operation phase.	Section 7.5.5, 10.1	0		••	A
	5-2	With reference to the process of usage, producing, storing, disposing and handling of oil, chemical, dangerous or hazardous materials in the project area, the tenants shall treat the materials safety on the covered area to prevent infiltration of the materials to ground, eliminate or dispose of all dangerous or hazardous materials and waste	Section 7.5.5, 10.1	© •		•	
	5-3	Status of control of solid and liquid waste which causes soil contamination will be monitored in accordance with the EMoP during the operation phase.	Section 10.2	0		•	•
Noise and Vibration	6-1	The Project set the target value of noise level that is set in NEQG (1.3 Noise Levels) and in the proposed internal regulation.	Section 2.3.3, 2.3.4	0	•	•	

			EIA	Supervise/Responsible (◎) Implementing (●) Examining (▲) (if any) Organizations			
Field	No.	Commitment	Reference	Project Proponent	Contractor	Tenant	TSMC
	6-2	The project proponent will consider the arrangement of the land allocation for each tenant and the installation of buffer zone with less noise and vibration impacts to the surrounding sensitive receivers (monastery, residence etc.)	Section 7.6.6, 10.1	•			
	6-3	The contractor will install sound-proofing sheet during the construction/closing phase.	Section 7.6.5, 10.1	0	•		
	6-4	The contractor will issue advanced notice for construction work time near the monastery and residential area during the construction/closing phase.	Section 10.1	0	•		
	6-5	The contractor will avoid construction at nighttime and intensive operation of construction machineries during the construction/closing phase.	Section 7.6.5, 10.1	0	•		
	6-6	The contractor will set the speed limit for drivers during the construction/closing phase.	Section 7.6.5, 10.1	0	•		
	6-7	The tenants will control noise by its own arrangement such as sound–absorbing materials, installing the facility in the house, having the enough buffer zone between the source and any property line or other suitable means so as to comply with the tentative target value.	Section 7.6.5, 10.1			•	
	6-8	Noise and vibration level and traffic volume will be monitored in accordance with the EMoP during the construction phase.	Section 10.2	0	•	© •	•
	6-9	Noise level and traffic volume will be monitored in accordance with the EMoP during the operation phase.	Section 10.2	$\odot lacktriangle$		•	•
Offensive Odor	7-1	The tenants will control emission gas and waste which causes offensive odor, as necessary during the operation phase.	Section 7.7.5, 10.1	0		•	
	7-2	Status offensive odor control will be monitored in accordance with the EMoP during the operation phase.	Section 10.2	0		•	
Bottom Sediment	8-1	The project proponent will operate and maintain the centralized wastewater treatment system during the operation phase.	Section 7.8.5, 10.1	©			
	8-2	In case that large amount discharge which includes heavy metals and toxic substance is expected and especially low flow season, the project proponent would review the internal target value and set strict standard for pre-treatment, if necessary.	Section 7.8.5, 10.1	0		•	
	8-3	Monitoring of water quality will be conducted in accordance with the EMoP during the operation phase.	Section 10.2	•			
Flora/Fauna and Ecosystem	9-1	The contractor will make clear boundary of the project site to prevent the contractor from clearing the vegetation outside of the project site during the construction/closing phase.	Section 7.9.5, 10.1	0	•		
	9-2	The project proponent/tenants will carry out planting trees, vegetation, sodding of public spaces such as road, retention ponds, and other open space of each tenant during the operation phase.	Section 7.9.5, 10.1	© •		•	
Hydrology	10-1	The contractor will use groundwater in a limited way and on a short-term basis, and will prepare tentative retention pond during the construction/closing phase.	Section 7.10.5, 10.1	0	•		
	10-2	The project proponent will manage retention ponds during the operation phase,	Section 7.10.5, 10.1	⊚●			
	10-3	The project proponent will install additional earth drain line around the boundary of the project area if a flood were to occur.	Section 7.10.5, 10.1	•			
	10-4	Groundwater lever, ground elevation level and consumption of groundwater amount will be monitored in	Section 10.2	0	•		

			EIA	Supervise/Responsible (◎) Implementing (●) Examining (▲) (if any) Organizations			
Field	No.	Commitment	Reference	Project Proponent	Contractor	Tenant	TSMC
		accordance with the EMoP during the construction phase.					
	10-5	Function of retention pond at heavy rain will be checked in accordance with the EMoP during the construction phase.	Section 10.2	0	•		
Soil Erosion	11-1	The contractor will provide temporary drainage and/or sandbag to minimize soil erosion of the bank due to rainy water during the construction/closing phase.	Section 7.11.5, 10.1	0	•		
	11-2	Planting trees, vegetation, and sodding in the bare area will be implemented as soon as possible after completion of landfilling.	Section 7.11.5	0	•		
	11-3	The project proponent will manage retention pond during the operation phase.	Section 7.11.5, 10.1	⊚●			
Involuntary Resettlement	12-1	TSMC will provide land compensation (if applicable) and assistance package based on the Resettlement Framework for 2,000 ha.	Section 7.12, 7.13.5, 10.1				⊚●
	12-2	TSMC will provide an Income Restoration Program (IRP) based on the Resettlement Framework for 2,000 ha in order to restore and stabilize the livelihood of displaced PAHs.	Section 7.12, 7.13.5				⊚ ●
	12-3	TSMC will provide preliminary discussion and compensation and assistance for the households in the proposed relocation site as necessary.	Section 7.12, 7.13.5, 10.1				•
Living and Livelihood	13-1	TSMC will provide assistance on loss of income source and implement income restoration program (IRP) based on the Resettlement Framework for 2,000ha.	Section 7.12, 7.14.5, 10.1				••
	13-2	The contractor will issue advance notice for construction work time and avoid intensive operation of construction vehicle.	Section 10.1	0	•		
	13-3	Implementation status for CSR activities such as community support program will be monitored in accordance with the EMoP during the construction and operation phase.	Section 10.2	•			
Vulnerable Group	14-1	TSMC will provide special assistance in addition to the assistance on loss of assets and income source based on the Resettlement Framework for 2,000 ha	Section 7.12, 7.15.5, 10.1				•
	14-2	The project proponent will provide special support targeting vulnerable people based on their request as necessary.	Section 7.15.5	••			
Local Conflict of Interests	15-1	TSMC will arrange adequate infrastructure and service based on the actual demand.	Section 7.12, 7.16.5, 10.1				•
	15-2	TSMC will provide support for social integration with host communities and support for establishment of the harmonization by IRP based on the Resettlement Framework for 2,000 ha.	Section 7.12, 7.16.5				© •
	15-3	The contractor will provide education and training to give instruction to workers to avoid the conflict with local people during the construction/closing phase.	Section 7.16.5, 10.1	0	•		
Misdistribution of Benefit and Damage	16-1	The project proponent will communicate with local community through community relation department in all phases.	Section 7.17.5, 10.1	•			
	16-2	The project proponent will implement community support program that will help to establish harmonization with local communities and to balance the social, environmental and economic impacts of the Project.	Section 7.17.5	•			
Children's Right	17-1	The relevant regulations/rules on illegal child labor as follows will be complied with in all phases.	Section 2.1	•	•	•	•

		No. Commitment			Impleme amining	esponsible enting ((() (if a izations)
Field	No.	Commitment	EIA Reference	Project Proponent	Contractor	Tenant	TSMC
		- The Shops and Establishment Act (1951) - The Factory Act (1951) - UN Global Government (principle 5: effective abolition of child labor)					
	17-2	TSMC will provide commuting assistance for school for children of relocated PAHs during the pre-construction phase.	Section 7.12, 7.18.5, 10.1				•
	17-3	MJTD will continuously implement educational support program based on needs and requests from communities,	Section 7.18.5	O			
Existing Social Infrastructures and Services	18-1	TSMC will arrange alternative option for infrastructure and service after relocation.	Section 7.12, 7.19.5, 10.1				•
	18-2	The project proponent will construct alternative community road during the pre-construction phase.	Section 7.19.5, 10.1	⊚●			
	18-3	The contractor will control traffic volume during the construction/closing phase.	Section 7.19.5, 10.1	0	•		
Water Usage	19-1	The project proponent will arrange alternative pond near the project area during the pre-construction phase.	Section 7.20.5, 10.1	⊚●			
	19-2	The contractor will use water from outside of the project area or use groundwater inside the project area, and the amount of water to be used will be limited.	Section 7.20.5	0	•		
	19-3	The contractor will install settling ponds or simple turbid water treatment, and septic tank during the construction/closing phase.	Section 7 .20.5, 10.1	0	•		
	19-3	The contractor will prepare the discharge water treatment plan during the construction/closing phase.	Section 7.20.5, 10.1	0	•		
	19-4	The project proponent will manage drainage ditch and retention ponds inside of the project area during the operation phase.	Section 7.20.5, 10.1	•			
	19-5	The water discharge from tenants will be treated at the treatment plant to comply with the target value of water quality.	Section 7.20.5	••		•	
Cultural Heritage/Asset	20-1	TSMC will conduct adequate dialogue with local community in order to discuss necessity of relocation and the detail process for cemetery before its relocation.	Section 7.12, 7.21.5, 10.1				•
	20-2	Adequate space for the assets will be secured to keep enough distance from the construction site during the construction/closing phase.	Section 7.21.5, 10.1	••	•		
Landscape	21-1	The project proponent/tenants will follow the rule of landscape in accordance with proposed industrial internal regulation to secure the environmental friendliness and keep harmonization with the surrounding area.	Section 7.22.5, 10.1	••		© •	
Risks for Infectious Diseases such as AIDS/HIV	22-1	The contractor and the tenants will conduct mitigation measures stipulated in the international guidelines such as EHS Guidelines of IFC such as; - To provide surveillance for worker's health - Prevention of illness among workers by undertaking health awareness and education initiatives and by conducting immunization programs for workers - To provide treatment through standard case management in on-site and community health care facilities as necessary - Educating project personnel and area residents on risks, prevention, and available treatment - Promoting collaboration with local authorities to enhance access of worker's families and the community to public health services and promote immunization as	Section 7.23.5, 10.1	0	•	⊙ •	

	No. Commitment		EIA	1	ervise/Re Impleme amining (Organi	nting ()
Field		Reference	Project Proponent	Contractor	Tenant	TSMC	
		necessary - Promoting use of repellents, clothing, netting, and other barriers to prevent insect bites - Prevention of larval and adult propagation through sanitary improvements and elimination of breeding habitats close to human settlements - Elimination of unusable impounded water					
	22-2	Awareness of infectious diseases will be monitored in accordance with the EMoP during the construction phase.	Section 10.2	0	•		
	22-3	Status of measures against infectious diseases will be monitored in accordance with the EMoP during the operation phase.	Section 10.2	© •		•	
	22-4	- Status of the implementation of CSR activities will be monitored in accordance with the EMoP during all phases.	Section 10.2	•		•	
Occupational Health and Safety (including labor's rights)	23-1	The relevant regulations/rules of labor's rights, health and safety as follows will be complied with. - The Worker's Compensation Act (1923) - The Payment of Wages Act (1936) - The Factory Act (1951) - The Shops and Establishment Act (1951) - The Leave and Holiday Act (1951, partially revised in 2014) - The Labour Organization Law (2011) - The Prevention and Control of Communicable Disease Law (2011) - The Social Security Law (2012) - The Labour Organization Rule (2012) - The Labour Dispute Settlement Law (2012) - The Employment and Skill Development Law (2013) - The Minimum Wage Law/Rules (2013) - The Prevention of Hazard from Chemical Substances Law (2013) - Myanmar Special Economic Zone Law (2014) - Notice to Ensure the Responsible Investment in the Thilawa SEZ (Notice No.04/2015)	Section 2.1.2	•	•	•	•
	23-2	The contractor and the tenants will conduct mitigation measures stipulated in the international guidelines such as EHS Guidelines of IFC such as; [Common] - To provide adequate health care facilities and first aid within construction sites - To provide OHS training program and information of basic site rules of work, basic hazard awareness, site specific hazards, safe work practices, and emergency procedure [Occupational Health] - To provide adequate lavatory facilities for the number of people expected to work in the facility - To provide adequate supplies and easy access of drinking water with a sanitary means - To provide temporary shelters to protect against the elements during working activities or for use as rest areas as needed - To promote the use of repellents, clothing, netting, and other barriers to prevent insect bites and snake bite [Occupation Safety]	Section 7.24.5, 10.1	©	•	•	

		No. Commitment		1	ervise/Re Impleme amining (Organi	nting (● (▲) (if a)
Field	No. Commitment	EIA Reference	Project Proponent	Contractor	Tenant	TSMC	
		- Adequate preventive measures from negative factors such as over-exertion, slips and falls, work in heights, struck by objects, moving machinery, dust, confined spaces and excavations, and other site hazards - To train and license industrial vehicle operators in the safe operation of specialized vehicles - To establish driving and traffic rules - To identify and provide appropriate PPE that offers adequate protection to the worker, co-workers, and occasional visitors - Proper maintenance of PPE and the instruction of proper use					
	23-3	Record of accidents and infectious diseases will be monitored in accordance with the EMoP during the construction phase.	Section 10.2	0	•		
	23-4	Record of accidents and infectious diseases will be monitored in accordance with the EMoP during the operation phase.	Section 10.2	© •		•	
	23-4	- Status of the implementation of CSR activities will be monitored in accordance with the EMoP during all phases.	Section 10.2	•		•	
Community Health and Safety (including human rights)	24-1	The contractor and the tenants will conduct mitigation measures stipulated in the international guidelines such as EHS Guidelines of IFC such as; [Common & Other] - Establish the plan of site safety and security measures to communities and its implementation - Education and instruction to the project personnel and construction workers on risks, prevention, and available treatment - Dispute settlement among stakeholders in case incidences occur - Arrangement of worker's accommodation as necessary - Securing the existing water source [General Site Hazard] - Restricting access to the site with a focus on high risk structures or areas depending on site-specific situations including fencing, signage, and communication of risks to the local community - Removing hazardous conditions on construction sites such as covering openings to small confined spaces, ensuring means of escape for larger openings such as trenches or excavations, or locked storage of hazardous materials [Traffic Safety] - Emphasizing safety aspects among drivers - Improving driving skills and requiring licensing of drivers - Adopting limits for trip duration and arranging driver rosters to avoid overtiredness - Avoiding dangerous routes and times of day to reduce the risk of accidents	Section 7.25.5, 10.1	©	•	$\odot lacktriangle$	
	24-2	The project proponent will install the speed bump with the sign board on the road as necessary. TSMC and the project proponent will provide	Section 7.25.5 Section	•			
	24-4	coordination with local people and handle complaints to solve as necessary. Record of accidents and infectious diseases related to the	7.12, 7.25.5 Section 10.2	○ ●○	•		◎●

		No. Commitment		1	Impleme amining	esponsible enting ((A) (if a dizations)
Field	No.	Commitment	EIA Reference	Project Proponent	Contractor	Tenant	TSMC
		community will be monitored in accordance with the EMoP during the construction phase.					
	24-5	Implementation status for CSR activities such as community support program will be monitored in accordance with the EMoP during the construction phase.	Section 10.2	0	•		
	24-6	Record of accidents and infectious diseases related to the community will be monitored in accordance with the EMoP during the operation phase.	Section 10.2	•		•	
	24-7	Implementation status for CSR activities such as community support program will be monitored in accordance with the EMoP during the operation phase.	Section 10.2	© •			
Usage of Chemicals	25-1	The relevant regulations/rules of usage of chemicals as follows will be complied with. - The Prevention of Hazard from Chemicals and Related Substances Law (1995, revised in 2011)	Section 2.1.2, 7.25.5	••	•	•	
	25-2	The chemicals management plan will be prepared which shall regulate their storage and usage condition, if chemicals are used in their plot.	Section 7.26.5, 10.1	•		•	
	25-3	The tenants will implement the proper storage and record of usage during the operation phase.	Section 7.26.5, 10.1	0		O	
	25-4	The tenants will provide training of safety usage and prepare the emergency response plans during the operation phase.	Section 10.1	0		••	
	25-5	The tenants will apply the adequate license with management plan in accordance with the relevant law and compliance with the law during the operation phase.	Section 7.26.5, 10.1	0		•	
	25-6	The tenants will provide protective equipment and clothes to workers as necessary.	Section 10.1	0		•	
	25-7	The tenants will monitor and record the type and quantity of chemicals and implementation status of control measures through self-inspection.	Section 10.2			•	
Flood Risk	26-1	Appropriate drainage system will be installed so as to prevent inundation in the project area.	Section 7.27.5	0	•	•	
	26-2	The contractor will prepare the disaster prevention equipment and management manual during the construction/closing phase.	Section 7.27.5, 10.1	0	•		
	26-3	The project proponent/tenants will prepare the disaster prevention equipment and management manual during the operation phase.	Section 7.27.5, 10.1	•		•	
Risk of Fire	27-1	TSMC's Standard Operational Procedure (SOP) for building construction and fire safety and the internal regulation will be complied with.	Section 7.28.5, 10.1	•	•		•
	27-2	The project proponent/tenants will install the fire hydrants along the road and implement emergency drill during the operation phase.	Section 7.28.5, 10.1	© •		••	
Earthquake	28-1	The contractor will prepare the disaster prevention equipment and management manual during the construction/closing phase.	Section 7.29.5, 10.1	0	•		
	28-2	The project proponent/tenants will comply with the required standard (so far Provisional Myanmar National Building Code 2012) in accordance with the TSMC's Standard Operational Procedure (SOP) for building construction and fire safety.	Section 7.29.5, 10.1	••	_	••	•
	28-3	The project proponent/tenants will implement emergency drill during the operation phase.	Section 7.29.5	•		•	
	28-4	The project proponent/tenants will prepare the disaster prevention plan such as emergency contact list during the	Section 7.29.5, 10.1	•		⊚●	

	No. Commitment	EIA	1	mpleme mining (sponsible nting (● (▲) (if a izations)	
Field	No.	Commitment	Reference	Project Proponent	Contractor	Tenant	TSMC
		operation phase.					
Global Warming	29-1	The contractor will control GHGs emission in the construction work during the construction/closing phase	Section 7.30.5, 10.1				
		by implementing such activities as management of operation time of construction machineries, avoidance of excessive loading operation, and education of construction workers/drivers about the idling stop practice for construction machineries and vehicles.		0	•		
	29-2	The tenants will control GHGs emission generated from its own factory during the operation phase.	Section 7.30.5, 10.1			•	
	29-3	The tenants will consider to install energy-saving equipment and fuels that emit less GHG in their factory.	Section 7.30.5			O	
	29-4	The tenants will provide commute bus during the operation phase.	Section 7.30.5, 10.1			•	

Note:

Supervise/ Responsible Organization, ●Implementing Organization, ▲Examining Organization Source: EIA Study Team

Annex 10-2

Environmental Monitoring Plan

Annex 10-2 Environmental Monitoring Plan

1. Environmental Monitoring Plan

Environmental monitoring plan including monitoring items, location, frequency and responsible organization at pre-construction stage, construction phase, and operation phase are shown in Table 1-1 to Table 1-3. Responsible organizations shall review the monitoring plan in accordance with the progress of the Project and status of the situation before monitoring, if necessary, and are in charge of monitoring and preparation of its results. The project proponent will submit the monitoring report at pre-construction phase, construction phase and operation phase to TSMC. Proposed monitoring form is attached in EMP as Attachment.

Table 1-1 Monitoring Plan (Pre-Construction Phase)

Category	Item	Location	Frequency	Responsible Organizations
Common	- Checking and revising the Environmental	Project Site	Once	Contractor
	Mitigation (as shown in Table 10.1-1, 10.1-2,			
	and 10.1-3 in the Final EIA report)and			
	Management Plan by reviewing the final			
	detailed design of the Project			
	- Checking the Environmental Monitoring Plan			
	during Construction prepared by Contractor			
Social Environment	- Monitoring of the implementation status of	Project Site	Once	TSMC
- Involuntary	Resettlement works such as provision of	and Relocation		
Resettlement,	assistance package for project affected	Site		
- Living and Livelihood	persons, and common assets			
- Vulnerable Group	- Monitoring of the implementation status for	Around	Once/year	TSMC
- Cultural Heritage/ Asset	CSR activities such as community support	Project Site		
	program			
Existing social infra-	- Securing of community accessibility	Around	Once	Contractor
structures and services		Project Site		

Source: EIA Study Team

Table 1-2 Monitoring Plan (Construction Phase)

Category	Item	Location	Frequency	Responsible Organizations
Common	- Monitoring of mitigation measures (as shown in Table 10.1-2)	Each location	Once/month	Contractor
Air Quality	- NO ₂ , SO ₂ , CO, PM _{2.5} , PM ₁₀	Construction site (1 point)*	1 week/3 months	Contractor
Water Quality	- Water temperature, pH, SS, DO, BOD ₅ , COD, coliforms, oil and grease, chromium	- Outflow of construction site to the creek (at least 3 sampling points/mixing point: i) discharge water, ii) upstream water, and iii) downstream water) ** - Well near the construction site (1 point)	Once/2 months	Contractor
Waste	- Amount and kind of solid waste	Construction site	Once/3 months	Contractor
Noise and Vibration	Noise and vibration level Traffic count	Preservation area such as residence around the proposed construction site (at least 1 point)	Once (24 hours)/3 months	Contractor
		Preservation site such as residence along the route for on-site vehicles (1point for noise and vibration and 2 points for	Once (24 hours)/3 months	Contractor

Category	Item	Location	Frequency	Responsible Organizations
		traffic count)		
Hydrology	Groundwater level Ground elevation level Consumption of groundwater amount	Well near the construction site	Once/ months	Contractor
Living and Livelihood/ Vulnerable Group/ Misdistribution of Benefit and Damage/ Children's Right	- The implementation status for CSR activities such as community support program	Around Project Site	Once/year	Project Proponent
Risks for Infectious Disease such as AIDS/HIV	- Awareness of infectious diseases	Construction site	Once/month	Contractor
Occupational Health and Safety	- Record of accidents and infectious diseases	Construction site	Once/month	Contractor
Community Health and Safety	- Record of accidents and infectious diseases related to the community	Around construction site	Once/month	Contractor
	- The implementation status for CSR activities such as community support program	Around Project Site	Once/year	Project Proponent

Source: EIA Study Team

Note: *Air quality monitoring site in the construction area should be selected in consideration of keeping the same location during construction phase.(A1 in Figure 1.1-1)

^{***} Traffic Count should be conducted at noise and vibration measurement section and construction gate of the Project.




Figure 1-1 Tentative Monitoring Point during Construction (Air, Noise and Vibration)

^{**} Water quality monitoring location should be selected at least three points for one discharge point to confirm the impact of the effluent water from the project site to the existing canal.




Figure 1-2 Tentative Monitoring Point during Construction (Water quality)

Table 1-3 Monitoring Plan (Operation Phase)

Survey Item	Item	Location	Frequency	Responsible Organizations
Common	- Monitoring of mitigation measures (as shown in Table 10.1-3of the Final EIA report)	Project site	Quarterly (3 years after operation) Yearly (after 3 years operation)	Project Proponent
Air Quality	- NO ₂ , SO ₂ , CO, PM _{2.5} , PM ₁₀	Representative point inside the project area	1 week each in the dry and rainy seasons (first 3 years after starting of the operation stage)	Project Proponent
Water Quality	 Water temperature, water flow rate, pH, SS, DO, BOD₅, COD, color and odor, Total Nitrogen, Total Phosphorus, Sulphide, HCN, Oil, Grease, Formaldehyde, Phenols, Free chlorine, Zinc, Chromium, Arsenic, Copper, Mercury, Cadmium, Barium, Selenium, Lead, and Nickel 	- Outflow of retention pond to the creek (at least 3 sampling points/mixing point: discharge water, upstream water, and downstream water)	Every month: Water temperature, pH, SS, DO, BOD ₅ , COD, color and odor, Every 3 month :all parameters	Project Proponent
Waste	Amount of non-hazardous waste management Amount of hazardous waste management	Each tenant	Twice/year (submission of the environmental report by the tenants)	Tenants
Soil Contamination	- Status of control of solid and liquid waste which causes soil contamination	Each tenant	Twice/year (submission of the environmental report by the tenants)	Tenants
Noise and Vibration	 Noise level at the monastery and residences Traffic count 	Tenants including Project Proponent	One time each in the dry and rainy seasons (first 3 years after starting the operation stage)	Tenants including Project Proponent
Offensive Odor	- Status offensive odor control by the tenants	Each tenant	Twice/year (submission of the environmental report by tenants)	Tenants
Bottom Sediment	- Water quality monitoring (as indicator of the pollution of the bottom sediment)	Same as the water quality monitoring	- Additional analysis on the bottom sediment of creek, in	Project Proponent

Survey Item	Item	Location	Frequency	Responsible Organizations
			case of finding continuous high concentration	
Hydrological Situation	- Checking the function of retention pond at heavy rain.	Retention pond	When the heavy rain	Project Proponent
Living and Livelihood/ Vulnerable Group/ Misdistribution of Benefit and Damage/ Children's Right	- The implementation status for CSR activities such as community support program	Around Project Site	Once/year	Project Proponent
Risks for Infectious Disease such as AIDS/HIV	- Status of measures against infectious diseases	Each tenant	Twice/year (Submission of the environmental report by the tenants)	Tenants including Project Proponent
Occupational Health and Safety	- Record of accidents and infectious diseases	Work site and office	Twice/year (Submission of the environmental report by the tenants)	Tenants including Project Proponent
Community Health and Safety	- Record of accidents and infectious diseases related to the community	Around the project site	Twice/year (Submission of the environmental report by the tenants)	Project Proponent
	- The implementation status for CSR activities such as community support program	Around Project Site	Once/year	Project Proponent

Source: EIA Study Team

2. Preparation of the Environmental Monitoring Report

2.1 Contents of the Environmental Monitoring Reports

Project proponent shall prepare the monitoring report and submit to Authorities on once at Pre-construction phase and on quarterly basis at Construction phase and on bi-annually base at Operation phase.

The contents of monitoring reports shall be including the latest result of the analysis and surround monitoring conditions, not limited as follows;

- -Objective of the Monitoring
- -Summary of Monitoring Activities
- -Project activities (summary of the construction work or operation work)
- -Difficulties encountered in implementing of the EMP and recommendations for remedying those difficulties and steps proposed to prevent or avoid similar future difficulties
- -Number and type of non-compliance with the EMP and proposed remedial measures and timelines for completion of remediation
- -Accidents or incidents relating to the occupational and community health and safety and the environment
- -Monitoring data on environmental parameters including sampling date, sampling and analysis method, sampling point, and laboratory result
- -Photos

2.2 Environmental Monitoring Form

Tentative Environmental Monitoring Form is shown as follows;

Environment Monitoring Form

The latest results of the below monitoring items shall be submitted to Authorities on once at Pre-construction phase and on quarterly basis at Construction Phase, and on bi-annually base at Operation Phase. The items, standards to be applied, measurement points, and frequency for each monitoring parameter are established based on the EIA Report for Thilawa Special Economic Zone Development Project (Industrial Area of Zone B). Should there be any changes to the original plan, such change shall be reviewed and evaluated by environmental expert.

 (1) General 1) Phase of the Project - Please mark the current phase. □ Pre-Construction Phase 2) Obtainment of Environmental Personal Project 		action Phase	☐ Operation Phas	<u>e</u>
Name of permits	Expected issuance date	Actual issuance date	Concerned authority	Remarks (Conditions, etc.)
Attached approval letter:				

3) Response/Actions to Comments and Guidance from Government Authorities and the Public

Monitoring Item	Monitoring Results during Report Period	Duration of Report Period	Frequency
Number and contents of formal comments made by the public		Same timing of	
N. I.		submission of	Upon receipt of comments/complaints
Number and contents of responses from Government agencies		Monitoring Report	

(2) Monitoring Results

1) Air Quality

Location	Item	Unit	Measured Value (Mean)	Measured Value (Max.)	Country's Standard	Target value to be applied	Referred International Standard	Frequency	Method	Note (Reason of excess of the standard)
Residential Area	NO ₂	ppm			None		To be Set			
	SO ₂	ppm			None		To be Set			
	CO	ppm			None		To be Set			
	PM _{2.5}	Ppm			None		To be Set			
	PM10	ppm			None		To be Set			
If yes, p	lease de	scribe t		f complains a	air quality in and its counter		ll in below the Counterme		□ No	-
- Are there	ent Poir any eff	_ luents t		in this monit	coring period?	☐ Yes			dand	
Location	Item	Unit	Measured Value (Mean)	Measured Value (Max.)	Country's Standard	Target value to be applied	Frequency	Method (Re	Note eason of the endard)	
					None	Refer the section				
					None	2.2 in EIA main				
					None	report				
Situations	<u>environ</u>	mental	y operation pl report from t	<u>enants</u>	ination in this	monitoring pe	eriod? 🗆 Ye	es. \Box	No	

If yes, please describe the contents of complains and its countermeasures to fill in below the table.										
Contents	of Issues	on Soi	l Contamina	tion	Countermeasures					
4) Noise <u>Noise Leve</u>	<u>1</u>									
Location	Item	Unit	Measured Value (Mean)	Measured Value (Max.)	Country's Standard	Target value to be applied	Referred International Standard	Frequency	Method	Note (Reason of excess of the standard)
Residential Area	Leq (day)	dB(A)			None		To be Set			
Along the road	Leq (night)	dB(A)			None		To be Set			
If yes, pl	any comp ease descr	laints fi		omplains ar		nonitoring peri neasures to fill	od? <u> </u>	ble.	<u>No</u>	
5) Solid Waste Measurement Point: Construction Site (Construction Phase), Storage for Sludge (Operation Phase) - Are there any wastes of sludge in this monitoring period?										
Item	G	enerate	ed Unit	Value		Solic	ı waste Manag	ement Activi	ities	

	from						
Amount of Sludge							
Amount of Sludge							
Amount of Sludge							
6) Ground Subside	dence and Hydr	ology					
Duration	Water Cor	sumption	Ground	d Level	Note		
(Week)	Quantity	Unit	Quantity	Unit	Note		
		m3/week		m			
		m3/week		m			
		m3/week		m			
		m3/week		m			
	complaints from	0	0		monitoring period? \Box Yes, \Box No so to fill in below the table.		
Contents of Complaints from Residents Countermeasures					Countermeasures		
- Are there any	Situations environmental report from tenants - Are there any serious issues regarding offensive odor in this monitoring period?						
Contents of Is	sues on Soil C	ontamination			Countermeasures		
8) Infectious disease, Working Environment, Accident Information from contractor (construction phase) or tenants (operation phase) - Are there any incidents regarding Infectious disease, Working Environment, Accident in this monitoring period? Yes, No No							
	tents of Incide				Countermeasures		

Note: If emergency incidents are	coccurred, the information shall	l be reported to the 1	elevant organizations and authorities imme	diately.	
9) Resettlement Works for Information from TSMC	•	(PAPs) and Com	mon Assets		
- Please describe the pro	gress and remarkable issu	ies (if any) to fill	in below the table.		
Rese	ntment Works		Progress in Narrative	Remarkable Issues	
D : 4 ACC 4 1 D	Land Acquisition and Re	elocation			
Project Affected Persons	Income Restoration Program				
Common Assets	Relocation				
If yes, please describe	es submitted, solved and p the contents of grievances Grievance	0 0	the table.	2011700	
Contents of Grievance Responses / Countermeasures					
	l l				
	Community Support Prog vities implemented in this the outline of CSR activit	monitoring peri			
- Are there any CSR activ	rities implemented in this	monitoring peri	to fill in below the table.	ion, Participant etc.)	
- Are there any CSR activ If yes, please describe	vities implemented in this the outline of CSR activity	monitoring peri	to fill in below the table.	ion, Participant etc.)	
- Are there any CSR activ If yes, please describe	vities implemented in this the outline of CSR activity	monitoring peri	to fill in below the table.	ion, Participant etc.)	


End of Document

Annex 11-1

Invitation Letter, Notice and List of Invitees for Public Consultation Meeting for EIA at Scoping Stage

Annex 11-1 Invitation Letter, Notice and List of Invitees for the Public Consultation Meeting for EIA at Scoping Stage

Invitation Letter for the Public Consultation Meeting for EIA on the Thilawa SEZ Development Project (Zone B)



(မှတ်ချက်- စုစုပေါင်းအစည်းအဝေး ၄ ကြိမ်ပြုလုပ်မည်ဖြစ်သော်လည်း တူညီသောအကြောင်းအရာများကိုသာ တင်ပြဆွေးနွေးမည် ဖြစ်ပါသည်။ စိတ်ပါဝင်စားသူများအနေဖြင့် ကြိုက်နှစ်သက်ရာ အစည်းအဝေးအချိန်တွင် တက်ရောက်နိုင်ပါသည်။)

၂။ ထို့အပြင်အဆိုပါစီမံကိန်း၏ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းဆိုင်ရာ နယ်ပယ်သတ်မှတ်ခြင်း အစီရင်ခံစာ (Scoping Report) မူကြမ်းအားအများ ပြည်သူသိရှိနိုင်စေရန်အတွက်အောက်ပါနေရာများတွင် ၂၃.၁၂.၂၀၁၅ နံနက်၁၀းဝ၀ နာရီမှ ၅.၁.၂၀၁၆ ညနေ ၄း၃၀နာရီအထိ အများပြည်သူအား ဖွင့်လှစ်ဖော်ပြ ပေးပါရန် မေတ္တာရပ်ခံအပ်ပါသည်။

- (၁) ရန်ကုန်တောင်ပိုင်းခရိုင်အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန
- (၂) သန်လျင်မြို့နယ်အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန
 - (က) ဘုရားကုန်းကျေးရွာအုပ်စု အုပ်ချုပ်ရေးမျူးရုံး
 - (ခ) လက်ယက်စမ်းကျေးရွာအုပ်စု အုပ်ချုပ်ရေးမှူးရုံး
 - (ဂ) အလွမ်းဆွတ်ကျေးရွာအုပ်စု အုပ်ချုပ်ရေးမှူးရုံး
- (၃) ကျောက်တန်းမြို့နယ်အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန
 - (က) အေးမြသိတာရပ်ကွက် အုပ်ချုပ်ရေးမှူးရုံး
 - (ခ) ရွှေပြည်သာယာရပ်ကွက် အုပ်ချုပ်ရေးမှူးရုံး
 - (ဂ) သီတာမြိုင်ရပ်ကွက် အုပ်ချုပ်ရေးမျူးရုံး
 - (ဃ) ရွှေပေါက်ကျေးရွာအုပ်စု အုပ်ချုပ်ရေးမှူးရုံး
- (၄) သီလဝါအထူးစီးပွားရေးဇုန်စီမံခန့်ခွဲမှုကော်မတီရုံး (သီလဝါအထူးစီးပွားရေးဇုန်)

(၅) မြန်မာ-ဂျပန်သီလဝါဖွံ့ဖြိုးတိုးတက်ရေးလီမိတက်ရုံး

ဥက္ကဌ (ကိုယ်စား)

(ဒေါက်တာ သန်းအောင်၊ အတွင်းရေးမှူး)

မိတ္ထူကို

မြန်မာ-ဂျပန်သီလဝါဖွံ့ဖြိုးတိုးတက်ရေးလီမိတက် ရုံးလက်ခံ

List of Invitees for Public Consultation Meeting

နောက်ဆက်တွဲ (၁)

လူထုဆွေးနွေးပွဲဇိတ်ကြားမည့်စာရင်း

၁။ ဂန်ကြီး၊ ရန်ကုန်တိုင်းဒေသကြီးအစိုးရအဖွဲ့ ဂင်၊ သီလဂါအထူးစီးပွားရေးဇုံစီမံခန့်ခွဲမှုကော်မတီ။

၂။ ညွှန်ကြားရေးမှူး၊ ပတ်ဂန်းကျင်ထိန်းသိမ်းရေးဦးစီးဌာန၊ ရန်ကုန်မြို့။

၃။ အုပ်ချုပ်ရေးမျူး၊ အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန၊ရန်ကုန်တောင်ပိုင်းခရိုင်။

၄။ အုပ်ချုပ်ရေးမှူး၊ အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန၊ သန်လျင်မြို့နယ်။

၅။ အုပ်ချုပ်ရေးမှူး၊ အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန၊ ကျောက်တန်းမြို့နယ်။

၆။ မြို့နယ်အရာရှိ၊ စည်ပင်သာယာရေးအဖွဲ့ ၊ သန်လျင်မြို့နယ်။

၇။ မြိုနယ်အရာရှိ၊ စည်ပင်သာယာရေးအဖွဲ့၊ ကျောက်တန်းမြို့နယ်။

၈။ မြို့ရွာနှင့်အိုးအိမ်ဖွံဖြိုးရေးဦးစီးဌာန၊ ဆောက်လုပ်ရေးပန်ကြီးဌာန၊ သန်လျင်မြို့နယ်။

၉။ မြို့နယ်အရာရှိ၊ ကျေးလက်ဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာန၊ သန်လျင်မြို့နယ်။

၁၀။ မြို့နယ်အရာရှိ၊ ကျေးလက်ဖွံ့မြိုးတိုးတက်ရေးဦးစီးဌာန၊ ကျောက်တန်းမြို့နယ်။

၁၁။ မြို့နယ်ကျန်းမာရေးအရာရှိ၊ ကျန်းမာရေးဦးစီးဌာန၊ သန်လျင်မြို့နယ်။

၁၂။ မြို့နယ်ကျန်းမာရေးအရာရှိ၊ ကျန်းမာရေးဦးစီးဌာန၊ ကျောက်တန်းမြို့နယ်။

၁၃။ သီလဂါအထူးစီးပွားရေးဇုံအနီးရှိကျေးရွာအုပ်ချုပ်ရေးမှူးများနှင့် ရွာသူရွာသားများ။

က။ သန်လျင်မြို့နယ်အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာနအောက်ရှိ

၁။ ဘုရားကုန်းကျေးရွာအုပ်စုရုံး

၂။ လက်ယက်စမ်းကျေးရွာအုပ်စုရုံး

၃။ အလွမ်းဆွတ်ကျေးရွာအုပ်စုရုံး

ခ။ ကျောက်တန်းမြို့နယ်အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာနအောက်ရှိ

၁။ အေးမြသီတာရပ်ကွက်ရုံး

၂။ ရွှေပြည်သာယာရပ်ကွက်ရုံး

၃။ သီတာပြိုင်ရပ်ကွက်ရုံး

၄။ ရွှေပေါက်ကျေးရွာအုပ်စုရုံး

၁၄။ မြန်မာ့ဆိပ်ကမ်းအာကာပိုင်၊ ပို့ဆောင်ရေးပန်ကြီးဌာန

၁၅။ သီလဂါအထူးစီပွားရေးဇုံ အတွင်းရှိ သက်ဆိုင်ရာ စက်ရုံများနှင့် ကုမ္ပဏီများ

၁၆။ စီမံကိန်းအားစိတ်ပါလင်စားသူများနှင့် အခြားအဖွဲ့ အစည်းများ။

သက်ဆိုင်သောအဖွဲ့ အစည်းမှ ဇိတ်ကြားမည့်သူစာရင်းများ

၁။ ဥက္ကဌ၊ သီလဂါအထူးစီးပွားရေးဇုံစီမံခန့် ခွဲမှုကော်မတီ

၂။ ဒုတိယဥက္ကဌ၊ သီလဂါအထူးစီးပွားရေးဇုံစီမံခန့် ခွဲမှုကော်မတီ

၃။ အတွင်းရေးမှူး၊ သီလဂါအထူးစီးပွားရေးဇုံစီမံခန့် ခွဲမှုကော်မတီ

၄။ အဖွဲ့ ဂင်များ၊ သီလဂါအထူးစီးပွားရေးဇုံစီမံခန့် ခွဲမှုကော်မတီ

၅။အဖွဲ့ ဝင်များ၊ One Stop Service Center၊ သီလဂါအထူးစီးပွားရေးဇုံ စီမံစန့် ခွဲမှုကော်မတီ

Notice for Public Consultation Meetings and Public Disclosure of the Draft Scoping Report of the Environmental Impact Assessment for the Thilawa SEZ Development Project (Zone B)

သီလဂါအထူးစီးပွားရေးဖုံဖွံ့ဖြိုးတိုးတက်မှုစီမံကိန်း (Zone B) အတွက် ပတ်ဂန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာမူကြမ်းအား အများပြည်သူများသို့ တင်ပြဆွေးနွေးခြင်း

ယခုအချိန်တွင် ဂျပန်မြန်မာဖွံ့ဖြိုးတိုးတက်မှုကော်မတီသည် သီလဂါအထူးစီးပွားရေးဖုံ ဖွံ့ဖြိုးတိုးတက်မှု စီမံကိန်း (Zone B)အတွက် ပတ်ပန်းကျင်ဆိုင်ရာထိရိုက်ဆန်းစစ်မှု အစီရင်ခံစာမူကြမ်းကို ပြင်ဆင်လျှက် ရှိပါသည်။ စီမံကိန်းနောက်ခံ၊ ဖြစ်နိုင်ခြေရှိသောထိခိုက်မှုများ နှင့် သဘာပပတ်ပန်းကျင်လေ့လာမှု အချက်အလက်များကို စီမံကိန်းပန်းကျင်ရှိ အများပြည်သူများ ရှင်းလင်းမြင်သာစေရန်နှင့် ပူးပေါင်းပါပင်လာနိုင်စေရန် တင်ပြဆွေးနွေးခြင်းကို၂၀၁၅ခုနှစ် ဒီဇင်ဘာ (၁၉)ရက်နှင့် (၂၂)ရက်နေ့များတွင် အောက်ပါအတိုင်း ကျင်းပပြုလုပ်ရန် စီစဉ်ထားသည်။

ထို့အပြင် အင်္ဂလိပ်ဘာသာဖြင့်ပြုစုထားသော အစီရင်ခံစာမူကြမ်းအပြည့်အစုံ နှင့် အနှစ်ချုပ်မြန်မာဘာသာ အစီရင်ခံစာမူကြမ်းတို့ကို အောက်ပါနေရာများတွင် ၂၀၁၅ခုနှစ် ဒီဇင်ဘာ (၂၃)ရက် မှ ၂၀၁၆ခုနှစ် ဇန်နပါရီ (၇)ရက် အထိ (အလုပ်လုပ်ရက် ၁၀ ရက်အတွင်း) တင်ပြထားရှိသွားမည်ဖြစ်ပြီး သဘောထားမှတ်ချက်များနှင့် ပေဇန်အကြံပြုချက်များကို အဆိုပါအချိန်နှင့် နေရာများတွင် တင်သွင်းနိုင် ပါသည်။

💠 အများပြည်သူများနှင့်တွေ့ဆုံဆွေးနွေးခြင်း

စဉ်	နေ့ရက်	အချိန်	စာရင်းပေးချိန်	နေရာ
ပထမအချိန်	၂၀၁၅၊ ဒီဇင်ဘာလ	နံနက် (၉:၃၀) မှ (၁၀:၄၅) နာရီ	နံနက် (၉:၀၀) မှစတင်	အစည်းအပေးခန်းမ၊ မြို့ရွာနှင့်အိုးအိမ်ဖွံဖြိုးရေး ဦးစီဌာန၊ သီလဂါအထူးစီးပွားရေးစုံ စီပံခန့်ခွဲမှုကော်မတီ၊ ကျောက်တန်းမြို့နယ်။
ဒုတိယအချိန်	(၁၉)ရက် (စနေနေ့)	နေ့လည် (၃:၀၀) မှ (၄:၁၅) နာရီ	နေ့လည် (၂:၃၀) မှစတင်	
တတိယအချိန်	၂၀၁၅၊ ဒီဇင်ဘာလ	နံနက် (၉:၃၀) မှ (၁၀:၄၅) နာရီ	နံနက် (၉:၀၀) မှစတင်	
စတုတ္ထအချိန်	(၂၂)ရက် (အင်္ဂါနေ့)	နေ့လည် (၃:၀၀) မှ (၄:၁၅) နာရီ	နေ့လည် (၂:၃၀) မှစတင်	

မှတ်ချက်။

- ၁။ ကြို/ပို့ယာဉ်များအား စီစဉ်ထားမည်ဖြစ်ပြီး၊ အချိန်နှင့်စုရပ်နေရာများအား သက်ဆိုင်ရာကျေးရွားအုပ်စုရုံး များတွင်ကြိုတင်ကြော်ငြာပေးမည်ဖြစ်သည်။
- ၂။ အစည်းအဂေးအချိန်(၄)ခုလုံးတွင် တင်ပြဆွေးနွေးမည့်အကြောင်းအရာမှာ အားလုံးအတူတူဖြစ်သဖြင့် မိမိအဆင်ပြေရာအချိန်ကိုတက်ရောက်နိုင်ပါသည်။

- တင်ပြထားရှိမည့်နေရာများ
- ၁။ ရန်ကုန်တောင်ပိုင်းခရိုင်အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန
- ၂။ သန်လျင်မြို့နယ်အထွေထွေအုပ်ချုပ်အုပ်ချုပ်ရေးဦးစီးဌာန
 - (က) ဘုရားကုန်းကျေးရွာအုပ်စုရုံး
 - (စ) လက်ယက်စမ်းကျေးရွာအုပ်စုရုံး
 - (ဂ) အလွမ်းဆွတ်ကျေးရွာအုပ်စုရုံး
- ၃။ ကျောက်တန်းမြို့နယ်အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန
 - (က) အေးမြသီတာရပ်ကွက်ရုံး
 - (ခ) ရွှေပြည်သာယာရပ်ကွက်ရုံး
 - (ဂ) သီတာမြိုင်ရပ်ကွက်ရုံး
 - (ဃ) ရွှေပေါက်ကျေးရွာအုပ်စုရုံး
- ၄။ သီလပါအထူးစီးပွားရေးဇုံစီမံခန့်ခွဲမှုကော်မတိရုံး
- ၅။ မြန်မာ-ဂျပန်သီလဂါဗွံ့ဖြိုးတိုးတက်ရေးလီမီတက် (MJTD)

လူကြီးမင်း၏ပူးပေါင်းပါဂင်အားအထူးလိုလားပါသည်။

Annex 11-2

Presentation Materials, Handout and Sample of the Feedback Form in Myanmar Language for Public Consultation Meeting for EIA at Scoping Stage

ဟက်တာ

၂၆၂ ခန့် ၂၆၇ ခန့်

အပိုင်း(က)

အလူးစီးပွာ ပြင်ပ

သယ်ယူပို့ဆောင် ရေး

Annex 11-2 Presentation Materials, Handout and Sample of the Feedback Form in Myanmar Language for Public Consultation Meeting for EIA at Scoping Stage

Presentation Material used at PCM at Scoping Stage



အစီအစဉ်

- သီလဝါအထူးစီးပွားရေးဇုန် အပိုင်း (စ) စီမံကိန်း မိတ်ဆက်နှင့် ဖော်ပြချက်
- ၂။ နယ်ပယ်သတ်မှတ်ရာတွင် သဘာဝနှင့် လူမှုဝန်းကျင်သက်ရောက်နိုင်မှုများ
- EIA တွင်လေ့လာမည့်အကြောင်းအရာများ
- ရှေ့ဆက်လုပ်ဆောင်မည့် EIA အချိန်ဇယား
- အမေး၊ အဖြေ ၅။



၁. အဝိုင်း(ခ)စီမံကိန်းမိတ်ဆက်နှင့်ဖော်ပြချက် ၁. အပိုင်း(ခ)စီမံကိန်းမိတ်ဆက်နှင့်ဖော်ပြချက် လူထူတွေ့ ဆုံပွဲကျင်းပရခြင်းရည်ရွယ်ချက် တိုးချဲ့ မည့်အစီအစဉ် လူထုတွေ့ ဆုံပွဲအား စီမံကိန်းရေးဆွဲကာလအတွင်းကျင်းပခြင်းဖြစ်ပြီး သက်ဆိုင်သူများ၏ စက်မှုလုပ်ငန်း သယ်ယူပို့ဆောင်စေ သဘာဝနှင့် လူမှုဝန်းကျင်များအပေါ် သက်ရောက်နိုင်ရြေအကြီညက်များကို ရယူကာ EIA လေ့လာဆန်းစစ်မှုများအား ပိုမိုထိရောက်စွာလုပ်ဆောင်နိုင်ရန်ဖြစ်သည်။ လူနေနင့် ကုန်သွယ် စုစုပေါင်း ဂုဝဝ ခန့် မှတ်ချက်။ စရိယာသတ်မှတ်ချက်မှာ အပြောင်းအလဲရှိနိုင်ပါသည်။ စီမံကိန်းအချက်အလက်များဖြစ်သော ရည်ရွယ်ချက်၊ အစီအစဉ်၊ သက်ရောက်နိုင်ခြေများ၊ လျော့ပါးစေရေးနည်းလမ်းများနှင့် အချိန်ဇယား စသည်တို့အားအသိပေးရန် ၂. စီမံကိန်းရေးဆွဲကာလအတွင်း သက်ဆိုင်သူများ၏ အကြံဉာက်များရယူခြင်း လူထုတွေ့ ဆုံပွဲမှရရှိသော အကြံဉာက်များအား စီမံကိန်းရေးဆွဲရာတွင် စက်မှုလုပ်ငန်း ထည့်သွင်းစဉ်းစားခြင်း ူ လူနေနင့် ကုန်သွယ် ၄. စီမံကိန်း၏ သဘာဝနှင့် လူမှုဝန်းကျင်သက်ရောက်မှုများအား အသိပေးရန်

၁. အဝိုင်း(၁)စီမံကိန်းမိတ်ဆက်နှင့်ဖော်ပြချက်

အခြေစံအဆောက်အခြီတိုးရှဲ့ ရေးအစီအစဉ် (၁)

မြေညှိခြင်း (ပင်လယ်ရေမျက်နှာပြင်အမြင့်)

- မှုကိုမှ (လင်လာသနေရှိကနာ ညေဒခြာမှု) စက်မှုလုပ်ငန်းစရိယာများအတွက် မျက်နာပြင်အမြင့် ၅ဝိတာအထက်မှ ၆.၅ ဝိတာထိ (ဖရိယာနယ်နှစ်တ်တွင် အမြင့် ၆ဝိတာအထက်မှ ၆.၅ဝိတာအထိ)
- သယ်ယူပို့ဆောင်ရေး၊ လူနေနှင့် ကုန်သွယ်ဧရိယာများအတွက် အမြင့် ၅ မီတာအထက်

- ရေဖြန့်ဝေခြင်း အပိုင်း(က)ရှိရေသန့်စင်စက်ရုံမှုရေအားဖြန့်ဝေခြင်း ၂၀၁၉ဝန်းကျွင်တွင်လုပ်ဆောင်မည့် အများပြည်သူသုံးရေပိုက်လိုင်းသို့ ဆက်သွယ်ခြင်း

ရေဆိုးသန့်စင်ခြင်း

- က်ယူလုဝ်ငန်းဖရိယာတွင် ဗဟိုရေးဆုံးသန့်စင်စက်ရုံတည်ဆောက်ရန် (မူဝါဒများအားအခြင်၍ စက်ရုံတစ်ရုံချင်းစီတွင် ပထမရေသန့်စင်စနစ်အားထားရှိရန်) သယ်ယူပို့ဆောင်ရေး၊ လူနေနှင့် ကုန်ယွယ်စရိယာများတွင် စီလွှာကန်များထားရှိခြင်း

၁. အပိုင်း(စ)စီမံကိန်းမိတ်ဆက်နှင့်ဖော်ပြချက်

အခြေစံအတောက်အခိုတိုးရဲ့ ရေးအစီအစဉ် (၂)

- ဖရစမြာင်းများ စက်မှုဇုန်ဖရိယာများတွင် သိုလှောင်ကန်နှင့်မြောင်းများတဆင့် လက်ရှိရေမြောင်းအတွင်း
- စွန့်ထုတ်ခြင်း သတိယူပို့ဆောင်ရေးရရိယာ၊ လူနေနှင့် ကုန်သွယ်ရရိယာများတွင် လက်ရှိရေပြောင်း အတွင်းတိုက်ရိုက်စွန့်ထုတ်ဖြင်း


- လေများ ရှေ့-နောက်နှင့် တောင်-မြောက်လမ်းမကြီးများ၊ စက်မှုဝန်အတွင်း အကွက်လိုက်ပိုင်းထားသကဲ့သို့ လမ်းသွယ်များတည်ထောက်ဖြင်း သယ်ယူပို့ဆောင်ရေးရရိယာ၊ လူနေနှင့် ကုန်သွယ်စရိယာများတွင် လမ်းမကြီးများနှင့် လမ်းသွယ်များတည်ထောက်ဖြင်း

စွန့်ပစ်အဝိုင်အခဲစီမံခြင်း

- ောက်နိုင်သမှုပြန်လည်အသုံးပြုရန် အပိုင်း(က)၏ စွန့်ဝစ်ပစ္စည်းသန့်စင်အဖွဲ့ ပု စိပ်ခန့်ခွဲရန် ရန်ကုန်စည်ပင်သာယာရေးကော်ဖတီမှ သိမ်းဆည်းသန့်စင်ရန်

၁. အဝိုင်း(ခ)စီမံကိန်းမိတ်ဆက်နှင့်ဖော်ပြချက်

အဝိုင်း(ခ)အတွက်ရွေးချယ်စရာနည်းလမ်းများအကျဉ်းချုပ် (၁)



၁. အပိုင်း(၁)စီမံကိန်းမိတ်ဆက်နှင့်ဖော်ပြချက်

အပိုင်း(စ)အတွက်ရွေးချယ်စရာနည်းလမ်းများအကျဉ်းချုပ် (၂)

နည်းလမ်း (က)	နည်းလမ်း (စ)
 အရှေ့ဘက်နှင့် မြောက်ဘက်ရှိ အပြင်လမ်းမကြီး တွင်ဂိတ်နှစ်ခုထားရှိခြင်းဖြင့် ယာဉ်ကြောကျပိတည်းမှု လျော့ပါးစေခြင်း 	✓အရှေ့ဘက်ရှိလမ်းမကြီးတွင် ဂိတ်တစ်ခုတည်း ထားရှိခြင်းဖြင့် ယာဉ်ကြောကျပ်တည်းမှု ပိုခိုစေခြင်း
 စရိယာ(၁)နှင့်(၂)အတွင်း အိမ်ထောင်စု ၁၅ဝ မှ ၂၀၀ ရန်မြောင်းရွေ့ရနို < လှုမျှဝန်းကျင်အဝပါ သက်ရောက်နိုင်ခြေနည်း၍ မြန်လည်နေရာချထားဖရာအတွက် နှစ်နာကြေး အနည်းငယ်သာလိုအပ် 	

အားရွေးရယ်ထားပါည်။

၁. အပိုင်း(၁)စီမံကိန်းမိတ်ဆက်နှင့်ဖော်ပြချက်

အပိုင်း(ခ)အတွက်ရွေးချယ်စရာနည်းလမ်းများအကျဉ်းချုပ် (၃)

ရှတောင်	စိမ်းကိန်းမရှိသည့်အဖြေအနေ	စိမ်ကိန်းရှိသည့်အခြေအနေ
φ <u>ρδιυρσ</u>	 ခရိယားစားလုံးတွင် အစီအဝဉ်မရှိ အဆင်ပြေသလိုဘိုးရဲ့မြင်း အစီအဝဉ်မရှိတိုးရဲ့မှုမောက်ပိုင်းတွင် အနာဂတ်တိုးရဲ့ ရန်အတွက် ကန့်သတ်မှုရှိခြင်း 	င် နေစ်တကူရည်ရွယ်ရျက်ရှိရှိ တိုးချဲ့ ရေအစီအစဉ်နှင့်အတူ အကျို့ခြစ်ထွန်းသော တိုးနဲ့ မှ
Bigologi	 - လက်ရှိအခြေအနေမှအနည်းငယ်လောအလုပ် အကိုင်များသာရရှိနိုင် - သီလင်္ဂအရာစီးပွားရေးရှိန်အနေဖြင့် စီးပွားရေး ခွဲ ခြို့မှာတာရှိအသက်ရှိနိုင် 	 အပိုင်း(၀)ပတ်ဝန်းကျင်တွင် ကုန်ကျစရိတ်သက်ထာသော အစခြင်းအဆောက်တခြင်မိုကိုန်းများခြင်းပေါင်း အလုပ်အကိုင်အခွင့်အလမ်း အများအမြားရခြင်
သဘာဝနှစ် ဂူမှုဝန်းကျင်	 ဘစ်အစဉ်မကျဝသာမြန်လည်နေရာချတားဝပမှန ဘစ်အစဉ်မကျဝသီးချိန်ခါတြာငှိ ပော့ ရှိနိုင်ဖွေ့ သဘာဝနင့်လူများနီးကျင် သုံးသပ်ချက်ရှင်တျေးမှုနေး 	ဘဘာဝမတီဝနီးကျွန်နှင့် ဂုဒ္ဓမတီဝနီးကျွန်အခပါ သက်ရောက်နိုင်စုံဖြူချား စနစ်တောက်ရှိနဲ့ ရှိချန်း သဘာဝမတီဝနီးကျွန်သက်ရောက်မှုများ အား မကျွာမ်းစေခြင်း ဒေသင်များအတွက် အခြေစံအသောက်အဦးများနှင့် နေတီင်မှုရှန်းကျွန်းများ တို့အာက်တာနိုင်ခြင်း

၂. သဘာဝနှင့်လူမှုရေးသက်ရောက်မှုများ (နယ်ပယ်သတ်မှတ်ခြင်း)

ဆောက်လုပ်ရေးနှင့်လည်ပတ်ရေးကာလအတွင်းကောင်းကျိုးသက်ရောက်မှုများ

သက်ရောက်မှုအမျိုးအစား	မျှင်မှန်းသက်ရောက်နိုင်ခြေများ	
စီးပွားရေးတိုးတက်မှ	အပိုင်း(ခ)အတွင်းနှင့် ဝန်းကျင်တွင် စီးပွားရေးလုပ်ငန်းများပိုမို ရဲ့ထွင်လာနိုင်ခြင်း	
အလုပ်အကိုင်အစွင့်အလမ်း	ဆောက်လုပ်ရေးနှင့်လည်ပတ်ရေးကာလအတွင်း အလုပ်အကိုင်များ ဖန်တီးပေးနိုင်ခြင်းနှင့် လူနေမှုဘဝများပိုမိုကောင်းမွန်လာစေခြင်း	
အခြေစံအဆောက်အဦ	အပိုင်း(စ)ဝန်းကျင်တွင် လူမှုအဆောက်အဦများတိုးတက်လာခြင်းနှင့် အတူလမ်းပန်းဆက်သွယ်ရေးများဇွဲ့ဖြိုးလာစေခြင်း	
အငယ်စာရီမြို့ပြစနစ်	အပိုင်း(ခ)ဝန်းကျင်တွင် လူအများအပြားရောက်ရှိခြင်းနှင့် စီးပွားရေးလုပ်ငန်းများပိုမိုချဲ့ထွင်လာနိုင်ခြင်းကြောင့် အငယ်စားမြို့ပြစ်နစ်ဖြစ်ပေါ်လာစေနိုင်ခြင်း	

၂, သဘာဝနှင့်လူမှုရေးသက်ရောက်မှုများ (နယ်ပယ်သတ်မှတ်ခြင်း)

ဆောက်လုပ်ရေးမတိုင်မီနှင့်ဆောက်လုပ်ရေးကာလ (ညစ်ညစ်းမှုနှင့်သဘာဝပတ်ဝန်းကျွင်)

သက်ရောက်မှုအမျိုးအစား	အဆင့်	မျှော်မှန်းသက်ရောက်နိုင်ခြေများ
လေထုအည်ေအသွေး	B-	ဆောက်လုပ်ရေးယုန္တရာများနှင့်ယာဉ်များမှ လေထုညစ်ညမ်း စေသည့်အရာများနှင့်ဖုန်မှုန့်များထွက်ရှိနိုင်ခြင်း၊
ရေထုအရည်အသွေး	В-	မြေသားညှိခြင်းလုပ်ငန်းကြောင့် ရွှံ့ရည်များမြစ်အတွင်းသို့ စီးဝင်နိုင်ခြင်း။
စွန့်ပစ်ပစ္စည်း	B-	ထောက်လုပ်ရေးလုပ်ငန်းနှင့် အလုပ်သမားများမှ စွန့်ပစ်ပစ္စည်းများ ထွက်ရှိနိုင်ခြင်း၊
မြေဆီလွှာ	B-	စီမံကိန်းဖရိယာအတွင်း မြေဆီလွှာညစ်ညမ်းမှုသည် ပြင်ပသို့ပျံနှံနိုင်ခြင်း။
အသံနှင့်တုန်ခါမှု	B-	ဆောက်လုပ်ရေးယန္တရာများနှင့်ယာဉ်များကြောင့် အသံနှင့်တုန်ခါမှုများ ပိုမိုထွက်ရှိနိုင်ခြင်း။
g(C)G03	В-	မြေယာပြုပြင်ခြင်းကြောင့် ဇလဗေဒဆိုင်ရာသက်ရောက်မှု ယာယီရှိနိုင်ခြင်း။

၂. သဘာဝနှင့်လူမှုရေးသက်ရောက်မှုများ (နယ်ပယ်သတ်မှတ်ခြင်း)

သက်ရောက်မှုအမျိုးအစား	အဆင့်	မျှော်မှန်းသက်ရောက်နိုင်ခြေများ
ပြန်လည်နေရာချထားခြင်း	A-	အပိုင်း(စ)ဧရိယာအတွင်း မြေနေရာရယူခြင်းနှင့် ပြန်လည်နေရာချထားခြင်း
နေထိုင်မှုနှင့်အသက်မွေးမှု	Α-	စီမံကိန်းသက်ရောက်သူများမှ လယ်ယာမြေများနှင့် သီးနံစိုက်ခင်းများဆုံးရှုံးနိုင်ခြင်း
လက်ရှိအခြေခံအဆောက် အဦများနှင့်ဝန်ဆောင်မှုများ	В-	ထောက်လုပ်ရေးယာဉ်များကြောင့် ယာဉ်ကြော ဝိတ်ဆိုမှုစြစ်ပေါ် လာနိုင်ခြင်း၊ ကျောင်း၊ ထေးရုံ ရေးဆိုင်များသို့ သွားလာရေးလမ်းကြောင်းပြောင်းလဲ လာနိုင်ခြင်း၊
ယဉ်ကျေးမှုအမွေအနစ်	B-	အပိုင်း(စ)အတွင်းရှိ သုသာန်နှင့် ဟိန္ဒူဘုရားကျောင်းအား သက်ရောက်မှုရှိနိုင်ခြင်း၊
လူထုကျန်းမာရေးနှင့် လုံခြုံရေး	B-	ဆောက်လုပ်ရေးလုပ်သားများဝင်ရောက်လာခြင်းနှင့် ယာဉ်သွားလာမှုများပြားလာခြင်းကြောင့် လူထုကျန်းမျာရေးနှင့် လုံခြုံရေးအပေါ် သက်ရောက်နိုင်ခြင်း

၂. သဘာဝနှင့်လူမှုရေးသက်ရောက်မှုများ (နယ်ပယ်သတ်မှတ်ခြင်း)

လည်ပတ်ကာလ (ညစ်ညမ်းမှုနှင့်သဘာဝပတ်ဝန်းကျင်)

သက်ရောက်မှုအမျိုးအစား	ဘထင်	မျှော်မှန်းသက်ရောက်နိုင်စြေများ
လေထုအရည်အသွေး	B-	ယာဉ်များ၊ စက်ရုံများနှင့် ကုန်သွယ်ရေးလုပ်ငန်းများ စသည်တို့မှ လေထုညစ်ညမ်း စေသည့်အရာများနှင့် ဗုန်မှုန့်များထွက်ရှိနိုင်ခြင်း၊
ရေထုအရည်အသွေး	B-	ဌားရမ်းလုပ်ကိုင်သည်လုပ်ငန်းများ၊ ကုန်သွယ်ရေးလုပ်ငန်းများ စသည်တို့မှထွက်ရှိသော စွန့်ပစ်ရေများသည် ရေအရည်အသွေးပေါ် သက်ရောက်နိုင်ခြင်း။
စွန့်ပစ်ပစ္စည်း	B-	စက်မှုရန်ခရိယာတွင် စက်မှုလုပ်ငန်းများမှုစွန့်ပစ်ပစ္စည်းများ ထွက်ရှိနိုင်ခြင်း။ လူနေစရိယာတွင် သယ်ယူဒို့စထာင်ခြင်း၊ အိမ်သုံးနှင့် ရောင်းပယ် ခြင်းများကြောင့် အိမ်သုံးစွန့်ယစ်စွည်းများထွက်ရှိနိုင်ခြင်း
အသံနှင့်တုန်ခါမှ	В-	ယာဉ်များ၊ စက်ရုံများနှင့် ကုန်သွယ်ရေးလုပ်ငန်းများ စသည်တို့ကြောင့် အသံနှင့်တုန်ခါမှုများ ပိုမိုထွက်ရှိနိုင်ခြင်း
800603	B-	ဖွဲ့ မြိုးရေးစရိယာများတည်ရှိနေခြင်းကြောင့်ဇလပေဒဆိုင်ရာ သက်ရောက်မှုရှိနိုင်ခြင်း။
အောက်ခြေအနည်အနစ်	B-	ဌားရမ်းနေထိုင်သူများနှင့် ရောင်းဝယ်ဖောက်ကားမှုများမှ စွန့်ပစ်ရေ များသည်အောက်ခြေအနည်အနှစ် ဖြစ်ထွန်းမှုအား သက်ရောက်စေ့ နိုင်ပါသည်။

၂. သဘာဝနှင့်လူမှုရေးသက်ရောက်မှုများ (နယ်ပယ်သတ်မှတ်ခြင်း)

လည်ပတ်ကာလ (လူမှဝန်းကျင်၊ ကျန်းမာရေး၊ လုံရြံမှု၊ အရေးပေါ် အခြေအနေစသည်)

သက်ရောက်မှုအမျိုးအစား	အဆင့်	မျှော်မှန်းသက်ရောက်နိုင်ခြေများ
နေထိုင်မှုနှင့်အသက်မွေးမှု	В-	စီမံကိန်းသက်ရောက်သူများ၏ ဝင်ငွေအရင်းမြစ်များ (စပါး သီနှံစိုက်ပျိုးခြင်းစသည်) ဆုံးရှုံးနိုင်ခြင်း။
လူထုကျန်းမာရေးနှင့် လုံခြုံရေး	B-	အလုပ်သမားများအများအပြားဝင်ရောက်လာခြင်း၊ ယာဉ်သွားလာမှုများပြားလာခြင်းနှင့် အငယ်စားမြို့ပြစနစ် ပေါ်ပေါက်လာခြင်းတို့ကြောင့် လူထုကျန်းမာရေးနှင့် လုံခြုံရေးအပေါ် သက်ရောက်နိုင်ခြင်း၊
လက်ရှိအခြေခံအဆောက် အဦများနှင့်ဝန်ဆောင်မှုများ	B-	စီမံကိန်းသက်ရောက်သူများ၏ ကျောင်း၊ ဆေးရုံ၊ ရေးဆိုင်များသို့ သွားလာရေးလမ်းကြောင်းပြောင်းလဲ လာနိုင်ခြင်း၊
ရှုခင်း	B-/B+	ပတ်ဝန်းကျင်တွင် အငယ်စားမြို့ပြစနစ်ပေါ်ပေါက်လာခြင်း ကြောင့်ရှုခင်းပြောင်းလဲလာနိုင်ခြင်း။
ကမ္ဘာကြီးပူနွေးလာမှု	B-	ယာဉ်များ၊ စက်ရုံများနှင့် ကုန်သွယ်ရေးလုပ်ငန်းများ စသည်တို့မှ ဖန်လုံအိမ်ဓါတ်ငွေ့ ထုတ်လွှတ်နိုင်ခြင်း။

၃. EIA တွင်လေ့လာမည့်အကြောင်းအရာများ

အခြေခံလေ့လာမည့်အကြောင်းအရာများအကျဉ်းချုပ်(၁)



၃. EIA တွင်လေ့လာမည့်အကြောင်းအရာများ

အခြေခံလေ့လာမည့်အကြောင်းအရာများအကျဉ်းချုပ်(



	လေ့လာမည့်အကြောင်းအရာများအကျ) Olles
echonometricoeth	အကြောင်းအရာ	အရှိန်ကာလ
UMgelin	a. ၂၀၁၀ဟက်တာမြန်လည်နေရာချွတာ၊ရေးအစီအဝဉ်အတွက် ကောက်ယူထားသော ကွမှ- စီးပွာအချက်အလက်များနှင့် အခြားရှိပြီးအရက်အလက်မှားအာအသင့်မြှေပါမည်။	uriĝasŭ .
ယဉ်ကျေးမှု	 အနဦးလေ့လာမှနှင့်ဒေသခံမှာအားမေးမြန်းရက်မှာစာရ သူတာနိနင့်ဘုရားကျောင်းအား သက်ရောက်နိုင်သနှင့် လေ့လာမှုအားပြုလုပ်မည်။ ၂၀၀၀ဟက်တာပြန်းလည်နေရာရာအားမေးစစ်စေရှိအတွက် ကောက်ယူထားသော လူမှု- စီးပွားအချက်အလက်များကို အသုံးပြန်မည်။ 	၂၀၀၆ ဝန်နဝါရီ အထိ
လူထုတွေ့ဆုံ တွေးနွေးဖြင်း	 ကုတ်လေ့ပါတာရေးနှင့်အား (၂၉၆၆)ရှာလိုင်မည်။ (မှာဘာဝီဝေ့အပွဲနေရာန်နှင့် EIA မျှံတစ် အာင်ဝီ ဗေါ်လှုပ်တင်နေစဉ်) စီးတိုင်းရှာဖြင့် - သီလင်္ကလေ့စာရာကျနေရာန်နိုင်ငံရှိနေရာလုံးခြည်သူမှာ သင်္ဂလုံးနှင့် ကျော်လာခဲ့ရှိ နှင့် ယူနေရာမို့မှာမှာ တော်စိုင်သောကျောက်မှာပြေးမှာပ ရန်ကုန်ကိုင်အသည်ကြောင်ရာလည်း သတုမ်သွားရောန်သတွင်၍ ကုမ္ပက်ရာ။ အချားလည်းရှိသည်မှာမျှနှင့်ပိတ်လေ့အသည်။ 	၂၀၁၅ ဒီဝင်ဘာန ၂၀၁၆ မတိ
သတင်အချက် အလက်အသိပေး တင်ဖြစ်ပဲ၊	နေ့ပါလို့တွာတို့တို့ပြီးအစီရင်စံတုမှုကြို့မြောင့် EA အစီရင်စံတုမှုကိုမားက အတိပေတပိုင် မိန့်ချိန် အတိပေတပိုင် မိန့်ချိန် အတောင်ပိုရီမရှိတဲ့ အစီရင်စံတုမှုကြို့များအာတာကို မိန့်ချိန် မှန်ထားကိုပိုင်းမရှိနိုင် ရောက်ပြောနေ တကွက်ပြန်းမှု မှန်ထားကို မယ်ထွေးအပြင် တကွက်ပြန်းမှုနှင့် မယ်ထွေးအပြင် တကွက်ပြန်းမှာ မောင်မြောင်မှုနှင့် မယ်ထွေးအပြင် မောင်မြောင်မှာမှုကောင်မှန်မှုနောက်သောပြီး မောင်မြောင်မှာမှုကောင်မှန်မှုနောက်သောပြီး မောင်မြ	၂၀၁၅ ဒီဝင်ဘာန ၂၀၁၆ ဖတ်

၄. ရှေ့ဆက်လု	ပ်ဆောင်မည့် E	EIA အချိန်ဇယား
1000000	(000)	2006

market Samuel	ეიაჟ		Jook			
выбразыр	လောင်ဘာ/ အောက်တို့အာ	\$otion	Secon	player	Bohooo	uch
၁. စိမ်ကိန်းအစီအစဉ်များအားဆုံးဖြတ်ခြင်း			411			
၂. နယ်ပယ်သတ်မှတ်ဖြင်း	1 -					
နယ်ပယ်သတ်မှတ်ခြင်းအစီရင်စံတ မူကြစ်မြင်ဆင်ခြင်း						
လူထုတွေ့ဆုံဆွေးနွေးပွဲ/လူထူသို့ အသိပေးတင်ပြုခြင်း			^			
၃. ကွင်းဆင်းလေ့လာမှ မိုရောသီကွင်းဆင်းလေ့လာမှ ခြောက်သွေ့ ရာသီကွင်းဆင်းလေ့လာမှ						
g. EIA						
EIA အစီရှင်ခံတမူကြမ်းပြင်ဆင်ခြင်း လူထုတွေ့ဆုံဆွေးနွေးပွဲ/လူထူသို့ အသိပေးတင်ပြခြင်း						A

 အသေးစိတ်အချက်အလက်များအား ၂၀၁၅ ဒီစင်ဘာ (၂၁)ရက်မှ ၂၀၁၆ ဇန်နဝါရီ (၄)ရက်အတွင်း မြို့နယ်ရုံးများနှင့်ကျေးရွားအုပ်စုရုံးများတွင် တင်ပြထားရှိမည့်နယ်ပယ်သတ်မှတ်ခြင်း အဇီရင်ခဲ့စာ မူကြမ်းတွင်လေ့လာနိုင်ပါသည်။

ဆွေးနွေးပွဲတက်ရောက်ခြင်းအတွက် အထူးကျေးဇူးတင်ပါသည်။

အကြံဉာက်များလည်းပေးနိုင်ပါသည်။

Handout used at PCM at Scoping Stage

သဘာဝပတ်ဝန်းကျင်နှင့် လူမှုပတ်ဝန်းကျင်သက်ရောက်နိုင်ခြေ အလားအလာမျာ

သဘာလောင်နာကျွင်နှင့် ကုမ္ပလတ်နားကျွင်နှင့် ကုမ္မပတ်ဝန်းကျွင်တို့ကို အနည်းငယ်သိသာ ထင်ရှားစွာ
စိမ်ကိန်းသည် သဘာဝပတ်ဝန်းကျွင်နှင့် ကုမ္မပတ်ဝန်းကျွင်တို့ကို အနည်းငယ်သိသာ ထင်ရှားစွာ
သက်ရောက်နိုင်ပါသည်။ စောက်လုပ်ရေးလုပ်ငန်းများမတဝင်ဒီ စိမ်ကိန်းကြောင့် ပြောင်းရွေ့နေရာ
ရထားခြင်းများရှိနိုင်ပါသည်။ စိမ်ကိန်းစရိယာအတွင်း လယ်သမားအများစာသည် စိမ်တို့ပိုင်မြေတွင်ငှင်း၊
အစိုးရုပိုင်မြေတွင်ငှင်း စိုက်ဖြိုရေးရလုပ်ငန်းများ လုပ်ကိုင်ရနေကြသောကြောင့် ထောက်လုပ်ရေးအနှိန်နှင့်
စိမ်ကိန်းလည်မာတို့မြီးရန်များတွင် ၎င်းတို့အိုလူနေမှုဘများအား ထိန်ကိနိုင်ကြောင်းမျှမှုမှန်းရပါသည်။
ထိုထိစိုက်နိုင်ရြေနှင့် လျောက်မေစေနေနည်းလမ်းများအား ပြန်လည်နေရာချသားရေးအစီအစ် ရေးဆိုရန်
အတွက်သီးခြားလေ့လာအနားစပါမည်။
အခြားတစ်စက်တွင်မူ အနာဂတိစီးပွားရေးမှန်နဲ့ ဖြိုးတိုးစာကိရေးအရ ဆောက်လုပ်ရေးနှင့် လည်ပတ်ရေး
လုပ်ငန်းများ၏ အလုပ်အကိုင်စန်တီးဖေးမများကြောင့် ဒေသတွင်းဖီးပွားရေး တိုးစာက်လာနိုင်ပါသည်။
ထင်လောင်းရေးထိုထားသောရွံ မြိုးရေးအစီအမ်များအရ လူမှုအခြေခံအဆောက်အာဉ်များနှင့် စမြယာ
အနေအထားများအတွက်လည်း ကောင်းကျိုး သက်ရောက်နိုင်ပါသည်။
အောက်လုပ်ရေးအခြန်

အနေအထားများအတွက်လည်း ကောင်းကျီး သက်ရောက်နိုင်ပါသည်။ တောက်လုပ်ရေးအရိန် သဘာဝပတ်ဝန်းကျင်ဆိုးကျီးသက်ရောက်မှုများအနေခြင့် သစ်ပင်များ ဆုံးရုံခြင်း၊ ဇုန်ထခြင်၊ လေထုည်စည်ခေါ်ခြင်း၊ ထူညီသံနှင့်တုန်ခါမှုများ၊ အလုပ်သမားစခန်းများနှင့် မြေညှိခြင်းတို့မှထွက်ရှိလာမည့်ရေထိုးများစသည်တို့ကို လုပ်ငန်းလည်ပတ်စဉ်ကာလတွင်လည်း တိုးပွားလာမည့်ယာဉ်သွားလာမှုများအရ ဆူညံသံ၊ တုန်ခါမှုနှင့် လေထုညစည်းမြေများအား မျှော်မှန်းပါသည်၊ စက်ရှိအာလုပ်ရှိများနှင့် လူနေအိမ်ချားမှ ထွက်ရှိလာမည့် စွန့်ပစ်ရေ၊ အိမ်သုံးရေနှင့် စက်ရှိမှုစွန့်ပစ်ရေများအားလည်း မျှော်မှန်းထားပါသည်။ စီမံကိန်းအခြေခိုင် သဘာဝပတ်ဝန်းကျင် စီမံခန့်ခွဲမှုအစီအမံများနှင့် စောင့်ကြည့်ထိန်းချုပ်ရေ၊ အစီအမ်များ အတိုင်း အကောင်အထည်စော်တောင်ရွက်မည်ခြစ်ပါသည်။

အနာဂတ်လူထူတွေ့ ဆုံပွဲလုပ်ရှာမှုများ

အနားတဲ့ကူထူတွေ, ဆုံးပူးပူးမှုမှုမှုမှ ဒုတိယအကြိမ် လူထုတွေ့ ဆုံးပွဲအား ၂၀၁၆ခုနှစ် မတ်လအတွင်းပြုလုပ်ရန်နီပြီး ၄င်းတွင် စိတ်နီးမနာကိဆုံးအစီအစဉ်၊ သက်ရောက်နိုင်ဖြေလေ့လာမှုကောင်။ အထိုပြုပေးပြုပါဖေရေးနည်းလမ်း၊ ပတ်ဝန်းကျင်စိပ်ရန့်ရှိမှအစီအပ်နှင့် ဖောင်ကြည့်ရေးအစီအမ်များအား တင်ပြုမည်ဖြစ်ပြီး၊ အများပြည်သူများ ထံမှအကြည်ာက်များရယူမည်ဖြစ်သည်။ EIA အစီရင်မီစာမှုကြမ်းအား ပြင်ဆင်ရန်နှင့် ထံမှအကြံဉာက်များရယူမည်ဖြစ်သည်။ EIA အစီရင်ခံစာမှကြမ် အကြံဉာက်များရယူရန် တင်ပြထားရှိထားမည်ဖြစ်သည်။ အကြည်ကိများရယူရန် တပ် ပြန်လည်နေရာချထားရေးအစီအစဉ်အတွက် အရကျင်းပသွားမည်ဖြစ်သည်။ တွေ့ဆုံပွဲအားလည်း သီးခြားလေ့လာမှ

EIA သတင်းအရွက်အလက်များအတွက် ထစ်မံသိရိုလိုပါကအောက်ပါအတိုင်းထက်သွယ်ပါရန်

Environment, Safety and Health Section, Operations Department,

ဖုန်း - ဝ၉၂၅၉၀၁၆၇၆၄

ပတ်ဝန်းကျင်သက်ရောက်မှုဆန်းစစ်ခြင်းအတွက် လူထုတွေ့ ဆုံဆွေးနွေးပွဲ (နယ်ပယ်သတ်မှတ်ခြင်းအဆင့်)

> သီလဝါအထူးစီးပွားရေးဇုန်ဖွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်း အပိုင်း (ခ)

> > သတင်းအချက်အလက်တစဉ်

၂၀၁၅ခုနှစ်၊ ဒီဇင်ဘာလ (၁၉) ရက်နှင့် (၂၂) ရက်



မြန်မာ-ဂျပန်သီလဝါဗွံ့ဖြိုးရေးလီမိတက် (MJTD) မြန်မာသီလဝါအထူးစီးပွားရေးဇုန်အများပိုင်လီမိတက် (MTSH)

သီလဝါဇွံ့ဖြိုးတိုးတက်ရေးစီမံကိန်းနှင့် ဦးတည်ရက်များ

မြန်မာနိုင်ငံတော်အစိုးရသည် နိုင်ငံခြားတိုက်ရိုက်ရင်းနီးမြှုပ်နှံမှုအား နိုင်ငံတွင်းဖွဲ့ ဖြို့တိုးတက်မှု အရက်တစ်ရွက်အစနေပြင် လုပ်ဆောင်နိုပါသည်။ အထူးသဖြင့် နိုင်ငံတော်အစိုးရသည် ရန်ကုန်မြို့ အမြင်အဝန်းရှိ သီလဝါအထူးစီးပွားရေးစုန်အား စီးပွားရေးဖွဲ့ ဖြိုးတိုးတက်မှတွင် အရေးပါသောအခန်းကက္က အဖြစ်ရွှေးမှိုးနှဲ့အားပါသည်။ ယင်းအပြေအေနအရ မြန်မာနိုင်ငံနှင့် ကျပန်နိုင်ငံတို့သည် သီလဝါ အတူးစီးပွားရေးစုန်ဖွဲ့ ဖြို့ရေးအတွက် (အပေါင်းဆောင်ရွက်ရန် နားလည်မှုတရွန်လှာအား ၂၀၁၂နှစ် ဒီစင်ဘာလတွင် လက်မှုတ်ရေးတို့အကြေသည်။ ၂၀၁၃နှစ် အောက်တိုဘာတွင် Myanmar Thilawa SEZ Holdings Public Limited (MTSH) နှင့် MMS

၂၀၁၃ခုနှစ် အောက်တိုဘာတွင် Myanmar Thilawa SEZ Holdings Public Limited (MTSH) နှင့် MMS Thilawa Development Company (MMST) တို့သည် အတြံရာဘူးနေပါင်းမှုအဝနေခြင့် Myanmar Japan Thilawa Development Limited (MJTD) အားတူထောင်ရှိ စည်းဖြစ် အတူးစီးပွားရေးမှန်အတွင်း ဟက်တာ (၄၀၀) စန့်ရှိ အပိုင်း(က)အား ကနည်းအစနေခြင့် ရှိခြီးရေးမိုးကိန်းများကုပ်ထောင်စိုပါသည်။ MJTD သည် ခြစ်တန်ခြေလေ့ကာမှုကြီးမီးခြီး သီးဝပါအထူးစီးပွားရေးနှစ်စိဝန်ခွဲရေးကာမတီမှ EIA အစီရင်စိမာအားအောက်ညီပြော်နောက် ၂၀၁၃ခုနှစ် ဒီစင်ဘာလမှတော်ကာ ဆောက်လုပ်ရေးကုပ်ငန်းများ ကုပ်ဆောင်စိုပါသည်။ အပိုင်း(က)၏ အရှို့အစိတ်အပိုင်းများအား ကုပ်ငန်းလည်းပတ်ရန် ၂၀၁၅ခုနှစ် က်ေတင်ဘာလတွင် တရားဝင်ဖွင့်လှစ်ခဲ့ပါသည်။

စက်တင်ဘာလတွင် တရာစင်ဗွင့်လုစ်နဲပါသည်။ တို့အပြင် MVID သည် အခြား(ဂုလ)ဟက်တာတိုးရဲးခြင်းစိမ်ကိန်း (ယခုစိမ်ကိန်း)အား အကောင်ထည့်စော်ဆောင်ရန် စိစဉ်ခဲ့ပြီး ၎င်းတွင် စက်မှုလုပ်ငန်း (၂၆၂) ဟက်တာ၊ သယ်ပပုံငို့ဆောင်ရေး (၂၆၇)ဟက်တာနှင့် လူနေနှင့်ရောင်းစယ်ဖောက်ကားရေး (၁၆၉)ဟက်တာရန်ပါဝင်ပါမည်။ ယင်းစီမံကိန်းအတွက် သဘာဝဟတ်နေးကျင်နှင့် လူမှုဟတ်ဝန်းကျင်သက်ရောက်မှုများအား သိရှိနိုင်ရန် လေ့လာလှုနာကိန်ပြီး သင့်ဖတာ်သောကျောပ်အစေရေနည်းလမ်းများ၊ ဟတ်ဝန်းကျင်စီပံစန်း၌ သူ အစီအစဉ်နှင့် တောင်ကြည့် ရေး အစီအစဉ်များကို ရေးဆွဲစည်ဖြစ်ပါသည်။

လူထုတွေ့ ဆုံပွဲကျင်းပရမြင်းရည်ရွယ်ရက်

လူထုတွေ့ ထုံပွဲကျင်းပရခြင်းရည်ရွယ်ရက်မှာ အများပြည်သူနှင့် အခြားသက်ဆိုင်သူမျာ အကြံဥာက်များရသူ၍ စီစံကိန်းအစီအပ်များ၊ သက်ရောက်နိုင်ခြေဆန်းစစ်မှုပ ပတ်ဝန်းကျင်စီပံခန့်နဲ့ မှုအစီအစဉ်နှင့် စောင့်ကြည့် ရေးအစီအစဉ်မှားအပေါ် ငိုမိုတိုးတက် ကောင်းမွန်စေ ဖြစ်ပါသည်။ အများပြည်သူနှင့် အခြားသက်ဆိုင်သူများ၏ မံများ၊ သက်ရောက်နိုင်ခြေဆန်းစစ်မှုများ၊

- အဓိကရည်ရွယ်ရွက်များ
 စ စီမံကိန်းအကြောင်းအရာများမြင်သော အစီအစ်များနှင့် အမြိန်ကာလတို့ကိုသိရှိစေရန်
 စ စီမံကိန်း၏ ကောင်းကျို။ ထိုးကျိုးသက်ရောက်မှုများကို တင်ငြရန်
 လှုပ်ခဲ့သွေး သက်ဆိုင်သူများထိုမှ စီမံကိန်းစီမံရက်ကာလနှင့်ပက်သက်သော
 အကြံဥာက်များကိုရယူ၍ စီမံရက်ရေးဆွဲရာတွင် ထည့်သွင်းစဉ်းစားရန်


රූගරිණිකලේ ප්රතිභාග

- အင်ိုင်း (စ) အခန့်ခြင့် စုစုဝေပါင်း ဟက်တာ (၇၀၀)ခန့် ဖွံ့ ဖြီးရေးလုပ်ဆောင်ရန်
 အင်ိုင်း (စ)တွင် ဖွံ့ဖြီးရေးစရိယာ (၃)စုပါဝင်ပါသည်။ က်ေးမှုလုပ်ငန်း (၂၆၂)ဟက်တာခန့် ဆင်ပည့်ပို့တောင်ရေး (၂၆၅)ဟက်တာခန့်နှင့် လူနေနှင့်ရောင်းဝယ်ဖောက်ကားရေး
- (၁၆၉)ဟက်တာခန့်ပါဝင်ပါမည်။

 စီဖံကိန်းပါဝင်စက်များ MITD (စက်မူရန်အတွက်) နှင့်MTSH (သယ်ယူပို့ထောင်ရေး၊ လူနေနှင့် ရောင်းဝယ်တေက်ကားရေးစရိယာများအတွက်)

ဆိုပြုပြေယာအသုံးပြုမှုအစီအစဉ်နှင့် ဒ 3034p

- အဝိုင်း(က)ရှိရေသန့်စင်စက်ရုံမှ ရေအား ၂၀၁၉ ခုနစ်တွင်လုပ်ဆောင်မည် အများ ပြည်သူသုံးစေပိုက်လိုင်းသို့ ဆက်သွယ်ပေးခြင်း၊ • ဝဟိုရေဆိုးသန့်စင်စက်ရှံအား စက်မှုစုန်
- ဇရိယာတွင်တပ်ဆင်ခြင်းနှင့် မိလ္လာကန်များအား သယ်ယူပို့ဆောင်ရေး၊ လူနေနှင့် ရောင်းဝယ်ဖောက်ကားရေး ရိယာများတွင် ထားရှိခြင်း။
- အဓိကလမ်းမများနှင့် လမ်းသွယ်များအား ဇရိယာ (၃) ခုလုံးတွင်တည်ဆောက်<u>ခြ</u>င်း
- စက်မှုဇုန်ဧရိယာများအတွက် ပင်လယ် ရေမျက်နှာပြင်အဖြင့် ၅ မှ ၆.၅ ဓီတာ၊ သယ်ယူပို့ဆောင်ရေး၊ လူနေနင့် ရောင်းဝယ်ဖောက်ကားရေး ဇရိယာများ အတွက် ၅ မီတာ အထက်ထားရှိခြင်း



EIA ကေ့လာမှု၏ရည်ရွယ်ရှက်အကျဉ်း

သဘာဝပတိဝန်းကျင်နှင့် လူမှုပတ်ဝန်းကျင် ရှုထောင့်များအရ စီမံကိန်းအောင်မြင်စေရန် MJTD နှင့်
MTSH တို့သည်သဘာဝပတိဝန်းကျင်ရောလာ ထန်းစစ်ခြင်းများကိုလုပ်ဆောင်လျှက်ရှိပါသည်။
EIA လေ့လာခြင်းအရည်ရွယ်ချက်အကျဉ်မှာ

စီမံကိန်းကြောင့် ခြစ်ပေးလာနိုင်သော လူမှု/သဘာဝ ဝန်းကျင်သက်ရောက်မှုများအားလေ့လာ
အက်ဖြတ်နိုင်ရန်အတွက် သဘာတ/လူမှ ပတ်ဝန်းကျင်ဆိုင်ရာအခြေအချော်အလက်များကောက်ယူရန်

လူမှု/သဘာဝ ဝန်းကျင်ဆိုးကိုမှူးသက်ရောက်မှုများအား ပြောလွှာစေရန်အတွက် သင့်တော်သော
ပတ်ဝန်းကျင်စိပ်စန်၌မူ အစီအစဉ်နှင့် စောင့်ကြည့်ရေးအစီအဝဉ်များ ရေးဆိုရန်

Sample of the Feedback Form used at PCM at Scoping Stage

		ilawa SEZ Development Project (Zone B) င့်တွေ့ဆုံဆွေးနွေးပွဲ (နယ်ပယ်သတ်မှတ်ခြင်းအဆင့်)
	ocial issues related to the pr	onsultation Meeting. Your suggestions and oject will help us to improve the plan and
ဆွေးနွေးပွဲတက်ရောက်သည့်အတွက်အထူးပ	်ကျေးဇူးတင်ပါသည်။ လူကြီးမင်းတို့ ည် စီမံကိန်းတန်ပြန်သက်ရောက်မှုမျ	၏ စီမံကိန်းနှင့်ဆက်နွယ်သော သဘာဝ ပတ်ဝန်းကျင်နှင့် pး လျော့ချရာတွင်လည်းကောင်း၊ စီမံကိန်းအစီအမံများ
Date:		
ရက်စွဲ		
1. Name:		
အမည်		
2. Township:	3. Village:	3. Mobile (if possible):
မြို့နယ်	ကျေးရွာ	ဖုန်း
4. Age:	6. Gender – Male	Female
အသက်	ന്വാ:	ə <u> </u>
7. Occupation: အလုပ်အကိုင်		
8. Vulnerability (if applicable):		
(a) Women headed household အမျိုးသမီးဦးစီးသောအိမ်ထောင်စု	(b) Disabled heade မသန်စွမ်းသူဦးစီးသေ	
(c)Below poverty line household ဆင်းရဲသောအိမ်ထောင်စု	Elderly headed ho သက်ကြီးရွယ်အိုဦးစီးရ	usehold
Household with the Disabled မသန်စွမ်းသူပါဝင်သောအိမ်ထောင်စု		
8. Suggestion to the Project propo သဘာဝပတ်ဝန်းကျင်နှင့်ပတ်သက်၍ စီမံ		
9. Suggestion to the Project propo လူမှုဝန်းကျင်နှင့်ပတ်သက်၍ စီမံကိန်းဖေ		
10.0 d d D 1		
10. Suggestion to the Project proj စီမံကိန်းဖော်ဆောင်သူများသို့အခြားအကြ		er Concern
Thank you very much for your pa တက်ရောက်ခြင်းအတွက် အထူးကျေးဇူးပ ပေးစေလိုပါသည်။		this to the receptionist before you leave. ပြန်လည်မထွက်ခွာမီ သက်ဆိုင်သူများသို့

Annex 11-3

List of Attendee at Public Consultation Meeting for EIA at Scoping Stage

Annex 11-3 List of Attendee at Public Consultation Meeting for EIA at Scoping Stage

First Session December 19th, 2015 A.M.

THSU	Session December	19th, 2013 A.M.
No	Name	Village
1		Ah Lwan Swat
2		Ah Lwan Swat
3		Ah Lwan Swat
4		Ah Lwan Swat
5		Ah Lwan Swat
6		Aye Mya Thida
7		Ah Lwan Swat
8		Ah Lwan Swat
9		Ah Lwan Swat
10		Ah Lwan Swat
11		Ah Lwan Swat
12		Ah Lwan Swat
13		Ah Lwan Swat
14		Ah Lwan Swat
15		Ah Lwan Swat
16		Ah Lwan Swat
17		Ah Lwan Swat
18		Ah Lwan Swat
19		Ah Lwan Swat
20		Ah Lwan Swat
21		Ah Lwan Swat
22		Ah Lwan Swat
23		Ah Lwan Swat
24		Ah Lwan Swat
25		Ah Lwan Swat
26		Ah Lwan Swat
27		Ah Lwan Swat
28		Ah Lwan Swat
29		Ah Lwan Swat
30		Ah Lwan Swat
31		Ah Lwan Swat
32		Ah Lwan Swat
33		Ah Lwan Swat
34		Ah Lwan Swat
35		Ah Lwan Swat
36		Ah Lwan Swat
37		Ah Lwan Swat
38		Ah Lwan Swat
39		Ah Lwan Swat
40		Ah Lwan Swat
41		Ah Lwan Swat
42		Ah Lwan Swat
43		Ah Lwan Swat
44		Ah Lwan Swat
45		Ah Lwan Swat
46		Ah Lwan Swat
47		Ah Lwan Swat
48		Ah Lwan Swat
49		Ah Lwan Swat
50		Ah Lwan Swat
51		Ah Lwan Swat
52		Ah Lwan Swat
53		Ah Lwan Swat
54		Ah Lwan Swat
55		Ah Lwan Swat
56		Ah Lwan Swat
113		Ah Lwan Swat
114		Ah Lwan Swat
115		Ah Lwan Swat
116		Ah Lwan Swat

No	Name	Village
57	Tulle	Ah Lwan Swat
58		Pha Yar Kon
59		Kon Chan Kon
60		Ah Lwan Swat
61		Ah Lwan Swat
62		Ah Lwan Swat
63		Ah Lwan Swat
64		Ah Lwan Swat
65	_	Ah Lwan Swat
66		Ah Lwan Swat
67		Ah Lwan Swat
68		Hpa Yar Kon
69		Ah Lwan Swat
70		Ah Lwan Swat
71		Ah Lwan Swat
72		Ah Lwan Swat
73		Ah Lwan Swat
74		Ah Lwan Swat
75		Ah Lwan Swat
76		Ah Lwan Swat
77		Ah Lwan Swat
78		Ah Lwan Swat
79		Ah Lwan Swat
80		Ah Lwan Swat
81 82		Ah Lwan Swat
83		Ah Lwan Swat Ah Lwan Swat
84		Ah Lwan Swat
85		Ah Lwan Swat
86		Ah Lwan Swat
87		Ah Lwan Swat
88		7 III Ewall Swat
89		Aye Mya Thida
90		Aye Mya Thida
91		Ah Lwan Swat
92		Ah Lwan Swat
93		Ah Lwan Swat
94		Ah Lwan Swat
95		Ah Lwan Swat
96		Ah Lwan Swat
97		Ah Lwan Swat
98		Aye Mya Thida
99		Aye Mya Thida
100		Ah Lwan Swat
101		Ka Lar Kon
102		Ka Lar Kon
103		Ka Lar Kon
104		Ka Lar Kon
105		Thi Dar Myaing
106		Thanlyn
107		Ah Lwan Swat
108		Ah Lwan Swat
109		Ah Lwan Swat
110		Ah Lwan Swat
111		Ah Lwan Swat
112		Ah Lwan Swat
174		Ah Lwan Swat
175 176		Ah Lwan Swat Ah Lwan Swat
177		Ah Lwan Swat

No	Name	Village
117		Ah Lwan Swat
118		Ah Lwan Swat
119		Ah Lwan Swat
120		Ah Lwan Swat
121		Ah Lwan Swat
122		Ah Lwan Swat
123		Ah Lwan Swat
124		Ah Lwan Swat
125		Ah Lwan Swat
126 127		Ah Lwan Swat Ah Lwan Swat
128		Ah Lwan Swat
129		Ah Lwan Swat
130		Ah Lwan Swat
131		Ah Lwan Swat
132		Ah Lwan Swat
133		Ah Lwan Swat
134		Ah Lwan Swat
135		Ah Lwan Swat
136		Ah Lwan Swat
137		Ah Lwan Swat
138		Ah Lwan Swat
139		Ah Lwan Swat
140		Ah Lwan Swat
141		Ah Lwan Swat
142		Ah Lwan Swat
143		Ah Lwan Swat
144		Ah Lwan Swat
145		Ah Lwan Swat
146		Ah Lwan Swat
147		Ah Lwan Swat
148		Ah Lwan Swat
149		Ah Lwan Swat
150		Ah Lwan Swat
151		Hpa Yar Kon
152		Ah Lwan Swat
153		Ah Lwan Swat
154		Ah Lwan Swat
155		Ah Lwan Swat
156		Ah Lwan Swat
157		Ah Lwan Swat
158 159		Ah Lwan Swat Ah Lwan Swat
160		An Lwan Swat Ah Lwan Swat
161		An Lwan Swat
162		Ah Lwan Swat
163		Ah Lwan Swat
164		Ah Lwan Swat
165		Aye Mya Thida
166		Ah Lwan Swat
167		Aye Mya Thida
168		Ah Lwan Swat
169		Ah Lwan Swat
170		Ah Lwan Swat
171		Ah Lwan Swat
172		Ah Lwan Swat
173		Ah Lwan Swat
235		Ah Lwan Swat
236		Ah Lwan Swat
237		Ah Lwan Swat
238		Ah Lwan Swat
239		Ah Lwan Swat
240		Ah Lwan Swat
241		Ah Lwan Swat
242		Ah Lwan Swat

No	Name	Village
178		Ah Lwan Swat
179		Ah Lwan Swat
180		Ah Lwan Swat
181		Ah Lwan Swat
182		Ah Lwan Swat
183		Ah Lwan Swat
184		Ah Lwan Swat
185		Ah Lwan Swat
186		Ah Lwan Swat
187		Ah Lwan Swat
188		Ah Lwan Swat
189		Ka Lar Kon
190		Ka Lar Kon
191		Ka Lar Kon
192		Lat Yat San
193		Lat Yat San
194		Lat Yat San
195		
196		
197		
198		Lat Yat San
199		
		Development Committee
200		Ah Lwan Swat
201		Ah Lwan Swat
202		Ah Lwan Swat
203		Ah Lwan Swat
204		Aye Mya Thida
205		Ah Lwan Swat
206		Ah Lwan Swat
207		Ah Lwan Swat
208		Ah Lwan Swat
209		Ah Lwan Swat
210		Ah Lwan Swat
211		Ah Lwan Swat
212		Ah Lwan Swat
213		Ah Lwan Swat
	_	
214		Ah Lwan Swat
215		Ah Lwan Swat
216		Ah Lwan Swat
217		Ah Lwan Swat
218		Ah Lwan Swat
219		MJTD
220		MJTD
221		JICA
222		Aye Mya Thida
223		Aye Mya Thida
		Hpa Yar Kon
224		
225		Aye Mya Thida
226		Thilawa Old Village
227		Ah Lwan Swat
228		Ah Lwan Swat
229		Aye Mya Thida
230		Aye Mya Thida
231		Ah Lwan Swat
232		Aye Mya Thida
233		Aye Mya Thida
234		Ah Lwan Swat
285		Aye Mya Thida
286		Aye Mya Thida
287		Aye Mya Thida
288		Bago Su
289		GAD Kyauk Than
290		Ah Lwan Swat
291		Thida Myaing
292		Shwe Pyi Tha Yar

- N.T.	NT	X 7'11
No	Name	Village
243	_	Ah Lwan Swat
244	_	Pha Lan Old Village
245		Ah Lwan Swat
246	_	Aye Mya Thida
247	_	Aye Mya Thida
248		Aye Mya Thida
249		Aye Mya Thida
250		Aye Mya Thida
251		Aye Mya Thida
252		Aye Mya Thida
253		Aye Mya Thida
254		Aye Mya Thida
255		Ah Lwan Swat
256		Ah Lwan Swat
257		Aye Mya Thida
258		Aye Mya Thida
259		Ah Lwan Swat
260		Aye Mya Thida
261		Aye Mya Thida
262		Ah Lwan Swat
263		Ah Lwan Swat
264		Ah Lwan Swat
265		Ah Lwan Swat
266		Ah Lwan Swat
267		Thanlynn
268		Aye Mya Thida
269		Aye Mya Thida
270		Aye Mya Thida
271		Ah Lwan Swat
272		Ah Lwan Swat
273		Ah Lwan Swat
274		Ah Lwan Swat
275		Aye Mya Thida
276		Ah Lwan Swat
277		Aye Mya Thida
278		Aye Mya Thida
279		Aye Mya Thida
280		Ah Lwan Swat
281		Aye Mya Thida
282		Aye Mya Thida
283		Aye Mya Thida
284		Aye Mya Thida
207		- 1.1,0 111,14 1111du

No	Name	Village
293		Aye Mya Thida
294		Ah Lwan Swat
295		Ah Lwan Swat
296		Aye Mya Thida
297		KA Lar Kon
298		KA Lar Kon
299		KA Lar Kon
300		KA Lar Kon
301		KA Lar Kon
302		Ah Lwan Swat
303		Ah Lwan Swat
304		Ah Lwan Swat
305		Ah Lwan Swat
306		Ah Lwan Swat
307		Ah Lwan Swat
308		Ah Lwan Swat
309		Ah Lwan Swat
310		Ah Lwan Swat
311		Ah Lwan Swat
312		Ah Lwan Swat
313		Ah Lwan Swat
314		Ah Lwan Swat
315		Ah Lwan Swat
316		Ah Lwan Swat
317		Ah Lwan Swat
318		Ah Lwan Swat
319		Ah Lwan Swat
320		Aye Mya Thida
321		Aye Mya Thida
322		Ah Lwan Swat
323		Ah Lwan Swat
324		Shwe Pyi Tha Yar
325		MJTD
326		Ah Lwan Swat
327		Ah Lwan Swat
328		Ah Lwan Swat
329		Ah Lwan Swat
330		Ah Lwan Swat
331		Ah Lwan Swat
332		Aye Mya Thida
333		Aye Mya Thida
334		SEZMC

Second Session December 22th, 2015 A.M.

No	Name	Village
1		Shwe Pyout
2		Shwe Pyout
3		Shwe Pyout
4		Shwe Pyout
5		Shwe Pyout
6		Shwe Pyout
7		Shwe Pyout
8		Shwe Pyout
9		Shwe Pyout
10		Shwe Pyout
11		Shwe Pyout
12		Shwe Pyout
13		Shwe Pyout
14		Shwe Pyout
15		Ah Lwan Swat
16		Rual Dept;
17		Shwe Pyout
18		Shwe Pyout
19		Shwe Pyout

No	Name	Village
20		Shwe Pyout
21		Shan Su Tract
22		Shwe Pyout
23		REM
24		EIA (NK)
25		NK
26		Shwe Pyout
27		Shwe Pyout
28		Shwe Pyout
29		Shwe Pyout
30		Shwe Pyout
31		Shwe Pyout
32		MTSH
33		Shwe Pyout
34		Shwe Pyout
35		Shwe Pyout
36		Shwe Pyout
37		Shwe Pyout
38		Shwe Pyout

Third Session December 22th, 2015 P.M..

	NY.	* 7*11
No	Name	Village
1		Hpa Yar Kon
2		Hpa Yar Kon
3		Green Asia Servise
4		Green Asia Servise
5		Hpa Yar Kon
6		Hpa Yar Kon
7		MOECAF
8		MOECAF
9		Ka Nar
10		Marine
11		Marine
12		Thell Phyu Chaung
13		Hpa Yar Kon
14		Hpa Yar Kon
15		Marine
16		Hpa Yar Kon
17		Marine
18		Hpa Yar Kon
19		Marine
20		Marine
21		Marine
22		Marine
23		Hpa Yar Kon
24		Marine
25		Marine
26		MCRB


No	Name	Village
27		Marine
28		Hpa Yar Kon
29		Hpa Yar Kon
30		Hpa Yar Kon
31		Hpa Yar Kon
32		Hpa Yar Kon
33		Hpa Yar Kon
34		Hpa Yar Kon
35		Hpa Yar Kon
36		Marine
37		Thell Phyu Chaung
38		Marine
39		Kon Chan Kon
40		Kon Chan Kon
41		Marine
42		Marine
43		Lat Yat San
44		REM
45		REM
46		Hpa Yar Kon
47		Hpa Yar Kon
48		Marine
49		Marine
50		
51		Hpa Yar Kon

Annex 11-4

Meeting Records of Public Consultation Meeting for EIA at Scoping Stage

Annex 11-4 Meeting Records of Public Consultation Meeting for EIA at Scoping Stage

First Session: December 19th, 2015 A.M.



ပတ်ဝန်းကျင်ထိခိုက်မှ ဆန်းစစ်ခြင်းဆိုင်ရာ အများပြည်သူ အကြံပြုဆွေးနွေးပွဲ

မေးရွန်း - ၄, အခုထုတ်ပြန်မယ့် အကြောင်းအရာ ဆိုရင် ပြည်သူတွေရှိတဲ့ နေရာနဲ့ ဝေးလွန်းပါတယ်။ ထို့ကြောင့် EIA မှကြမ်းကို ကျွန်တော်တို့ဆီရောပေးပို့ပေးနိုင်မလား

အဖြေ - ၄, EIA တအုဝ်ကိုပို့ပေးပါ့မယ်။ (TSMC)

မေးရွန်း - ၅, ဘယ်နေရာကိုပို့ပေးရင် အဆင်ပြေနိုင်မလဲ (REM)

အဖြေ - ၅, အလွှမ်းဆွတ် ဆိုရင်ကျွန်တော်တို့ ဆီ ပေးပို့ပေးပါ

မေးရွန်း - ၆, EIA/SIA ကဒေသခံ တော်တော်များများ နားလည်ဖို့ က်ေခဲပါတယ်။ ယခု EIA နှင့် ပတ်သတ်ပြီး အပိုင်း ခ နှင့် ပတ်သတ်ပြီး ပြောင်းရွေ့ ရတဲ့ လူတွေဘဲပြောနေကြတာတွေပါတယ်။ သဘာဝဝန်းကျင်က ကျယ်ဝန်းပါတယ်။ TSEZ နှင့်ပတ်သက်ပြီး power supply နဲ့ ပတ်သက်ပြီး ရှင်းရှင်းလင်းလင်းသိချင်ပါတယ်။ Water Resourse က ကျောက်တန်းဆီက ယူသုံးရင် ကြာရင် မြေအောက်ရေထီခိုက်နိုင်ပါတယ်။ (ဘုန်းကြီး)

အရြေ - ၆, ကျွန်မတို့ ဟက်တာဂုဝ၀ ကို အခြေခံ ဒေတာယူတာပါ။ စီးက Thanlyin Sub- Station ကယူတာပါ။ အရေးပေါ်အတွက် 50MW တည်ဆောက်ထားပါတယ်။ နောက်ထစ် ၂၃၀KV က ရန်ကုန်က လာမှာပါ။ ယခုလက်ရှိ စီးကတော့ စာမက်ီဆည်ကနေ သုံးပါတယ်။ တစ်နေ့ကို ၆၀၀၀ ကုဗဗ ခန့် သုံးပါတယ်။ လက်ကွင်းပင် ရေပေးဝေရေး ကနေ ၂၀၁၈ မှာ ရောက်အောင် ပို့ပေးမှာပါ။ ဘန့်ဘွေးကုန်း ကနေလည်းမယူပါဘူး ။ မြေအောက်ရေလည်း တူးနှင့်မပေးပါဘူး။ (TSMC)

Second Session: December 22th, 2015 A.M.

ပတ်ဝန်းကျင်ထိခိုက်မှု ဆန်းစစ်ခြင်းဆိုင်ရာ အများပြည်သူ အကြံပြုဆွေးနွေးပွဲ

ဒုတိယနေ့၊ ပြည်သူ့အကြံပြုဆွေးနွေးပွဲ၊ အစည်းအဝေးမှတ်တမ်း

<u>കൂള് - പ്രപാ</u>വ

နေရာ - သီလဝါအိုးအိမ်ရုံး (ယာယီ)

အမျိန် - နံနက် ၉း၃၀

၁. အဇွင့်အမှာစကားပြောကြားခြင်း

ပြောကြားခြင်းမရှိပါ

၂. သီလဝါအထူးစီးပွါးရေးစုန် အပိုင်း (စ) နှင့်သက်ဆိုင်သော လေ့လာချက်များအား အစီစဉ်အလိုက်ရှင်းလင်း ပြောကြားခြင်း

သီလဝါ အထူးစီးပွါးရေးဇုနီ အပိုင်း (ခ) စီမံကိန်း မိတ်ဆက်နှင့် ဇော်ပြချက်၊ နယ်ပယ်သတ်မှတ်ရာတွင် သဘာဝနှင့်လူမှဝန်းကျင် သက်ရောက်နိုင်မှုများ၊ EIA တွင်လေ့လာမည့် အကြောင်းအရာများ၊ ရှေ့ဆက်လုပ်ဆောင်မည့် EIA အခြေအနေများကို REM မှတာဝန်ရှိသူ

၃. အမေး၊ အမြေ

မေးစွန်း - ၁, ကျွန်တော်တို့ ရွှေပျောက် အပိုင်းထဲမှာအိမ်ခြေ ၄၅ လုံးရွှေပြောင်းရမှာ ဖြစ်ပါတယ်။ ထို့ကြောင့်မြေယာအစားထိုးမှုအား တောင်းဆိုချင်တာရှိပါတယ်။ အေးမြသီတာ နှင့် ရွှေပြည်သာယာ ကြားကခုန်နေရာလေးလိုချင်ပါတယ်။

အဖြေ - ၁, ဇုန်စရိယာထဲမှာ ကျနေပါတယ်။ ပထမဦးစားပေးနေရာက ရွာ ၂ ရွာကြားတောင်းဆိုသည့်အကြောင်းအား အထက်ကို တင်ပြပေးပါမယ်။ ဒုတိယ ဦးစားပေးအနေဖြင့် ရဲတပ်ရင်းနားလို့ သိရှိရကြောင်းနှင့် ရွှေပြည်သာယာ သီလဝါက ကုလားဘုရားကျောင်းနားတွင်လည်း ပထမဦးစားပေးတောင်းဆိုထားကြောင်းသိရပါတယ်။ တောင်းဆိုမှတွေကို အထက်ကို တင်ပြပေးပါမယ်။ မြေကိစ္စကို တစ်ပိုင်းတင်ပြ သွားပေးပါမယ်။ ရွှေမှော်ဝန်းအဖွဲ့ (ပ) သီလဝါအထူးစီးပွားရေးစုန် အကြောင်း အမျိုးမျိုးကြောင့် ပျက်စီးအောင်လုပ်မယ့် သူတွေကို ပြန်တိုက်စိုက်မယ့် အဖွဲ့ပါ။ သီလဝါလူထုဖွံ့ဖြိုးတိုးတက်ရေးအဖွဲ့ (ဒု)က လူထုဘက်က ရပ်တည်မှာပါ။ ၎င်း နှစ်ဖွဲ့ ကို အစီရင်ခံစာ မူကြမ်းစာအုပ် ပေးပို့ရင် ပိုကောင်းပါတယ်။ ဒါမှသာ အကြံဥာက်တွေရရှိမှာ ဖြစ်ပါတယ်။

တွေးနွေးတင်ပြခြင်း

အဓိက ဒီနေ့ အစည်းအဝေးက သီလဝါ Zone B အတွက် သဘာဝ ပတ်ဝန်းကျင် လေ့လာတာဖြစ်ပါတယ်။ အောက်တိုဘာ (၁၀)နှင့် (၁၂) ရက်တို့တွင် ပြန်လည် နေရာချထားရေး အစီအစဉ်ကို ဆွေးနွေးတိုင်ပင်ခဲ့ပါတယ်။ ဇန်နဝါရီ လတွင် အဆုံးသတ် ဆွေးနွေးရေးဆွဲ နေပါတယ်။ (TSMC)

ပတ်ဝန်းကျင်ထိနိက်မှ ဆန်းစစ်ခြင်းဆိုင်ရာ အများပြည်သူ အကြံပြုဆွေးနွေးပွဲ

မေးရွန်း - ၂. EIA အဖွဲ့ကို ဗဟုသုတ အနေဖြင့် တစ်ခုလောက်မေးချင်ပါတယ်။ ဂုဝဝ ဟက်တာ အပြင် ဘယ်လောက်အကွာအဝေးမှာနေထိုင်လျှင်ဆိုးကျိုးထိခိုက်မှု မရှိနိုင်ဘူးလဲ သိချင်ပါတယ်။

အရေ - ၂, စီမံကိန်းမစတင်စို နှင့် စတင်ချိန်ကာလတွေမှာ လေ့လာခဲ့ပါသည်။ လည်ပတ်နေစဉ်ကာာလမှာ လဲ MITD ကို အကြံဥာက်ပေးပါသည်။ ဘေးအွန္တရယ်လျော့ ကျနိုင်တဲ့ နည်းလမ်းတွေ ကို အကြံဥာက်ပေးပါတယ်။ အကောင်းဆုံးအကြံ ဥာက်ပေးရေငင် စီမံကိန်းခရိယာနှင့်အဝေးဆုံးမှာနေတိုင်ပါ။ အကိုတို့ ကို တိုက်ရိုက် မဟုတ်သော်လည်း သွယ်ဝိုက်သောနည်းလမ်းနှင့် ပတ်သတ်နိုင်ပါတယ်။ ပုံမှန်ထက် ဖုန် မှုန့်တွေ များရင် ပြောကြားပါ။ဂျပန်ကုပ္ပကိက ဦးဆောင်တာပါ။ စီမံကိန်းခရိယာမှာ တစ်နေ့ရေဘယ်နှစ်ခေါက် မြန်းရမယ်ဆိုတာ ပါပါတယ်။လျော့ပါးနိုင်မယ့် နည်းလမ်းတွေ အကြံပြုထားပါတယ်။ လိုက်နာတာ ၊ မလိုက်နာတာ ကတော့ ကုပ္ပက်ီဝိုင်ရှင်ဘက်ကပါ။ သဘာဝပတ်ဝန်းကျင်နှင့် ပတ်သတ်ပြီး တစ်ဦးတစ်ယောက်နဲ့ မဆိုင်ပါဘူး။ နိုင်ငံတော် အစိုးရမှအစ ပြည်သူတွေ တစ်ရင်လုံးပူးပေါင်း ပါဝင်ဆွေးနွေးရမှာဖြစ်ပါတယ် (REM) Third Session: December 22th, 2015 P.M.

ပတ်ဝန်းကျင်ထိခိုက်မှ ဆန်းစစ်ခြင်းဆိုင်ရာ အများပြည်သူ အကြံပြုဆွေးနွေးပွဲ ဒုတိယနေ့၊ ပြည်သူ့အကြံပြုဆွေးနွေးပွဲ၊ အစည်းအဝေးမှတ်တမ်း ക്രേള് - പ്രാപാര နေရာ - သီလဝါအိုးအိမ်ရုံး (ယာယီ) အမျိန် - နေ့လည် ၁. အဖွင့်အမှာစကားပြောကြားခြင်း ပြောကြားခြင်းမရှိ ၂. သီလဝါအထူးစီးပွါးရေးဇုန် အပိုင်း (စ) နှင့်သက်ဆိုင်သော လေ့လာချက်များအား ခြုံငုံ၍ ရှင်းလင်းပြောကြားခြင်း သီလဝါ အထူးစီးပွါးရေးစုနီ အပိုင်း (ခ) စီမံကိန်း မိတ်ဆက်နှင့် ဖော်ပြချက်၊ နယ်ပယ်သတ်မှတ်ရာတွင် သဘာဝနှင့်လူမှု ဝန်းကျင်သက်ရောက်နိုင်မှုများ၊ EIA တွင်လေ့လာမည့် အကြောင်းအရာများ၊ ရှေ့ဆက်လုပ်ဆောင်မည့်EIA အခြေအနေများကို REMမှတာဝန်ရှိသူ ၃. အမေး၊ အမြေ ပရိ တွေးနွေးတဝိပြခြင်း ရန်ကုန်တိုင်းဒေသကြီး ပတ်ဝန်းကျင်ထိန်းသိမ်းရေးဋ္ဌာနတွင်တာဝန်ထမ်းဆောင်နေသော ဦးစီးမျာမှ ယခင်လွန်ခဲ့သောနစ်များက စက်ရုံများတည်ဆောက်လျှင် ယစုကဲ့သို့ ပတ်ဝန်းကျင်ဆိုင်ရာ သက်ရောက်မှုဆန်းစစ်ခြင်းများမရှိခဲ့ကြောင်း ယစုအစိုးရလက်ထက်တွင် ၂၀၁၂ **ဓနစ်နောက်ပိုင်း** စီးပွားရေးဖွံ့ဖြိုးတိုးဘက်မှုများ လုပ်ဆောင်ရာတွင် ပတ်ဝန်းကျင် ထိခိုက်မှုဆန်းစစ်ခြင်းများကို ထည့်သွင်းလုပ်ဆောင်ရန် ပြန်လည်နေရာချထားရေး ကိစ္စများဆောင်ရွက်ရာတွင်လည်း ဥပဒေများချမှတ်ထားကြောင်း၊ ပွင့်လင်းမြင်သာမှရှိလာပြီဖြစ်ကြောင်း သုံးသဝ်တင်ပြခဲ့ပါသည်။

Annex 11-5

Announcement Letter for Public Disclosure of the Scoping Report

Annex 11-5 Announcement Letter for Public Disclose of the Draft Scoping Report

Announcement of Public Disclosure

Myanmar Japan Thilawa Development Limited (MJTD)/ Myanmar Thilawa SEZ Holdings Public Limited (MTSH) have started to plan the development of 700ha in Thilawa SEZ as "Zone B Area". In response to this, the Environmental Impact Assessment (EIA) study has been started in order to assess environmental and social impacts of the Zone B development and prepare appropriate mitigation measures.

Public disclosure of the draft scoping report was planned from 23rd December 2015 to 7th January 2016. However, the schedule is now changed from 31st December, 2015 to 14th, January, 2016 for 10 working days.

Thank you very much for your attention and cooperation.

Draft Scoping Report of EIA Disclosure Places

- 1. Yangon Southern District General Administration Office
- 2. Thanlyin Township General Administration Office
 - a) Hpa Yar Kone Village Tract Office
 - b) Let Yet San Village Tract Office
 - c) Ah Lun Soke Village Tract Office
- 3. Kyauktan Township General Administration Office
 - a) Aye Mya Thi Dar Ward Office
 - b) Shwe Pyi Thar Yar Ward Office
 - c) Thi Tar Myaing Ward Office
 - d) Shwe Pyauk Village Tract Office
- 4. Thilawa SEZ Management Committee Office (Temporary) near Thilawa SEZ
- 5. Myanmar Japan Thilawa Development Limited Office in Thilawa SEZ

အများပြည်သူသို့ ဖွင့်လှစ်တင်ပြရန်ကြေညာခြင်း

မြန်မာ-ဂျပန် သီလဂါဗွဲဖြိုးရေးလီဓိတက် (MJTD) နှင့်မြန်မာ-သီလဝါ SEZ ဦးဝိုင်လီဓိတက် (MTSH) တို့သည် အထူးစီးပွါးရေးဇုန်အတွင်းရှိ ဟတ်တာ ၄၀၀ ခန့်ရှိသော အဝိုင်း (ခ) အား ကနဦးအနေဖြင့် ဗွံဖြိုးရေးစီမံကိန်းများလုပ်ဆောင်ခဲ့ပါသည်။ ယင်းစီမံကိန်းအတွက် သဘာဝပတ်ဝန်းကျင်နှင့် လူမှူဝန်းကျင်သက်ရောက်မှုများအား သိရှိနိုင်ရန်လေ့လာလျက်ရှိပြီး သင့်တော်သော လျော့ပါးစေရေးနည်းလမ်းများ၊ ပတ်ဝန်းကျင်စီမံခန့်ခွဲမှု အစီအစဉ်နှင့် စောင့်ကြည့်ရေးအစီအစဉ်များကိုရေးစွဲမည်ဖြစ်ပါသည်။

အစီရင်ခံစာမူကြမ်းအား စီမံကိန်းရေးစွဲပြီး ၃၁.၁၂.၁၅ မှ ၁၄.၁.၁၆ ထိထုတ်ဖော်ပြသမည် ဟုဖော်ပြခဲ့ပါသည်။ သို့သော် အစီအစဉ်အား ၂၀၁၅ ဒီဇင်ဘာ ၃၁ရက်မှ ၂၀၁၆ ဇန်နဝါရီ ၁၄ ရက် အထိ အလုပ်လုပ်ရှိန် ၁၀ ရက်အတွင်းပြောင်းလဲထားပါသည်။ ပူးပေါင်းပါဝင်မှုအားကျေးဇူးအထုးတင်ရှိပါသည်။

အစီရင်ခံစာမူကြမ်းအားရှင်းလင်းဖော်ထုတ်ပြသမည့်နေရာများ

၁။ ရန်ကုန်တောင်ပိုင်းခရိုင်အထွေထွေအုပ်ချုပ်ရေးဦးစီဌာန

၂။သန်လျင်မြို့နယ်အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန

- (က) ဘုရားကုန်းကျေးရွာအုပ်စုရုံး
- (စ) လက်ယက်စမ်းကျေးရွာအုပ်စုရုံး
- (ဂ) အလွမ်းဆွတ်ကျေးရွာအုပ်စုရုံး

၃။ ကျောက်တန်းမြို့နယ်အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန

- (က) အေးမြသီတာရပ်ကွက်ရုံး
- (ခ) ရွှေပြည်သာယာရပ်ကွက်ရုံး
- (ဂ) သီတာမြိုင်ရပ်ကွက်ရုံး
- (ဃ) ရွှေပျောက်ကျေးရွာအုပ်စု
- ၄။ သီလဝါစီးပွါးရေးဇုန်စီမံခန့်ခွဲမှုကော်မတီရုံး
- ၅။ မြန်မာ ဂျပန်သီလဝါဖွံဖြိုးရေးလီမိတက် (MJTD)

Announcement of Public Disclosure

31st December 2015

Myanmar Japan Thilawa Development Limited (MJTD)/ Myanmar Thilawa SEZ Holdings Public Limited (MTSH) have started to plan the development of 700ha in Thilawa SEZ as "Zone B Area". In response to this, the Environmental Impact Assessment (EIA) study has been started in order to assess environmental and social impacts of the Zone B development and prepare appropriate mitigation measures.

Public disclosure of the draft scoping report on industrial area is conducted from 31st December 2015 to 14th January 2016. However, the schedule for the public disclosure of the draft scoping report on logistic, residence and commercial area is now changed from middle of January 2016 for 10 working days.

Thank you very much for your attention and cooperation.

Draft Scoping Report of EIA Disclosure Places

- 1. Yangon Southern District General Administration Office
- 2. Thanlyin Township General Administration Office
- 3. Kyauktan Township General Administration Office
- Thilawa SEZ Management Committee Office (Temporary) near Thilawa SEZ
- Myanmar Japan Thilawa Development Limited Office in Thilawa SEZ
- 6. Hpa Yar Kone Village Tract Office (Under Thanlyin Tsp.)
- 7. Let Yet San Village Tract Office (Under Thanlyin Tsp.)
- 8. Ah Lun Soke Village Tract Office (Under Thanlyin Tsp.)
- 9. Aye Mya Thi Dar Ward Office (Under Kyauktan Tsp.)
- 10. Shwe Pyi Thar Yar Ward Office (Under Kyauktan Tsp.)
- 11. Thi Tar Myaing Ward Office (Under Kyauktan Tsp.)
- 12. Shwe Pyauk Village Tract Office (Under Kyauktan Tsp.)

အများပြည်သူသို့ ဗွင့်လှစ်တင်ပြရန်ကြေညာခြင်း

၂၀၁၅ ခုနှစ်၊ ဒီဇင်ဘာလ (၃၁) ရက်

Myanmar Japan Thilawa Development Limited (MJTD) နှင့် Myanmar Thilawa SEZ Holdings Public Limited (MTSH) တို့သည် အထူးစီးပွါးရေးဇုန်အတွင်းရှိ ဟတ်တာ ဂုဝဝ ခန့်ရှိသော အပိုင်း (ခ) အား ကနဦးအနေဖြင့် ဖွံဖြိုးရေးစီမံကိန်းများလုပ်ဆောင်ခဲ့ပါသည်။ ယင်းစီမံကိန်းအတွက် သဘာဝပတ်ဝန်းကျင်နှင့် လူမှုဝန်းကျင်သက်ရောက်မှုများအား သိရှိနိုင်ရန် သဘာဝပတ်ဝန်းကျင်ဆိုင်ရာ ထိခိုက်မှုများကို လေ့လာလျက်ရှိပြီး သင့်တော်သော လျော့ပါးစေရေးနည်းလမ်းများ၊ ပတ်ဝန်းကျင်စီမံခန့်ခွဲမှု အစီအစဉ်နှင့် စောင့်ကြည့်ရေးအစီအစဉ်များကို ရေးဆွဲမည်ဖြစ်ပါသည်။

စက်မှုုဇုန် ဇရိယာအတွက် နယ်ပယ်သတ်မှတ်ခြင်း အစီရင်ခံစာမူကြမ်းအား ၂၀၁၅ခုနှစ်၊ ဒီဇင်ဘာ (၃၁) ရက် မှ ၂၀၁၆ခုနှစ်၊ ဇန်နဝါရီ (၁၄) ရက် ထိ ပြည်သူလူထုအား ထုတ်ဖော်ကြေညာသွားမည် ဖြစ်သည်။ သို့သော် သယ်ယူပို့ဆောင်ရေးစရိယာ၊ လူနေဇရိယာနှင့် ရောင်းဝယ်ဖောက်ကားရေးဧရိယာများ၏ နယ်ပယ်သတ်မှတ်ခြင်း အစီရင်ခံစာမူကြမ်းအား ပြည်သူလူထုအားထုတ်ဖော် ကြေညာရန်အတွက် အစီအစဉ်အား ၂၀၁၆ခုနှစ် ဇန်နဝါရီလလယ်တွင် အလုပ်လုပ်ချိန် (၁၀) ရက်ကြာအသိပေး ပြောင်းလဲကြေငြာမည်ဖြစ်သည်။ ပူးပေါင်းပါဝင်မှုအားကျေးစူးအထူးတင်ရှိပါသည်။

အစီရင်ခံစာမူကြမ်းအားရှင်းလင်းဖော်ထုတ်ပြသမည့်နေရာများ

၁။ ရန်ကုန်တောင်ပိုင်းခရိုင်အထွေထွေအုပ်ချုပ်ရေးဦးစီဌာန ၂။သန်လျင်မြို့နယ်အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန ၃။ ကျောက်တန်းမြို့နယ်အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန ၄။ သီလဝါစီးပွါးရေးဇုန်စီမံခန့်ခွဲမှုကော်မတီရုံး ၅။ မြန်မာ - ဂျပန်သီလဝါဖွံ့ဖြိုးရေးလီမိတက် (MJTD)

၆။ ဘုရားကုန်းကျေးရွာအုပ်စုရုံး (သန်လျင်မြို့နယ်)
ဂု။ လက်ယက်စမ်းကျေးရွာအုပ်စုရုံး (သန်လျင်မြို့နယ်)
၈။ အလွင်းဆွတ်ကျေးရွာအုပ်စုရုံး (သန်လျင်မြို့နယ်)
၉။ အေးမြသီတာရပ်ကွက်ရုံး (ကျောက်တန်းမြို့နယ်)
၁၀။ ရွှေပြည်သာယာရပ်ကွက်ရုံး (ကျောက်တန်းမြို့နယ်)
၁၁။ သီတာမြိုင်ရပ်ကွက်ရုံး (ကျောက်တန်းမြို့နယ်)
၁၂။ ရွှေပျောက်ကျေးရွာအုပ်စု (ကျောက်တန်းမြို့နယ်)

Announcement of Public Disclosure

14th January 2016

Myanmar Japan Thilawa Development Limited (MJTD)/ Myanmar Thilawa SEZ Holdings Public Limited (MTSH) have started to plan the development of 700ha in Thilawa SEZ as "Zone B Area". In response to this, the Environmental Impact Assessment (EIA) study has been started in order to assess environmental and social impacts of the Zone B development and prepare appropriate mitigation measures.

Public disclosure of the draft scoping report on industrial area is conducted from 31st December 2015 to 14th January 2016. However, the schedule for the public disclosure of the draft scoping report on logistic, residence and commercial area is now changed from 15th January 2016 to 28th January 2016 for 10 working days.

Thank you very much for your attention and cooperation.

Kyauktan Township General Administration Office

5. Myanmar Japan Thilawa Development Limited Office in

near Thilawa SEZ

Thilawa SEZ

Thilawa SEZ Management Committee Office (Temporary)

Draft Scoping Report of EIA Disclosure Places

- Yangon Southern District General Administration Office
 Hpa Yar Kone Village Tract Office (Under Thanlyin Tsp.)
- Thanlyin Township General Administration Office
 Let Yet San Village Tract Office (Under Thanlyin Tsp.)
 - 8. Ah Lun Soke Village Tract Office (Under Thanlyin Tsp.)
 - 9. Aye Mya Thi Dar Ward Office (Under Kyauktan Tsp.)
 - 10. Shwe Pyi Thar Yar Ward Office (Under Kyauktan Tsp.)
 - 11. Thi Tar Myaing Ward Office (Under Kyauktan Tsp.)
 - 12. Shwe Pyauk Village Tract Office (Under Kyauktan Tsp.)

အများပြည်သူသို့ ဗွင့်လှစ်တင်ပြရန်ကြေညာရြင်း

၂၀၁၆ ခုနှစ်၊ ဇန်နပါရီလ (၁၄) ရက်

Myanmar Japan Thilawa Development Limited (MJTD) နှင့် Myanmar Thilawa SEZ Holdings Public Limited (MTSH) တို့သည် အထူးစီးပွါးရေးဇုန်အတွင်းရှိ ဟတ်တာ ဂုဂဂ ခန့်ရှိသော အဝိုင်း (ခ) အား ကနဦးအနေဖြင့် ဖွံ့ဖြိုးရေးစီမံကိန်းများလုပ်ဆောင်ခဲ့ပါသည်။ ယင်းစီမံကိန်းအတွက် သဘာဂပတ်ဂန်းကျင်နှင့် လူမှုဝန်းကျင်သက်ရောက်မှုများအား သိရှိနိုင်ရန် သဘာဂပတ်ဂန်းကျင်ဆိုင်ရာ ထိရိုက်မှုများကို လေ့လာလျက်ရှိပြီး သင့်တော်သော လျော့ပါးစေရေးနည်းလမ်းများ၊ ပတ်ဂန်းကျင်စီမံခန့်ခွဲမှု အစီအစဉ်နှင့် စောင့်ကြည့်ရေးအစီအစဉ်များကို ရေးဆွဲမည်ဖြစ်ပါသည်။

စက်မှူဇုန် စရိယာအတွက် နယ်ပယ်သတ်မှတ်ခြင်း အစီရင်ခံစာမူကြမ်းအား ၂၀၁၅ခုနှစ်၊ ဒီစင်ဘာ (၃၁) ရက် မှ ၂၀၁၆ခုနှစ်၊ ဇန်နဂါရီ (၁၄) ရက်ထိ ပြည်သူလူထုအား ထုတ်ဖော်ကြေညာသွားမည် ဖြစ်သည်။ သို့သော် သယ်ယူပို့ဆောင်ရေးစရိယာ၊ လူနေရေိယာနှင့် ရောင်းပယ်ဖောက်ကားရေးစရိယာများ၏ နယ်ပယ်သတ်မှတ်ခြင်း အစီရင်ခံစာမူကြမ်းအား ပြည်သူလူထုအားထုတ်ဖော် ကြေညာရန်အတွက် အစီအစဉ်အား ၂၀၁၆ခုနှစ် ဇန်နပါရီလ(၁၅)ရက်မှ ၂၀၁၆ခုနှစ် ဇန်နပါရီလ (၂၈) ရက်အထိ အလုပ်လုပ်ချိန် (၁၀) ရက်ကြာအသိပေး ပြောင်းလဲကြေပြာမည် ဖြစ်သည်။

ပူးပေါင်းပါကင်မှူအားကျေးဇူးအထူးတင်ရှိပါသည်။

အစီရင်ခံစာမူကြမ်းအားရှင်းလင်းဖော်ထုတ်ပြသမည့်နေရာများ

၁။ ရန်ကုန်တောင်ပိုင်းစရိုင်အထွေထွေအုပ်ချုပ်ရေးဦးစီဌာန ၂။သန်လျင်မြို့နယ်အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန ၃။ ကျောက်တန်းမြို့နယ်အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန ၄။ သီလဂါစီးပွါးရေးဇုန်စီမံခန့်ခွဲမှူကော်မတိရုံး ၅။ မြန်မာ - ဂျပန်သီလဂါဖွံဖြိုးရေးလီမိတက် (MJTD)


၆။ ဘုရားကုန်းကျေးရွာအုပ်စုရုံး (သန်လျင်မြို့နယ်) ဂု။ လက်ယက်စမ်းကျေးရွာအုပ်စုရုံး (သန်လျင်မြို့နယ်) ၈။ အလွမ်းဆွတ်ကျေးရွာအုပ်စုရုံး (သန်လျင်မြို့နယ်) ၉။ အေးမြသီတာရပ်ကွက်ရုံး (ကျောက်တန်းမြို့နယ်) ၁၀။ ရွှေပြည်သာယာရပ်ကွက်ရုံး (ကျောက်တန်းမြို့နယ်) ၁၁။ သီတာမြိုင်ရပ်ကွက်ရုံး (ကျောက်တန်းမြို့နယ်) ၁၂။ ရွှေပျောက်ကျေးရွာအုပ်စု (ကျောက်တန်းမြို့နယ်)

Annex 11-6

Invitation Letter, Notice and List of Invitees for Public Consultation Meeting for EIA at draft EIA Stage

Annex 11-6 Invitation Letter, Notice and List of Invitees for the Public Consultation Meeting for EIA at Draft EIA Stage

Invitation Letter for the Public Consultation Meeting for EIA on the Thilawa SEZ Development Project (Zone B)



၂။ ထို့အပြင် အဆိုပါစီမံကိန်း၏ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်း အစီရင်ခံစာမှုကြမ်းအာ။ ပြည်လူအများ သိရှိနိုင်စေရန်အတွက် ဆောက်ပါနေရာများတွင် ၂၄,၃၂၀၁၆ ရက်ခန့မှ ၂၃,၄၂၀၁၆ ရက်နေ့အထိ အများပြည်သူများအား ဖွင့်လှစ်ဖော်ပြသေးနိုင်ပါရန် မေတ္တာရပ်ခံအပ်ပါသည်။

- (၁) အတွေ့တွေအုပ်ချုပ်ရေးဦးစီးဌာနရုံး၊ ရခိုကုန်တောင်ပိုင်းခရိုင်
- (၂) အတွေတွေအုပ်ချုပ်ရေးဦးစီးဌာနရုံး) သန်လျှင်မြို့နယ်
 - (သ) ရပိက္ခတ်/ကျေးရွာ အုပ်ချုပ်ရေးမှုးရုံး၊ ဘုရားကုန်းကျေးရွာအုပ်စု
 - (ခ) ရပ်ကွက်/ကျေးရွာ အုပ်ချုပ်ရေးမျူးရုံး၊ လက်ယက်စမ်းကျေးရွာအုပ်စု
 - (ဂ) ရပ်ကွက်/ကျေးရွာ အုပ်ချုပ်ရေးမျူးရုံး၊ အလွမ်းဆွတ် ကျေးရွာအုပ်စု
- (၃) အထွေတွေအုပ်ချုပ်ရေးဦးစီးဌာနရုံး၊ ကျောက်တန်းမြို့နယ်
 - (က) ရပ်ကွက် အုပ်ချုပ်ရေးမျူးရုံး၊ အေးမြသီတာရပ်ကွက်
 - (၈) ရပိကျက် အုပ်ချပ်ရေးမျှးရုံး၊ ရွှေပြည်သာယာ ရပ်ကွက်
 - (ဂ) ရပ်ကွက်/ ကျေးရွာ အုပ်ချုပ်ရေးမှူးရုံး၊ ရွှေပေါက်ကျေးရွာအုပ်စု
- (၄) သီလဝါအထူးစီးပွားရေးခုန်စီမံစန့်ခွဲမှုကော်မတီရုံး (သီလဝါအထူးစီးပွားရေးခုန်)
- (၅) မြန်မာ-ဂျပန် သီလဝါဖွဲ့မြိုးတိုးတက်ရေးလီမိဘက်ရုံး

ဥတ္တဋ္ဌ(ကိုယ်စား) (အင်္ဂြက်တသန်းသန်းသွယ်) တွဲဖက်အတွင်းရေးမျှး)

ခ်တ္ထုတို

မြန်မာ-ဂျပန် သီလဝါစွဲဖြိုးတိုးတက်ရေးလီမိတက် ရုံးလက်ခံ

List of Invitees for Public Consultation Meeting

နောက်ဆက်တွဲ (၁)

လူထုဆွေးနွေးပွဲဖိတ်ကြားမည့်စာရင်း

၁။ ဝန်ကြီး၊ ရန်ကုန်တိုင်းဒေသကြီးအစိုးရအဖွဲ့ ဝင်၊ သီလဝါအထူးစီးပွားရေးဖုံစီမံရန့်ခွဲမှုကော်မတီ။ ၂။ ညွှန်ကြားရေးမူး၊ ပတ်ဝန်းကျင်ထိန်းသိမ်းရေးဦးစီးဌာန၊ ရန်ကုန်မြို့။ ၃။ အုပ်ချုပ်ရေးမူး၊ အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာန၊ရန်ကုန်တောင်ပိုင်းစရိုင်။ ၄။ အုပ်ချုပ်ရေးမှု။ အတွေတွေအုပ်ချုပ်ရေးဦးစီးဌာန၊ သန်လျင်မြို့နယ်။ ၅။ အုပ်ချုပ်ရေးမှု။ အထွေထွေအုပ်ချပ်ရေးဦးစီးဌာန၊ ကျောက်တန်းမြို့နယ်။ ၆။ မြို့နယ်အရာရှိ၊ စည်ပင်သာယာရေအဖွဲ့ ၊ သန်လျှင်မြို့နယ်။ ၇။ မြနယ်အရာရှိ၊ စည်ပင်သာယာရေးအဖွဲ့ ၊ ကျောက်တန်းမြို့နယ်။ ၈။ မြို့ရွာနှင့်အိုးအိမ်စွဲပြီးရေးဦးစီးဌာန၊ ဆောက်လုပ်ရေးဝန်ကြီးဌာန၊ သန်လျင်မြို့နယ်။ ၉။ မြို့နယ်အရာရှိ၊ ကျေးလက်ဖွံ့ဖြိုးတိုးတက်ရေးဦးစီးဌာန၊ သန်လျင်မြို့နယ်။ ၁၀။ မြို့နယ်အရာရှိ၊ ကျေးလက်ဖွဲ့ဖြိုးတိုးတက်ရေးဦးစီးဌာန၊ ကျောက်တန်းမြို့နယ်။ ၁၁။ မြို့နယ်ကျန်းမာရေးအရာရှိ၊ ကျန်းမာရေးဦးစီးဌာန၊ သန်လျှင်မြို့နယ်။ ၁၂။ မြို့နယ်ကျန်းမာရေးအရာရှိ၊ ကျန်းမာရေဦးစီးဌာန၊ ကျောက်တန်းမြို့နယ်။ ၁၃။ သီလဝါအထူးစီးပွားရေးဖုံအနီးရှိကျေးရွာအုပ်ချုပ်ရေးများများနှင့် ရွာသူရွာသားများ။ က။ သန်လျင်မြို့နယ်အတွေတွေအုပ်ချပ်ရေဦးစီးဌာနအောက်ရှိ ၁။ ဘုရားကုန်းကျေးရွာအုပ်စုရုံး ္။ လက်လက်စမ်းကျေးရွာအုပ်စုရုံး ၃။ အလွှမ်းဆွတ်ကျေးရွာအုပ်စုရုံး စ။ ကျောက်တန်းမြို့နယ်အထွေထွေအုပ်ချပ်ရေးဦးစီးဌာနအောက်ရှိ ၁။ အေးမြသီတာရပ်ကွက်ရုံး ၂။ ရွှေပြည်သာယာရပ်ကွက်ရုံး ၃။ သီတာမြင်ရပ်ကွက်ရုံး ၄။ ရွှေပေါက်ကျေးရွာအုပ်စုရုံး

၁၄၊ မြန်မာ့ဆိပ်ကမ်းအာကာဝိုင်၊ ဝို့ဆောင်ရေဝန်ကြီးဌာန ၁၅၊ သီလဝါအထူးစီပွားရေးစုံ အတွင်းရှိ သက်ဆိုင်ရာ စက်ရုံများနှင့် ကုမ္ပကီများ

၁၆။ စီမံကိန်းအားစိတ်ပါဝင်စားသူများနှင့် အခြားအဖွဲ့ အစည်းများ။

သက်ဆိုင်သောအဖွဲ့ အစည်းမှ ဇိတ်ကြားမည့်သူစာရင်းများ

ာ၊ ဥက္ကဌ၊ သီလဝါအထူးစီးပွားရေးဇုံစီမံခန့် ခွဲမှုကော်မတီ ၂။ ဒုတိယဥက္ကဌ၊ သီလဝါအထူးစီးပွားရေးဇုံစီမံခန့် ခွဲမှုကော်မတီ ၃။ အတွင်းရေးမှုး၊ သီလဝါအထူးစီးပွားရေးဇုံစီမံခန့် ခွဲမှုကော်မတီ ၄။ အဖွဲ့ ဝင်များ၊ သီလဝါအထူးစီးပွားရေးဇုံစီမံခန့် ခွဲမှုကော်မတီ ၅။အဖွဲ့ ဝင်များ၊ One Stop Service Center၊ သီလဝါအထူးစီးပွားရေးစုံ စီမံခန့် ခွဲမှုကော်မတီ Notice for Public Consultation Meetings and Public Disclosure of the Draft EIA Report of the Environmental Impact Assessment for the Thilawa SEZ Development Project (Zone B)

သီလဝါအထူးစီးပွားရေးစုံဖွဲ့ဖြိုးတိုးတက်မှုစီမံကိန်း (Zone B) ၏ သယ်ယူဝို့ဆောင်ရေးစရိယာ၊ လူနေနှင့် ရောင်းဝယ်ဇောက်ကားရေး စရိယာအတွက် ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းအစီရင်ခံစာမူကြမ်းအား အများပြည်သူများသို့ တင်ပြဆွေးနွေးခြင်း

သတ္တခနိန်တွင် နယ်ပယ်သတ်မှတ်ခြင်း အစီရင်ခံတမှုကြမ်းကို အတည်ပြုပြီးနောက် လုပ်ဆောင်မှုများကို ပတ်ဝန်းကျင်ထိနိက်မှုဆန်းစစ်ခြင်းဆိုင်ရာ အစိတ်အပိုင်းတစ်အေဖြစ် ဂျပန်မြန်မာစွဲ မြီးတိုးတက်မှုကော်မတီ (MJTD) နှင့် သီလဝါ ပရောပါတီ ဒီဗလော့ဒ်မန့် လီမိတက် (TPD) တို့သည် သီလဝါအထူးစီးပွားရေးစုံ စွဲ့ဖြိုးတိုးတက်မှ စီမံကိန်း (Zone ပတ်ဝန်းကျင်ထိရိက်မှုဆန်းစစ်ခြင်း အစီရင်စံစာမှုကြမ်းကို ပြင်ဆင်လျက် ရှိပါသည်။ ပတ်ဝန်းကျင်ထိရိက်မှ ဆန်းစစ်ခြင်းဆိုင်ရာ အစီရင်ခံစာမှကြမ်းနှင့် အနှစ်ချုပ်ကို အင်္ဂလိပ်ဘာသာနှင့် မြန်မာဘာသာနှစ်ခုလုံးဖြင့် အောက်ပါနေရာများတွင် ၂၀၁၆ ခုနှစ် မတ်လ (၂၄) ရက် မှ ၂၀၁၆ ခုနှစ် စပြီလ (၂၄) ရက်နေ့အထိ (၁လခန့်) တင်ပြထားရှိသွားမည်ဖြစ်ပြီး သဘောထားမှတ်ချက်များနှင့် ဝေဇန်အကြံပြုချက်များကို သတ်မှတ်ထားသော အချိန်အတောအတွင်း သက်ဆိုင်ရာနေရာများတွင် တင်သွင်းနိုင်ပါသည်။ ထို့အပြင် ကွင်းဆင်းလေ့လာခြင်း ရလဒ်နှင့် ပတ်ဝန်းကျင်ဆိုင်ရာ၊ လူမှုဝန်းကျင်ဆိုင်ရာ ထိခိုက်မှုဆန်းစစ်ခြင်း နှင့် ယင်းထိခိုက်မှုများလျော့ပါးစေရေး၊ စောင့်ကြင်ကြည့်ရှုရေးစသည့် အစီအစဉ်များ၊ သဘာဝပတ်ဝန်းကျင်ထိခိုက်မှ ဆန်းစစ်လေ့လာခြင်းကို ရှင်းပြပီး စီမံကိန်းဝန်းကျင်ရှိ အများပြည်သူများ ရှင်းလင်းမြင်သာစေရန်နှင့် ပူးပေါင်းပါဝင်လာနိုင်စေရန် တင်ပြရေးနွေးခြင်းပြုလုပ်နိုင်ရန် လူထုအကြဲပြုဆွေးနွေးပွဲကို ထုတ်ဇော်တင်ပြရန်သတ်မှတ်ထားသော ကာလအတွင်း ၂၀၁၆ ခုနှစ် စပြီလ ၂ ရက်နေ့နှင့် ၅ ရက်နေ့ များတွင် ကျင်းပပြုလုပ်သွားမည်ဖြစ်သည်။

တဝိပြထားရှိမည့်နေရာ

၁။ ရန်ကုန်တောင်ပိုင်းခရိုင်အထွေထွေအုပ်ချုပ်ရေးမှူးရုံး

၂။ သန်လျင်မြို့နယ်အထွေတွေအုပ်ချုပ်ရေးဦးစီးဌာနအောက်ရှိ

- က)ဘုရားကုန်းကျေးရွာအုပ်စုရုံး
- a) လက်ယက်စမ်းကျေးရွာအုပ်စုရုံး
- ဂ) အလွမ်းဆွတ်ကျေးရွာအုပ်စုရုံ

၃။ ကျောက်တန်းမြို့နယ်အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာနအောက်ရှိ

- က) အေးမြသီတာရပ်ကွက်ရုံး
- a) ရွှေပြည်သာယာရပ်ကွက်ရုံး
- ဂ) သီတာမြင်ရပ်ကွက်ရုံး
- ယ) ရွှေပျောက်ကျေးရွာအုပ်စုရုံး

၄။ ရာအိမ်မှုးအိမ်နှင့် သီလဝါ SEZ ဝန်းကျင်အတွင်းနေထိုင်သူ ၅။ သီလဝါ SEZ စီမံခန့်ခွဲရေးကော်မတီရုံး (ယာယီ) သီလဝါ SEZ အနီး ၆။ သီလဝါ SEZ ရှိ မြန်မာ - ဂျပန် သီလဝါဖွဲခြီးရေး လီမိတက်ရုံး (MJTD)

အများပြည်သူများနှင့်တွေ့ဆုံရေားနွေးခြင်း

စဉ်	နေ့ရက်	အမြန်	တရင်းပေးချိန်	နေရာ
ပထမအရိန်	၂၀၁၆၊ ခရီလ	နံနက် (၁၀:၁၀) မှ (၁၁:၃၀) နာရီ	နံနက် (၉:၃၀) မှစတင်၍	အည်းအဝေးခန်းမ၊ မြို့ရွာနှင့်အိုးအိပ်ဖွဲမြီးရေး ဦးစီဌာန၊ သီလဝါအတူးစီးပွားရေးစုံ
ခုတိယအရှိန်	(၂)ရက် (စနေနေ့)	နေ့လည် (၁:၃၀) မှ (၃:၀၀) နာရီ	နေ့လည် (၁:၀၀) မှစတင်၍	စီမံစန့်ခွဲမှုကော်မတီရုံး (ယာယီ)၊ ကျောက်တန်းမြို့နယ်။
တတိယအရိန်	၂၀၁၆၊ ခင်္ပီ လ (၇)ရက်	နံနက် (၁၀:၀၀) မှ (၁၀:၃၀) နာရီ	နံနက် (၉:၃၀) မှတောင်၍	
စတုတ္ထအရိန်	(ကြာသပတေးနေ့)	နေ့လည် (၁:၃၀) မှ (၃:၀၀) နာရီ	နေ့လည် (၁:၀၀) မှစတင်၍	

မှတ်ချက်။

- ၁။ ကြို/ပို့ယာဉ်များအား စီစဉ်ထားမည်ဖြစ်ပြီး၊ အချိန်နှင့်စုရပ်နေရာများအား သက်ဆိုင်ရာကျေးရွားအုပ်စုရုံး များတွင်ကြိုတင်ကြော်ပြာပေးမည်ဖြစ်သည်။
- ၂။ အစည်းအဝေးအရိန် (၄)ခုလုံးတွင် တင်ပြဆွေးနွေးမည့်အကြောင်းအရာမှာ အားလုံးအတူတူဖြစ်သဖြင့် ဖိမိအဆင်ပြေရာအရိန်ကိုတက်ရောက်နိုင်ပါသည်။

လူကြီးမင်း၏ပူးပေါင်းပါဝင်အားအထူးလိုလားပါသည်။


Annex 11-7


Presentation Materials, Handout and Sample of the Feedback Form in Myanmar Language for Public Consultation Meeting for EIA at Draft EIA Stage


Annex 11-7 Presentation Materials, Handout and Sample of the Feedback Form in Myanmar Language for Public Consultation Meeting for EIA at Draft EIA Stage


Presentation Material used at PCM at Draft EIA Stage



























Handout used at PCM at Draft EIA Stage

သဘာဝနှင့်လူမှသက်ရောက်နိုင်မြေဆန်းစစ်မြင်း၊ ပတ်ဝန်းကျင်လျှော့ပါးစေရေး (၁၄) စီမံစန့်ခွဲမှအစီအစဉ်

သက်ရှိပတ်ရန်းတွင်
အဓိကထိုးကျိုးသက်ရောက်နိုင်ဖြေများအနေဖြင့် စီပံကိန်းနယ်မြေအတွင်းနှင့်ပါတ်ဝန်းကျင်တွင် ပါတ်ငွေနှင့်
အဓိကထိုးကျိုးသက်ရောက်နိုင်ဖြမြှမှာအေနဖြင့် စီပံကိန်းနယ်မြေအတွင်းနှင့်ပါတ်ဝန်းကျင်တွင် ပါတ်ငွေနှင့်
စုန်မှုန်မှုကတွက်ရှိနိုင်ပြင်း၊
တို့ကိုမျှော်မှန်မေါသည်။ သို့သော်လည်းမှင်းကိုသည်အာရန်ထာသတ်နှင့်တာဖြစ်နိုင်ပါသည်။
သင့်တော်သောလျှောပါစေရေးနည်းလုပ်များနှင့် စီပံစန့်ခွဲမှုအစီအစဉ်မှာအခြင်သော စုန်ထပြင်းမှ ကာကွယ်ရန်စြေခြန်ခြင်။ ဆောက်လုပ်ရေးဘာလအတွင်း ပန္တရားများအားအလွန်အကျွံအသုံးပြမြင်း မှရောင်ကြည်ပြင်း၊ ဌားချင်းလုပ်ကိုင်သူများမှ ကြိုလို့ယာဉ်များစီဝဉ်ပေမြင်း၊ ရေသန်ဝင်တက်မှုမှ သာယီ မသတ်မှတ်ရက်နှင့်ကိုက်ညီသောရေများစုန်ထုတ်မြင်း သည့်အားခြင့် ထိုဆိုးကျိုးသက်ရောက်မှုများ အားလျှောနှည့်စစနိုင်ပါသည်။

သဘာဝမတ်ဝန်းကျွင် ဂေဟစနင်အရ ကာကွယ်ထားသောစရိယာရှိသော်လည်း ဆောက်လုပ်ရေးကာလအတွင်း လက်ရှိ သဘာဝမေါက်ပင်မှာအားရှင်းလင်းခြင်း အနေမြင့်သက်ရောက်နိုင်မြေရှိပါသည်။ ငှင်းသက်ရောက်နိုင်မြေ ကိုလျော့ရရန် အများရည်သံသူနေရာများတွင် သစ်ပင်များကိုအလှင်အမြန်စိုက်ပျိုးမြင်းနှင့် လက်ရှိရေမြောင်း တစ်လျှောက်ပင်ကန်းကျင်အနေအောအားများအား တိန်းသိမ်းမြင်းများအား ပတ်ဝန်းကျင်စီမံရန်ရွံမှအစီအဝဉ်တွင် ထည့်သွင်းထားမည်မြင်သည်။

ထည့်သွင်းတားမည်ဖြစ်သည်။ ဌာနမှာလုံးခြင်းနှင့်ပြန်လည်နော့ရထားမှုအနည်းငယ်ရှိနိုင်ပါသည်။ ထိုရိုက်လွယ်သောလူများနှင့် မြေနော့ရယူခြင်းနှင့်ပြန်လည်နော့ရထားမှုအနည်းငယ်ရှိနိုင်ပါသည်။ ထိုရိုက်လွယ်သောလူများနှင့် အလာတွယ်များပါဝင်သော စီမံကိန်းသက်ရောက်ခံထုံပေးခြင်းနှင့် ဝင်ငွေပြန်လည်ရရှိစေရေး အစီအစဉ်များပါဝင်သော သီလပါအထူးစီးမွားရေးရန် ၂ဝဝဝ ဟက်တာ၏ပြန်လည်နေရာရထားခြင်း မှတ်များအား TSMC မှပြင်ဆင်တားပြီး၊ ထိုလူမှုပတ်ဝန်းကျင်သက်ရောက်မှုမှား ကျောနည်းစေရန် အကောင်ထည်ဖော်သွားမည်ဖြစ်သည်။ အခြားတစ်ဗက်တွင်မူ ကောင်းကျီးသက်ရောက်မှုများအနေမြင့် အလုပ်အကိုင်အစွင့်အလမ်းများနှင့် အခြေမံအဆောက်အဦးများ တိုးတက်လားခြင်းများရှိနိုင်ပါသည်။

ကျွန်မာရေးနှင့်(ဂုဏ္ဏ ကျွန်မာရေးနှင့်လုံမြိုရေအခပါသက်ရောက်မျှနိုင်ပြီး၊ မတော်တစာမှုများ လုပ်ငန်းနှင့်(ဂုဏ္ဏ ကျွန်မာရေးနှင့်လုံမြိုရေအခပါသက်ရောက်မျှနိုင်ပြီး၊ မတော်တစာမှုများ တိုးလာနိုင်ပါသည်။ ၄င်းတို့အားလျှောပါအရေးနဲ့ ထောက်လုပ်ရေအခြေအနေများအား စီဝံကွင်ကဲခြင်း နှင့် ဆောက်လုပ်ရေး(လည်ယတ်ရောကာလအတွင်း လုံမြိုရေတောရိုရန်နှင့်ကာကွယ်ရေးနည်းလမ်းများအား ထိန်းသိမ်းဆောင်ရွက်ရန်တို့အား မတ်ပန်းကျင်စီမံနေ့ခွဲမှုအစီအစဉ်တွင် ထည့်သွင်ထားမည်ခြစ်သည်။

လူထုအကြိုပြဲများစန်းမြင်းနှင့်ထုတ်ဖော်ပြသဖြင့်

ရှာလူနှစ်မှုအမှုနှစ်မှုအမှာတွဲသော ဥပျှလေး နယ်မယ်သတ်မှတ်ဖြင်းအဆင့်အတွက် လူထုတွေးခန့်းမှဲ ဥကြိမ်အား ၂၀၁၅ ဒီစင်ဘာတွင်ကျင်းမခဲ့ပြီး၊ စီမံကိန်းနှင့်နယ်မတ်သတ်မှတ်ဖြင်းမျကြမ်းအား သက်ထိုင်သူများနှင့်ပြည်သူလူထုအားတင်ပြာကာ အငြင်ချင်း ဇလုယ်ခဲ့ကြပ်သည်။ ၎င်းနေတာ် နယ်မယ်သတ်မှတ်ဖြင်းအစီရင်စီစာမှကြမ်းအား သီလဝါအထူးစီးပွားရေရာန် အတွင်းနှင့်ပတ်ဝန်းကျင် ၁၂ဖနရာတို့တွင် ၁၀ရက်စန့် ထုတ်ဖော်ပြသစွဲပါသည်။ လက်စံရရှိလာသော အကြိမြချက်များအား EIA အစီရင်စီစာမှကြမ်းတွင် ထည့်သွင်းထားပါသည်။

EIA အဆင့်အဘွက်စက်မှုခရိယာနှင့် သယ်ယူပို့ဆောင်ရေး အိစ်ယာနှင့်ရောင်းဝယ်တောက်ကားရေးခရိယာများ ၏ EIA အစီရင်စံတမှုကြမ်းများအား သီလပါအထူးစီးပွားရေးရန် အတွင်းနှင့်ဟတ်ဝန်းကျင် ၁၅ ခနောကိုတွင် ၂၀၁၆ မတ် ၂၄ မှ ဧပြီ ၂၃ အထိလက်ရှိထုတ်ဖော်မြသထားပါသည်။ လူထု၏အကြဲဥာက်များအား ထိုကာလအတွင်းနှင့် မြိဳ့ ၂ ရက်နှင့် ၇ ရက်နေ့များတွင်ပြုလုပ်သော ဆွေးနွေးခွဲများအတွင်း ရယူသွားပါမည်။ ပတ်ဝန်းကျင်သက်ရောက်မှုဆန်းစစ်ခြင်းအတွက်လူထုတွေ့ဆုံဆွေနွေးပွဲ (EIA အစီရင်စံစာမူကြစ်း)

> သီလဝါအထူးစီးပွားရေးဇုန်ဖွံ့မြိုးတိုးတက်ရေးစီမံကိန်း အဝိုင်း (စ)

> > သတင်းအချက်အလက်စာစဉ်

၂၀၁၆ခုနှစ်၊ ဇပြီလ (၂) ရက်နှင့် (၅) ရက်



Myanmar Japan Thilawa Development Limited (MJTD)

AND

Thilawa Property Development Ltd. (TPD)

ထပ်မံသိရှိလိုပါကဆက်သွယ်ရန်

Environment, Safety and Health Section, Operations

Department, MJTD (ဖုန်း၁၉၂၅၉၀၁၆၇၆၃)

ပြည်သူဆက်ဆံရေးဌာန၊ MJTD (ဝ၉၂၅၀၁၇၈၃၇၈)

စီမံကိန်းရုံး၊ Thilawa Property Development Ltd., (ဖုန်း ၁၉၂၅၇၇၇ဝ၈၇၇)

လူထုအကြိမ်းအစည်းအစားကျင်းပရမြင်းရည်ရွယ်ရွက်

အစည်းအဝေးကျင်းပခြင်းချိစည်စွယ်ရက်မှာ စိပ်ကိန်းအစီအဝဉ်ရေးချမှတ်နေစဉ် အများပြည်သူများနှင့် စိပ်ကိန်းနှင့်ဆက်ဆိုင်သောသူများ၏ အကြံညာက်များအားရသူကာ စိပ်ကိန်း၏အစီအဝဉ်ရေးထွဲခြင်း၊ သက်ရောက်နိုင်ခြေထန်းတစ်ခြင်း၊ ပတ်ဝန်းကျင်စီဝန်နွဲမှုအစီအဝဉ်နှင့် ပတ်ဝန်းကျင်တောင့်ကြည့်အစီအဝဉ် တို့အားနိုင်တိုးတက်တောင်းမွန်အောင် လုပ်ဆောင်နိုင်ရန်ခြစ်ပါသည်။ အစီကရည်စွယ်ရှက်များမှာ

အဓိကရည်ရွယ်ရက်များမှာ -> စီမံကိန်းအစီအစဉ်နှင့် အချိန်လေားအား ကျယ်ကျယ်ပြန်ပြန့်သိရှိစေရန

- မောက်နှာအားအပညာမှာ အချိန်တော်အားက ကျသာကျသာမှုညနညာနှာသူစာမနာ
 စိပ်ကိုနိုး၏၏ကောင်းကျိန်နှင့်စိုးကျိန်သက်ရောက်နိုင်စခြများနှင့် တိုးကျိန်သက်ရောက်နိုင်စြများအတွက် အဆိုပြုလျာပါစေစရနေညီးလင်းများအား အသိပေးရန်

သီလဝါဂွ် မြီ့အရးစီမံကိန်းနှင့်အပိုင်း(စ)စီမံကိန်းအကြောင်းအရာ

ပြန်မာနိုင်ငံတော်အချိန်ရာသည် သီလဝါအထူးစီးများခရေရန်သည် စီးများချေခဲ့ဖြစ်တိုးတက်ရေအတွက် အဓိကာကျသော အခန်းကတူ တစ်စု အဖြစ်တောင်ရွက်ကိုပိုမည်ဟု ချော်လင့်ထားပါသည်။ တို့ ကြောင့် သီလဝါအထူးစီးများခရရန် မွှစ်ရကိုတော်ရေအတွက် ပြန်မာ-ရေးနဲ နားလည်မှု စာချွန်လွှာကို ၂၀၁၂ခုနှစ် စီစင်ဘာလတွင် လက်မှတ်ရေးထိုးမှပါသည်။ ၂၀၁၄ခုနှစ် ရန်မျှင်လည် KMS Thilawa Development Company (MMST) သီလဝါအထူးစီးများခရေရန် စိပ်စန့်ခွဲမှုတော်မတီ (Thilawa SEZ Management



ဟက်တာအား အောက်ခော်ပြပါအတိုင်း အပိုင်း(စ) ခော်လှတ်မှု စီမံကိန်းအခြင်ခြင် အကောင်အသည်မှာစီထောင်ရွက်ရနိုင်ခြင့်မိုင်သည်။ သဘာဝဟင်ခန်းကျင်နှင့် လူမှတ်ဝန်းကျင် သက်ရောက်နိုင်ခြင့်များအာအားခြင်းလေ့လာပြီး ထိုးကျိုးသက်ရောက်မှု ကျော့ပါစစစေရနည်းလမ်းများနှင့် ပတ်ဝန်းကျင် စိစ်ခြေခဲ့ကောင်အဝဉ်များကို ရေသို့မည့် ပတ်ဝန်းကျင်တိုင်ကိုမှာစာမိုခင်ခြင်းများအား တပြိုင်နက်စတင်ပြုလုပ်ခဲ့ပါသည်။ ခေါ်ပြီးမြင်းဟာ (၁)ရက်ရှိခင် စီမံကိန်းမက်ထောင်သူမှာသည် တင်ဦးတည်းမဟုတ်ပဲ ကွဲပြားသောကြောင့် သက်ဆိုင်ရာရနိမ်း ပတ်ဝန်းကျင်တိနိုက်မှုတန်းစစ်ခြင်းကို သက်ဆိုင်ရာစီမံကိန်းမတင်တောင်သူ တစ်ဦးရည်းမီက သိခြားစီတောင်ရွက်ကြသည် ခြင်ပါသည်။

အဝိုင်း(စ)စစ်မြေအသုံးပြုမှုအစီအဝဉ်

မြေအသုံးပြုမှု	ဧရိယာ (ဟက်တာ)	စီမံကိန်းဖော်ဆောင်သူ
စတ်မှုစရိယာ	၂၆၂ ခန့်	МЈТО
သယ်ယူပို့ဆောင်ရေးဧရိယာ	၂၆၇ ခန့်	TPD
အိမ်ယာနှင့်ရောင်းဝယ်ဖောက်ကားရေးမရိယာ	၁၆၉ ခန့်	TPD
စုစုပေါင်း	၇၀၀ ခန့်	

စရိယာအသီးသီးခန့်အခြေခံအထောက်အဦးတိုးရဲ့ ရေးအစီအစဉ်

	စက်မှုရေိယာ	သလ်ယူပို့ဆောင်ရေး အိမ်ယာနှင့် ရောင်းဝလ်ဇောက်ကားရေးရေယာ
<u>ටේට</u> ර්කදීර්ක <u>ට</u> ර්	ပြင်လယ်ရေမျက်နာပြင်အမြင့် ၅ စီတာ မှ ဂု ဒီတာအကြား	စရိယာနယ်နှစိတ်အား အမြင့် ၅ မီတာအထက်
လမ်း	စရိယာအသီးသီးတွင် အဓိကလမ်းမကြီးနှင့်လမ်း	သွယ်များ
ရေတောက်ပုံမှု	အပိုင်း(က)ရှိရေသန့်ဝင်စက်ရုံမှရေအားဖြန့်ဝေခြင် ဝန်းကျင်တွင်သွယ်တန်းမည့်အများပြည်သူသုံးရေ	်းနှင့် လဝွန်းပြင်ဆည်ရေအား ၂၀၁၉ ပိုက်လိုင်းသို့ပေးပို့ခြင်း
<u>ရေလိုးနှင့်ခိုလွှာ</u>	ရေလိုးသန့်စင်သည့်စက်ရုံတွင် သန့်စင်ရန်	အိမ်ဟာနှင့်ကုန်သွယ်ရေးရှိယာများရှိ ရေရာိးသန့်စင်ကုန် တွင်သန့်စင်ရန် သတ်ယူပို့ဆောင်ရေး ရေီယာတွင် ဌာရာရီးလုပ်ကိုင်သူများ၏ စွန့်ပစ်ရေသိုးများ အတွက် ကိုယ်ပိုင်ရေရအိုးသန့်စင်စက်များ တဝ်ဆင်ရန်
ရေနတ်မြောင်း	ရေများအားရေနတ်မြောင်းနှင့် ရေထိန်းကန်များ မှတဆင့်ရွှေပျောက် ရောင်းအတွင်းသို့ စွန့်ထုတ်ပါမည်။	
ရေလိုးစနစ်	ဌားရမ်းလုပ်ကိုင်သူများ၏ရေဆိုးများအား ဗဟို ရေဆိုးသန့်စင်စက်ရုံတွင်သန့်စင်ပါမည်။	
ඉතියාවේ	သန်လျင်ဓါတ်အားခွဲရှိမှ သီလဝါဓါတ်အားခွဲရှိသို့ သီလဝါ ဓါတ်အားခွဲရှိတွင် ၂၃၀ ဧကဦအား ၃၃ ဧ အပိုင်း(စ)အားရှိန့်ဖြူပည်ဖြစ်သည်။	
စွန့်ပစ်ပစ္စည်း	စက်မှုစွန့်ပစ်ပစ္စည်းများနှင့် စီးပွားရေးစွန့်ပစ်ပစ္စည် ပြန်လည်အသုံးမပြန်ဝိသောစွန့်ပစ်ပစ္စည်းများအာ	း အပိုင်း(က)ရှိစွန့်ပစ်ပစ္စည်းသန့်ဝင်အဖွဲ့အစည်း ဒီမံနေ့်ရွဲမည်ဖြစ်သည်။ အိမ်ယာများမှ ထွက်ရှိလာသော
စိန်းလန်းစိုပြေရေး		လူသွားလမ်းနှင့်မြောင်းတို့တွင်စိုက်ပျိုးမည်ဖြစ်သည်။

Sample of the Feedback Form used at PCM at Draft EIA Stage

	ing for EIA (Draft EIA report Stage) of Thilawa SEZ Development Project (Zone B) (စ) တိုးရဲ့ခြင်းများအတွက်အများပြည်သူများနှင့် တွေထုံရော့မနွေးပွဲ (EIA အစီရင်စံတမူကြမ်းအဆင့်)
Thank you very much for your	r participation in this Public Consultation Meeting, Your suggestions and feedback of
	s related to the project will help us to improve the plan and minimize the adven
impacts of the project.	a reaction of the project that help us to migrate the part and minimize the date.
တွေးနွေးပွဲသို့တက်ရောက်သည့်အဝ	
သဘာဝပတ်ဝန်းကျင်နှင့် လူမှုဝန် လည်းကောင်း၊ စီပံကိန်း အစီအစဉ်မ	းကျင်ဆိုင်ရာ အကြံပြုချက်များသည် စီမံကိန်း တန်ပြန်သက်ရောက်မှုများ လျော့ချရာတွ ျား ရေးဆွဲရာတွင်လည်းကောင်း များစွာ အထောက်အကူ ဖြစ်စေနိုင်ပါသည်။
Date:	
ရက်စွဲ	
1. Name:	
အမည်	
2. Township:	3. Village: 4. Mobile (if possible):
B _\$0S	ဖကျရ <u>ာ</u> ဖုန်း
5. Age;	6. Gender – Male Female
အသက် ၊	ogps
7. Occupation:	
အလုပ်အကိုင် :	
B. No. of person living together	at home :
အိမ်တွင်နေထိုင်သောအတူနေလူဦးစ	
9. Main income source	
ဝင်ငွေရရှိသောအဓိကအလုပ်အကိုင်	
(a) Farmer	□ (b) Odd job worker □
လတ်သမား	နေ့စားအလုပ်သမား(ကျပန်း)
(c) Wage worker	☐ Self - employed ☐
လစားအလုပ်သမား	ကိုယ်စိုင်လုပ်ငန်း
Other	
(အ ရြား)	
	oponent in terms of Environmental Concern
	စီမံကိန်းဖော်ထောင်သူများသို့ အကြံပြုရက်များ
11, Suggestion to the Project pr	oponent in terms of Social Concern
	ဖော်ဆောင်သူများသို့ အကြံပြုရက်များ
12, Suggestion to the Project pr	oponent in terms of Any Other Concern
စီမံကိန်းအဆိုပြုသူများသို့ အခြားအ(ဘိုပြုချက်များ
and the second s	participation. Please submit this to the receptionist before you leave.
ဘက်ရောက်မြင်းအတွက် အထူးကွေ	ဖူးတင်ပါသည်။ ဤအကြံပြုစာအား ပြန်လည်မတွက်မီ သက်ဆိုင်သူများသို့ပေးစလိုပါသည်။

Annex 11-8

List of Attendee at Public Consultation Meeting for EIA at Draft EIA Stage

Annex 11-8 List of Attendee at Public Consultation Meeting for EIA at Draft EIA Stage

First Session April 2nd, 2016 A.M.

No			
Ah Lwan Sauk	No	Name	Village
Ah Lwan Sauk	1	A	h Lwan Sauk
3 Ah Lwan Sauk 4 Ah Lwan Sauk 5 Ah Lwan Sauk 6 Aye Mya Thida 7 Ah Lwan Sauk 8 Ah Lwan Sauk 9 Ah Lwan Sauk 10 Shwe Pyi Tar Yar 11 Ah Lwan Sauk 12 Ah Lwan Sauk 13 Hpa Yar Kon 14 Ah Lwan Sauk 15 Ah Lwan Sauk 16 Sa Moe Nar 18 Sa Moe Nar 19 Sa Moe Nar 20 Sa Moe Nar 21 Ah Lwan Sauk 22 Ah Lwan Sauk 23 Ah Lwan Sauk 24 Ah Lwan Sauk 25 Ah Lwan Sauk 26 Ah Lwan Sauk 27 ECD 28 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 33 Ah Lwan Sauk 44 Ah Lwan Sauk	2		
4 Ah Lwan Sauk 5 Ah Lwan Sauk 6 Aye Mya Thida 7 Ah Lwan Sauk 8 Ah Lwan Sauk 9 Ah Lwan Sauk 10 Shwe Pyi Tar Yar 11 Ah Lwan Sauk 12 Ah Lwan Sauk 13 Hpa Yar Kon 14 Ah Lwan Sauk 15 Ah Lwan Sauk 16 Sa Moe Nar 18 Sa Moe Nar 19 Sa Moe Nar 20 Sa Moe Nar 21 Ah Lwan Sauk 22 Ah Lwan Sauk 23 Ah Lwan Sauk 24 Ah Lwan Sauk 25 Ah Lwan Sauk 26 Ah Lwan Sauk 27 ECD 28 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 33 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk <td></td> <td></td> <td></td>			
5 Ah Lwan Sauk 6 Aye Mya Thida 7 Ah Lwan Sauk 8 Ah Lwan Sauk 9 Ah Lwan Sauk 10 Shwe Pyi Tar Yar 11 Ah Lwan Sauk 12 Ah Lwan Sauk 13 Hpa Yar Kon 14 Ah Lwan Sauk 15 Ah Lwan Sauk 16 Sa Moe Nar 18 Sa Moe Nar 19 Sa Moe Nar 20 Sa Moe Nar 21 Ah Lwan Sauk 22 Ah Lwan Sauk 23 Ah Lwan Sauk 24 Ah Lwan Sauk 25 Ah Lwan Sauk 26 Ah Lwan Sauk 27 ECD 28 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 33 Ah Lwan Sauk 34 Ah Lwan Sauk 35 Ah Lwan Sauk 40 Ah Lwan Sauk		A	h Lwan Sauk
6 Aye Mya Thida 7 Ah Lwan Sauk 8 Ah Lwan Sauk 9 Ah Lwan Sauk 10 Shwe Pyi Tar Yar 11 Ah Lwan Sauk 12 Ah Lwan Sauk 13 Hpa Yar Kon 14 Ah Lwan Sauk 15 Ah Lwan Sauk 16 Sa Moe Nar 18 Sa Moe Nar 19 Sa Moe Nar 20 Sa Moe Nar 21 Ah Lwan Sauk 22 Ah Lwan Sauk 23 Ah Lwan Sauk 24 Ah Lwan Sauk 25 Ah Lwan Sauk 26 Ah Lwan Sauk 27 ECD 28 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 33 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk </td <td>4</td> <td>A</td> <td>h Lwan Sauk</td>	4	A	h Lwan Sauk
6 Aye Mya Thida 7 Ah Lwan Sauk 8 Ah Lwan Sauk 9 Ah Lwan Sauk 10 Shwe Pyi Tar Yar 11 Ah Lwan Sauk 12 Ah Lwan Sauk 13 Hpa Yar Kon 14 Ah Lwan Sauk 15 Ah Lwan Sauk 16 Sa Moe Nar 18 Sa Moe Nar 19 Sa Moe Nar 20 Sa Moe Nar 21 Ah Lwan Sauk 22 Ah Lwan Sauk 23 Ah Lwan Sauk 24 Ah Lwan Sauk 25 Ah Lwan Sauk 26 Ah Lwan Sauk 27 ECD 28 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 33 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk </td <td>5</td> <td>A</td> <td>h Lwan Sauk</td>	5	A	h Lwan Sauk
7 Ah Lwan Sauk 8 Ah Lwan Sauk 9 Ah Lwan Sauk 10 Shwe Pyi Tar Yar 11 Ah Lwan Sauk 12 Ah Lwan Sauk 13 Hpa Yar Kon 14 Ah Lwan Sauk 15 Ah Lwan Sauk 16 Sa Moe Nar 18 Sa Moe Nar 19 Sa Moe Nar 20 Sa Moe Nar 21 Ah Lwan Sauk 22 Ah Lwan Sauk 24 Ah Lwan Sauk 25 Ah Lwan Sauk 26 Ah Lwan Sauk 29 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 33 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 38 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk <td>6</td> <td></td> <td></td>	6		
8 Ah Lwan Sauk 9 Ah Lwan Sauk 10 Shwe Pyi Tar Yar 11 Ah Lwan Sauk 12 Ah Lwan Sauk 13 Hpa Yar Kon 14 Ah Lwan Sauk 15 Ah Lwan Sauk 16 Sa Moe Nar 18 Sa Moe Nar 19 Sa Moe Nar 20 Sa Moe Nar 21 Ah Lwan Sauk 22 Ah Lwan Sauk 24 Ah Lwan Sauk 25 Ah Lwan Sauk 26 Ah Lwan Sauk 27 ECD 28 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 33 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 38 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk <	_		•
9	<u> </u>		
Shwe Pyi Tar Yar	8	A	h Lwan Sauk
11	9	A	h Lwan Sauk
11	10	S	hwe Pvi Tar Yar
12	_		
13		· ·	
14 Ah Lwan Sauk 15 Ah Lwan Sauk 16 Sa Moe Nar 17 Sa Moe Nar 18 Sa Moe Nar 20 Sa Moe Nar 21 Ah Lwan Sauk 22 Ah Lwan Sauk 23 Ah Lwan Sauk 24 Ah Lwan Sauk 25 Ah Lwan Sauk 26 Ah Lwan Sauk 27 ECD 28 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 33 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 39 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk </td <td></td> <td></td> <td></td>			
15	13	H	lpa Yar Kon
16 Sa Moe Nar 17 Sa Moe Nar 18 Sa Moe Nar 20 Sa Moe Nar 21 Ah Lwan Sauk 22 Ah Lwan Sauk 23 Ah Lwan Sauk 24 Ah Lwan Sauk 25 Ah Lwan Sauk 26 Ah Lwan Sauk 27 ECD 28 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 33 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 39 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk </td <td>14</td> <td>A</td> <td>h Lwan Sauk</td>	14	A	h Lwan Sauk
16 Sa Moe Nar 17 Sa Moe Nar 18 Sa Moe Nar 20 Sa Moe Nar 21 Ah Lwan Sauk 22 Ah Lwan Sauk 23 Ah Lwan Sauk 24 Ah Lwan Sauk 25 Ah Lwan Sauk 26 Ah Lwan Sauk 27 ECD 28 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 33 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 39 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk </td <td>15</td> <td>A</td> <td>h Lwan Sauk</td>	15	A	h Lwan Sauk
17 Sa Moe Nar 18 Sa Moe Nar 20 Sa Moe Nar 21 Ah Lwan Sauk 22 Ah Lwan Sauk 23 Ah Lwan Sauk 24 Ah Lwan Sauk 25 Ah Lwan Sauk 26 Ah Lwan Sauk 27 ECD 28 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 33 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 39 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk 49 Ah Lwan Sauk	16		
18 Sa Moe Nar 20 Sa Moe Nar 21 Ah Lwan Sauk 22 Ah Lwan Sauk 23 Ah Lwan Sauk 24 Ah Lwan Sauk 25 Ah Lwan Sauk 26 Ah Lwan Sauk 27 ECD 28 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 33 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 39 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk 49 Ah Lwan Sauk 49 Ah Lwan Sauk			
Sa Moe Nar Sa			
20 Sa Moe Nar 21 Ah Lwan Sauk 22 Ah Lwan Sauk 23 Ah Lwan Sauk 24 Ah Lwan Sauk 25 Ah Lwan Sauk 26 Ah Lwan Sauk 27 ECD 28 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 33 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 39 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 49 Ah Lwan Sauk			
21 Ah Lwan Sauk 22 Ah Lwan Sauk 24 Ah Lwan Sauk 25 Ah Lwan Sauk 26 Ah Lwan Sauk 27 ECD 28 Ah Lwan Sauk 29 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk 49 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk <td>19</td> <td>S</td> <td>a Moe Nar</td>	19	S	a Moe Nar
21 Ah Lwan Sauk 22 Ah Lwan Sauk 24 Ah Lwan Sauk 25 Ah Lwan Sauk 26 Ah Lwan Sauk 27 ECD 28 Ah Lwan Sauk 29 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk 49 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk <td>20</td> <td>S</td> <td>a Moe Nar</td>	20	S	a Moe Nar
22 Ah Lwan Sauk 23 Ah Lwan Sauk 24 Ah Lwan Sauk 25 Ah Lwan Sauk 26 Ah Lwan Sauk 27 ECD 28 Ah Lwan Sauk 29 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 39 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk <td></td> <td> </td> <td></td>		 	
23 Ah Lwan Sauk 24 Ah Lwan Sauk 25 Ah Lwan Sauk 26 Ah Lwan Sauk 27 ECD 28 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 33 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 39 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk <td></td> <td></td> <td></td>			
24 Ah Lwan Sauk 25 Ah Lwan Sauk 26 Ah Lwan Sauk 27 ECD 28 Ah Lwan Sauk 29 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 38 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk <td></td> <td> </td> <td></td>		 	
25 Ah Lwan Sauk 26 Ah Lwan Sauk 27 ECD 28 Ah Lwan Sauk 29 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 33 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 38 Ah Lwan Sauk 39 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk			
26 Ah Lwan Sauk 27 ECD 28 Ah Lwan Sauk 29 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 33 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 38 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk	24	A	h Lwan Sauk
27 ECD 28 Ah Lwan Sauk 29 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 33 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 38 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk	25	A	h Lwan Sauk
27 ECD 28 Ah Lwan Sauk 29 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 33 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 38 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk	26	A	h Lwan Sauk
28 Ah Lwan Sauk 29 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 33 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 38 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk			
29 Ah Lwan Sauk 30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 33 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 38 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk			
30 Ah Lwan Sauk 31 Ah Lwan Sauk 32 Ah Lwan Sauk 33 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 38 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk			
31 Ah Lwan Sauk 32 Ah Lwan Sauk 33 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 38 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk	29	A	h Lwan Sauk
32 Ah Lwan Sauk 33 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 38 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk	30	A	h Lwan Sauk
32 Ah Lwan Sauk 33 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 38 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk	31	A	h Lwan Sauk
33 Ah Lwan Sauk 34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 38 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk	32.		
34 Pha Lan 35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 38 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk			
35 Ah Lwan Sauk 36 Ah Lwan Sauk 37 Ah Lwan Sauk 38 Ah Lwan Sauk 39 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk			
36 Ah Lwan Sauk 37 Ah Lwan Sauk 38 Ah Lwan Sauk 39 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk			
37 Ah Lwan Sauk 38 Ah Lwan Sauk 39 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk	35	A	h Lwan Sauk
37 Ah Lwan Sauk 38 Ah Lwan Sauk 39 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk	26		1. I C1.
38 Ah Lwan Sauk 39 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk	30	A	iii Lwaii Sauk
38 Ah Lwan Sauk 39 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk	37	A	h Lwan Sauk
39 Ah Lwan Sauk 40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk			
40 Ah Lwan Sauk 41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk			
41 Ah Lwan Sauk 42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk			
42 Ah Lwan Sauk 43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk	40	A	ın Lwan Sauk
43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk	41	A	h Lwan Sauk
43 Ah Lwan Sauk 44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk	42	A	h Lwan Sauk
44 Ah Lwan Sauk 45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk	43		
45 Ah Lwan Sauk 46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk			
46 Ah Lwan Sauk 47 Ah Lwan Sauk 48 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk			
47 Ah Lwan Sauk 48 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk	_		
48 Ah Lwan Sauk 49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk			
49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk	47	A	h Lwan Sauk
49 Ah Lwan Sauk 50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk	48	A	h Lwan Sauk
50 Ah Lwan Sauk 51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk			
51 Ah Lwan Sauk 52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk			
52 Ah Lwan Sauk 53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk			
53 Ah Lwan Sauk 54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk			
54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk		A	h Lwan Sauk
54 Ah Lwan Sauk 55 Ah Lwan Sauk 56 Ah Lwan Sauk	53	A	h Lwan Sauk
55 Ah Lwan Sauk 56 Ah Lwan Sauk		A	h Lwan Sauk
56 Ah Lwan Sauk			
57 Ah Lwan Sauk	_		
	57	A	h Lwan Sauk

	1	1
No	Name	Village
58		Pha Yar Kon
59		Kon Chan Kon
60		Ah Lwan Sauk
61		Ah Lwan Sauk
62		Ah Lwan Sauk
63		Ah Lwan Sauk
64	_	Ah Lwan Sauk
65		Ah Lwan Sauk
66		Ah Lwan Sauk
67		Ah Lwan Sauk
68		Hpa Yar Kon
69		Ah Lwan Sauk
70		Ah Lwan Sauk
71		Ah Lwan Sauk
72		Ah Lwan Sauk
73 74		Ah Lwan Sauk Ah Lwan Sauk
75 76		Ah Lwan Sauk Ah Lwan Sauk
77		Ah Lwan Sauk
78		An Lwan Sauk Ah Lwan Sauk
79		Ah Lwan Sauk
80		Thi La Wa
81		Ah Lwan Sauk
82		Ah Lwan Sauk
83		Ah Lwan Sauk
84		Ah Lwan Sauk
85		Ah Lwan Sauk
86		Ah Lwan Sauk
87		Ah Lwan Sauk
88		Ah Lwan Sauk
89		Aye Mya Thida
90		Aye Mya Thida
91		Ah Lwan Sauk
92		Ah Lwan Sauk
93		Environmental Conservation
		Department (OSSC/TSMC)
94		TPD
95		Ah Lwan Sauk
96 97		Ah Lwan Sauk
		Ah Lwan Sauk
98 99		Aye Mya Thida Aye Mya Thida
100		Aye Mya Thida Ah Lwan Swat
101		Ka Lar Kon
102		Ka Lar Kon
103		Ka Lar Kon
104		Ka Lar Kon
105		Thida Myaing
106		Thanlyn
107		San Pho Nar
108		Ah Lwan Sauk
109		Ah Lwan Sauk
110		Ah Lwan Sauk
111		Ah Lwan Sauk
112		Ah Lwan Sauk
113		Ah Lwan Sauk

Second Session April 7th, 2016 A.M.

	r	,
No	Name	Village
1		Let Yet San
2		Let Yet San
3		Let Yet San
4		Let Yet San
5		Let Yet San
6		Let Yet San
7		Let Yet San
8		Let Yet San
9		Let Yet San
10		Let Yet San
11		Let Yet San
12		Ah Lwan Sauk
13		Ah Lwan Sauk
14		Ah Lwan Sauk
15		Ah Lwan Sauk
16		Sa Moe Nar
17		Sa Moe Nar
18		Sa Moe Nar
19		Sa Moe Nar
20		Sa Moe Nar
21		Ah Lwan Sauk
22		Ah Lwan Sauk
23		Ah Lwan Sauk
24		Ah Lwan Sauk
25		Ah Lwan Sauk
26		Ah Lwan Sauk
27		Ah Lwan Sauk
28		Ah Lwan Sauk
29		Ah Lwan Sauk
30		Ah Lwan Sauk
31		Ah Lwan Sauk
32		Ah Lwan Sauk
33		Ah Lwan Sauk
34		Ah Lwan Sauk
35		Ah Lwan Sauk

N	N	X7'11
No	Name	Village
36		Ah Lwan Sauk
37		Ah Lwan Sauk
38		Ah Lwan Sauk
39		Ah Lwan Sauk
40		Ah Lwan Sauk
41		Ah Lwan Sauk
42		Ah Lwan Sauk
43		Ah Lwan Sauk
44		Ah Lwan Sauk
45		Ah Lwan Sauk
46		Ah Lwan Sauk
47		Environmental Conservation
47		Department (OSSC/TSMC)
48		TSMC
49		MJTD
50		MJTD
51		MJTD
52		Pha Yar Kon
53		Pha Yar Kon
54		Ah Lwan Sauk
55		Ah Lwan Sauk
56		Ah Lwan Sauk
57		Ah Lwan Sauk
58		Ah Lwan Sauk
59		Ah Lwan Sauk
60		Ah Lwan Sauk
61		Ah Lwan Sauk
62		Ah Lwan Sauk
63		Ah Lwan Sauk
64		Ah Lwan Sauk
65		Ah Lwan Sauk
66		Ah Lwan Sauk
67		Ah Lwan Sauk
68		Ah Lwan Sauk
69		Ah Lwan Sauk
70		Ah Lwan Sauk

Third Session April 7th, 2016 P.M..


No	Name	Village
1		Aye Mya Thida
2		Aye Mya Thida

Annex 11-9

Meeting Records of Public Consultation Meeting for EIA at Draft EIA Stage

Annex 11-9 Meeting Records of Public Consultation Meeting for EIA at Draft EIA Stage

First Session: April 2nd, 2016 A.M.



ပတ်ဝန်းကျင်ထိနိုက်မှု ဆန်းစစ်ခြင်းဆိုင်ရာ အများပြည်သူ အကြံပြုဆွေးနွေးပွဲ

၄. အစိုင်အခဲစွန့်ပစ်မှုက တစ်နှစ်ကို တန် ၄၁၀၀ မြေမြှစ် ရပါမယ်။ ဒိုဝါစက်ရုံဟာ နှစ်ရှည်မြေမြှုစ်နိုင်တဲ့အခြေနေ မရှိပါဘူး။ အခုတစ်ပြတဲ့ အစီအစဉ်တွေဟာမြည့်စုံပါဘူး၊ ဒီထက်အသေးစိတ် ရှင်းပြသင့်ပါတယ်။ အိမ်သုံးအမှိုက်များကို စည်ပင်သာယာက အမှိုက်ပုံမှာ စွန့်ပစ်မယ်ဆိုတာက ယေဘုယျဆန်နေပါတယ်။
၅.အကြံပြချက်များနဲ့မေးရွန်းများကိုပိုပြီးတော့တိတိကျကျမြေကြားစေလိုပါတယ်။
၆.ဓာတုပစ္စည်း သုံးစွဲမှုနဲ့ပတ်သက်ပြီး ဌာရမ်းလုစ်ကိုင်သူတွေကို မည်သို့လုစ်ဆောင်ရန် ညွှန်ကြားထားပါသလဲ။
၇. ထိနိုက်လွယ်သောအိမ်ထောင်စု ၃၆ စုအတွက် အလုစ်အကိုင်အစွင့်အလမ်းနဲ့ ပတ်သက်ပြီး မည်သို့စီစဉ်ထားသည်ကို သိရှိလိုပါတယ်။
စ. မတည်ဆောက်စင်နဲ့ တည်ဆောက်ဆဲကာလတွေမှာ သဘာပတ်ဝန်းကျစ်စီမံခန့်ခွဲမှု အစီအစဉ်ပြုလုစ်မည့်အဖွဲ့စည်းမှား အကြောင်းကို ပြည့်ပြည့်စုံစုံစော်ပြသင့်ပါသည်။
၉. ပြည်သူလူထုတွေကို စီမံကိန်းအစီအစဉ်၊ လက်ရှိ စီမံကိန်းအခြေအနေကို ဆွေးနေးတစ်ပြီး အကြံပေးချက်တွေရယူကာ အစီရင်စံစာတွင်ထည့်သွင်း ဖော်ပြသင့်ပါသည်။
၁၀. လယ်ယာမြေကိုအခြေခံသောအသက်မွေးဝစ်အကြာင်းလုစ်ကိုင်သူသက်ရောက်ခံအိမ်ထောစ်စုများအ တွက်

၁၁. စီမံကိန်းပိတ်သိမ်းသည့်စနစ်၊ အစိုးရနှင့်ဌားရမ်းလုပ်ကိုင်သူတို့အကြား ချုပ်ဆိုထားသောစာချုပ်ကို အစီရင်ခံစာတွင်ထည့်သွင်းသင့်ပါသည်။

ဝင်ငွေပြန်လည်ထူထောင်ရေး အစီအစဉ်ကိုမည်သို့လုပ်ဆောင်ထားပါလဲ။

၁၂. အစီရင်ခံစာသည် ပြည်သူလူထုကို အသိပေးရုံသက်သက်ပဲလား၊ ပြည်သူလူထုကိုကာကွယ်ပေးမှာလား၊ ပြည်သူ့ဆက်ဆံရေးဌာန၏ နေရာကိုသိရိုလိုပါသည်။

အဖြေ - ၁,၇,၁၀- ရေနှင့်ပတ်သက်ပြီးတော့ ဘယ်လောက်သုံးစွဲမယ် ဘယ်လောက်ပိုမယ်ဆိုတာကို သေချာအောင် ပြန်လည်တွက်ချက်ပြီးတော့ ပြန်လည်ဖြေကြားပေးပါမယ်။ -အခုလိုတင်ပြမှုတွေကိုလည်း ကြိုဆိုပါတယ်။ အလုပ်ကိုင်အစွင့်လမ်း ပြန်လည်နေရာချထားပေးရေး များကိုလည်း ထည့်သွင်းစဉ်းစားပေးမှာပါ။ ထိနိုက်တဲ့ အိမ်ထောင်စုများကိုလည်း အလုပ်ကိုင်နွဲ့ပတ်သက်ပြီး သင်တန်းပေးတာတွေပြုလုပ်ပေးသွားမှာပါ။

ပတ်ဝန်းကျင်ထိနိက်မှ ဆန်းစစ်ခြင်းဆိုင်ရာ အများပြည်သူ အကြုံပြုဆွေးနွေးပွဲ

အဖြေ - ၂၊ ၃၊ ၄၊ ၅၊ ၆၊ ၈၊ ၉၊ ၁၁၊ ၁၂ -လေထု၊ ရေထုအရည်သွေးနဲ့ပတ်သက်ပြီး ကျွန်မရဲ့အတွေ့အကြုံအရရှင်းပြချင်ပါတယ်။ လေထု၊ ရေထုတိုင်းတာမှု နည်းပညာတွေက ပြည်သူလုထုနားလည်ဖို့ စက်စံပါတယ်။ ဒါပေမယ့် တိုင်းတာမှုရလဒ်အားလုံးဟာ သတ်မှတ်ထားတဲ့စံချိန် စံညွှန်းအောက်မှာဘဲရှိနေပါတယ်။ ၂၀၁၂ စုနှစ် မတိုင်စင်က မြန်မာနိုင်ငံမှာ EIAနဲ့ပတ်သက်သော ဥပဒေ၊ နည်းဥပဒေလုပ်ထုံးလုပ်နည်းများ မရှိခဲ့ပါဘူး။ စက်မှုစုံတော်တော်များများကို EIA မလုပ်ဆောင်ဘဲ အကောင်အထည်ဖော်ခွဲကြပါတယ်။ သီလဝါအထူးစီးပွားရေးရုံဟာ မြန်မာနိုင်ငံမှာ ပထမဆုံး EIAလုပ်ထုံး လုပ်နည်းများနှင့်အညီ အကောင်ထည်ဖော်ခဲ့တာဖြစ်ပါတယ်။ အသိပေးရုံသက်သက်မဟုတ်ဘဲ EIAအစီရင်စံစာဟာလည်း ပြည်သူလူထုကို လူမျပတ်ဝန်းကျင်၊ သဘာဝပတ်ဝန်းကျင်ကိုကာကွယ်ရန် ဖြစ်ပါတယ်။ ယခုအစီရင်စံစာကို နေပြည်တော်ရှိ ပတ်ဝန်းကျင်ထိန်းသိမ်းရေးဌာနကို တင်ပြရမှာဖြစ်ပါတယ်။ ရွေ့လျားအကဲဖြတ်စီစစ်ရေးအဖွဲ့ က စစ်ဆေးပြီး ခွင့်ပြုချက်ထုတ်ပေးမှာဖြစ်ပါတယ်။ သဘာဝပတ်ဝန်းကျင် ကာကွယ်ရေးနှင့် ထိန်သိမ်းရေးအစီအစဉ် (ECPP) မှာ စက်မှုလုပ်ငန်းမှ စွန့်ပစ်ပစ္စည်းများ နှင့်အိမ်သုံးအမှိုက်များကိုမည်သို့ စွန့်ပစ်ရမည်၊ မည်သူမှတာဝန်ယူရမည်၊ အလုပ်သမားများ၏ကျန်းမာရေးကို တစ်နှစ်လျှင် နစ်ကြိမ် စစ်ဆေးပေးရမည်ဟုပါရှိသည်။ ထို့အပြင် ဓာတ္ဓေဒပစ္စည်းများသုံးစွဲမျစနစ်နှင့် ကိုင်သူသုံးစွဲသူအလုပ်သမားများအတွက် လုံခြုံရေးအစီအမံများ ထည့်သွင်းထားသည်။ ဒိုဝါစက်ရုံတစ်ခုထဲကိုဘဲ စက်မှုလုပ်ငန်းမှစွန့်ပစ်အစိုင်အခဲများအတွက်အားကိုးနေမှာမဟုတ်ဘဲပြန်လည်သုံးစွဲနိုင်သည့်စွန့်ပစ်ပစ္စည်းများကို ပြန်လည်သုံးစွဲသွားမှာဖြစ်ပါတယ်။ သီလဝါအထူးစီးပွားရေးစုံအတွင်းရှိ စက်ရုံအများစုမှာ ပတ်ဝန်းကျင် အားဆိုးကျိုး သက်ရောက်မှုနည်းအောင် အဆင့်မြင့်နည်းပညာများကိုအသုံးပြထားတာဖြစ်ပါတယ်။ သွားရောက်ပြီးတော့လည်း လေ့လာနိုင်ပါတယ်။ ယခုစီမံကိန်းဟာ မြန်မာနိုင်ငံမှာ ပထမဦးဆုံး EIA လုဝ်ထုံး လုဝ်နည်းများနှင့်အညီ ဆောင်ရွက်တာဖြစ်သောကြောင့် လိုအပ်ချက်များရှိနိုင်ပါတယ်။ လူကြီးမင်းများ၏ အကြံပေးချက်များကို လက်ခံကြိုဆိုပါတယ်။ (ECD)

မေးရွန်း - ၁၃, လမ်းတွေစုန်ထတာ လျော့နည်းစေဇို့အတွက် ရေဖြန်းတာကတော့ကောင်းပါတယ်။ ဒါပေမယ့် ရေတွေဖြန်းတာ များပြီး လမ်းတွေကမကောာင်းတော့ ရေအိုင်တွေဖြစ်ပြီး ဆိုင်ကယ်မတော်တဆမှုတွေ ကောကေ ဖြစ်နေပါတယ်။

အရေ - ၁၃, မှတ်တမ်းတင်ထားပါမည်။ အကြံပြုချက်ကို ကျေးဇူးတင်ပါတယ်။ (TSMC)

မေးရွန်း - ၁၄, ဦးမြလိုုင်ရဲ့ မေးခွန်များ၊ အကြံပြုချက်များကို ထောက်ခံပါတယ်။ လမ်းပန်းဆက်သွယ်ရေးတွေ ပိုကောင်းအောင်လုပ်ပေးစေခြင်ပါတယ်။

အဖြေ - ၁၄, မှတ်တစ်းတင်ထားပါမည်။ အကြံပြုချက်ကို ကျေးဇူးတင်ပါတယ်။ (TSMC)

Second Session: April 7th, 2016 A.M.

ပတ်ဝန်းကျင်ထိရိက်မှု ဆန်းစစ်ခြင်းဆိုင်ရာ အများပြည်သူ အကြံပြုဆွေးနွေးပွဲ

ဒုတိယနေ့၊ ပြည်သူ့ အကြံပြုဆွေးနွေးပွဲ၊ အစည်းအဝေးမှတ်တမ်း

ခင့် - ၇.၄.၁၆

နေရာ - သီလဝါအိုးအိမ်ရုံး (ယာယီ)

အမျိန် - နံနက် ၉း၃၀

၁. အဖွင့်အမှာစကားပြောကြားခြင်း

မှ အစည်းအဝေးသို့ တက်ရောက်လာသူများကို ကျေးဇူးတင်ကြောင်း၊ ယခုအစည်းအဝေးသည် ပတ်ဝန်းကျင်ထိစိုက်ဆန်းစစ်မှု လေ့လာခြင်းများအား ပြည်သူလူထုသိရှိစေရန် အသိပေးခြင်းဖြစ်ကြောင်း၊ ပြန်လည်နေရာချထားရေးနှင့် မသက်ဆိုင်ကြောင်း ရှင်းလင်းပြောကြားခဲ့ပါသည်။

၂. သီလဝါအထူးစီးပွါးရေးစုနီ အပိုင်း (စ) နှင့်သက်ဆိုင်သော လေ့လာချက်များအား အစီစဉ်အလိုက်ရှင်းလင်း ပြောကြားခြင်း သီလဝါ အထူးစီးပွါးရေးစုနီ အပိုင်း (စ) စီမံကိန်း EIA နှင့်ပတ်သက်သော လေ့လာခဲ့မှုများအကြောင်း၊ အပိုင်း(စ) စရိယာအတွင်းဆောင်ရွက်မည့် စက်မှုလုပ်ငန်း စရိယာ၊ လူနေ နှင့် ကုန်သွယ်မှု သယ်ယူပို့ဆောင်ရေးစရိယာဆောင်ရွက်မည့် စီမံကိန်းများအကြောင်း၊ နယ်ပယ်သတ်မှတ်ခြင်းအဆင့် မူကြမ်းတွင် တွေရှိခုသော အဓိကကောင်းကျိုး၊ ဆိုးကျိုးများ၊ EIA လေ့လာမှုနယ်ပယ်သတ်မှတ်ခြင်း၊၊ EIA လုပ်ဆောင်မည့် အချိန်စယားတင်ပြခြင်း၊ သဘာဝနှင့် လူမှု ဝန်းကျင် သက်ရောက်နိုင်မှု ရှေ့ဆက်လုပ်ဆောင်မည့် EIA အခြေအနေများကို REM မှတာဝန်ရှိသူ

၃. အမေး၊ အဖြေ

မေးရွန်း ၁. အခုအစည်းဝေးမှာ လူကြီးမင်းတို့ပြောတာတွေကို အစည်းဝေးလာတက်တဲ့သူတွေဘဲ သိရတာပါ အလုပ်တစ်ခုကို ထိထိရောက်ရောက်လုပ်တော့မယ်ဆိုရင် ကျွန်တော်အကြံပြုချင်တာကတော့ ဟတ်တာ-၂၀၀၀ ထဲမှာပါသမှုကူတွေအားလုံးကို တစ်အိမ်ဆင်းတစ်အိမ်တက် အဖွဲ့စည်းတွေကတစ်ဆင့် တစ်ဆင့်စကားတစ်ဆင့်ကြားနိုင်အောင် ဖြစ်နိုင်ရင်လုပ်ပေးစေချင်ပါတယ်။ ဘာလို့လဲဆိုတော့ အခုအစည်းဝေး တက်လာတဲ့သူတွေက နဲနဲဘဲရှိပါတယ် ကျန်တဲ့သူတွေကအများကြီးရှိပါသေးတယ် အစည်းအဝေးလာတက်တဲ့သူတွေ အနေနဲ့ ပြန်ပြောဇို့ဆိုတာက ပြန်ပြောပြတတ်တာရှိသလို ပြန်မပြောပြတတ်တာတွေရှိပါတယ် သဘောတရားတွေ ကွဲလွဲမှာစိုးလို့ပါ။ အခုအစည်းဝေးကိုလည်း ကျွန်တော်တို့ ကြိုမသိခဲ့ပါဘူး အစည်းဝေးကို ကြိုတင်မပြောခဲ့တဲ့အတွက် အစည်းဝေးမတက်ရတဲ့သူတွေ အများကြီးရှိနေပါသေးတယ်။ စီမံကိန်းကိုကျွန်တော်က ကန့်ကွက်တာ မဟုတ်ပါဘူး။ လုပ်တဲ့လုပ်ငန်းတွေကို ထိထိရောက်ရောက်လုပ်စေချင်ပါတယ်။

ပတ်ဝန်းကျင်ထိရိက်မှ ဆန်းစစ်ခြင်းဆိုင်ရာ အများပြည်သူ အကြံပြုဆွေးနွေးပွဲ

အရေ - ၁- ကျွန်မတို့ဒီစင်ဘာလမှာပြုလုပ်တဲ့အစည်းရေး ယစု စပြီလမှာလုပ်တဲ့အစည်းဝေးနှစ်ကြိမ်လုံးမှာ အစည်းဝေးမကျင်းပမီ တစ်ပတ်ကြိုတင်ပြီးတော့ အစည်းဝေးစိတ်စာများကို သက်ဆိုင်ရာကျေးရွာ အုပ်ချစ်ရေးမှူးများက တစ်ဆင့် အစည်းဝေးများကို ဖိတ်ကြားခဲ့ပါတယ်။ ဒေသခံများ အစည်းဝေးတက်ရောက်စွဲက အလုပ်းဝေးတဲ့ အတွက်ကြောင့် သယ်ယူပို့ဆောင်ရေး အတွက်ကိုပါ စီစဉ်ပေးပါမည်လို့ အုပ်ချစ်ရေးမှုးများနှင့် ကြိုတင်ညှိနှိုင်းဆောင်ရွက်ခဲ့ပါတယ်။ ကြို့ ပို့ ကားများလည်း စီစဉ်ပေးထားပါတယ်။ ကျွန်မတို့အနေနဲ့ တစ်အိမ်တက်ဆင်းလိုက်ဖိတ်စုံ့ဆိုတာကလည်း အဆင်မပြေပါဘူး။ အဲ့ခံကြောင့် သက်ဆိုင်ရာအုပ်ချစ်ရေးမှုးများမှ တစ်ဆင့် တစ်ပတ်ကြိုတင်ပြီးတော့ ဖိတ်ကြားခဲ့ပါတယ်။ စီမံကိန်းအကြောင်းရာများကို ပြည်သူလူထု ပိုမိုသိရှိအောင်ဆိုပြီး သက်ဆိုင်ရာ ကျေးရွာအုပ်ချုပ်ရေးမှုးများမှာ စီမံကိန်းနဲ့ပတ်သက်တဲ့အစီရင်စံတများကိုလည်း ဖြန့်ဝေပေးထားပါတယ်။ စီမံကိန်းနဲ့ ပတ်သက်ပြီး အကြံပေးလို့ရနိုင်အောင်လည်းတစ်ပါတည်း ဆောင်ရွက်ပေးထားပါတယ်။ ကျွန်မတို့အစည်းဝေးကို အလွမ်းဆွတ်တစ်ရွာထဲမဟုတ်ပါဘူး။ သံလျှင်မြို့နယ်နဲ့ ကျောက်တန်းမြို့နယ်မှာရှိတဲ့ကျေးရွာများကိုလည်း စာစ်ပတ်ကြိုတင်ပြီးတော့ အစည်းဝေးကို ဖိတ်ကြားခဲ့ပြီး အစီရင်ခံစာများကိုလည်း ဖြန့်ဝေထားပါတယ်။ လူကြီးမင်းတို့ရဲ့ ပူးပေါင်ပေ အကြံပြုချက်များကိုကြုံဆိုပါတယ်။ (REM)

မေရွန်း - ၂, ကျွန်တော်မေးချင်တာကတော့ သီလဝါစက်မှုစုံကြီးကိုသာလုပ်နေကြတာ လမ်းမှာမီးလုံးဝမရှိပါဘူး။ စုံထဲမှာတော့မီးတွေလင်းနေပါတယ်။ လမ်းမကြီးတွေမှာတော့မီးကမရှိပါဘူး။ လမ်းမီးများမရှိတဲ့အတွက်ကြောင့် ယာဉ်မတော်တဆမှုတွေ စကာကေဖြစ်နေပါတယ်။ အဲ့ဒါတွေကို လျှစ်စစ်စွမ်းအင်ဌာနနှင့် မည်သို့များ ပူးပေါင်းဆောင်ရွက်နေပါလဲထိုတာကိုသိချင်ပါတယ်။

အစြေ -၂. လမ်းမီးကတော့ ကျွန်မတို့စုံနဲ့တော့ မဆိုင်ပါဘူး။ ဇုံထဲမှာမီးရရှိရေးကတော့ ကျွန်မတို့နဲ့သက်ဆိုင်ပါတယ်။ လမ်းမကြီးအပိုင်းကတော့ သံလျင်လျှစ်စစ်ဖြန့်ဝေရေးနဲ့ ဆိုင်သွားပါပြီ။ ကျွန်မတို့က သူတို့ကို တိုက်ရိုက်တင်ပြမှရမှာပါ။ ကျွန်မတို့စုံရဲ့ နယ်နဓိတ်အပြင်ဘက်ကတော့ ကျွန်မတို့နှင့် မသက်ဆိုင်ပါဘူး။ ဒါပေမယ့် လူကြီးမင်းတို့ရဲ့ အကြံပြုချက်ကို သက်ဆိုင်ရာကို ကျွန်မတို့ ပြန်လည်တင်ပြပေးပါ့မယ်။

မေးရွန်း -၃. အဝေးကလာရောက် အလုပ်လုပ်ကိုင်သူတွေ အတွက် နေထိုင်ဖို့ ဘယ်လိုစီစဉ်ထားလဲဆိုတာသိချင်ပါတယ်။

အစြေ -၃, ကျွန်မတို့ စုံ(က)မှာ အလုပ်သမားတွေနေထိုင်ဖို့ ၆ထပ်အိမ်ယာတွေဆောက်နေပါတယ်။ အိမ်ယာဆောက်လုပ်ပြီးသွားရင် အဲ့ဒီအိမ်ယာတွေကို ဌားမှာပါ။ အဲ့မှာ အလုပ်သမားတွေ တစ်ထောင်ကျော်နေလို့ရပါတယ်။ သက်ဆိုင်ရာ ကုမ္ပကီတွေနဲ့ အိမ်ယာဝိုင်တဲ့သူတွေနဲ့ စာချစ်တွေချုပ်ဆိုပြီး အဝေးကလာရောက်အလုပ်လုပ်ကိုင်သူတွေကိုပေးနေရမှာပါ။ စီမံကိန်းဆောက်လုပ်တာပြီးတော့မှာပါ စပြီလကုန်လောက်မှာ ဆောက်လုပ်ရေးအပြီးသတ်လောက်မှာပါ။ အဲ့ဒါက အိမ်ယာအဝိုင်းမှာပါတာပါ။ ကျေးစူးတင်ပါတယ်။ (ECD) Third Session: April 7th, 2016 P.M.

ခန့်စွဲ - ၇.၄.၁၆

အမျိန် - နေ့လည် ၂း၃၀

ပတ်ဝန်းကျင်ထိခိုက်ဆန်းစစ်မှ

ပတ်ဝန်းကျင်ထိရိုက်မှု ဆန်းစစ်ခြင်းဆိုင်ရာ အများပြည်သူ အကြံပြုဆွေးနွေးပွဲ ဒုတိယနေ့၊ ပြည်သူ့ အကြံပြုဆွေးနွေးပွဲ၊ အစည်းအဝေးမှတ်တမ်း နေရာ - သီလဝါအိုးအိမ်ရုံး (ယာယီ) အစည်းအဝေး ဒုတိယနေ့ မွန်းလွဲပိုင်းအစီအစဉ်တွင် တက်ရောက်သူနှစ်ဦးသာရှိခဲ့ပါသည်။ (ECD) မှ အစည်းအဝေးသို့ တက်ရောက်လာသူများကို ကျေးစူးတင်ကြောင်း၊ ယခုအစည်းအဝေးသည် လေ့လာခြင်းများအား ပြည်သူလူထုသိရှိစေရန် အသိပေးခြင်းဖြစ်ကြောင်း၊ ပြန်လည်နေရာချထားရေးနှင့် သေက်ဆိုင်ကြောင်း ရှင်းလင်းပြောကြားခဲ့ပါသည်။

မှ သီလဝါ အထူးစီးပွါးရေးဇုန် အပိုင်း (စ) စီမံကိန်း EIA နှင့်ပတ်သက်သော လေ့လာခဲ့မှများအကြောင်း ၊အပိုင်း(စ) စရိယာအတွင်းဆောင်ရွက်မည့် စက်မှလုပ်ငန်း စရိယာ၊ လူနေ နှင့် ကုန်သွယ်မှု သယ်ယူပို့ ဆောင်ရေးစရိယာ ဆောင်ရွက်မည့် စီမံကိန်းများအကြောင်း၊ နယ်ပယ်သတ်မှတ်ခြင်းအဆင့် မူကြမ်းတွင် တွေရှိရသော အဓိကကောင်းကျိုး၊ ဆိုးကျိုးများ၊ EIA လေ့လာမှုနယ်ပယ်သတ်မှတ်ခြင်း။

EIA လုပ်ဆောင်မည့် အချိန်ဇယားတင်ပြခြင်း၊ သဘာဝနှင့်လူမှ ဝန်းကျင်သက်ရောက်နိုင်မှ ရှေ့ဆက်လုပ်ဆောင်မည့် EIA အခြေအနေများကို ရှင်းပြခဲ့ပါသည်။

(တက်ရောက်သူနစ်ဦးမှမေးခွန်းများမေးမြန်းမှမရှိခဲ့ပါ။)

Annex 11-10

Announcement Letter for Public Disclosure of the Draft EIA Report

Annex 11-10 Announcement Letter for Public Disclose of the Draft EIA Report

သီလဝါအထူးစီးပွားရေးစုံဖွဲ့ မြိုးတိုးတက်မှုစီမံကိန်း (Zone B) ၏ စက်မှုဇုန်ဧရိယာ၊ သယ်ယူပို့ဆောင်ရေးဇရိယာ၊ လူနေနှင့် ရောင်းဝယ်ဖောက်ကားရေး ဇရိယာအတွက် ပတ်ဝန်းကျင်ထိနိက်မျဆန်းစစ်ခြင်းအစီရင်ခံစာမှကြမ်းအား အများပြည်သူများသို့ တင်ပြဆွေးနွေးခြင်း

ယခုအချိန်တွင် နယ်ပယ်သတ်မှတ်ခြင်း အစီရင်စံစာမှကြမ်းကို အတည်ပြပြီးနောက် ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းဆိုင်ရာ လုပ်ဆောင်မှုများကို အစိတ်အဝိုင်းတစ်ခုအဖြစ် ျပန်မြန်မာစွဲ့ဖြီးတိုးတက်မှုကော်မတီ (MJTD) နှင့် သီလဝါ ပရောပါတီ ဒီဗလော့ဒ်မန့် လီမိဘက် (TPD) တို့သည် သီလဝါအထူးစီးပွားရေးဇုံ ဖွံ့မြိုးတိုးတက်မှ စီမံကိန်း ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်း အစီရင်ခံစာမှကြမ်းကို ပြင်ဆင်လျှက် ရှိပါသည်။ ပတ်ဝန်းကျင်ထိခိုက်မှ ဆန်းစစ်ခြင်းဆိုင်ရာ အစီရင်ခံစာမှုကြမ်းနှင့် အနှစ်ချပ်ကို အင်္ဂလိပ်ဘာသာနှင့် မြန်မာဘာသာနှစ်ခုလုံးဖြင့် အောက်ပါနေရာများတွင် ၂၀၁၆ ခုနှစ် မတ်လ (၂၄) ရက် မှ ၂၀၁၆ ခုနှစ် ဖပြီလ (၂၄) ရက်နေ့အထိ (၁လခန့်) တင်ပြထားရှိသွားမည်ဖြစ်ပြီး သဘောထားမှတ်ချက်များနှင့် ဝေဖန်အကြံပြုချက်များကို သတ်မှတ်ထားသော အချိန်အတောအတွင်း သက်ဆိုင်ရာနေရာများတွင် တင်သွင်းနိုင်ပါသည်။ ထို့အပြင် ကွင်းဆင်းလေ့လာခြင်း ရလဒ်နှင့် မတ်ဝန်းကျင်ဆိုင်ရာ၊ လူမှုဝန်းကျင်ဆိုင်ရာ ထိရိက်မှုဆန်းစစ်ခြင်း နှင့် ယင်းထိနိုက်မှုများလျော့ပါးစေရေး၊ စောင့်ကြပ်ကြည့်ရှုရေးစသည့် အစီအစဉ်များ၊ စီမံကိန်းနှင့် သဘာဝပတ်ဝန်းကျင်ထိခိုက်မှ ဆန်းစစ်လေ့လာခြင်းကို ရှင်းပြပြီး စီမံကိန်းဝန်းကျင်ရှိ အများပြည်သူများ ပူးပေါင်းပါဝင်လာနိုင်စေရန် ရှင်းလင်းမြင်သာစေရန်နှင့် တင်ပြဆွေးနွေးခြင်းပြုလုပ်နိုင်ရန် လူထုအကြံပြုဆွေးနွေးပွဲကို ထုတ်ဖော်တင်ပြရန်သတ်မှတ်ထားသော ကာလအတွင်း ၂၀၁၆ ခုနှစ် ဖပြီလ ၂ ရက်နေ့နှင့် ၇ ရက်နေ့ များတွင် ကျင်းပပြုလုပ်သွားမည်ဖြစ်သည်။

- တဝ်ပြထားရှိမည့်နေရာ
 ၁။ ရန်ကုန်တောင်ပိုင်းခရိုင်အထွေထွေအုပ်ချုပ်ရေးမှူးရုံး
 ၂။ သန်လျင်မြို့နယ်အထွေထွေအုပ်ချပ်ရေးဦးစီးဌာနအောက်ရှိ
 - က)ဘုရားကုန်းကျေးရွာအုပ်စုရုံး
 - a) လက်ယက်စမ်းကျေးရွာအုပ်စုရုံး
 - ဂ) အလွမ်းဆွတ်ကျေးရွာအုပ်စုရုံး

၃။ ကျောက်တန်းမြို့နယ်အထွေထွေအုပ်ချုပ်ရေးဦးစီးဌာနအောက်ရှိ

- က) အေးမြသီတာရပ်ကွက်ရုံး
- a) ရွှေပြည်သာယာရပ်ကွက်ရုံး
- ဂ) သီတာမြိုင်ရပ်ကွက်ရုံး
- ယ) ရွှေပျောက်ကျေးရွာအုပ်စုရုံး

- ၄။ ရာအိမ်မူးအိမ်နှင့် သီလဝါ SEZ ဝန်းကျင်အတွင်းနေထိုင်သူ
- ၅။ သီလဝါ SEZ စီမံခန့်ခွဲရေးကော်မတီရုံး (ယာယီ) သီလဝါ SEZ အနီး
- ၆။ သီလဝါ SEZ ရှိ မြန်မာ ဂျပန် သီလဝါဖွံ့ဖြိုးရေး လီမိတက်ရုံး (MJTD)

အများပြည်သူများနှင့်တွေ့ ဆုံဆွေးနွေးခြင်း

စဉ်	နေ့ရက်	အရိန်	တရင်းပေးချိန်	ဖနရာ
ပထမအချိန်	၂၀၁၆၊ စပြီလ (၂)ရက် (စနေနေ့)	နံနက် (၁၀:၀၀) မှ (၁၀:၃၀) နာရီ	နံနက် (၉:၃၀) မှစတင်၍	အစည်းအလေခန်းမ၊ မြို့ရွာနှင့်အိုးအိပ်ဖွံမြိုးရေး ဦးစီဌာန၊ သီလဝါအထူးစီးပွားရေးစုံ စီမံခန့်ခွဲမှုကော်မတီရုံး (ယာယီ)၊ ကျောက်တန်းမြို့နယ်။
ဒုတိယအချိန်		နေ့လည် (၁:၃၀) မှ (၃:၀၀) နာရီ	နေ့လည် (၁:၀၀) မှစတင်၍	
တတိယအရှိန်	၂၀၁၆၊ စပြီလ (၇)ရက် (ကြာသပတေးနေ့)	နံနက် (၁၀:၀၀) မှ (၁၁:၃၀) နာရီ	နံနက် (၉:၃၀) မှတောင်၍	
စတုတ္ထအရှိန်		နေ့လည် (၁:၃၀) မှ (၃:၀၀) နာရီ	နေ့လည် (၁:၀၀) မှစတင်၍	

မှတ်ချက်။

- ၁။ ကြို/ပို့ယာဉ်များအား စီစဉ်ထားမည်ဖြစ်ပြီး၊ အချိန်နှင့်စုရပ်နေရာများအား သက်ဆိုင်ရာကျေးရွားအုပ်စုရုံး များတွင်ကြိုတင်ကြော်ငြာပေးမည်ဖြစ်သည်။
- ၂။ အစည်းအဝေးအချိန်(၄)ခုလုံးတွင် တင်ပြဆွေးနွေးမည့်အကြောင်းအရာမှာ အားလုံးအတူတူဖြစ်သဖြင့် စိဓိအဆင်ပြေရာအချိန်ကိုတက်ရောက်နိုင်ပါသည်။

"Approval of Scoping Report (TSEZ-EIA-003)" issued by TSMC on February 26th, 2016

"Approval of Scoping Report (TSEZ-EIA-003)" issued by TSMC on February 26th, 2016

FORM-2



Republic of the Union of Myanmar Thilawa Special Economic Zone Management Committee

APPROVAL OF SCOPING REPORT

Our Ref: TSEZ-EIA-003
Date: 26 February 2016

To: MYANMAR JAPAN THILAWA DEVELOPMENT LIMITED

Administration Complex Area, Zone A, Thilawa Special Economic

Zone

Subject: Approval of the Scoping Report on Environmental Impact Assessment

for Development of Industrial Area of Zone B in the Thilawa Special

Economic Zone

Reference: Your application No. MJTDO/16-02-277 dated on 11 February 2016

for approval of Final Scoping Report

With reference to the above mentioned Final Scoping Report, the Thilawa Special Economic Zone Management Committee hereby approves, under the conditions described herein, Environmental Impact Assessment for Development of Industrial Area in of Zone B in the Thilawa Special Economic Zone under the name of MYANMAR JAPAN THILAWA DEVELOPMENT LIMITED in Thilawa Special Economic Zone.

Terms and Conditions for Approval:

- (i) You shall describe the contact address, profile, and relevant experience of the organization which has been conducting the EIA study as well as information on environmental, social, and health experts as key personnel including each person's experience in the field of environmental, social, and health impacts assessment, academic credentials, and relevant certificates and accreditations.
- (ii) You shall describe international conventions, treaties and agreements related to your project as the project's policy and legal framework.

- (iii) You shall set project's target levels for environment taking into consideration Myanmar National Environmental Quality (Emission) Guidelines issued by Ministry of Environmental Conservation and Forestry on 29 December 2015 and conditions of surrounding area.
- (iv) You shall describe institutional arrangement for environmental management by your organization including organization chart, a section in charge of environment, and its role and responsibility in construction stage and operation stage at least.
- You shall describe detailed project information in order to assess environmental, social, and health impacts properly.
- (vi) You shall include socio-economic components such as access to public services and natural resources in the TOR for the EIA Investigation in order to assess social impacts properly.
- (vii) You shall conduct scoping evaluation for impacts on soil erosion, usage of chemicals, and earthquakes, and shall conduct its impact assessment if any.
- (viii) You shall conduct scoping evaluation for residual impact in the stage of after project closure and conduct its impact assessment if any.
- (ix) In addition to the impact assessment for the development of industrial area of Zone B, you shall assess cumulative impact including the development of Zone A and the development of logistic area and residential and commercial area of Zone B.
- (x) You shall reflect all of the above comments to the draft EIA Report.

Set Aung

Chairman, Management Committee

Thilawa Special Economic Zone

Copy forwarded to:-

Vice Chairman of Thilawa Special Economic Zone

Secretary of Thilawa Special Economic Zone

Joint secretary of Thilawa Special Economic Zone

Environment Section of One Stop Service Center of Thilawa Special Economic Zone Environmental Conservation Department of Ministry of Environmental Conservation and Forestry

"Notification of the Comments on Draft EIA Report (TSEZ-EIA-005)" issued by TSMC on May 17th, 2016

"Notification of the Comments on Draft EIA Report (TSEZ-EIA-005)" issued by TSMC on 17 May, 2016



Republic of the Union of Myanmar Thilawa Special Economic Zone Management Committee

NOTIFICATION OF THE COMMENTS ON DRAFT EIA REPORT

Our Ref: TSEZ-EIA-005 Date: 17 May 2016

To: MYANMAR JAPAN THILAWA DEVELOPMENT LIMITED

Administration Complex Area, Zone A, Thilawa Special Economic

Zone

Subject: Finding and Comments on Draft Environmental Impact Assessment

Report for Development of Industrial Area of Zone B in the Thilawa

Special Economic Zone

Reference: Your letter No. MJTD /O/16-03-297 dated on 22 March 2016 for

submission of Draft EIA Report

- 1. With reference to the above mentioned draft Environmental Impact Assessment Report, the Environment Section of One Stop Service Center under the Thilawa Special Economic Zone Management Committee together with the Mobile EIA Review Team, which is composed of Ministry of Natural Resources and Environmental Conservation. Ministry of Industry, Ministry of Construction, Ministry of Health, and Ministry of Labor, Immigration and Population, reviewed the draft EIA Report for Development of Industrial Area of Zone B in the Thilawa Special Economic Zone under the name of MYANMAR JAPAN THILAWA DEVELOPMENT LIMITED in Thilawa Special Economic Zone.
- 2. The Environment Section of One Stop Service Center finalizes findings and comments on the draft EIA Report that have been identified in the enclosure based on the result of the EIA Review Meeting on 5 and 6 May 2016 in the Thilawa Special Economic Zone among the Mobile EIA Review Team, the Project Proponents, the EIA Study Team, the Environment Section of One Stop Service Center, and the Thilawa Special Economic Zone Management Committee.

3. In response to the enclosed finding and comments on the Draft EIA Report, the Thilawa Special Economic Zone Management Committee and the Environment Section of One Stop Service Center request you to revise the Draft EIA Report and to submit the Final EIA Report at your earliest convenience.

Enclosure:

Finding and Comments on Draft EIA Report by Mobile Review Team and Environment Section of One Stop Service Center for Development of Industrial Area of Zone B in the Thilawa Special Economic Zone

Set Aung

Chairman, Management Committee Thilawa Special Economic Zone

Copy forwarded to:-

Vice Chairman of Thilawa Special Economic Zone Management Committee
Secretary of Thilawa Special Economic Zone Management Committee
Joint secretary of Thilawa Special Economic Zone Management Committee
Environment Section of One Stop Service Center of Thilawa Special Economic Zone
Management Committee
Leader of the Mobile EIA Review Team, Environmental Conservation Department of

Ministry of Natural Resources and Environmental Conservation Department of

Finding and Comments on Draft EIA Report by Mobile Review Team and Environment Section of OSSC

Project: Industrial Area of Zone B Development
Project Proponent: Myanmar Japan Thilawa Development Limited
EIA Consultant: Ninnon Koei Co. 11d and

EIA Consultant: Nippon Koei Co., Ltd. etc. Date of Preparation: 16th May 2016

Chapter	Section	Page	Frinchman		
Common	-1		SGH IDDIT	Comments	Note
				Names of the Ministry and numbers of Same comments ministry which reformed in April 2016 shall the project.	Same comments as the project.
Сопппол	L	- (A letter of endorsement by the Project Proponent is too attached in the draft EIA Report.	A letter of endorsement by the Project The project proponent shall issue a letter of Article 62 of EIA Proponent is not attached in the draft EIA endorsement and attach in the Final EIA procedure (same Report.	Article 62 of EIA procedure (same
Common			PA suite states		report)
			Environmental Conservation Department (ECD) of Ministry of Natural Resources and Environmental Conservation for undertaking EAA.	Environmental Conservation Department for registration of undertaking Report. Environmental Conservation Department for registration of undertaking EIA to the Final EIA comment as the other EIA.	Article 21 of ElA procedure (same comment as the other report)
Common			Resertlement Work Plan (RWP) including It is recommended that Imalization of the Income Restoration Plan (IRP) for PAHs are RWP and completion of the signing prepared and will be implemented by TSMC. compensation assistance with PAHs shall be The project proponent is a position to wait a condition in the approval letter of EtA to	Resettlement Work Plan (RWP) including It is recommended that finalization of the Same comments as prepared and will be implemented by TSMC. Compensation assistance with PAHs shall be The project proponent is a position to wait a condition in the approval letter of ELA to	Same comments as the other Project.

Chanter	1745.5. 1147.11	1'age	camping.		
			"Land Lease Agreement" and start construction. After land lease agreement, the project proponent is a position to support income restoration for PAHs indirectly through TSMC after the Land Lease Agreement		
Саттоп	5		impact assessments are d for only air, water, noise, and the impacts on flora/ launa and and community health and ot described.	The cumulative impact on flora/ fauna and biodiversity, and community health and safety, and traffic (for both construction and operation stages) shall be described in the Final EIA Report.	Same comments as the other Project.
Сојпиол	,	×	tal management nt and sub-zone sured.	anagement It shall be described in the Final EIA Report. Similar continents as sub-zone that ECPP (kind of EMP), IEF or EIA for the other Project. each projects/lactories in Zone B shall be conducted.	Similar connents as the other Project.
Сотивоп			Project Commitments is not clearly mentioned in the draft ETA Report.	The Project Propoment should provide a clear Same comments list of commitments that the Project will the other Project, undertake. This includes compliance with the relevant laws and standards and all proposed mitigation measures to be undertaken. This should include the provision of adequate services for the workers on the SEZ (which may include medical services and other services). It would also include any	Same comments as the other Project.

Chapter	Section	1	Page	Findings	Comments	Note	
					mitigation measures to be carried out for the whole SEZ, including waste management and landscaping. CSR should be treated as a separate component. It is not to be considered as a part of the requirements of the EIA. It may be included but separate from the Project Committee.		
Executive		Y	The res Executi	The results of PCM are not mentioned in Executive Summary	The results of PCM shall be added to Same comments as	Same comment	585
Executive Summary	Table 6	<u>e</u>	Living ar mitigation r	Living and livelihood, Impacts and mitigation must be considered as part of EIA not as CSR.	Living and livelihood: Impacts and Wording of results of impact assessment shall Same comments not as CSR. The other project.	the other project. Same comments the other project.	8
		100	Flood re	Flood risk-low impact due to EL - 5m	It shall be described in the Final EIA Report how have climate change impacts been modeled and considered over life of project including increase thoods, eyclones and sea	Same comments the other project.	- F
Executive	Table3-8	17	Impacts	Impacts and mitigation measures	level rise. Does not address existence of valuerable and Same comments as	Same comments	20
Chapter 2		7	ī		near threatened species of fauna.	the other project,	
				- 20 6	Proponent's corporate environmental and Same comments social policies should be provided in detail (if the other project, available)	Same comments as the other project.	SE SE

	Section	Page	Findings	Comments	2100	T
0			- h is described the fundamental laws and	The following modification shall be	Same comments	S
3	1	S.	The design of the second secon	The state of the State of Land 191A Report	the other project.	
3	Fundamental		regulations related to the environmental and	implemental in the Linar Error response		
- 3	han san I		social considerations in Myanmar. But, some	- To change the enacted year of Prevention of		
-			Carlot on an increase of the	Hazard from Chemical and Related		
Z.	Regulations		related laws are needed to mention in course			
rel	related to		2.1-1 and summary of related laws.	Substances Law, (not in 2003, enacted in		
1	invironmental		Some of the laws referred in some chapters 2013)	2013)		
	Initial Couries		of the report are not described in table	- To describe some internal laws in table		
É	12		2.1-1. and summaries of key laws, such as the	2.1-1, and summaries of key laws, such as the 2.1-1 and summarize some important laws		
2			Shops and establishment Act (2051) and The such as:	such ass:		
			Factories Act (2051).	- Prevention of Hazard from Chemical and		
			- Prevention of Hazard from chemicals and	Related (2013)		
			related substances law was enacted in 2013.	- Substances Law (2013)		
			not in 2003	- Labour Dispute Settlement Law (2012)		
				- Foreign investment law (2012)		
				- Myanmar Citizen Investment Law		
				- Social Security Law (2014)		
				- Boiler Law (2015)		
				- Export and Import Law (2012)		
				- Electricity Law(2015)		
				- Labour Organization Law(2011)		
				- Workmen Compensation Act(1955)		
				- The Prevention and Control of		
				Communicable Diseases Law		
				- Payment of Wages Law/Rules		

Chapter	Эссион	Page	ge Findings	Comments	Note
				- Factor, Act (1951) - The Explosive Act(1987) - The Explosive Substances Act(1908) - The Explosive Substances Act(1908) - The Conservation of Water Resources Law(2006) - The Conservation of Water Resources Rules(2013) - The Shops and Establishment Act(1951) - Leaves and Holidays Act (1951) - Minimum Wages Law and Rules (2013) - Employment and skill development law	
-1	2.1,2 Fundamental Laws and Regulations related to Environmental and Social Consideration	62	- It is described about the major international. The following international conventions and agreements and Treaties that the Myanmar treaties shall be added, has ratified related to environment and social. b) Montreal Protocol (1989)	The following international conventions and treaties shall be added. a) Vienna Convention (1985). b) Montreal Protocol (1989).	Same comments a the other project.
Chapter 2	2.2.1 Air Qualfity	5-6	Target level of emission gas is not described. Besides target level of ambient air quality, Some tenants have a plan to install target level of emission gas shall be set small-medium combustion facilities such as taking into completions.	Besides target level of ambient air quality. Same comments target level of emission gas shall be set the other Project.	Same comments as the other Project.

				Š	SE SE	4
2000			Same countents as the other project.	Same comments the other project.	Same comments the other project.	Same comments the other project.
Comments	Environmental Quality (Emission) Guidelines.	In table 2.2-2. MEQG value should be added in order to correlate the other standards.	Remaining ministries at the OSSC, such as Same confurents the Central Bank, Ministry of Industry, etc shall the other project, be added.	Table 2.3-5 shall be included more detailed. Same comments information CSR activities by the Project the other project. Proponent (list of activities with date, number of participants, etc.), describe the effective period of the CSR activities.	Project development and implementation Same comments time schedules shall be described in the Final the other project. ETA Report.	Detailed information on materials for land For the land reclamation plan, estimates of Same comments as reclamation from outside is not clear. Sand) from outside, source, and expected sand) from measures in sourcing.
Findings	boiler and melting furnace.	In 2,2.1, it is described that there is no ambient air quality standard in Myammar. But, ambient air quality standards are mentioned in MEQG. In table 2,2-2, there is no MEQG value in parallel with other standards.			Project development and implementation time schedules are not described (It is required by EIA Procedures.).	Detailed information on materials for land reclamation from outside is not clear.
Page		9-5-	2-13	2-21		3-6
Section			2.3 Institutional	2,3 Institutional Arrangement		3.4 Land reclamation
Chanter			Chapter 2	Chapter 2	Chapter 3	Chapter 3

Annex 12-2-8

		us as	y for	
Note		Same comments the other Profect.	Comments only MJTD.	Same comments the other Project.
Comments	transporting, placing shall be described if		The capacities of existing treatment system Comments only and estimated wastewater volume from the MJTD. Zone A at the timing of starting operation of Zone B shall be described.	
Findings		The capacities of retention pond and retention canal for prevention of flood are not found. It is difficult to assess flood risk inside of the Project Site.	e existing centralized nt system of Zone A and ter volume from Zone A. Thus it is difficult to be treatment system still apacity of receiving ne B tenants in the initial	Target parameters of design wastewater The design wastewater quality and diagram. Same comments quality are only BOD and SS (Table 3.8-2), of wastewater treatment or target level of the other Project. Wastewater treatment (Table 2.2-4) such as by tenant shall be revised to archive the front, silver, total phosphorus, ammonia, and target wastewater quality discharging to fluoride are not covered compare with the water body. Target wastewater quality discharging to addition, information on the location of water body (Table 2.2-7). It is not clear that waste water treatment plant and mention which treatment facilities (pre-treatment) facilities and the location plant capacity.
Fage		3-9	<u>e</u>	3-17 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
Попрас		3.6 Drainage Plan	3.7.2 Water Supply Distribution System	Wastewater Treatment Plant
		Chapter 3	Chapter 3	Chapter 3

Chapter	Section	Page	Findings	Comments	Note	T
			will treat these parameters.	described.	_	T
Chapter 3	3,10 Solid Waste Management	3-20	It is described that the waste which cannot be reused or recycled may be managed by the particularly reg waste treatment Irm in Zone A or through hazardous waste? public service such as by the Pollution tenants it may Control and Cleansing Department of the improper dispos Yangon City Development Committee hazardous waste. (YCDC).	Are there any internal regulations for tenants particularly regarding the disposal of hazardous waste? If there is no instruction to tenants, it may be arisen an issue due to improper disposal ways particularly for hazardous waste.	Same comments as the other Project.	Se
		3-7	In figure 3.10-1, type of treatment will not be representing the solid waste management of project proponent.	The solid waste management of industrial area by the project proponent should be mention clearly. Need to provide the detailed information on the estimate annual amount of hazardous wastes (if possible) and disposal system.	Same comments the other Project.	S
Chapter 3	3.11 Greening Plan	3-21	The area information of greening is not described in this section. The information will be a basic indicator of mitigation measures for flora, fauna, and ecosystem.	The area information of greening is not Area information of greening in the non-sales described in this section. The information area shall be added to Section 3.11 and will be a basic indicator of mitigation monitored as a part of environmental measures for flora, fauna, and ecosystem.	Same comments the other Project.	S
Chapter 4			The SEZ is one of the large areas located on the bank of Yangon River. Baseline information on river water quality and biodiversity of the river.	Baseline survey for river water quality is Same comments recommended to implement in order to the other-Project identify impact on water pollution before and after development of SEZ.	Same comments the other Project.	25
Chapter 4	,	i	Public health components (Infant mortality	Public health components (Infant mortality) Public health components shall be included. Same comments as	Same comments	98

Chapter	Section	Page	-	Comments	Note	
			Fate. Maternal Mortality Rate, Crude Death in the Final EIA Report. Rate, morbidity, occurrence of diseases, Communicable diseases Incidence under DUNS, accidents and injuries, and social health determinants) are not mentioned.	in the Final E1A Report	the other project.	
Chapter 4	F. 1.4	4-4	Existing noise assessment: The ambient noise measures taken in April 2013 show that the roise level during daytime along the road is above the criteria. The noise levels are acceptable level during rightime. It is proposed to increase this level from 58 d18(A) to 70 d18(A) along the roadway. See Table 2.2-11 at page 2-12. No justification has been provided for this.	Results of noise monitoring shall be reconsidered to make consistency.	Same comments as the other project:	SIS
Chapter 4	4.2.6 Flora. Fauna. and Biodiversity	-	a such irea of This assess	Information on natural conservation area Same comments such as reserved forests shall be added to the other Project. Section 4.2.6. The impact on flora, fauna, and ecosystem shall be assessed based on the information if necessary.	Same comments the other Project.	× a
Chapter 4	4.3.6 Livelihood	77	Not mention about the Livelihood of people Information on the livelihood of those Same comments as persons using the creeks to access the the other Project, agriculture land shall be added in the Final EIA Report.	Information on the livelihood of those Same comments persons using the creeks to access the the other Project, agriculture land shall be added in the Final	Same comments the other Project.	8
Chapter 6	6.3	6-14	Tables 2.2-10 and 2,2-11. The noise levels set. The justification of the reason why tenjative. Same, government	the justification of the reason why tentative	Same someone	2

Annex 12-2-11

Note	oject.	ments as	nments as
380	the other P	Same comments the other project.	Same comments
Comments	target noise level from traffic in the Table the other Project. Report.	Consistency among Section 7.1 (summary of impact assessment). Section 7.17 (Forecast Results) and Section 9.1 (Mitigation Measures) shall be ensured in the Final EIA. Report.	In the note in Page 7-8, it is understandable. Impact on PM from vehicle shall be assessed. Same comments as
Findings	in the MEQS related to impact at receptors. The MEQS would apply unless the project can justify why any level should be chosen. The receptor should be the most sensitive point at the location closest to the source. In the case of traffic there needs to be an assessment of the number and type of vehicles and the transport routes to be taken. Noise assessments within the SEZ are likely to be high. Whilst each tenant will be required to adopt noise mitigation measures and provide hearing protection where required, this should also be a requirement of the TSMC.	In table 7.1-1, it is described that increasing of traffic volume might be affect the safety of children and project proponent shall design the mitigation measures for security of school children. It is also not link with 7.17.1 Forecast Item of Children's Rights, But in chapter (9), there is no mitigation measure for that and also need to link with 7.17.1.	In the note in Page 7-8, it is understandable. Impact on PM from yel
Page		7-3	7-8
Section	Noise	7.1 Summary of Environ- mental and Social impact Assessment	7.2 Air
Chapter		Chapter 7	Chapter 7

Chapter	Section	Page	Findings	Comments	Note
			impact assessment on air quality from vehicle among NO2, SO2, and CO. However, it is not clear why impact on PM is not described. Some impact may be occur due to construction activities in and around Thilawa SEZ.		3106
Chapter 7	7.2 Air Quality	7-15	With respect to impact from tenants in Impact assessment on em- Industrial and Logistic Area, some tenants in in Industrial and Logist Zone A have already had a plan to install implemented taking imo small-medium combustion facilities such as Internal Regulations of Zon boiler and melting furnace. Impact of ECPP by OSSC/TSMC assessment shall be implemented taking into consideration of Internal Regulations of Zone A and Appraisal of ECPP by OSSC/TSMC	With respect to impact from tenants in Impact assessment on emission from tenants. Same comments Industrial and Logistic Area, some tenants in in Industrial and Logistic Area shall be the other Project. Zone A have already had a plan to install implemented taking into consideration of small-medium combustion facilities such as Internal Regulations of Zone A and Appraisal of ECPP by OSSC/TSMC. A and Appraisal of ECPP by OSSC/TSMC.	Same comments the other Project.
Chapter 7	7.3 Water Quality	7-18	80000	The reason why water quality survey and impact assessment was not taken into account of tidal affect from Yangson River shall be described in the Final EIA Report.	Same comments as the other Project.

	7-19/	
1 8	7-19/	7-19/ 7.8 7-39/ 7-63 afer

F)

Chapter	Section	Page	Findings	Oummont	1	
hapter 7	7.4 Solid Waste Management	7-22	It is described that the operator of SWM What are the restrictions for types of wastes facilities checks the waste sample the sample and generators want to dispose of and conduct SWM company. If the waste is not accepted by the sample analysis to evaluate whether the SWM company, from such wastes will be waste can be received and managed properly. The assessment of waste is not clear as no There should be a clear letter of intent that details have been provided of the estimated the land-fill site will accept the waste, number of people on site or the possible including hazardous waste. No details have been provided in the EIA (except references to the DOWA Eco-system and Table 4.3–13 at page 4-20) that there is a suitable facility for the disposal of hazardous and dangerous waste in accordance with the laws of Myanmar.	What are the restrictions for types of wastes which can be managed properly by the SWM Company. If the waste is not accepted by the SWM company, how such wastes will be controlled? There should be a clear letter of intent that the fand-till site will accept the waste, including hazardous waste.	Same comments the other Project.	S e
			For hazardous waste management during construction and operation stages should be fully considered the facts that in proper recycling of hazardous wastes, lazardous wastes neither Golden Dowa Ecosystem Myanmar nor YCDC can treat (eg. PCB, infectious waste).	Treatment methodology of hazardous waste. Same comments which neither Golden DOWA Ecosystem the other Project. Myanimar nor YCDC can treat shall be described in the Final EIA Report.	Same comments the other Project.	2
		.,	For non-hazardous wastes during The countermeasures of illegal dumped Same comment construction and operation stages should be waste generated in the surrounding that it is the surrounding the state of the state o	The countermeasures of illegal dumped Same comments	1	a a

		\$	é	sa
Note		Same comments the other Project	Same comments as the other Project,	Same comments the other Project.
Comments	related to Zone A and Zone B shall be described in the Final EIA Report.	Actual mitigation measures to prevent infiltration of wastewater to ground shall be added to the Final EIA Report taking into consideration of Zone A Internal Regulations.	Measures for compliance of target level of noise and vibration in operation phase shall be re-considered and described in the Final EIA Report in case that more than expected large-scale machinery will be installed.	The forecast result at Section 7.6.6 needs Arrangement of lot layout plan to allocate the Same comment further justification. The management option tenant and installation of buffer zone with the other Project at page 7-34 to halt work 30m from impacted less noise and vibration impacts to the homes during the day and 200m from impact surrounding sensitive receivers (monastery, homes during the night requires detailed houses etc.) shall be considered taking into investigation to identify how many homes account of actual and planned information of
Findings	considered the facts that to collect the public related to Zone A and Zone I wastes from out of service area in Thilawa described in the Final EIA Report. SEZ, domestic wastes from Zone A and Zone B and other waste from surrounding area.	Actual mitigation measures to prevent infiltration of wastewater to ground such as installation of water proof floor, enough thickness of floor, and adequate dramage to divide water use area and non-water use area are not described.	More than large-scale machinery such as grinding/ milling machines are planned to install by some tenants. In case that, control methodology of noise and vibration by the project proponent together with TSMC shall be required.	The forecast result at Section 7.6.6 needs further justification. The management option tenant and installation of buffer zone with at page 7-34 to halt work 30m from impacted less noise and vibration impacts from from impact surrounding sensitive receivers (monastery, homes during the night requires detailed from second of actual and planned information of investigation to identify how many fromes
Page		7-27	7-32 and 7-33	7,34
Section		7.5 Soil Contamination	7,6 Noise and Vibration	
Chapter		Chapter 7	Chapter 7	

Chapter	Section	Page	Findings	Comments		
			will be impacted. It may be better to provide Zone A. a buffer zone and landscaping.		Noie	
Chapter 7	7.7 Offensive Odor	7-27	Actual mitigation measures to prevent Actual mitigation measures to offensive odor such as installation of offensive odor shall be added to the decodorization system, ventilation system are EIA Report taking into consideration not described.	Actual mitigation measures to offensive odor shall be added to the EIA Report taking into consideration.	prevent Same comments as the Final the other Project	85
Chapter 7	7.9 Flora/ Fauna and Biodiversity	7-40	With respect to assessment of biodiversity and ecosystem, land use change, remaining area of natural area in and around the SEZ, and mitigation measures such as greening are unconsidered.		Same comments the other Project.	85
Chapter 7	7.10 Hydrology	7-42	With respect to assessment of surface water flow, drainage plan of boundary of the project site is not clear to prevent generation of backwater from surrounding area in rainy season.	With respect to assessment of surface water Drainage plan of boundary of the project site. Same comments flow, drainage plan of boundary of the to prevent generation of project site is not clear to prevent generation surrounding area shall be added in the Final of backwater from surrounding area in rainy. EIA Report.	Same comments the other Project.	S
Chapter 7		7-45	Mitigation measures of prevention of soil erosion caused by discharging storm water from retention pond are not clear.	Impact assessment on soil crosion shall be implemented taking into consideration of mitigation measures of prevention of soil crosion caused by discharging storm water from retention road	Comments only for MITD.	Total Control
Chapter 7	Social Impact (Direct Impact		The Resettlement Work Plan by Myanmar Outline of Resettlement of Work Plan by Same comment. Government should be provided with the Myanmar Government such as clarification of the statement and the second of the statement of the	Outline of Resettlement of Work Plan by Myanmar Government such as closeffication of	100	358

Page Findings File must have find extensive public	40	ve public resp	Comments responsibilities for the Plan, cost for	Note
consultation. In addition, given the recommendations made by the JICA Reviewers, the RAP needs to be revisited to ensure compliance with best practice and the EIA Procedure 2015.	addition. made by needs to be with best pract	iven the implie LICA mai	addition, given the implementation of the Plan, and measures on made by the JICA maintaining current fivelihood of PAPs shall be a needs to be revisited to summarized in the Final EIA Report.	
7-64 One cemetery and one temple are located in the Project Site but it is not clear that actual relocation method has not been decided. Clear provision needs to be made for an assessment of the cultural values of the assets identified in 6.7.1.	If one temple are it is not clear that not been de needs to be mi cultural values o		It is recommended that completion of actual implementation of relocation of cemetery and tempte with agreement of PAH shall be a condition in the approval letter of EIA to start construction work.	Similar comments as the other Project.
7-66 It is described the tenant industry shall be responsible for landscaping the plot and maintaining the same in a well-kept condition. But not limited to trimming, watering and fertilization, Tenants will have to follow the internal regulations of MJTD.	landscaping the same in a not limited to ilization. Tenaminal regulations of	y shall be It is plot and ma well-kept afte trimming. The will have as I CMJTD, and	It is described the tenant industry shall be responsible for landscaping the plot and maintaining the same in a well-kept after the Zone A and Zone B development? Condition. But not limited to trimming. The estimated area which will be maintained watering and fertilization. Tenants will have to follow the internal regulations of MJTD.	Same comments as the other project,
7-68 It is mentioned about that the risk for infectious disease and only described the management of AIDS/IIIV as an example.	about that if and only de DS/HIV as an e		Shall be mentioned other infectious disease such as Hepatitis C. Hepatitis B. and outbreak prone diseases such as Diarrhoea. food poisoning, meningitis etc. Shall be mentioned on other communicable.	Same comments as the other project.

	c	Findings	Comments tuberculosis, sexually transmitted diseases	Note
			Shall include diseases preventable by immunization such as diphtheria, measles etc. Shall set up health education program, early	
			reporting and referral system, and immunization program for under 5 years old children from family at construction site and	
7.23 Occupational Itealth and Safety	7-70	Concrete activities on occupational health and safety stipulated in IEC General EHS Guidelines are not described. For any workers living on the SEZ, there is a need to undertaken an assessment based on concrete activities on occupational health the IFC General EHS Guidelines. This and safety stipulated related to the Project in should also be the minimum standard if any IFC General EHS Guidelines and labour tenants also provide worker accommodation. Plated laws and regulations in Myanmar No assessment has been made on the number shall be added, Of workers for Zone B. ElA study according to the laour related laws and regulations in Myanmar. [1) labour rights 2) contract between tenants and labours working days	Mass casualty events and disaster should be Same comments mentioned and preparedness and response the other Project, plan should be developed. Snake bite should be mentioned, Concrete activities on occupational health and safety stipulated related to the Project in IFC General EHS Guidelines and labour related laws and regulations in Myanmar shall be added. The following facts should be considered in EIA study according to the Jaour related laws and regulations in Myanmar. EIA study according to the Jaour related Jaws and regulations in Myanmar. D) abour rights 2) contract between tenants and Jabours Which includes working hours, working days	Same comments as the other Project.

		A
2100		Same comments as the other Project.
Comments	3) safety awareness and health check 4) safety health plan 5) work place diseases and accidents 6) accommodation facilities for the workers with family. A Grievance Mechanism needs to be established to assist in the resolution of disputes during construction and operation of the Zone B. This should enable disputes to be resolved quickly and easily to promote harmonious relationships between the communities and the TSMC. Once tenants are on the site they should be involved with the Dispute Resolution Committee if required.	Safe water supply should be mentioned. Mass casualty events and disaster should be the other Project. mentioned and preparedness and response plan should be developed. Concrete activities on community health and safety stipulated related to the Project in IEC General EHS Guidelines shall be added. Security safety for community, the following facts should be considered:
Findings		Concrete activities on community health and safety stipulated in IFC General EHS Guidelines are not described.
Page		7-72
Section		7.24 Community Health and Safety
Chapter		Chapter 7

Chapter	Section	Page	e Findings	Comments	Note	
				Traffic accidents Increase of crime, infectious diseases such as Hepatitis C. Hepatitis B. Diarrhoea etc. Utilization of worker's accommodation		
Chapter 7	7,25 Usage of Chemical	7-74	Actual/ planned control measures of usage of chemical in Zone A such as preparation of list of chemical and its Material Safety Data Sheet (MSDS), monitoring of amount and control measures, and implementation of self-inspection are not described.		Same comments the other Project.	as
Chapter 7	7.26 Flood Risks	7-75	Setting elevation of flood risk is only taking. The elevation shall be set taking into Same comments into consideration of the highest level of consideration of not only the highest level of the other Project. MITT but not clear of highest date. It is not MITT but also past flood and eyclone.	The elevation shall be set taking into consideration of not only the highest level of MITT but also past flood and eyclone.	Same comments the other Project.	SB.
Chapter 7	7.28 Earthquake	7-78	s ne eture	Impact assessment on carthquake for infrastructure facilities shall be included in the Final ETA Report.	Same comments the other Project.	S.
Chapter 7	7.29 Global Warming	7-80	80 - L	Concrete activities on minimization of GHGs emission by tenant in their operation shall be added taking into consideration of actual activities in Zone A	Same comments as the other Project.	g

T		SE
Note		Same comments the other Project.
Comments		Environmental miligation measures and Same comments management plan shall be revised in the the other Project. Final EIA Report as much as possible taking into consideration of the finding in the left column.
Findings	locations. Provide estimates (tonnes per year) of GHG emissions (e.g., CO; NO ₂ , SO ₂ CH ₄ , VOC).	Need to link with Chapter 2. Provide a description of the Proponent staff management plan shall be revised in the that will be responsible for supervision and implementation of the Environmental Management Plan. Please indicate the responsibilities of construction contractors for implementation of environmental management plans. Please elarify that independent monitoring consultants and agencies will conduct environment monitoring under EIA procedure Chapter IX. Monitoring. Include the Proponent's responsibilities for monitoring and reporting under EIA procedure Chapter IX. Monitoring. Include who will be responsibilities for ensuring/monitoring compliance by individual tenants. Similarly, who will be aggregating the monitoring reports from individual tenants. The role and responsibilities of the finding in the little and responsibilities of the finding the monitoring reports from individual tenants.
Page		
Section		9.1 Environmental Management Plan
Chapter		Chapter 9

Chapter	Section	Page	Findings	Community	
			(ECD) including the Yangon Region ECD needs to be described.	CHRISTIAN	Note
Chapter 9	9.1 Environmental Mitigation and Management Plan		Specific EMPs are not mentioned. Need to mention the following points in manager detail: 1) Verify the items in each of the into con environmental mitigation and management column, plans in Table 9.1-1, 9.1-2, 9.1-3. 2) Each plan needs staffing requirements, cost estimation, and capacity development and training should be separated for mitigation and monitoring programs. 3) plans to address full implementation of the IRP and to include details of the program-eensus of PAPs, budget estimates, time frame, institutional arrangements and reporting. 4) plans to address mitigation measures and monitoring requirements for incineration, common waste water treatment plant, sludge disposal facilities, hazardous wastes management sits etc. 5) the mechanism for grievance redress and community outreach offsee, and accommunity outreach offsee.	Specific EMPs are not mentioned. Need to mention the following points in management plan shall be revised in the other Project. Final EIA Report as much as possible taking in the left final environmental mitigation and management column. D) Verify, the items in each of the into consideration of the finding in the left final EIA Report as much as possible taking environmental mitigation and management column. D) Each plan needs staffing requirements. Every extraction and mentioning programs. Extra EIA Report as much as possible taking in the left final EIA Report as much as possible taking in the left final EIA Report as more consideration of the programment plant strangements and toofforing requirements for incineration. Splans to address mitigation measures and confloring requirement flow incineration. Splans to address mitigation measures and confloring requirement plant, sludge sporting. Sposal flucifities, hazardous wastes anagement sits etc. The mechanism for girevance redress and munimity outreach efforts to deal wast.	Same comments the other Project.

Chapter	Section	Page	Findings			
	Mitigation and	-	With interest adult to	Comments	Note	
	Managara		are impacts to some extent.	EIA Report.		
	Plan	Ť	In table 9, 1-3, under Pollution, proposed mitigation measures and environmental management for air quality is only emphasize to control the emission from vehicles, not include to control the emission from various, kinds of factory in Zone B.	It should be mentioned implementation organization tenants and project proponents control the emission from factory w management plan.	that the Same comments as including the other Project. have to dih proper	2
		9-2 to		Mitigation measures on water use, social Same comments infrastructure shall be described specifically the other Project.	Same continents the other Project.	25
Chapter 9	9.2	9.5 10	Mondowing	as much as possible in the Final EIA Report.		
	Environmental Monitoring		(category) which ass not described.	for some elements All of the elements (category) which Same comments as esseed in Chapter 7 are assessed in Chapter 7 shall be included in the the other Project.	Same comments the other Project.	ਲੇ
		7-6	As the results of Gada.	memorating plans		
			regarding section 7.3 Water Quality, frequency of water quality monitoring at outlet of centralized wastewater may be insufficient.	regarding section 7.3 Water Quality, centralized wastewater is recommended from the other Project, frequency of water quality monitoring at every two months to every month (basic outlet of centralized wastewater may be parameter) and from every six months to	Same comments the other Project,	å
		6-6	Monitoring plan Car and Sa	every mice months (toxic and heavy metals).		
			aspect is not clear Spect is not clear Programs related to EIA shall be including the Environmental Magnetical D.		Same comments the other Project.	S
Chapter 9	9.3 Budget for the	8-6	Wastewater treatment will be treated by the The operation and maintenance cost shall be Comments only for central wastewater treatment plant in Zone, A 1913	The operation and maintenance cost shall be	Comments only t	3
			V allow in maniferment was the control of the contr	idded in the Final E1A Report.	MITD	

		8 2	its as		
Note		Same comments as the other Project.	Same comments the other Project.		
Comments	Budget plan shall be revised in the Final EIA. Same comments report as much as possible taking into the other Project. consideration of the finding as shown in the left column.				
Findings	for the time being, but there is no mentioned about operation and maintenance cost of the plant in Zone A.	A budget is needed with: 1) costs for establishment and operation of the Proponents environmental management system: 2) costs for Third Party Environmental Consultant services: 3) cost of monitoring and reporting for compliance with the ECC and EMP. 4) costs of further preparation, training, and implementation of environmental mitigation and management plans for: (i) preconstruction phase (Table 9.1.1); (ii) construction phase (Table 9.1.2); and operation phase (Table 9.1.3.); 5) costs for Land Acquisition and Resettlement. 6) the costs for construction and operation of the central waste water treatment plant.	Public consultation meeting: For each issue, explain how the Project Chapter 10 provides a listing and summary of Arrthe Proponent are addressing the issue.		
Page		8-6	10-1		
Section	Environmental Management	9.3 Budget for the Environmental Management			
Chapter		Chapter 9	Chapter 10		

Note	
Comments	the jublic consultation process shall be confinited periodically. Rey elements are required to ensure that the public consultation achieves a minimum acceptable level: 1) A stakeholder engagement plan shall be developed to ensure engagement with PAP. PAH and eivil society. 2) The PAP and PAH need to be consulted on the mitigation measures for noise and traffe safety. 3) The PAP and PAH need to be consulted on the RAP and should provide comments and feedback for consideration 4) There should be consulted in particular on the air quality and waste issues to ensure that this can be addressed 5) The Community of Township (using Cemetery) need to be consulted and approval received to relocate the cerenony. This must be done in accordance with any conditions required by that community.
Findings	the issues and concerns raised by the communities and the public. Many responses the questions, implied that the issues would be addressed in the EIA Report
Page	
Section	
Chapter	